

THE IMPERIAL GAZETTEER OF INDIA.

MORRISON AND GIBB, EDINBURGH,
PRINTERS TO HER MAJESTY'S STATIONERY OFFICE.

THE IMPERIAL GAZETTEER OF INDIA.

W. W. HUNTER, C.S.I., C.I.E., LL.D.,

DIRECTOR GENERAL OF STATISTICS TO THE GOVERNMENT OF INDIA.

VOLUME VI.

INDIA.

SECOND EDITION

TRÜBNER & CO., LONDON, 1886.


INDIAN EMPIRE

prepared for Dr W W Hunter's

L GAZETTEER OF INDIA

Scale of Miles

0 10 20 30 40 50 60 70 80 90 100



PREFACE TO THE SECOND EDITION

THIS book tries to present, within a small compass, an account of India and her people. The materials on which it is based are condensed from my larger works. In 1869, the Government of India directed me to execute a Statistical Survey of its dominions,—a vast enterprise, whose records now make 128 printed volumes, aggregating 60,000 pages. The scale of the operations, although by no means too elaborate for the administrative purposes for which they were designed, necessarily placed their results beyond the reach of the general public. The hundred volumes of *The Statistical Survey* were therefore reduced to a more compendious form as the twelve volumes of *The Imperial Gazetteer of India*. The present book distils into one volume the essence of the whole.

I have elsewhere explained the mechanism by which the materials for the Statistical Survey were collected in each of the 240 Districts, or territorial units, of British India¹. Without the help of a multitude of fellow-workers, the present volume could never have been written. It represents the fruit of a long process of continuous condensation. But in again acknowledging my indebtedness to brethren of my Service in India, I wish to specially commemorate the obligations which I also owe to a friend at home. Mr J S Cotton, late Fellow of Queen's College, Oxford, has rendered important aid at many stages of the work.

¹ See Preface to Volume I of *The Imperial Gazetteer of India*.

Continuous condensation, although convenient to the reader, has its perils for the author. Many Indian topics are still open questions, with regard to which divergences of opinion may fairly exist. In some cases, I have been compelled by brevity to state my conclusions without setting forth the evidence on which they rest, and without any attempt to combat alternative views. In other matters, I have had to content myself with conveying a correct general impression, while omitting the modifying details. For I here endeavour to present an account, which shall be at once original and complete, of a continent inhabited by many more races and nations than Europe, in every stage of human development, from the polyandric tribes and hunting hamlets of the hill jungles, to the most complex commercial communities in the world. When I have had to expose old fables, or to substitute truth for long accepted errors, I clearly show my grounds for doing so. Thus, in setting aside the legend of Mahmúd the Idol-Breaker, I trace back the growth of the myth through the Persian Historians, to the contemporary narrative of Al Biruni (970-1029 A.D.). The calumnies against Jagannáth are corrected by the testimony of three centuries, from 1580, when Abul Fazl wrote, down to the police reports of 1870. Macaulay's somewhat fanciful story of Plassey has been told afresh in the words of Clive's own despatch. The history of Christianity in India is written, for the first time, from original sources and local inquiry.

But almost every period of Indian history forms an arena of controversy. Thus, in the early Sanskrit era, each date is the result of an intricate process of induction; the chapter on the Scythic inroads has been pieced together from the unfinished researches of the Archaeological Survey and from local investigations; the growth of Hinduism, as the religious and social nexus of the Indian races, is here for the first time written. In

attempting to reconstruct Indian history from its original sources in the fewest possible pages, I beg oriental scholars to believe that, although their individual views are not always set forth, they have been respectfully considered. I also pray the English reader to remember that, if he desires a more detailed treatment of the subjects of this volume, he may find it in my larger works.

W. W. H.

March 1886.

TABLE OF CONTENTS.

GENERAL PLAN.

	PAGE		PAGE
Physical Aspects	1-42	Early European Settlements,	356-377
The Population of India,	43 52	History of British Rule,	378-430
The Non Aryan Races	53 74	British Administration of India,	431 481
The Aryans in Ancient India	75 131	Agriculture and Products,	482 544
Buddhism in India	132-162	Means of Communication,	545 554
The Greeks in India	163 173	Commerce and Trade	555 597
Scythic Inroads into India	174-190	Arts and Manufactures,	598 617
Rise of Hinduism,	191 228	Mines and Minerals	618 630
Christianity in India	229 267	Geology,	631 640
Early Muhammadan Rulers	268 289	Meteorology,	641 651
The Mughal Empire,	290-316	Zoology and Botany,	652 664
The Maratha Power,	317-324	Vital Statistics	665 686
The Indian Vernaculars and their Literature	325-355	Statistical Appendices I X	687 703
		Index, .	705 747

CHAPTER I

PHYSICAL ASPECTS

	PAGE
General Description of India, Boundaries, . . .	1-4
The Three Regions of India,	4
First Region, the Himālayas, their Scenery and Products,	4-10
Second Region, the Northern River Plains,	10-34
The Great Rivers, their Work, Land making,	10-33
The Indus, Brahmaputra, and Ganges,	10-16
The Gangetic River System, the Highway of Bengal,	16-20
Great Gangetic Cities,	20, 21
Three Stages in the Life of an Indian River,	21, 22
Delta of the Ganges its Age and Process of Formation,	23-28

	PAGE
The Rivers as Highways and as Destroyers,	29-32
Scenery and Crops of the Northern River Plains,	32-34
Third Region of India ; the Southern Table-land,	34-41
The Deccan ; the Gháts, and their Passes,	35-38
The Four Forest Regions of Southern India,	38-40
Crops and Scenery of Southern India,	40, 41
British Burma ; its Geography and Products,	41, 42

CHAPTER II.

THE POPULATION OF INDIA.

Feudatory India ; the Chiefs and their Powers,	43
The Twelve British Provinces ; how governed,	43, 44
Population Tables,	44, 45
Pressure of Population ; overcrowded Districts,	46
Under-peopled Provinces ; the ' immobile ' Indian Peasant, .	47
Nomadic System of Husbandry,	47
The Land and Labour Question in India ; Serfdom,	48, 49
Unequal Pressure of Population ; its Remedies,	49, 50
Population of India in 1872 and 1881 ; Increase,	50
The Ethnical Elements of the Indian People,	51, 52

CHAPTER III.

THE NON-ARYAN RACES.

Kistvaen Builders ; Flint and Bronze Periods,	53
The Non-Aryans of Vedic India described,	53, 54
Andaman Islanders ; Anamalai Hill Tribes,	55
Polyandry among the Nairs ; the Gonds,	55, 56
Leaf-wearing Juangs of Orissa ; Himálayan Tribes,	56, 57
The Santáls ; Village and Tribal Government,	57
Santál Customs, Religion, and History,	58-60
The Kandhs ; Tribal Government, Wars, and Blood Revenge,	60, 61
Kandh Marriage by Capture ; Human Sacrifice,	61, 62
The Three Non-Aryan Stocks—Tibeto-Burmans, Dravidians, and Kolarians ; their Languages,	63-69
Statistics of Non-Aryan Races in 1872 and 1881,	69-71

	PAGE
Crushed Tribes, Gipsy Clans, Predatory Tribes,	71, 72
Character of the Non Aryan Tribes,	72, 73
Mhairs and Bhils, their Reclamation by good Government,	73 74

CHAPTER IV

THE ARYANS IN ANCIENT INDIA

The Indo European Stock,	75
Its Early Camping ground in Central Asia,	75, 76
Common Origin of European and Indian Religions,	76
The Indo Aryans on the March, and in their new Homes,	76, 77
The Rig Veda, Widow burning unknown,	77, 78
Development of Caste,	78, 87, 88, 89 90, 91, 94, 95, 96
Aryan Civilisation in the Veda,	79-86
The Aryan Tribes organized into Kingdoms,	87
Origin and Growth of Priestly Families,	87, 88
The Four Vedas, Brahmanas, Sutras,	88, 89
The Warrior and Cultivating Castes,	89, 90
The Four Castes formed,	90, 91
Struggle between the Bráhmans and Kshattriyas,	92-94
Bráhmaṇ Supremacy established, Brahman Ideal Life	94-97
Brahman Theology,	97
Rise of the Post Vedic Gods, the Hindu Triad,	97, 98
Brahman Philosophy, its Six Schools,	98, 99
Bráhmaṇ Science and Grammar, Panini,	100, 101
Sanskrit mss and Prákrít Dialects,	101-104
The Indian Alphabets,	102, 103
Bráhmaṇ Astronomy, its Three Periods,	104-106
Bráhmaṇ Mathematics, Medicine, and Surgery,	106-110
Hindu Art of War,	110
Indian Music, its Peculiarities and Modern Revival,	110-112
Indian Architecture, Art work, and Painting,	112, 113
Bráhmaṇ Law, Codes of Manu and Yajñavalkya,	113-115
Hindu Customary Law, Perils of Codification,	116-118
Secular Literature of the Hindus,	118
The <i>Mahábhárata</i> , its Growth and Central Story,	119-122
The Polyandry of Draupadi,	121, 122
The <i>Rámáyana</i> , its Story and its Author, Valmiki,	122, 124
Later Sanskrit Epics,	124, 125

	PAGE
The Hindu Drama ; Kálidása,	125-127
The Hindu Novel ; Beast Stories,	127, 128
Sanskrit Lyric Poetry ; Jayadeva,	128
Mediaeval Theology ; the Puráṇas,	128-130 ; 216, 217
The Six Attacks on Bráhmaṇism,	130, 131

CHAPTER V.

BUDDHISM (543 B.C. TO 1000 A.D.).

Buddha's Story modelled on the Sanskrit Epic,	132
Buddha, the Spiritual Development of the Heroic Aryan Man,	133, 134
Buddha's Parentage, Early Life, and Great Renunciation,	133, 134
His Forest Life, Temptation, and Teachings,	134, 135
His Later Years and Death,	136, 137
The Northern and Southern Buddhist Schools,	138
Political Life of Buddha ; his Opponents ; Devadatta,	139, 140
Doctrines of Buddha ; <i>Karma</i> , <i>Nirváṇa</i> ,	141, 142
Moral Code of Buddha ; its Missionary Aspects,	143
Political Development of Buddhism ; the Four Councils,	143, 144 ; 147
The Work of Asoka ; his Council and Edicts,	144-147
The Work of Kanishka,	147
The Northern and Southern Buddhist Canons,	147-149
Spread of Buddhism throughout Asia,	149, 150
Buddhist Influences on Christianity,	150
Buddha as a Christian Saint,	151, 152
Buddha's Personality denied,	153
Buddhism did not oust Bráhmaṇism,	154, 155
The Chinese Buddhist Pilgrims, Fa Hian and Hiuen Tsiang,	155, 156
Buddhism under Siláditya ; Monastery of Nalanda,	156, 157
Mingling of Buddhism and Bráhmaṇism,	157
Buddhism an Exiled Religion ; its Foreign Conquests,	158
Buddhist Survivals in India,	157-162
The Jains ; their Relation to the Buddhists,	157-162

CHAPTER VI.

THE GREEKS IN INDIA (327 TO 161 B.C.).

Early Greek Writers ; Hekataios, Strabo, Pliny, and Arrian,	163
Alexander in India ; Results of his Invasion,	164-166

	PAGE
Seleukos and Chandra Gupta,	166, 169
The India of Megasthenes,	168 169
Indo Greek Treaty, Later Greeks,	170
Greek Survivals in Indian Art,	171, 172
Ancient and Modern Greeks, the Yavanas,	172, 173

CHAPTER VII

SCYTHIC INROADS INTO INDIA (126? B.C. TO 544 A.D.)

Early Scythic Migrations towards India, Tue Chi Settlements,	174, 175
Pre Buddhist Scythic Influences, the Horse Sacrifice,	175, 176
Was Buddha a Scythian? Tibetan Traditions,	176-178
Scythic Buddhism and Settlements in India,	178, 179
Scythian Elements in India, the Jats and Rájputs (?),	179, 180
Indian Struggle against the Scythians,	180-182
Indo-Scythic Settlements, Sen, Gupta, and Valabhi Dynasties,	181, 182
Pre Aryan Kingdoms in Northern India,	183, 184
The Takshaks and Nágas,	184-186
Ghakkars, Bhars, Bhils, Kochs, Ahams, Gonds, etc.,	186-189
Scythic and Naga Influences on Hinduism,	189, 190

CHAPTER VIII

RISE OF HINDUISM (750 TO 1520 A.D.)

Decay and Persecution (?) of Buddhism,	191, 192
Twofold Basis of Hinduism—Caste and Religion,	192
Caste founded on 'Race,' 'Occupation,' and 'Locality,'	192, 193
The Bráhmaṇ Caste analysed,	193, 194
Building up of Caste, Hindu Marriage Law,	194, 195
Changes of 'Occupation' by Castes,	196, 197
Plasticity and Rigidity of Caste,	197
Caste a System of Trade-Guilds, an Indian Strike,	197, 198
Practical Working of Caste, no Poor Law, Rewards and Punishments,	198-200
Religious Basis of Hinduism,	200, 201
Buddhist Influences, Beast Hospitals, Monasteries,	201, 202
A Japanese Temple and a Christian Church,	202, 203

	PAGE
Shrines common to Different Faiths,	203
Serpent-Worship ; Nágá Rites ; Phallic Emblems,	204
Fetish-Worship in Hinduism ; the <i>Sálagráma</i> ,	205, 206
Bráhmaṇ Founders of Hinduism ; Low-Caste Apostles,	207
The <i>Acta Sanctorum</i> of Hinduism, the Bhakta-Málá,	208
Kumáрила Bhatta ; Sankara Achárya,	209
Growth of Siva-Worship ; its Twofold Aspects,	210-212
Human Offerings ; the Charak Pujá,	212, 213
The Thirteen Sivaite Sects ; their Gradations,	213, 214
Siva and Vishnu compared,	215
Friendly Vishnu ; the Vishnu Purána,	215, 216
Bráhmaṇical and Popular Vishnuism,	217
Vishnuite Founders ; Rámánuja, Rámánand,	217, 218
Kabír ; Chaitanya ; Vallabha-Swámi,	218-222
Krishna-Worship ; the Chief Vishnuite Sects,	222, 223
The Bráhmaṇical and Buddhist Origin of Jagannáth,	224
Christian Calumnies against Jagannáth,	224-226
Modern Fate of the Hindu Triad,	227, 228

CHAPTER IX.

CHRISTIANITY IN INDIA (CIRCA 100 TO 1881 A.D.).

Christianity coeval with Buddhism for 900 years,	229
Origin of Christianity in India,	229
The Three Legends of St. Thomas,	230-239
St. Thomas the Apostle, Thomas the Manichæan, Thomas the Armenian,	231, 232
Wide Meaning of 'India' in the Fathers,	233
Early Indian Christians (190 A.D.),	234, 235
The Nestorian Church in Asia ; its Wide Diffusion,	235, 236
'Thomas Christians' of Persia and of India,	237
Mixed Worship at the alleged Shrine of St. Thomas near Madras,	238
Troubles of the Ancient Indian Church,	240
Extinction of the Nestorian Church,	241, 242, 243
First Portuguese Missionaries, 1500 A.D. ; the Syrian Rite,	243-245
Xavier and the Jesuits ; Work done by,	244, 245
Jesuit Literature in India,	246, 250, 253

TABLE OF CONTENTS

xv

PAGE

Parochial Organization of Portuguese India,	247
Jesuit Colleges and Rural Settlements,	247-250
The Jesuit Malabar Mission in the 17th and 18th Centuries,	251, 252
The Portuguese Inquisition at Goa,	253, 254
The Jesuits suppressed (1759-1773), re established (1814)	254, 255
Organization of Roman Catholic Missions,	255, 256
Distribution of Roman Catholics in India,	257, 259
First Protestant Missionaries, 1705, Danish Lutherans	259 260
Schwartz, Kiernander, the Serampur Missionaries,	260
Bishopric of Calcutta, Indian Sees	261
Presbyterian and other Missions,	261
Statistics of Protestant Missions, and their Progress,	261, 263, 265
General Statistics of Christian Population in India,	264
The Indian Ecclesiastical Establishment,	266, 267

CHAPTER X

EARLY MUHAMMADAN RULERS (711 TO 1526 A D)

Early Arab Expeditions to Bombay and Sind,	268
India on the Eve of the Muhammadan Conquest,	268, 269
Hindu Kingdoms (1000 A D),	269
The Muhammadan Conquests only short lived and temporary,	270
Table of Muhammadan Dynasties (1001 to 1857 A D),	271
First Turki Invasions, Subuktigin (977 A.D),	272
Mahmud of Ghazni, his 17 Invasions, Somnâth,	273, 274
House of Ghor (1001-1030 A.D), Muhammad of Ghor's Invasions,	275-278
Hindu Kingdoms, Rájput Dissensions (1184 A.D),	276, 277
Muhammadan Conquest of Bengal,	277, 278
Slave Dynasty (1206-1290 A D), Altamsh, the Empress Raziya,	278, 279
Mughal Irruptions into Northern India, and Rájput Revolts,	279, 280
Balban's Cruelties and his Royal Pensioners, End of Slave Dynasty,	280
House of Khilji, Alâ ud-din's Conquest of Southern India,	280, 282
Mughal Mercenaries for the Suppression of Hindu Revolts,	282, 283
House of Tughlak (1320-1414 A.D), Muhammad Tughlak's Expeditions and Cruelties,	283
His Forced Currency, Revenue Exactions, and Revolts against him,	283, 284

	PAGE
Firuz Sháh Tughlak's Canals (1351-1388 A.D.),	285
Timur (Tamerlane), 1398 A.D. ; Sayyid and Lodi Dynasties,	285, 286
Hindu Kingdoms of the Deccan ; Vijayanagar,	286, 287, 288
Five Muhammadan States of the Deccan ; Bághmani Kings,	287, 288
Independent Náyaks and Pálegárs of Southern India,	288
State of India on the Eve of the Mughal Conquest,	288, 289

CHAPTER XI.

THE MUGHAL EMPIRE (1526 TO 1761 A.D.).

Bábar's Early Life ; his Invasion of India ; Battle of Pá nipat (1526),	290
Humáyun ; Sher Sháh the Afghán,	290, 291
Akbar the Great ; his Work in India (1560-1605),	291-297
His Conciliation of the Hindus ; Intermarriages,	293
Akbar's Hindu Military and Revenue Officers,	293
Reform of Hindu Customs ; Change of Capital to Agra,	293, 294
Akbar's Subjugation of Khándesh ; his Death,	294, 295
Akbar's Religious Principles ; his New Faith,	295, 296
Akbar's Organization of the Empire ; Military and Judicial Reforms,	296
Akbar's Financial System ; Table of his Revenues,	296-298
Revenues of the Mughal Empire (1593-1761),	299, 300
Jahángír, Emperor (1605-1627) ; the Empress Nur Jahán,	300, 301
Sir Thomas Roe, Ambassador ; Drinking Bouts at Court,	301, 302
Jahángír's Personal Character ; his Justice and Religion,	302
Sháh Jahán, Emperor (1628-1658) ; his Deccan Conquests,	302-304
Sháh Jahán's Architectural Works ; Tá j Mahál and Moti Masjid,	304
The Great Mosque and Imperial Palace at Delhi,	304
Rebellion of Prince Aurangzeb, and Deposition of Sháh Jahán,	305
Provinces and Revenues under Sháh Jahán,	305
Aurangzeb, Emperor (1658-1707),	306-312
Murder of his Brothers,	307
Conquests in Southern India ; Rise of the Maráthás,	307, 308
Aurangzeb's twenty years' Maráthá War ; his Despair and Death,	308, 309
Aurangzeb's Oppression of Hindus ; Rájput Revolts,	309, 310

TABLE OF CONTENTS

	xvii
	PAGE
Aurangzeb's Provinces and Revenues,	310, 311
Character of Aurangzeb,	312
Six Puppet Successors of Aurangzeb,	313
Decline and Fall of the Mughal Empire (1707-1858),	312, 313
Independence of the Deccan, Oudh, and Rájput States,	314
Invasions of Nadir Shah the Persian, and Ahmad Shah the Afghán (1739-1761),	314, 315
Last Battle of Pánipat (1761) and Fall of the Mughal Empire,	315, 316

CHAPTER XII

THE MARATHA POWER (1634 TO 1818 A D)

India won, not from the Mughals, but from the Hindus,	317
Rise of the Marathás, Sháhji Bhonsla (1634),	317
The Hindu Party in Southern India,	317, 318
Sivaji the Great (1627-1680),	318, 319
His Guerilla Warfare with the Mughals,	319
Sambhaji (1680-1689), Sahu (1707),	319, 320
Rise of the Peshwas, Balaji Viswanáth,	320
Growth of the Maráthá Confederacy,	320
Maráthá Raids to Deccan, Bengal, and the Punjab, <i>Chauth</i> ,	320, 321
Defeat of the Marathás at Panipat (1761),	321
The Five Great Marathá Houses, Decline of the Peshwás,	321-323
British Wars with the Marathas (1779-1781, 1803-1804 and 1817-1818),	323-324

CHAPTER XIII

THE INDIAN VERNACULARS AND THEIR LITERATURE

The Three Stages in Indian History,	325, 326
The Dravidian Route through India,	327
The Dravidian Family of Languages, its Place in Philology,	327, 328
Pre Aryan Dravidian Civilisation,	328
Bráhmánic Influence on the Dravidians,	329
Dravidian Languages, Tamil,	330-333
Aryan Languages of Northern India, Sanskrit,	334, 335

	PAGE.
The Prákrits or Ancient Aryan Vernaculars,	336-338
The Modern Vernaculars evolved from the Ancient Prákrits,	338
Sanskrit, Prákrit, and Non-Aryan Elements in Modern Vernaculars,	339-342
The Seven Modern Vernaculars,	342-344
The Modern Vernaculars ; their Literature and Authors,	343-355
Hindí, its Historical Development and Chief Authors,	345, 346
Maráthi, its Historical Development and Chief Authors,	346
Bengalí, its Historical Development and Chief Authors,	346-354

CHAPTER XIV.

EARLY EUROPEAN SETTLEMENTS (1498 TO 18TH CENTURY A.D.).

Vasco da Gama's Expedition (1498),	356-358
Portuguese Voyages and Supremacy in the East ; Albuquerque and his Successors,	357-360
Downfall of the Portuguese ; their Possessions in 1881.	361
The Dutch in India (1602-1824),	361, 362
Their Brilliant Progress, but Short-sighted Policy,	362
Fall of the Dutch Power ; Dutch Relics in India,	362, 363
Early English Adventurers (1496-1596),	363, 364
English East India Companies,	364, 365
Early English Voyages (1602-1611),	365, 366
Naval Fights with the Portuguese ; Swally (1615).	366, 367
Wars with the Dutch ; Massacre of Amboyna,	367, 368
Early English Factories ; Surat, Masulipatam, Huglí,	368, 369
Madras Founded (1639) ; Bombay Ceded (1661),	369, 370
Calcutta Founded (1686),	371
Other European East India Companies,	371-377

CHAPTER XV.

HISTORY OF BRITISH RULE (1757 TO 1885).

First British Territorial Possessions,	378
French and English Wars in the Karnátik ; Dupleix, Clive,	378-380
The English in Bengal (1634-1696),	380

Native Rulers of Bengal (1707-1756), the 'Black Hole' Tragedy, .	380, 381
Battle of Plassey (1757), and its Results	381-383
Clive, Governor of Bengal (1758), List of Governors and Viceroys,	384
Clive's Wars in Oudh, Madras, and Bengal	385
Massacre of Patna, First Sepoy Mutiny, Battle of Buxar,	386
The Grant of the <i>Durán</i> (1765),	387
Clive's Reorganization of the Company's Service (1766)	387
Administration of Warren Hastings (1772-1785),	387-392
Abolition of the Dual System of Administration (1772)	388
Hastings' Policy towards Native Powers	388-390
Rohilla, Maráthi, and Mysore Wars	390-392
Charges against Hastings, his poor Excuse,	391
Lord Cornwallis (1786-1793), the Permanent Settlement,	392, 393
Second Mysore War,	394
Marquis of Wellesley (1798-1805), his Work in India,	394-398
Treaty with the Nizám, and Extinction of French Influence	395, 396
Third Mysore War, and Fall of Seringapatam (1799)	396, 397
Second Maratha War (1802-1805) and Extension of British Territory,	397, 398
Sir George Barlow (1805), the Vellore Sepoy Mutiny	399
Earl of Minto (1807-1813) Embassies to Persia and Afghanistan,	399, 400
Marquis of Hastings (1814-1823),	400-402
The Nepál, Pindári, and last Marathá War	401, 402
Lord Amherst (1823-1828),	403, 404
First Burmese War, Capture of Bhartpur,	404
Lord William Bentinck (1828-1835),	404-406
His Financial Reforms, <i>Sati</i> and <i>Thagi</i> suppressed	404, 405
Renewal of Charter, Mysore protected, Coorg annexed,	405, 406
Lord Metcalfe (1835-1836), Liberty of the Press,	406
Lord Auckland (1836-1842)	406, 408
The First Afghan War (1839-1841), its Disastrous Termination,	408
Lord Ellenborough (1842-1844),	408-410
The Army of Retribution, 'Gates of Somnáth,'	408, 409
Sind War, and Gwalior Outbreak,	409, 410

	PAGE
Lord Hardinge (1844-1848); the First Sikh War,	410, 411
Earl of Dalhousie (1848-1856),	411-417
Second Sikh War, and Annexation of the Punjab,	412, 413
Second Burmese War, and Annexation of Pegu,	413, 414
Dalhousie's Policy towards Native States; the Doctrine of Lapse,	414
Sátára; Jhánsí; Nágpur; Berar,	415
Annexation of Oudh,	415-417
Lord Dalhousie's Work; Extensions of Territory,	417
Earl Canning (1856-1862),	417-424
The Mutiny of 1857-1858,	417-422
Downfall of the Company; India transferred to the Crown,	422, 423
Queen's Proclamation of November 1st, 1858,	423, 424
Financial and Legal Reforms,	424
Lord Elgin (1862); Lord Lawrence (1864-1869),	424, 425
Lord Mayo (1869-1872); Ambála <i>Darbár</i> ; Visit of Duke of Edinburgh,	425
Financial Reforms; Abolition of Inland Customs Lines,	425
Lord Northbrook (1872-1876); Visit of Prince of Wales,	425, 426
Lord Lytton (1876-1880); Proclamation of the Queen as Empress,	426, 427
Famine of 1876-1878; Second Afghán War,	426, 427
Marquis of Ripon (1880-1884); End of the Afghán War,	427
Rendition of Mysore; Legal and Financial Reforms,	427-429
Education Commission; Abolition of Import Duties,	429
Bengal Tenancy Bill,	429
Earl of Dufferin (1884),	430
Annexation of Upper Burma,	430

CHAPTER XVI.

BRITISH ADMINISTRATION OF INDIA.

Control of India in England,	431
Under the Company, and under the Crown,	431
The Secretary of State; the Viceroy,	431
The Executive and Legislative Councils,	432, 433
High Courts; the Law of India,	433, 434
Provincial Administration in different Provinces,	434, 435

'Regulation' and 'Non Regulation' Districts,	435
The District Officers, their Duties,	435, 436
Districts and Sub-Districts of India,	436, 437
The Secretariats, Imperial and Provincial,	437, 438
The Land Tax,	438-441
Ancient Land System under Hindus and Musalmáns,	438, 439
Land System under the Company, the <i>Zamíndar</i> ,	439
Landed Property in India, Growth of Private Rights,	439, 440
Rates of Land Tax, Government Share of the Crop	440, 441
The Land Settlement, 'Survey and Settlement	441
Permanent Settlement of Bengal,	441-443
Land Law of 1859, Rent Commission of 1880	443 444
Temporary Settlements, in Orissa, in Assam,	445
<i>Rayatwari</i> Settlement in Madras, Sir Thomas Munro,	445, 446
Permanent Settlement in Madras, Sub Tenures,	446, 447
Extension of Tillage in Madras, Reduction of Average Land	
Tax	447, 448
Land System of Bombay, the 'Survey' Tenure,	448, 449
The Deccan Cultivator, Agriculturists' Relief Acts (1879 and	
1881),	449, 450
Land System of North Western Provinces and Punjab,	451
Of Oudh and the Central Provinces,	451, 452
Land Revenue of British India,	452
The Salt Tax, Systems of Manufacture,	453, 454
Excise, Distilleries and Breweries,	454, 455
Opium, <i>Gánja</i> , <i>Charas</i> ,	455
Municipal Administration, the Old <i>Pancháyat</i> ,	455-457
<i>Finance and Taxation of British India</i> ,	457-470
Obscurities in Indian Accounts,	458
Taxation under the Mughals and the British compared,	459-463
Heavy Taxation in Native States,	464
Incidence of Taxation in British India,	464, 465
Balance Sheet of British India,	465-468
Analysis of Indian Revenues,	465, 467, 468
Indian Expenditure, Army, Public Debt, Famine Relief,	468, 469
Exchange, Public Works, Railways, Irrigation,	469, 470
Imperial and Municipal Finance, .	470
The Army of India, its Constitution,	470, 471

	PAGE
Lord Hardinge (1844-1848); the First Sikh War,	410, 411
Earl of Dalhousie (1848-1856),	411-417
Second Sikh War, and Annexation of the Punjab,	412, 413
Second Burmese War, and Annexation of Pegu,	413, 414
Dalhousie's Policy towards Native States; the Doctrine of Lapse,	414
Sátara; Jhānsi; Nāgpur; Betar,	415
Annexation of Oudh,	415-417
Lord Dalhousie's Work; Extensions of Territory,	417
Earl Canning (1856-1862),	417-424
The Mutiny of 1857-1858,	417-422
Downfall of the Company; India transferred to the Crown,	422, 423
Queen's Proclamation of November 1st. 1858,	423, 424
Financial and Legal Reforms,	424
Lord Elgin (1862); Lord Lawrence (1864-1869),	424, 425
Lord Mayo (1869-1872); Ambāla <i>Darbhār</i> ; Visit of Duke of Edinburgh,	425
Financial Reforms; Abolition of Inland Customs Lines,	425
Lord Northbrook (1872-1876); Visit of Prince of Wales,	425, 426
Lord Lytton (1876-1880): Proclamation of the Queen as Empress,	426, 427
Famine of 1876-1878; Second Afghān War,	426, 427
Marquis of Ripon (1880-1884); End of the Afghān War,	427
Rendition of Mysore; Legal and Financial Reforms,	427-429
Education Commission; Abolition of Import Duties,	429
Bengal Tenancy Bill,	429
Earl of Dufferin (1884),	430
Annexation of Upper Burma,	430

CHAPTER XVI.

BRITISH ADMINISTRATION OF INDIA.

Control of India in England,	431
Under the Company, and under the Crown,	431
The Secretary of State; the Viceroy,	431
The Executive and Legislative Councils,	432, 433
High Courts; the Law of India,	433, 434
Provincial Administration in different Provinces,	434, 435

'Regulation' and 'Non Regulation' Districts,	435
The District Officers, their Duties,	435, 436
Districts and Sub Districts of India,	436, 437
The Secretariats, Imperial and Provincial,	437, 438
The Land Tax,	438-441
Ancient Land System under Hindus and Musalmáns,	438, 439
Land System under the Company, the <i>Zamindar</i> ,	439
Landed Property in India, Growth of Private Rights	439, 440
Rates of Land Tax, Government Share of the Crop	440, 441
The Land Settlement, 'Survey and Settlement	441
Permanent Settlement of Bengal,	441-443
Land Law of 1859, Rent Commission of 1880	443, 444
Temporary Settlements, in Orissa in Assam,	445
<i>Ráyatwarí</i> Settlement in Madras, Sir Thomas Munro	445, 446
Permanent Settlement in Madras, Sub Tenure,	446, 447
Extension of Tillage in Madras, Reduction of Average Land	
Tax	447, 448
Land System of Bombay, the 'Survey' Tenure,	448, 449
The Deccan Cultivator, Agriculturists' Relief Acts (1879 and	
1881),	449, 450
Land System of North Western Provinces and Punjab,	451
Of Oudh and the Central Provinces,	451, 452
Land Revenue of British India	452
The Salt Tax, Systems of Manufacture,	453, 454
Excise, Distilleries and Breweries,	454, 455
Opium, <i>Ganja</i> , <i>Charas</i> ,	455
Municipal Administration, the Old <i>Pancháyat</i> ,	455-457
Finance and Taxation of British India,	457-470
Obscurities in Indian Accounts,	458
Taxation under the Mughals and the British compared,	459-463
Heavy Taxation in Native States,	464
Incidence of Taxation in British India,	464, 465
Balance Sheet of British India,	465-468
Analysis of Indian Revenues,	465, 467, 468
Indian Expenditure, Army, Public Debt, Famine Relief,	468, 469
Exchange, Public Works, Railways, Irrigation,	469, 470
Imperial and Municipal Finance,	470
The Army of India, its Constitution,	470, 471

	PAGE
Police and Jails,	472
Education,	472-479
Education in Ancient India; Sanskrit <i>Tols</i> and Village Schools,	472, 473
Early English Efforts; the Calcutta <i>Madrasa</i> and other Colleges,	473
Mission Schools,	473
State System of Education in India,	473, 474
Education Commission of 1882-1883,	474
Education Statistics, 1878 to 1883,	474, 475
Indian Universities, Colleges, and Schools,	475-477
Primary Schools, Girls' Schools, Normal and other Special Schools,	477-479
The Vernacular Press; Newspapers and Books,	480-481

CHAPTER XVII.

AGRICULTURE AND PRODUCTS.

Agriculture almost the Sole Occupation of the People,	482, 483
Various Systems of Agriculture; Irrigation; Manure,	483
Rice in the different Provinces; Area; Out-turn,	484-486
Wheat; Millets; Pulses; Oil-seeds; Vegetables,	486-490
Fruits; Spices; Palms; Sugar,	490, 491
Cotton Cultivation in different Provinces; Exports,	491-494
Jute Cultivation and Preparation; Exports,	494, 495
Indigo Cultivation in various Provinces,	495, 496
Exports of Indigo; System of Planting,	497, 498
Opium Cultivation and Manufacture,	498, 499
Tobacco Cultivation; Trade and Method of Curing,	499, 500
Table of Crop Statistics; Acreage,	501
Coffee; its Introduction into India; Progress and Growth,	502-504
Tea in India; its History and Statistics,	504-507
Processes of Tea Cultivation and Manufacture,	508, 509
Cinchona Cultivation and Manufacture; Statistics of,	509-511
The Company's Silk Factories,	511, 512
Silk Area of Bengal; Silk Statistics,	512, 513
Jungle Silk; Lac; Lac-dye,	513-515

TABLE OF CONTENTS

viii

PAGE

Model Farms, the Problem of improved Husbandry,	515-517
The Impediments to better Husbandry,	517-519
Agricultural Stock of India,	519-523
Breeds of Cattle, Horse Fairs, Studs, Wild Elephants,	520-522
The Forest Department,	522 524-528
Wanton Destruction of Forests, Indian Timber Trees,	522, 524-526
Forest Conservancy, its Results,	526, 527
Nomadic Tillage, its Destructiveness,	527, 528
Irrigation, its Function in India,	528, 529
Irrigated Area in Sind, Bombay, Punjab,	529-532
In the N W Provinces, Oudh, Bengal, Orissa,	532-535
In Madras, Mysore, Central Provinces,	535-537
Statistics of Cultivation and Irrigation,	538
Famines, their Causes, Drought, Flood, Blight, War,	539, 540
Necessity for husbanding and utilizing the Water-Supply,	540, 541
History of previous Famines (1769 to 1876),	541, 542
The Famine of 1876-1878, its Area,	542, 543
Remedial Efforts, Mortality, Expenditure,	542-544
Famine, a Weak Check on Population,	544

CHAPTER XVIII

MEANS OF COMMUNICATION

Indian Railway System, Lord Dalhousie's Trunk Lines,	545
Lord Mayo's Branch Lines,	545
The Four Classes of Indian Railways,	546
'Guaranteed' Railways,	546, 547
'State Railways,'	547, 548
'Assisted' and 'Native State' Railways,	548, 549
Railway Statistics,	549, 550
Roads, Old Military Routes,	550
The Grand Trunk Road, Bombay Inland Route,	550
Extension of Roads, Bridges of Boats,	551
Navigable Rivers,	551, 552
Navigable Canals, Malabar Back waters, etc,	553, 554

CHAPTER XIX.

COMMERCE AND TRADE.

	PAGE
Ancient, Mediæval, and Modern Trade of India,	555, 556
Large Sea-borne Trade impossible under the Mughals,	556
Growth of Trading and Industrial Cities under British Rule,	556-558
Rise of Calcutta and Bombay,	557
Summary of Indian Exports (1700-1885),	558
India's Balance of Trade and Yearly Savings,	558, 559
Fourfold Division of Modern Indian Trade,	559
The Sea-borne Trade of India,	559, 560
Early Portuguese Trade (1500-1600),	560
Dutch Monopoly (1600),	560
English Factories and Early Trade (1600-1700),	560, 561
Growth of Trade; Quinquennial Table of Foreign Trade,	561, 562
Indian Foreign Trade Statistics; Imports and Exports,	563-581
Imports; Cotton Goods; Treasure,	565, 566; 568, 569
Exports; Raw Cotton; Jute; Rice; Wheat,	569-572
Exports; Oil-seeds; Indigo and Dyes; Tea; Coffee,	573-575
Export of Cotton and Jute Manufactures,	575, 576
Countries with which India trades; England,	577
China; Straits; Ceylon; Mauritius; France; Italy,	577, 578
United States; Australia,	578
Distribution of Foreign Trade of India,	579, 580
Effects of the Suez Canal on Indian Trade,	581
Sir R. Temple on the Balance of India's Foreign Trade,	581-583
Coasting Trade of India; Shipping Statistics,	584-586
Frontier Trade with Afghánistán and Central Asia,	586, 587
The Himálayan Trade Routes; Nepál; Tibet,	587, 588
Trade with Bhután and the North-Eastern Frontier,	588
Trade with Independent Burma and Siam,	588, 589
Tables of Trans-Frontier Landward Trade,	589, 590
Internal Trade; Trading Castes,	591, 592
Local Trade; the Village Money-lender,	592
Religious Fairs; Village Markets,	593
Internal Trade a Safeguard against Famine,	593, 594
Statistics of Internal Trade in certain Provinces,	594, 595
Growth of Large Marts; Local Trading Centres,	595-597

CHAPTER XX

ARTS AND MANUFACTURES

	PAGE
Manufactures of India, Art work,	598
Competition with the English Artisan	598
Native Industries, Village Crafts,	599
Cotton weaving, its Decline,	599, 600
But still a Domestic Industry throughout India	600, 601
Special Fabrics, Muslins, Chintzes, <i>Saris</i>	601, 602
Silk weaving, Classes of Silk Fabrics,	602, 603
Steam Silk Factories	603
Embroidery, Kashmir Shawls, Leather work,	603
Carpets and Rugs, Processes of Manufacture,	604, 605
Goldsmiths and Jewellers' Work, Precious Stones,	605, 606
Iron-work, Cutlery, Chain Armour, Damascening	606, 607
Brass and Copper Work, <i>Bidari</i> Ware,	607, 608
Indian Pottery and Sculpture,	608, 609
Wood-carving, Inlaying, Ivory carving,	609
European Industries, Steam Cotton Mills,	610-612
Their Manufactures, Competition with Manchester	611, 612
Statistics of Bombay Cotton Mills, their Future Prospects,	610, 611, 613
Jute Mills, Manufacture of Gunny,	614, 615
Exports of Jute, Indian Consumption, Growth of the Trade,	615, 616
Brewing, Paper making, Leather, etc.,	616, 617

CHAPTER XXI

MINES AND MINERALS

Indian Iron, Native System of Working	618
Failure of Early English Efforts,	618, 619
Difficulties of Iron smelting in India,	619
Indian Coal, its Inferior Quality,	619
History of Coal mining in Bengal,	619-621
The Four Great Coal Fields, Future of Indian Coal	622
Salt Manufacture, the Punjab Salt Range,	622, 623

	PAGE
Saltpetre ; Manufacture and Export of,	623, 624
Gold and Gold-mining ; the Wainád Quartz Reefs,	624, 625
Copper ; Lead ; Tin ; Antimony ; Cobalt,	625, 626
Petroleum and Mineral Oils,	626, 627
Stone ; Lime ; <i>Kankar</i> ; Marble ; Slate,	627, 628
Diamonds ; Carnelians ; Pearl Fisheries,	628, 629

CHAPTER XXII.

GEOLOGY.

Geology ; the Himálayan Region,	631, 632
The Lower Himálayas ; Siwáliks ; Salt Range,	632, 633
Indo-Gangetic Plain ; its Geological Age and History,	633, 634
Peninsular India ; Vindhyan Rocks,	634, 635
Gondwána, Páncet, Tálcher, and Dámodar Series,	635, 636
The Ráníganj Coal Seams,	637
Deccan Trap ; Laterite,	638, 639
Geology of Burma,	639, 640

CHAPTER XXIII.

METEOROLOGY.

Meteorological Geography ; the Eastern and Western Himá- layas,	641, 642
Air-currents ; Vapour-bearing Winds,	642
Punjab Frontier ; Indus Plain ; the Great Indian Desert,	642, 643
Gangetic Plain ; Eastern Bengal ; Assam,	643, 644
Central Table-land ; Sátapura Range,	644
Málwá Plateau ; Aravalli Range,	644
Southern Plateau ; Anamalai Hills ; Coast Strip,	644, 645
Ceylon and Burma,	646, 647
Observatory Stations,	646, 647
Temperature ; Atmospheric Pressure ; Wind ; Humidity, etc.,	647, 648
Rainfall Returns,	649, 650
'Sun-spot Cycles,	650, 651

CHAPTER XXIV

ZOOLOGY AND BOTANY

	PAGE
Mammals of India, Lion, Tiger, Leopard,	652, 653
Wolf, Fox, Jackal, Dog, Hyena,	654, 655
Bear, Elephant, Rhinoceros, Wild Hog,	655-657
Sheep and Goats, Antelopes, <i>Nilgai</i> , Deer,	657, 658
Bison and Buffalo,	658
Ornithology, Birds of Prey and Game Birds,	659
Reptiles, Loss of Life from Snake bite, the 'Cobra,	660
Fishes, Insects, Locusts,	661
Indian Flora in Various Provinces,	662-664

CHAPTER XXV

VITAL STATISTICS

Sources of Health Returns, their Untrustworthiness,	665, 666
Death rate in India, Average Duration of Life,	666, 667
Vital Statistics in different Provinces,	667-675
Tables of Birth and Death Rates,	676-679
Health of the European Army, Causes of Mortality,	675, 680-682
Health of the Native Army, Causes of Mortality,	682-684
Health Statistics of the Jail Population,	684, 685

TABLE OF CONTENTS

xxii

APPENDICES

	PAGE
APPENDIX I Area, Towns and Villages, Houses, Population, etc., of British India in 1881,	689
" II Towns and Villages of British India, classified according to Population,	690
" III Cultivated, Cultivable, and Uncultivable Area, Land Revenue, etc., in Provinces for which Returns exist,	691
" IV Population of British India, classified according to Sex and Age,	692
" V Population of British India, classified according to Religion,	693
" VI Asiatic Non Indian Population of British India, classified according to Birthplace,	694
" VII Non Asiatic Population of British India, classified according to Birthplace,	695
" VIII List of 149 Towns in British India of which the Population exceeds 20,000,	696, 697
" IX Population of British India, classified according to Education,	698-702
" X Population of British India, classified according to Caste, Sect, and Nationality,	703
INDEX, .	705-747

VOWEL SOUNDS

a	has the sound of <i>a</i> as in	rural
á	has the sound of <i>a</i> as in	far
e	has the vowel sound in	grey
i	has the sound of <i>i</i> as in	police
í	has the vowel sound in	pier
o	has the sound of <i>o</i> as in	bone
u	has the sound of <i>u</i> as in	bull
ú	has the sound of <i>u</i> as in	sure
ai	has the vowel sound in	lyre

Accents have been used as sparingly as possible, and omitted in such words or terminals as *pur*, where the Sanskrit family of alphabets takes the short vowel instead of the long Persian one. The accents over *i* and *u* have often been omitted, to avoid confusing the ordinary English reader, when the collocation of letters naturally gives them a long or open sound. No attempt has been made by the use of dotted consonants to distinguish between the dental and lingual *d*, or to represent similar refinements of Indian pronunciation.

Where the double *oo* is used for *u*, or the double *cc* for *i*, and whenever the above vowel sounds are departed from, the reason is either that the place has obtained a popular fixity of spelling, or that the Government has ordered the adoption of some special form.

I have borne in mind four things—First, that this work is intended for the ordinary English reader. Second, that the twenty-six characters of the English alphabet cannot possibly be made to represent the fifty letters or signs of the Indian alphabets, unless we resort to puzzling un-English devices of typography, such as dots under the consonants, curves above them, or italic letters in the middle of words. Third, that as such devices are unsuitable in a work of general reference, some compromise or sacrifice of scholarly accuracy to popular convenience becomes inevitable. Fourth, that a compromise to be defensible must be successful, and that the spelling of Indian places, while adhering to the Sanskrit vowel sounds, should be as little embarrassing as possible to the European eye.

W W H

IMPERIAL GAZETTEER

OF

INDIA.

VOLUME VI

INDIA

CHAPTER I.—PHYSICAL ASPECTS

INDIA forms a great irregular triangle, stretching southwards from Mid Asia into the sea. Its northern base rests upon the Himalayan ranges, the chief part of its western side is washed by the Arabian Sea, and the chief part of its eastern side by the Bay of Bengal. It extends from the eighth to the thirty fifth degree of north latitude, that is to say, from the hottest regions of the equator to far within the temperate zone. The capital, Calcutta, lies in $88\frac{1}{2}^{\circ}$ E long so that when the sun sets at six o'clock there, it is just past mid day in England.

General outline

The length of India from north to south, and its greatest breadth from east to west, are both about 1900 miles, but the triangle tapers with a pear shaped curve to a point at Cape Comorin, its southern extremity. To this compact dominion the English have added, under the name of British Burma, the strip of country on the eastern shore of the Bay of Bengal. The whole territory thus described contains close on $1\frac{1}{2}$ millions of square miles, and over 256 millions of inhabitants. India, therefore, has an area and a population about equal to the area and population of the whole of Europe, less Russia. Its people more than double Gibbon's estimate of 120 millions for all the races and nations which obeyed Imperial Rome.

Dimensions

This vast Asiatic peninsula has, from a very ancient period, been known to the external world by one form or other of the 'India'.

Origin of the word 'India'

name which it still bears. The early Indians did not themselves recognise any single designation for their numerous and diverse races; their nearest approach to a common appellation for India being Bhárata-varsha, the land of the Bháratas, a noble warrior tribe which came from the north. But this term, although afterwards generalized, applied only to the basins of the Indus and the Ganges, and strictly speaking to only a part of them. The Indus river formed the first great landmark of nature which arrested the march of the peoples of Central Asia as they descended upon the plains of the Punjab. That mighty river impressed itself on the imagination of the ancient world. To the early comers from the high-lying camping grounds of inner Asia, it seemed a vast expanse of waters.

Sanskrit,
Zend, and
Greek
forms.

They called it in Sanskrit by the word which they gave to the ocean itself, *Sindhus* (from the root *syand*, 'to flow'): a name afterwards applied to the ocean-god (Varuna). The term extended itself to the country around the river, and in its plural form, *Sindhavas*, to the inhabitants thereof. The ancient Persians, softening the initial sibilant to an aspirate, called it *Hendu* in the Zend language: the Greeks, again softening the initial by omitting the aspirate altogether, derived from it their *Indikos* and *Indos*. These forms closely correspond to the ancient Persian word *Idhus*, which is used in the inscriptions of Darius for the dwellers on the Indus. But the native Indian form (*Sindhus*) was known to the Greeks, as is proved by the *Sinthos* of the *Periplus Maris Erythraei*, and by the distinct statement of Pliny, 'Indus incolis Sindus appellatus.' Virgil says, 'India mittit ebur.'

Buddhist
derivation
of 'In-tu.'

The eastern nations of Asia, like the western races of Europe, derived their name for India from the great river of the Punjab. The Buddhist pilgrims from China, during the first seven centuries of our era, usually travelled landward to Hindustán, skirting round the Himálayas, and entering the holy land of their faith by the north-western frontier of India. One of the most celebrated of these pious travellers, Hiuen Tsiang (629-645 A.D.), states that India 'was anciently called Shin-tu, also Hien-tau; but now, according to the right pronunciation, it is called In-tu.' This word in Chinese means the moon; and the cradle-land of Buddhism derived its name, according to the good pilgrim, from its superior glory in the spiritual firmament, *sicut luna inter minora sidera*. 'Though there be torches by night and the shining of the stars,' he says, 'how different from the bright (cool) moon! Just so the bright connected light of holy men and sages, guiding the world as the shining of the moon, have made this country

eminent, and so it is called *In tu*¹ Notwithstanding the pious philology of the pilgrim, the great river of the Punjab is, of course, the origin of the Chinese name

The term *Hindustán* is derived from the modern Persian form (*Hind*), and properly applies only to the Punjab and the central basin of the Ganges It is reproduced, however with a wider signification in the title of the Queen Empress, *Kaisar* ^{*Kaisar*} *Hind* ^{*Hind*}, the Cæsar, Kaiser, Czar, or Sovereign paramount of India

India is shut off from the rest of Asia on the north by a vast mountainous region, known in the aggregate as the Himalayas. Among their southern ranges lie the Independent States of Bhutan and Nepál the great table land of Tibet stretches northward behind the Native Principality of Kashmir occupies their western corner At this north western angle of India (in lat. 36° N, long 75° E), an allied mountain system branches southwards Its lofty offshoots separate India on the west, by the well marked ranges of the Safed Koh and the Suláí mán, from Afghánistán, and by a southern continuation of lower hills (the Hálas, etc.) from Baluchistan The southernmost part of the western land frontier of India is the river Hab, and the boundary ends with Cape Monze, at the mouth of its estuary, in lat. $24^{\circ} 50'$ N, long $66^{\circ} 43'$ E. Still proceeding southwards, India is bounded along the west and south west by the Arabian Sea and Indian Ocean Turning northwards from its southern extremity at Cape Comorin (lat $8^{\circ} 4' 20''$ N, long $77^{\circ} 35' 35''$ E), the Bay of Bengal forms the main part of its eastern boundary

But in the north east, as in the north west, India has again a land frontier The Himalayan ranges at their north eastern angle (in about lat 28° N, long 97° E.) throw off long spurs and chains to the southward These spurs separate the British Provinces of Assam and Eastern Bengal from Independent Burma They are known successively as the Abar, Nága, Patkoi, and Bárel ranges Turning almost due south in lat 25° , they culminate in the Blue Mountain, 7100 feet, in lat $22^{\circ} 37'$ N, long $93^{\circ} 10'$ E, and then stretch southwards under the name of the Arakan Yomas, separating British Burma from Independent Burma, until they again rise into the great mountain of Mýn matin (4700 feet) in $19\frac{1}{2}$ degrees of north latitude Up to this point, the eastern hill frontier runs in a southerly direction, and follows, generally speaking, the watershed which divides the river systems of Bengal and

¹ *Sí ju kí* Buddhist Records of the Western World, translated from the Chinese of Hsuen Tsiang by Samuel Beal Vol. I. p. 69 Trubner 1884

Tenasserim
boundary.

British Burma (namely, the Brahmaputra, Meghna, Kuladan, etc.) from the Irawadi basin in Independent Burma. But from near the base of the Myin-main Mountain, the British frontier stretches almost due east in a geographical line, which divides the lower Districts and delta of the Irawadi in British Burma, from the middle and upper Districts of that river in Independent Burma. Proceeding south-eastwards from the delta of the Irawadi, a confused succession of little explored ranges separates the British Province of Tenasserim from the Native Kingdom of Siam. The boundary line runs down to Point Victoria at the extremity of Tenasserim (lat. $9^{\circ} 59' N.$, long. $98^{\circ} 32' E.$), following the direction of the watershed between the rivers of the British territory on the west and of Siam on the east.

Physical
aspects.

The three
Regions
of India.

The Empire included within these boundaries is rich in varieties of scenery and climate, from the highest mountains in the world, to vast river deltas raised only a few inches above the level of the sea. It forms a continent rather than a country. But if we could look down on the whole from a balloon, we should find that India consists of three separate and well-defined tracts. The first includes the lofty Himálaya Mountains, which shut it out from the rest of Asia, and which, although for the most part beyond the British frontier, form a most important factor in the physical geography of Northern India. The second region stretches southwards from the base of the Himálayas, and comprises the plains of the great rivers which issue from them. The third region slopes upward again from the southern edge of the river plains, and consists of a high three-sided table-land, buttressed by the Vindhya Mountains on the north, and by the Eastern and Western Gháts which run down the coast on either side of India, till they meet at a point near Cape Comorin. The interior three-sided table-land, thus enclosed, is dotted with peaks and ranges, broken by river valleys, and interspersed by broad level uplands. It comprises the southern half of the peninsula.

First
Region—
The Himá-
layas.

The first of the three regions is the Himálaya Mountains and their offshoots to the southward. The Himálayas—literally, the 'Abode of Snow,' from the Sanskrit *hima*, frost (Latin, *hiems*, winter), and *álaya*, a house—consist of a system of stupendous ranges, the loftiest in the world. They are the *Emodus* or *Imaus* of the Greek geographers, and extend in the shape of a scimitar, with its edge facing southwards, for a distance of 1500 miles along the northern frontier of India. At the north-eastern angle of that frontier, the Dihang river,

the connecting link between the Tsan pu (Sangpu) of Tibet and the Brahmaputra of Assam, bursts through the main axis of the *Himálayas*. At the opposite or north western angle, the Indus in like manner pierces the *Himálayas*, and turns southwards on its course through the Punjab. The *Himálayas*, like the Kuen luen chain, the *Tián shan*, and the Hindu Kush, converge towards the Pamir table land—that central knot whence the great mountain systems of Asia radiate. With the Kuen luen the *Himálayas* have a closer connection, as these two mighty ranges form respectively the northern and southern buttresses of the lofty Tibetan plateau. The *Himalayas* project east and west beyond the Indian frontier. Their total length is about 1750 miles, and their breadth from north to south from 150 to 250 miles.¹

Regarded merely as a natural frontier separating India from the Tibetan plateau, the *Himalayas* may be described as a double mountain wall running nearly east and west, with a trough or series of deep valleys beyond. The southernmost of the two walls rises steeply from the plains of India to 20,000 feet, or nearly 4 miles, in height. It culminates in KANCHANJANGA, 28,176 feet, and MOUNT EVEREST, 29,002 feet, the latter being the loftiest measured peak in the world. This outer or southern wall of the *Himálayas* subsides on the northward into a series of dips or uplands, reported to be 13,000 feet above the level of the sea, beyond which rises the second or inner range of Himalayan peaks. The double *Himálayan* wall thus formed, then descends into a great trough or line of valleys, in which the Sutlej, the Indus, and the mighty Tsan pu (Sangpu) gather their waters.

The Sutlej and the Indus flow westwards, and pierce through the Western *Himalayas* by separate passes into the Punjab. The Tsan pu, after a long unexplored course eastwards along the valley of the same name in Tibet, finds its way through the Dihang gorge of the Eastern *Himálayas* into Assam, where it takes its final name of the Brahmaputra. On the north of the river trough, beyond the double *Himálayan* wall, rise the Karakoram and Gangri mountains, which form the immediate escarpment of the Tibetan table land. Behind the Gangris, on the north, the lake studded plateau of Tibet spreads itself out at a height averaging 15,000 feet. Broadly speaking, the double *Himálayan* wall rests upon the low lying plains of

¹ Some geographers hold that the *Himalayan* system stretches in a continuous chain westwards along the Oxus to 68° E long, and that only an arbitrary line can be drawn between the *Himalayan* ranges and the elevated regions of Tibet to the north of them.

India, and descends northward into a river trough beyond which rises the Tibetan plateau. Vast glaciers, one of which is known to be 60 miles in length, slowly move their masses of ice downwards to the valleys. The higher ranges between India and Tibet are crowned with eternal snow. They rise in a region of unbroken silence, like gigantic frosted fortresses one above the other, till their white towers are lost in the sky.

Himáláyan
passes.

This wild region is in many parts impenetrable to man, and nowhere yields a passage for a modern army. It should be mentioned, however, that the Chinese outposts extend as far as a point only 6000 feet above the Gangetic plain, north of Khatmandu. Indeed, Chinese armies have seriously threatened Khatmandu itself; and Sir David Ochterlony's advance from the plains of Bengal to that city in 1816 is a matter of history. Ancient and well-known trade routes exist, by means of which merchandise from the Punjab finds its way over heights of 18,000 feet into Eastern Túrkestán and Tibet. The Mustagh (Snowy Mount), the Karakoram (Black Mount), and the Chang-chenmo are among the most famous of these passes.

Offshoots
of the
Himá-
layas;
on east;

The Himálayas not only form a double wall along the north of India, but at both their eastern and western extremities send out ranges to the southwards, which protect India's north-eastern and north-western frontiers. On the north-east, those offshoots, under the name of the Nágá and Patkoi mountains, etc., form a barrier between the civilised British Districts and the wild tribes of Upper Burma. The southern continuations of these ranges, known as the Yomas, separate British from Independent Burma, and are crossed by passes, the most historic of which, the An or Aeng, rises to 4517 feet, with gradients of 472 feet to the mile.

and west.

On the opposite or north-western frontier of India, the mountainous offshoots run down the entire length of the British boundaries from the Himálayas to the sea. As they proceed southwards, their best marked ranges are in turn known as the Safed Koh, the Suláimán, and the Hála mountains. These massive barriers have peaks of great height, culminating in the Takht-i-Suláimán, or Throne of Solomon, 11,317 feet above the level of the sea. But, as already mentioned, the mountain wall is pierced at the corner where it strikes southwards from the Himálayas by an opening through which the Indus river flows into India. An adjacent opening, the KHAIBAR PASS (3400 feet above sea-level, amid neighbouring heights rising to 6800 feet), with the Kuram Pass on the south of it, the Gwalarí Pass near Dera Ismáíl Khán, the Tál Pass debouching near Dera

The Gate-
ways of
India.

Ghází Khán, and the famous Bolán Pass (5800 feet at top), still farther south, furnish the gateways between India and Afghanistan. The Hála, Brahui, and Pab mountains form the southern hilly offshoots between India and Baluchistan, but they have a much less elevation than the Safed Koh or the Suláiman.

The Himalayas, while thus standing as a rampart and strong defence around the northern frontier of India, collect and store up water for the tropical plains below. Throughout the summer, vast quantities of water are exhaled from the Indian Ocean. This moisture gathers into vapour, and is borne northward by the monsoon or regular wind, which sets in from the south in the month of June. The monsoon carries the water-laden clouds northwards across India, and thus produces the 'rainy season, on which agriculture so critically depends. But large quantities of the moisture do not condense or fall as rain in passing over the hot plains. This vast residue is eventually dashed against the Himalayas. Their lofty double walls stop its farther progress northwards, and it either descends in rain on their outer slopes, or is frozen into snow in its attempt to cross their inner heights. Very little gets beyond them, so that while the southern spurs of the Himalayas receive the largest measured rainfall in the world, and pour it down to the Indian rivers, the great plateau of Tibet on the north of the double Himálayan wall gets scarcely any rainfall.

At Cherra Punji, where the monsoon first strikes the hills in Assam, 489 inches of rain, according to returns for 25 years ending 1881, fall annually. In one year (1861) as many as 805 inches were reported, of which 366 inches fell in the single month of July. While, therefore, the yearly rainfall in London is about 2 feet, and that of the plains of India from 1 to 6 feet, the rainfall at Cherra Punji is 40 feet, a depth more than is required to float the largest man of war, and in one year, 67 feet of water fell from the sky, or sufficient to drown a three-storied house. The mighty mountains that wall in India on the north form, in fact, a rain-screen which catches the vapour-clouds from the Southern Ocean, and condenses them for the hot Bengal plains. The outer slopes of the Himalayas swell the Indian rivers by their torrents during the rainy season, their inner ranges and heights store up the rainfall in the shape of snow, and thus form a vast reservoir for the steady supply of the Indian rivers throughout the year.

This heavy rainfall renders the southern slopes of the Himalayas very fertile, wherever there is any depth of tith scenery.

millet and small grains. Vegetables are also raised on a large scale. The potato, introduced from England, is a favourite crop, and covers many sites formerly under forest.

The hillman clears his potato ground by burning a ring round the stems of the great trees, and then lays out the side of the mountain into terraces. After a few years the bark and leaves drop off the branches, and the forest stands bleached and ruined. Some of the trees rot on the ground, like giants fallen in confused flight, others still remain upright, with white trunks and skeleton arms. In the end the rank green potato crop marks the spot where a forest has been slain and buried. Several of the ruder hill tribes follow an even more wasteful mode of tillage. Destitute of either ploughs or oxen, they burn down the jungle, and exhaust the soil by a quick succession of crops, raised by the hoe. In a year or two the whole settlement moves off to a fresh patch of jungle, which they clear and exhaust, and then desert in like manner.

Rice is only grown in the Himalayas on ground which has an unfailing command of water—particularly in the damp hot valleys between the successive ranges which roll upwards into the interior. The hillmen practise an ingenious system of irrigation, according to which the slopes are laid out in terraces, and the streams are diverted to a great distance by successive parallel channels along the mountain side. They also utilize their water power for mill purposes. Some of them are ignorant of cog wheels for converting the vertical movement of the mill wheel into the horizontal movement required for the grindingstone. They therefore place their mill wheel flat instead of upright, and lead the water so as to dash with great force on the horizontal paddles. A horizontal rotary movement is thus obtained, and conveyed direct by the axle to the millstone above.

The chief saleable products of the Himalayas are timber, charcoal, barley, millets, potatoes, other vegetables, honey, jungle products, borax, and several kinds of inferior gems. Strings of ponies and mules straggle with their burdens along the narrow pathways, which are at many places mere ledges cut out of the precipice. The hillmen and their hard working wives load themselves also with pine stems and conical baskets of grain. The yak cow and hardy mountain sheep are the favourite beasts of burden in the inner ranges. The little yak cow, whose bushy tail is manufactured in Europe into lace, patiently toils up the steepest gorges with a heavy burden on her back. The sheep, laden with bags of borax, are driven

Clearing a
hill forest

Irrigation
and mill
power

Himalayan
saleable
produce

to marts on the outer ranges near the plains, where they are shorn of their wool, and then return into the interior with a load of grain or salt. Hundreds of them, having completed their journey from the upper ranges, are sold for slaughter at a nominal price of perhaps a shilling a-piece, as they are not worth taking back to the inner mountains.

Himálayan
animals
and tribes.

The characteristic animals of the Himálayas include the yak-cow, musk-deer, several kinds of wild sheep and goat, bear, ounce, leopard, and fox ; the eagle, great vultures, pheasants of beautiful varieties, partridges, and other birds. Ethnologically, the Himálayas form the meeting-ground of the Aryan and Turanian races, which in some parts are curiously mingled, although generally distinguishable. The tribes or broken clans of non-Aryan origin number over fifty, with languages, customs, and religious rites more or less distinct. The lifelong labours of Mr. Brian Houghton Hodgson, of the Bengal Civil Service, have done much to illustrate the flora, fauna, and ethnology of the Himálayas ; and no sketch of this region would be complete without a reference to Mr. Hodgson's work.

Second
Region of
India—
The
northern
River
Plains.

The wide plains watered by the Himálayan rivers form the second of the three regions into which India is divided. They extend from the Bay of Bengal on the east, to the Afghán frontier and the Arabian Sea on the west, and contain the richest and most densely-crowded Provinces of the Empire. One set of invaders after another have, from pre-historic times, entered by the passes on the north-eastern and north-western frontiers of India. They followed the courses of the rivers, and pushed the earlier comers southwards before them towards the sea. About 150 millions of people now live on and around these river plains in the Provinces known as the Lieutenant-Governorship of Bengal, Assam, the North-Western Provinces, Oudh, the Punjab, Sind, Rájputána and other Native States.

The three
River
systems of
N. India.
(1) The
Indus,
with the
Sutlej.
(2) The
Tsan-pu or
Brahma-
putra.

The vast level tract which thus covers Northern India is watered by three distinct river systems. One of these river systems takes its rise in the hollow trough beyond the Himálayas, and issues through their western ranges upon the Punjab as the Indus and Sutlej. The second of the three river systems also takes its rise beyond the double wall of the Himálayas, not very far from the sources of the Indus and the Sutlej. It turns, however, almost due east instead of west, enters India at the eastern extremity of the Himálayas and becomes the Brahmaputra of Assam and Eastern Bengal. These rivers

collect the drainage of the northern slopes of the Himálayas, and convey it, by long, tortuous, and opposite routes, into India. Indeed, the special feature of the Himálayas is that they send down the rainfall from their northern as well as from their southern slopes to the Indian plains. Of the three great rivers of Northern India, the two longest, namely the Indus with its feeder the Sutlej, and the Brahmaputra, take their rise in the trough on the north of the great Himálayan wall. That trough receives the drainage of the inner or northern escarpment of the Himálayas, together with such water supply as emerges from the outer or southern escarpment of the lofty but almost rainless plateau of Tibet.

The third river system of Northern India receives the drainage of the outer or southern Himalayan slopes, and unites into the mighty stream of the Ganges. In this way, the rainfall, alike from the northern and southern slopes of the Himalayas, and even from the mountain buttresses of the Tibet plateau beyond, pours down upon the plains of India. The long and lofty spur of the outer Himálayas, on which stands Simla, the summer residence of the Government of India, forms the watershed between the river systems of the Indus and Ganges. The drainage from the west of this narrow ridge below the Simla Church flows into the Arabian Sea, while that which starts a few feet off, down the eastern side, eventually reaches the Bay of Bengal.

The INDUS (Sanskrit, *Sindhus*, Ἰνδός, Σινδός) rises in an unexplored region (lat 32° N, long 81° E) on the slopes of the sacred Kailás mountain, the Elysium or Siva's Paradise of ancient Sanskrit literature. The Indus has an elevation of about 16,000 feet at its source in Tibet, a drainage basin of 372,700 square miles, and a total length of over 1800 miles. Shortly after it passes within the Kashmír frontier, it drops to 14,000 feet, and at Leh is only about 11,000 feet above the level of the sea. The rapid stream dashes down ravines and wild mountain valleys, and is subject to tremendous floods. The Indus bursts through the western ranges of the Himálayas by a wonderful gorge near Iskardoh, in North Western Kashmír—a gorge reported to be 14,000 feet in sheer depth.

Its great feeder, the SUTLEJ, rises on the southern slopes of the Kailas mountain, also in Tibet. It issues from one of the sacred lakes, the Mánasarowar and Ravana hráda (the modern Rákhás Tál), famous in Hindu mythology, and still the resort of the Tibetan shepherds. Starting at an elevation of 15,200 feet, the Sutlej passes south west across the plain of

Gugé, where it has cut through a vast accumulation of deposits by a gully said to be 4000 feet deep, between precipices of alluvial soil. After traversing this plain, the river pierces the Himálayas by a gorge with mountains rising to 20,000 feet on either side. The Sutlej is reported to fall from 10,000 feet above sea-level at Shipki, a Tibetan frontier outpost, to 3000 feet at Rámpur, the capital of a Himálayan State about 60 miles inward from Simla. During this part of its course, the Sutlej runs at the bottom of a deep trough, with precipices and bare mountains which have been denuded of their forests, towering above. Its turbid waters, and their unceasing roar as the river dashes over the rapids, have a gloomy and disquieting effect. Sometimes it grinds to powder the huge pines and cedars entrusted to it to float down to the plains. By the time it reaches Biláspur, it has dropped to 1000 feet above sea-level. After entering British territory, the Sutlej receives the waters of the Western Punjab, and falls into the Indus near Mithánkot, after a course of 900 miles.

Lower
course of
Indus.

A full account of the Indus will be found in the article on that river in volume vii. of *The Imperial Gazetteer of India*. About 800 miles of its course are passed among the Himálayas before it enters British territory, and it flows for about 1000 miles more, south-west, through the British Provinces of the Punjab and Sind. In its upper part it is fordable in many places during the cold weather; but it is liable to sudden freshets, in one of which Ranjít Singh is said to have lost a force, variously stated at from 1200 to 7000 horsemen, while crossing by a ford. A little way above Attock, the Indus receives the Kábul river, which brings down the waters of Northern Afghánistán. The volume of those waters, as represented by the Kábul river, is about equal to the volume of the Indus at the point of junction. At Attock, the Indus has fallen, during a course of 860 miles, from its elevation of 16,000 feet at its source in Tibet to under 2000 feet. These 2000 feet supply its fall during the remaining 940 miles of its course.

The discharge of the Indus, after receiving all its tributaries, varies from 40,857 to 446,086 cubic feet per second, according to the season of the year. The enormous mass of water spreads itself over a channel of a quarter of a mile to a mile (or at times much more) in breadth. The effect produced by the evaporation from this fluvial expanse is so marked that, at certain seasons, the thermometer is reported to be 10° F. lower close to its surface than on the surrounding arid plains. The Indus supplies a precious store of water

for irrigation works at various points along its course, and forms the great highway of the Southern Punjab and Sind. In its lower course it sends forth distributaries across a wide delta, with Haidarabad (Hyderabad) in Sind as its ancient political capital, and Karachi (Kurrachee) as its modern port. The silt which it carries down has helped to form the seaboard islands, mud banks, and shallows, that have cut off the ancient famous emporia around the Gulf of Cambay from modern commerce.

The BRAHMAPUTRA, like the Sutlej, rises near to the sacred lake of Mánasarowar. Indeed, the Indus, the Sutlej, and the Brahmaputra may be said to start from the same water parting. The Indus rises on the western slope of the Kailas mountain, the Sutlej on its southern, and the Brahmaputra at some distance from its eastern base. The Mariam la and other saddles connect the more northern Tibetan mountains, to which the Kailás belongs, with the double Himálayan wall on the south. They form an irregular watershed across the trough on the north of the double wall of the Himálayas, thus, as it were, blocking up the western half of the great Central Asian trench. The Indus flows down a western valley from this transverse watershed, the Sutlej finds a more direct route to India by a south western valley. The Brahmaputra, under its Tibetan name of Tsan pu or Sangpu, has its source in 31° N. lat and 83° E. long. It flows eastwards down the Tsan pu valley, passing not very far to the south of Lhasa, the capital of Tibet, and probably 800 to 900 miles, or about one half of its total course, are spent in the hollow trough on the north of the Himálayas. This brief account assumes that the Brahmaputra of India is the true continuation of the Sangpu of Tibet. The result of the latest researches into that long mooted question are given under article BRAHMAPUTRA, in volume III of *The Imperial Gazetteer of India*.

After receiving several tributaries from the confines of the Chinese Empire, the river twists round a lofty eastern range of the Himálayas, and enters British territory under the name of the DIHANG, near Sadiyá in Assam. It presently receives two confluent rivers, the DIHANG river from the northward, and the Brahmaputra proper from the east (lat $27^{\circ} 20'$ N., long $95^{\circ} 50'$ E.). The united stream then takes its well known appellation of the Brahmaputra, literally the 'Son of Brahma the Creator'. It represents a drainage basin of 361,200 square miles, and its summer discharge at Goalpara in Assam was

for long computed at 146,188 cubic feet of water per second. Recent measurements have, however, shown that this calculation is below the truth. Observations made near Dibrugarh during the cold weather of 1877-78, returned a mean low-water discharge of 116,484 cubic feet per second for the Brahmaputra at the upper end of the Assam valley, together with 16,945 cubic feet per second for its tributary the SUBANSIRI. Total cold-weather discharge for the united stream, over 133,000 cubic feet per second near Dibrugarh. Several affluents join the Brahmaputra during its course through Assam; and the mean low-water discharge at Goálpára, in the lower end of the Assam valley, must be in excess of the previous computation at 146,188 cubic feet per second. During the rains the channel rises 30 or 40 feet above its ordinary level, and its flood discharge is estimated at over 500,000 cubic feet per second.

Brahma-
putra silt.

The Brahmaputra rolls down the Assam valley in a vast sheet of water, broken by numerous islands, and exhibiting the operations of alluvion and diluvion on a gigantic scale. It is so heavily freighted with silt from the Himálayas, that the least impediment placed in its current causes a deposit, and may give rise to a wide-spreading, almond-shaped mud-bank. Steamers anchoring near the margin for the night sometimes find their sterns aground next morning on an accumulation of silt, caused by their own obstruction to the current. Broad divergent channels split off from the parent stream, and rejoin it after a long separate existence of uncontrollable meandering. By centuries of alluvial deposit, the Brahmaputra has raised its banks and channel in parts of the Assam valley to a higher level than the surrounding country. Beneath either bank lies a low strip of marshy land, which is flooded in the rainy season. Beyond these swamps, the ground begins to rise towards the hills that hem in the valley of Assam on both sides.

The
Brahma-
putra in
Bengal.

After a course of 450 miles south-west down the Assam valley, the Brahmaputra sweeps round the spurs of the Gáo Hills due south towards the sea. It here takes the name of the Jamuná, and for 180 miles rushes across the level plains of Eastern Bengal, till it joins the Ganges at Goálanda (lat. $23^{\circ} 50' N.$, long. $89^{\circ} 46' E.$). From this point the deltas of the two great river systems of the Ganges and the Brahmaputra unite into one. But before reaching the sea, their combined streams have yet to receive, by way of the CACHAR valley, the drainage of the eastern watershed between Bengal and Burma,

(Jamuná
and
Meghná.)

under the name of the MEGHNA river, itself a broad and magnificent sheet of water.

The Brahmaputra is famous not only for its vast alluvial deposits, but also for the historical changes which have taken place in its course. One of the islands (the Májulī *char*), which it has created in its channel out of the silt torn away from the distant Himálayas, covers 441 square miles. Every year, thousands of acres of new land are thus formed out of mud and sand, some of them destined to be swept away by the inundations of the following year, others to become the homes of an industrious peasantry or the seats of busy river marts. Such formations give rise to changes in the bed of the river—changes which within a hundred years have completely altered the course of the Brahmaputra through Bengal. In the last century, the stream, on issuing from Assam, bent close round the spurs of the Garo Hills in a south easterly direction. This old bed of the Brahmaputra, the only one recognised by Major Rennel in 1765-75, has now been deserted. It retains the ancient name of the Brahmaputra, but during the hot weather it is little more than a series of pools. The modern channel, instead of twisting round the Garo Hills to the east, bursts straight southwards towards the sea under the name of the Jamuna, and is now separated at places by nearly 100 miles of level land from the main channel in the last century. A floating log thrown up against the bank, a sunk boat, or any smallest obstruction, may cause the deposit of a mud island. Every such silt bank gives a more or less new direction to the main channel, which in a few years may have eaten its way far across the plain, and dug out for itself a new bed at a distance of several miles. Unlike the Ganges and the Indus, the Brahmaputra is not used for artificial irrigation. But its silt charged overflow annually replenishes the land. Indeed, the plains of Eastern Bengal watered by the Brahmaputra yield unfailling harvests of rice, mustard, oil seeds, and the exhausting jute crop, year after year, without any deterioration. The valley of the Brahmaputra in Assam is not less fertile, although inhabited by a less industrious race.

The Brahmaputra is the great high road of Eastern Bengal and Assam. Its tributaries and bifurcations afford innumerable waterways, almost superseding roads, and at the same time rendering road construction and maintenance very difficult. The main river is navigable by steamers as high up as DIBRUGARH, about 800 miles from the sea, and its broad surface is crowded with country craft of all sizes and rigs, from

Brahma
putra silt
islands

Great
changes in
its course

The
Brahma
putra as a
high road

the dug-out canoe and timber raft to the huge cargo ship, with its high bow and carved stern, its bulged-out belly, and spreading square-sails. The busy emporium of SIRAJGANJ, on the western bank of the Brahmaputra, collects the produce of the Districts for transmission to Calcutta. Fifty thousand native craft, besides steamers, passed Sirájganj in 1876.

Brahma-
putra
traffic.

The downward traffic consists chiefly of tea (to the value of about $1\frac{1}{2}$ million sterling), timber, caoutchouc, and raw cotton, from Assam; with jute, oil-seeds, tobacco, rice, and other grains, from Eastern Bengal. In return for these, Calcutta sends northwards by the Brahmaputra, European piece-goods, salt, and hardware; while Assam imports from the Bengal delta, by the same highway, large quantities of rice (amounting to 14,749 tons in 1883-84) for the labourers on the tea plantations. The total value of the river-borne trade of the Brahmaputra was returned at a little over three millions sterling in 1882-83. But it is impossible to ascertain the whole produce carried by the innumerable native boats on the Brahmaputra. The railway system of India taps the Brahmaputra at Goálanda and Dhubri; while a network of channels through the Sundarbans supply a cheaper means of water transit for bulky produce across the delta to Calcutta.

The
Gangetic
river
system.

As the Indus, with its feeder the Sutlej, and the Brahmaputra, convey to India the drainage from the northern or Tibetan slopes of the Himálayas, so the GANGES, with its tributary the Jumna, collects the rainfall from the southern or Indian slopes of the mountain wall, and pours it down upon the plains of Bengal. The Ganges traverses the central part of those plains, and occupies a more prominent place in the history of Indian civilisation than either the Indus in the extreme west, or the Brahmaputra in the extreme east of Hindustán. It passes its whole life to the south of the Himálayas, and for thousands of years has formed an overruling factor in the development of the Indian races.

The Ganges issues, under the name of the Bhágíráthí, from an ice-cave at the foot of a Himálayan snowbed, 13,800 feet above the sea-level (lat. $30^{\circ} 56' 4''$ N., long. $79^{\circ} 6' 40''$ E.). After a course of 1557 miles, it falls by a network of estuaries into the Bay of Bengal. It represents, with its tributaries, an enormous catchment basin, bounded on the north by a section of about 700 miles of the Himálayan ranges, on the south by the Vindhya mountains, and embracing 391,100 square miles. Before attempting a description of the functions performed by

the Ganges, it is necessary to form some idea of the mighty masses of water which it collects and distributes. But so many variable elements affect the discharge of rivers, that calculations of their volume must be taken merely as estimates.

At the point where it issues from its snow-beds the infant stream ^{The} is only 27 feet broad and 15 inches deep, with an elevation of ^{growth} 13,800 feet above sea level. During the first 180 miles of its ^{of the} course, it drops to an elevation of 1024 feet. At this point, Hardwar, its lowest discharge, in the dry season, is 7000 cubic feet per second. Hitherto the Ganges has been little more than a snow-fed Himalayan stream. During the next thousand miles of its journey, it collects the drainage of its catchment basin, and reaches Rajmahal about 1180 miles from its source. It has here, while still about 400 miles from the sea, a high ^{Discharge} flood discharge of 1,800,000 cubic feet of water per second, ^{of Gan- ges} and an ordinary discharge of 207,000 cubic feet, longest duration of flood, about forty days. The maximum discharge of the Mississippi is given at 1,200,000 cubic feet per second¹. The maximum discharge of the Nile at Cairo is returned at only 362,200 cubic feet and of the Thames at Staines at 6600 cubic feet of water per second. The Meghna, one of the many outflows of the Ganges, is 20 miles broad near its mouth, with a depth, in the dry season, of 30 feet. But for a distance of about 200 miles, the sea-face of Bengal entirely consists of the estuaries of the Ganges, intersected by low islands and promontories, formed out of its silt.

In forming our ideas with regard to the Ganges, we must ^{The} begin by dismissing from our minds any lurking comparison of ^{Jumna} its gigantic stream with the rivers which we are familiar with in England. A single one of its tributaries, the JUMNA, has an independent existence of 860 miles, with a catchment basin of 118,000 square miles, and starts from an elevation at its source of 10,849 feet above sea level. The Ganges and its principal tributaries are treated of in *The Imperial Gazetteer of India*, in separate articles under their respective names. The following account confines itself to a brief sketch of the work which these Gangetic rivers perform in the plains of Northern India, and of the position which they hold in the thoughts of the people.

Of all great rivers on the surface of the globe, none can ^{Sanctity} compare in sanctity with the Ganges, or Mother Ganga, as she ^{of the} is affectionately called by devout Hindus. From her source in ^{Ganges}

¹ *Hydraulic Manual*, by Lewis D. Jackson, Hydraulic Statistics, Table 11, Appendix, p. 2 (1875)

the dug-out canoe and timber raft to the huge cargo ship, with its high bow and carved stern, its bulged-out belly, and spreading square-sails. The busy emporium of SIRAJGANJ, on the western bank of the Brahmaputra, collects the produce of the Districts for transmission to Calcutta. Fifty thousand native craft, besides steamers, passed Sirájganj in 1876.

Brahma-
putra
traffic.

The downward traffic consists chiefly of tea (to the value of about $1\frac{1}{2}$ million sterling), timber, caoutchouc, and raw cotton, from Assam; with jute, oil-seeds, tobacco, rice, and other grains, from Eastern Bengal. In return for these, Calcutta sends northwards by the Brahmaputra, European piece-goods, salt, and hardware; while Assam imports from the Bengal delta, by the same highway, large quantities of rice (amounting to 14,749 tons in 1883-84) for the labourers on the tea plantations. The total value of the river-borne trade of the Brahmaputra was returned at a little over three millions sterling in 1882-83. But it is impossible to ascertain the whole produce carried by the innumerable native boats on the Brahmaputra. The railway system of India taps the Brahmaputra at Goálanda and Dhubrí; while a network of channels through the Sundarbans supply a cheaper means of water transit for bulky produce across the delta to Calcutta.

The
Gangetic
river
system.

As the Indus, with its feeder the Sutlej, and the Brahmaputra, convey to India the drainage from the northern or Tibetan slopes of the Himálayas, so the GANGES, with its tributary the Jumna, collects the rainfall from the southern or Indian slopes of the mountain wall, and pours it down upon the plains of Bengal. The Ganges traverses the central part of those plains, and occupies a more prominent place in the history of Indian civilisation than either the Indus in the extreme west, or the Brahmaputra in the extreme east of Hindustán. It passes its whole life to the south of the Himálayas, and for thousands of years has formed an overruling factor in the development of the Indian races.

The Ganges issues, under the name of the Bhágíráthí, from an ice-cave at the foot of a Himálayan snowbed, 13,800 feet above the sea-level (lat. $30^{\circ} 56' 4''$ N., long. $79^{\circ} 6' 40''$ E.). After a course of 1557 miles, it falls by a network of estuaries into the Bay of Bengal. It represents, with its tributaries, an enormous catchment basin, bounded on the north by a section of about 700 miles of the Himálayan ranges, on the south by the Vindhya mountains, and embracing 391,100 square miles. Before attempting a description of the functions performed by

the Ganges, it is necessary to form some idea of the mighty masses of water which it collects and distributes. But so many variable elements affect the discharge of rivers, that calculations of their volume must be taken merely as estimates.

At the point where it issues from its snowbed the infant stream ^{The growth of the Ganges} is only 27 feet broad and 15 inches deep, with an elevation of 13,800 feet above sea level. During the first 180 miles of its course, it drops to an elevation of 1024 feet. At this point, Hardwar, its lowest discharge, in the dry season, is 7000 cubic feet per second. Hitherto the Ganges has been little more than a snow fed Himalayan stream. During the next thousand miles of its journey, it collects the drainage of its catchment basin, and reaches Rájmahal about 1180 miles from its source. It has here, while still about 400 miles from the sea, a high ^{Discharge of Ganges} flood discharge of 1,800,000 cubic feet of water per second, and an ordinary discharge of 207 000 cubic feet, longest duration of flood, about forty days. The maximum discharge of the Mississippi is given at 1,200 000 cubic feet per second¹. The maximum discharge of the Nile at Cairo is returned at only 362,200 cubic feet, and of the Thames at Staines at 6600 cubic feet of water per second. The Meghna, one of the many outflows of the Ganges, is 20 miles broad near its mouth, with a depth, in the dry season, of 30 feet. But for a distance of about 200 miles, the sea face of Bengal entirely consists of the estuaries of the Ganges, intersected by low islands and promontories, formed out of its silt.

In forming our ideas with regard to the Ganges, we must ^{The} begin by dismissing from our minds any lurking comparison of ^{Jumna} its gigantic stream with the rivers which we are familiar with in England. A single one of its tributaries, the JUMNA, has an independent existence of 860 miles, with a catchment basin of 118,000 square miles, and starts from an elevation at its source of 10,849 feet above sea level. The Ganges and its principal tributaries are treated of in *The Imperial Gazetteer of India*, in separate articles under their respective names. The following account confines itself to a brief sketch of the work which these Gangetic rivers perform in the plains of Northern India, and of the position which they hold in the thoughts of the people.

Of all great rivers on the surface of the globe, none can ^{Sanctity of the Ganges} compare in sanctity with the Ganges, or Mother Gangá, as she is affectionately called by devout Hindus. From her source in

¹ *Hydraulic Manual*, by Lewis D.A. Jackson. Hydraulic Statistics, Table II., Appendix, 1. 2 (1875)

the Himálayas, to her mouth in the Bay of Bengal, her banks are holy ground. Each point of junction of a tributary with the main stream has its own special claims to sanctity. But the tongue of land at Allahábád, where the Ganges unites with her great sister river the Jumna, is the true *Prayág*, the place of pilgrimage whither hundreds of thousands of devout Hindus repair to wash away their sins in her sanctifying waters. Many of the other holy rivers of India borrow their sanctity from a supposed underground connection with the Ganges. This fond fable recalls the primitive time when the Aryan race was moving southward from the Gangetic plains. It is told not only of first-class rivers of Central and Southern India, like the Narbadá, but also of many minor streams of local sanctity.

Legend
of the
Ganges.

An ancient legend relates how Gangá, the fair daughter of King Himálaya (Himávat) and of his queen the air-nymph Menaka, was persuaded, after long supplication, to shed her purifying influence upon the sinful earth. The icicle-studded cavern from which she issues is the tangled hair of the god Siva. Loving legends hallow each part of her course; and from the names of her tributaries and of the towns along her banks, a whole mythology might be built up. The southern offshoots of the Aryan race not only sanctified their southern rivers by a fabled connection with the holy stream of the north. They also hoped that in the distant future, their rivers would attain an equal sanctity by the diversion of the Ganges' waters through underground channels. Thus, the Bráhmans along the Narbadá maintain that in this evil age of the world (indeed, about the year 1894 A.D.), the sacred character of the Ganges will depart from that polluted stream, and take refuge by an underground passage in their own river.

Gangetic
pilgrim-
ages.

The estuary of the Ganges is not less sacred than her source. Sagar Island at her mouth is annually visited by a vast concourse of pilgrims, in commemoration of her act of saving grace; when, in order to cleanse the 60,000 damned ones of the house of Sagar, she divided herself into a hundred channels, thus making sure of reaching their remains, and so forming the delta of Bengal. The six years' pilgrimage from her source to her mouth and back again, known as *pradakshina*, is still performed by many; and a few devotees may yet be seen wearily accomplishing the meritorious penance of 'measuring their length' along certain parts of the route. To bathe in the Ganges at the stated festivals washes away guilt, and those who have thus purified themselves carry back bottles of her water to their kindred in far-off provinces.

To die and to be cremated on the river bank, and to have their ashes borne seaward by her stream, is the last wish of millions of Hindus. Even to ejaculate 'Ganga, Ganga,' at the distance of 100 leagues from the river, say her more enthusiastic devotees, may atone for the sins committed during three previous lives.

The Ganges has earned the reverence of the people by centuries of unfailling work done for them. She and her tributaries are the unwearied water carriers for the densely peopled provinces of Northern India and the peasantry reverence the bountiful stream which fertilizes their fields and distributes their produce. None of the other rivers of India comes near to the Ganges in works of beneficence. The Brahmaputra and the Indus have longer streams as measured by the geographer, but their upper courses lie beyond the great mountain wall in the unknown recesses of the Himalayas.

Not one of the rivers of Southern India is navigable in the proper sense. The Ganges begins to distribute fertility by irrigation as soon as she reaches the plains, within 200 miles of her source, and at the same time her channel becomes in some sort navigable. Thenceforward she rolls majestically down to the sea in a bountiful stream, which never becomes a merely destructive torrent in the rains, and never dwindles away in the hottest summer. Tapped by canals, she distributes millions of cubic feet of water every hour in irrigation, but her diminished volume is promptly recruited by great tributaries and the wide area of her catchment basin renders her stream inexhaustible in the service of man. Embankments are in but few places required to restrain her inundations, for the alluvial silt which she spills over her banks affords in most parts a top dressing of inexhaustible fertility. If one crop be drowned by the flood, the peasant comforts himself with the thought that the next crop from his silt manured fields will abundantly requite him. The function of the Ganges as a land maker on a great scale will be explained hereafter.

The Ganges has also played a pre-eminent part in the commercial development of Northern India. Until the opening of the railway system, 1855 to 1870, her magnificent stream formed almost the sole channel of traffic between Upper India and the seaboard. The products not only of the river plains, but even the cotton of the Central Provinces, were formerly brought by this route to Calcutta. Notwithstanding the revolution caused by the railways, the heavier and more

Work
done by
the
Ganges,

The water
carrier and
fertilizer
of Bengal

The
Ganges
the great
highway
of Bengal

bulky staples are still conveyed by the river, and the Ganges may yet rank as one of the greatest waterways in the world.

Traffic
on the
Ganges.

The upward and downward trade of the interior with Calcutta alone, by the Gangetic channels, was valued in 1881 at over 20 millions sterling. This is exclusive of the sea-borne commerce. At Bámanghâta, on one of the canals east of Calcutta, 178,627 cargo boats were registered in 1876-77; at Húglí, a river-side station on a single one of the many Gangetic mouths, 124,357; and at Patná, 550 miles from the mouth of the river, the number of cargo boats entered in the register was 61,571. The port of Calcutta is itself one of the world's greatest emporia for sea and river borne commerce. Its total exports and imports landward and seaward amounted in 1881 to about 140 millions sterling.

Not
diminished
by the
railway.

Articles of European commerce, such as wheat, indigó, cotton, opium, and saltpetre, prefer the railway; so also do the imports of Manchester piece-goods. But if we take into account the vast development in the export trade of oil-seeds, rice, etc., still carried by the river, and the growing interchange of food-grains between various parts of the country, it seems probable that the actual amount of traffic on the Ganges has increased rather than diminished since the opening of the railways. At well-chosen points along her course, the iron lines touch the banks, and these river-side stations form centres for collecting and distributing the produce of the surrounding country. The Ganges, therefore, is not merely a rival, but a feeder, of the railway. Her ancient cities, such as ALLAHABAD, BENARES, and PATNA, have thus been able to preserve their former importance; while fishing villages like SAHIBGANJ and GOALANDA have been raised into thriving river marts.

The great
Gangetic
cities.

For, unlike the Indus and the Brahmaputra, the Ganges is a river of great historic cities. CALCUTTA, PATNA, and BENARES are built on her banks; AGRA and DELHI on those of her tributary, the Jumna; and ALLAHABAD on the tongue of land where the two sister streams unite. Many millions of human beings live by commerce along her margin. Calcutta, with its suburbs on both sides of the river, contains a population of over $\frac{3}{4}$ of a million. It has a municipal revenue of £270,000 to £290,000; a sea-borne and coasting commerce of about 65 millions sterling, with a landward trade of 75 millions sterling. These figures vary from year to year, but show a steady increase. Calcutta lies on the HUGLI, the most westerly of the mouths by which the Ganges enters the sea. To the eastwards stretches the delta, till it is hemmed

Calcutta.

in on the other side by the MEGHNA, the most easterly of the mouths of the Ganges, or rather the vast estuary by which the combined waters of the Brahmaputra and Gangetic river systems find their way into the Bay of Bengal

In order, therefore, to understand the plains of Northern India, we must have a clear idea of the part played by the great rivers, for the rivers first create the land, then fertilize it, and finally distribute its produce. The plains of Bengal were in many parts upheaved by volcanic forces, or deposited in an aqueous era, before the present race of man appeared. But in other parts they have been formed out of the silt which the rivers bring down from the mountains, and at this dry we may stand by and watch the ancient process of land making go on.

A great Indian river like the Ganges has three distinct stages in its career from the Himalayas to the sea. In the first stage of its course, it dashes down the Himalayas, cutting out for itself deep gullies in the solid rock, ploughing up glens between the mountains, and denuding the hillsides of their soil. In wading over the Sutlej feeders among the hills in the rainy season the ankles are sore from the pebbles which the stream carries with it, while even in the hot weather, the rushing sand and gravel cause a prickly sensation across the feet.

The second stage in the life of an Indian river begins at the point where it emerges from the mountains upon the plains. It then runs peacefully along the valleys, searching out for itself the lowest levels. It receives the drainage and mud of the country on both sides, absorbs tributaries, and rolls forward with an ever increasing volume of water and silt. Every torrent from the Himalayas brings its separate contribution of new soil, which it has torn from the rocks or eroded from its banks. This process repeats itself through out more than ten thousand miles, that is to say, down the course of each tributary from the Himalayas or Vindhya, and across the plains of Northern India. During the second stage of the life of a Bengal river, therefore, it forms a great open drain, which gradually deepens itself by erosion of its channel. As its bed thus sinks lower and lower, it draws off the water from swamps or lakes in the surrounding country. Dry land takes the place of fens, and in this way the physical configuration of Northern India has been greatly altered, even since the Greek descriptions 2000 years ago.

As long as the force of the current is maintained by a

First and second stages of a great river, as a silt-collector.

sufficient fall per mile, the river carries forward the silt thus supplied, and adds to it fresh contributions from its banks. Each river acquires a character of its own as it advances, a character which tells the story of its early life. Thus, the Indus is loaded with silt of a brown hue; the Chenáb has a reddish tinge; while the Sutlej is of a paler colour. The exact amount of fall required per mile depends upon the specific gravity of the silt which it carries. At a comparatively early stage, the current drops the heavy particles of rock or sand which it has torn from the Himálayan precipices. But a fall of 5 inches per mile suffices to hold in suspension the great body of the silt, and to add further accretions in passing through alluvial plains. The average fall of the Ganges between Benares and the delta-head (about 461 miles) is nearly 5 inches per mile. In its upper course its average declivity is much greater, and suffices to bear along and pulverize the heavier spoils torn from the Himálayas.

Loss of carrying power.

By the time the Ganges reaches its delta in Lower Bengal (Colgong to Calcutta), its average fall per mile has dropped to 4 inches. From Calcutta to the sea the fall varies in the numerous distributaries of the parent stream, according to the tide, from 1 to 2 inches. In the delta the current seldom suffices to carry the burden of its silt, except during the rains, and so deposits it.¹

Third stage of an Indian river, as a land-maker.

In Lower Bengal, therefore, the Ganges enters on the third stage of its life. Finding its speed checked by the equal level of the plains, and its bed raised by the deposit of its own silt, it splits out into channels, like a jet of water suddenly obstructed by the finger, or a jar of liquid dashed on the ground. Each of the new streams thus created throws out in turn its own set of distributaries to right and left. The country which their many offshoots enclose and intersect forms

¹ The following facts may be useful to observers in Bengal who wish to study the most interesting feature of the country in which they live, namely the rivers. Ten inches per mile is considered to be the fall which a navigable river should not exceed. The average fall of the Ganges from the point where it unites with the Jumna at Allahábád to Benares (139 miles), is 6 inches per mile; from Benares to Colgong (326 miles), 5 inches per mile; from Colgong to the delta-head, where the Bhágirathí strikes off (about 135 miles), 4 inches per mile; from the delta-head to Calcutta (about 200 miles), also 4 inches per mile; from Calcutta to the sea *viâ* the Húglí (about 80 miles), 1 to 2 inches per mile, according to the tide. The fall of the Nile from the first Cataract to Cairo (555 miles), is $6\frac{1}{2}$ inches per mile; from Cairo to the sea, it is very much less. The fall of the Mississippi for the first hundred miles from its mouth, is 1·80 inch per mile; for the second hundred miles, 2 inches; for the third hundred, 2·30

the delta of Bengal The present delta of the Ganges may be taken to commence at a point 1231 miles from its source, and 326 from the sea by its longest channel At that point the head waters of the Hugli break off, under the name of the Bhágirathi, from the parent channel, and make their way south to the sea The main volume of the Ganges pursues its course to the south east, and a great triangle of land, with its southern base on the Bay of Bengal, is thus enclosed


Between the Hugli on the west and the main channel on the east, a succession of offshoots strike southward from the Ganges The network of streams struggle slowly seaward over the level delta Their currents are no longer able, by reason of their diminished speed, to carry along the silt or sand which the more rapid parent river has brought down from Northern India They accordingly drop their burden of silt in their channels or along their margins, producing almond shaped islands, and by degrees raising their banks and channels above the surrounding plains When they spill over in time of flood, the largest amount of silt is deposited on their banks, or near them on the inland side In this way not only their beds, but also the lands along their banks, are gradually raised

The delta of Bengal

The deltaic district is

how they raise their banks above surrounding country

SECTION OF A DELTAIC CHANNEL OF THE GANGES



a The river channel *b b* the two banks raised by successive deposits of silt from the spill water in time of flood *c c* the surface of the water when not in flood *d d* the low lying swamps stretching away from either bank in which the river flows when it spills over its banks in time of flood, *e e* the dotted lines represent the ordinary level of the river surface

inches, for the fourth hundred, 2 57 inches, and for the whole section of 855 miles from the mouth to Memphis, the average fall is given as 4½ inches to the mile.

The following table, calculated by Mr David Stevenson (*Canal and River Engineering*, p 315), shows the silt carrying power of rivers at various velocities —

Inches per second	Mile per Hour	
3	=	0 170 will just begin to work on fine clay
6	=	0 340 will lift fine sand
8	=	0 4545 will lift sand as coarse as linseed
12	=	0 6819 will sweep along fine gravel
24	=	1 3638 will roll along rounded pebbles 1 inch in diameter
36	=	2 045 will sweep along slippery angular stones of the size of an egg

Delta
rivers build
themselves
up into
high-level
canals.

The rivers of a delta thus build themselves up, as it were, into high-level canals, which in the rainy season overflow their banks and leave their silt upon the low country on either side. Thousands of square miles in Lower Bengal receive in this way each summer a top-dressing of new soil, carried free of cost for more than a thousand miles by the river currents from Northern India or the still more distant Himálayas—a system of natural manuring which yields a constant succession of rich crops.

Junction
of Ganges,
Brahma-
putra, and
Meghná.

At Goálanda, about half-way between the delta-head and the sea, the Ganges unites with the main stream of the Brahmaputra, and farther down with the Meghná. Their combined waters exhibit deltaic operations on the most gigantic scale. They represent the drainage collected by the two vast river systems of the Ganges and the Brahmaputra, from an aggregate catchment basin of 752,000 square miles on both sides of the Himálayas, together with the rainfall poured into the Meghná from the eastern Burmese watershed.

Their
combined
delta.

The forces thus brought into play defy the control even of modern engineering. As the vast network of rivers creeps farther down the delta, they become more and more sluggish, and raise their beds still higher above the adjacent flats. Each set of channels has a depressed tract or swamp on either side, so that the lowest levels in a delta lie about half-way between the rivers. The stream constantly overflows into these depressed tracts, and gradually fills them up with its silt. The water which rushes from the river into the swamps has sometimes the colour of pea-soup, from the quantity of silt which it carries. When it has stood a few days in the swamps, and the river flood subsides, the water flows back from the swamps into the river channel; but it has dropped all its silt, and is of a clear dark-brown hue. The silt remains in the swamp, and by degrees fills it up, thus slowly creating new land. The muddy foliage of the trees which have been submerged bears witness to the fresh deposit. We shall presently see, buried roots and decayed trunks; while nearer the top the earth is strewed with broken pottery, and within historic times the scene is a wilderness.

Deltaic
swamps,

how filled
up by silt.

t scene
life

The last scene of forest and malarious solitude. Here all the river channels deposit mo

wilderness
id whos
into t
isclos
ht of
eme

from the estuary as banks or blunted headlands. The ocean currents also find themselves impeded by the outflow from the rivers, and in their turn drop the burden of sand which they sweep along the coast. The two causes combine to build up breakwaters of mingled sand and mud along the foreshore. In this way, while the solid earth gradually grows outward into the sea, owing to the deposits of river silt, peninsulas and islands are formed around the river mouths from the sand dropped by the ocean currents, and a double process of land making goes on.

The great Indian rivers, therefore, have not only supplied new solid ground by draining off the water from neighbouring lakes and marshes in their upper courses, and by depositing islands in their beds lower down. They are also constantly filling up the low lying tracts or swamps in their deltas, and are forming banks and capes and masses of low lying land at their mouths. Indeed, they slowly construct their entire deltas by driving back the sea. Lower Egypt was thus 'the gift of the Nile,' according to her priests in the age of Herodotus, and the vast Province of Lower Bengal is in the strictest scientific sense the gift of the Ganges, the Brahmaputra, and the Meghna. The deltas of these three river systems are in modern times united into one, but three distinct delta heads are observable. The delta head of the Brahmaputra commences near the bend where the river now twists due south round the Garo Hills, 220 miles from the sea as the crow flies. The present delta head of the Ganges begins at the point where the Bhagirathi breaks southward from the main channel, also about 220 miles in a direct line from the sea. The delta of the Meghna, which represents the heavy southern rainfall of the Khási Hills together with the western drainage of the watershed between Bengal and Independent Burma, commences in Sylhet District.

The three deltas, instead of each forming a triangle like the Greek Δ , unite to make an irregular parallelogram, running inland 220 miles from the coast, with an average breadth also of about 220 miles. This vast alluvial basin of say 50,000 square miles was once covered with the sea, and it has been slowly filled up to the height of at least 400 feet by the deposits which the rivers have brought down. In other words, the united river systems of the Ganges, Brahmaputra, and Meghna have carried away from the Himalayas and North-eastern Peninsula of India earth to build up a lofty island, with an area of 50,000 square miles, and a height of 400 feet.

Successive
depressions of
the delta.

Care has been taken not to overstate the work performed by the Bengal rivers. Borings have been carried down to 481 feet at Calcutta, but the auger broke at that depth, and it is impossible to say how much farther the alluvial deposits may go. There seem to have been successive eras of vegetation, followed by repeated depressions of the surface. These successive eras of vegetation now form layers of stumps of trees, peat-beds, and carbonized wood. Passing below traces of recently submerged forests, a well-marked peat-bed is found in excavations around Calcutta at a depth varying from 20 to 30 feet; and decayed wood, with pieces of fine coal, such as occur in mountain streams, has been met with at a depth of 392 feet. Fossilized remains of animal life have been brought up from 372 feet below the present surface. The footnote¹ illustrates the successive layers of the vast and lofty island, so to speak, which the rivers have built up—an island with an area of 50,000 square miles, and 400 feet high from its foundation, although at places only a few inches above sea-level.

Its subterranean
structure.

¹ 'Abstract Report of Proceedings of Committee appointed to superintend the Borings at Fort-William, December 1835 to April 1840.' 'After penetrating through the surface soil to a depth of about 10 feet, a stratum of stiff blue clay, 15 feet in thickness, was met with. Underlying this was a light-coloured sandy clay, which became gradually darker in colour from the admixture of vegetable matter, till it passed into a bed of peat, at a distance of about 30 feet from the surface. Beds of clay and variegated sand, intermixed with *kankar*, mica, and small pebbles, alternated to a depth of 120 feet, when the sand became loose and almost semi-fluid in its texture. At 152 feet, the quicksand became darker in colour and coarser in grain, intermixed with red water-worn nodules of hydrated oxide of iron, resembling to a certain extent the laterite of South India. At 159 feet, a stiff clay with yellow veins occurred, altering at 163 feet remarkably in colour and substance, and becoming dark, friable, and apparently containing much vegetable and ferruginous matter. A fine sand succeeded at 170 feet, and this gradually became coarser, and mixed with fragments of quartz and felspar, to a depth of 180 feet. At 196 feet, clay impregnated with iron was passed through; and at 221 feet sand recurred, containing fragments of limestone with nodules of *kankar* and pieces of quartz and felspar; the same stratum continued to 340 feet; and at 350 feet a fossil bone, conjectured to be the humerus of a dog, was extracted. At 360 feet, a piece of supposed tortoiseshell was found, and subsequently several pieces of the same substance were obtained. At 372 feet, another fossil bone was discovered, but it could not be identified, from its being torn and broken by the borer. At 392 feet, a few pieces of fine coal, such as are found in the beds of mountain streams, with some fragments of decayed wood, were picked out of the sand, and at 400 feet a piece of limestone was brought up. From 400 to 481 feet, fine sand, like that of the sea-shore, intermixed largely with shingle composed of fragments of primary rocks, quartz, felspar, mica, slate, and limestone, prevailed, and in this stratum the bore has been terminated.'

It should be remembered, however, that the rivers have been aided in their work by the sand deposited by the ocean currents. But, on the other hand, the alluvial deposits of the Ganges and Brahmaputra commence far to the north of the present delta head, and have a total area greatly exceeding the 50,000 square miles mentioned in a former paragraph. The Brahmaputra has covered with thick alluvium the valley of Assam, its confluent, the Meghna, or rather the upper waters which ultimately form the Meghna, have done the same fertilizing task for the valleys of Cachar and Sylhet, while the Ganges, with its mighty feeders, has prepared for the uses of man thousands of square miles of land in the broad hollow between the Himalayas and the Vindhya, far to the north west of its present delta. A large quantity of the finest and lightest silt, moreover, is carried out to sea, and discolours the Bay of Bengal 150 miles from the shore. The plains of Bengal are truly the gift of the great rivers.

Several attempts have been made to estimate the time which the Ganges and Brahmaputra must have required for accomplishing their gigantic task. The borings already cited, together with an admirable account by Colonel Baird Smith in the *Calcutta Journal of Natural History*,¹ and the Rev Mr Everest's calculations, form the chief materials for such an estimate. Sir Charles Lyell² accepts Mr Everest's calculation made half a century ago, that the Ganges discharges 6366 millions of cubic feet of silt per annum at Ghazipur.

This would alone suffice to supply 355 millions of tons a year, or nearly the weight of 60 replicas of the Great Pyramid. 'It is scarcely possible,' he says, 'to present any picture to the mind which will convey an adequate conception of the mighty scale of this operation, so tranquilly and almost insensibly carried on by the Ganges.' About 96 per cent of the whole deposits are brought down during the four months of the rainy season, or as much as could be carried by 240,000 ships, each of 1400 tons burthen. The work thus done in that season may be realized if we suppose that a daily succession of fleets, each of two thousand great ships, sailed down the river during the four months, and that each ship of the daily 2000 vessels deposited a freight of 1400 tons of mud every morning into the estuary.

¹ Vol 1 p 324. The other authorities, chiefly from the *Journal* of the Bengal Asiatic Society, are fully quoted in the *Geology of India*, by Messrs Medlicott and Blanford, vol 1 pp 396 *et seq* (Calcutta Government Press, 1879).

² *Principles of Geology*, vol 1 pp 478 *et seq* (1875).

Estimated
silt of
united
river
system at
the delta.

But the Ganges at Gházipur is only a single feeder of mighty mass of waters which have formed the delta of Bengal. The Ganges, after leaving Gházipur, receives many of principal tributaries, such as the GOGRA, the SON, the GANDAK and the KUSI. It then unites with the Brahmaputra, and finally with the Meghná, and the total mass of mud brought down by these combined river systems is estimated by Charles Lyell to be at least six or seven times as much as that discharged by the Ganges alone at Gházipur. We have therefore, at the lowest estimate, about 40,000 millions of cubic feet of solid matter spread over the delta, or deposited at the river mouths, or carried out to sea, each year; according to Charles Lyell, five times as much as is conveyed by the Mississippi to its delta and the Gulf of Mexico. The silt brought along during the rainy season alone represents the work of a daily succession of fleets, each of 13,000 ships a-piece, sailing down the Ganges during the four rainy months would perform if each ship of the daily 13,000 vessels discharged a freight of 1,400 tons a-piece each morning into the Bay of Bengal. This vast accumulation of silt takes place every rainy season in the delta or around the mouths of the Ganges; and the process is modified by volcanic upheavals and depressions of the delta has been going on during uncounted thousands of years.

Time
required
by rivers to
construct
the delta.

General Strachey took the area of the delta and coastal plain within influence of the deposits at 65,000 square miles, and estimated that the rivers would require 45·3 years to raise the delta by 1 foot, even by their enormous deposit of 40,000 millions of cubic feet of solid earth per annum. The rivers must have been at work 13,600 years in building up the delta 300 feet. But borings have brought up fluvial deposits from a depth of at least 400 feet. The present delta forms, moreover, but a very small part of the vast alluvial area which the rivers have constructed in the great dip between the Himálayas and the Vindhyan mountains. The more closely we scrutinize the various elements in such estimates, the more vividly do we realize ourselves in the presence of an almost immeasurable labour carried on during an almost immeasurable past.

River
irrigation.

The land which the great Indian rivers thus create, they also fertilize. In the lower parts of their course we have seen how their overflow affords a natural system of irrigation and manuring. In the higher parts, man has to step in, and bring their water by canals to his fields. Some idea of the enormous irrigation enterprises of Northern India may be obtained in the four articles in *The Imperial Gazetteer* on the

Ganges and Jumna canals The Ganges Canal had, in 1883, a length of 445 miles, with 3428 miles of distributaries, an irrigated area of 856,035 acres (including both autumn and spring crops), and a revenue of £279,449, on a total outlay of $2\frac{3}{4}$ millions sterling (£2,767,538 to 1883). The Lower Ganges Canal will bring under irrigation nearly $1\frac{1}{4}$ million acres (including both autumn and spring crops). It has already (1882-83) a main channel of 556 miles, with 1991 miles of distributaries, an irrigated area of 606,017 acres, and a clear revenue of £107,000, or 4·13 per cent on the total outlay up to 1883 (£2,589,624). The Eastern Jumna Canal has a length of 130 miles, with 618 miles of main distributaries. In 1883, the total distributaries aggregated nearly 900 miles, with an irrigated area of 240,233 acres, and a revenue of £82,665, or 28·4 per cent on the total outlay to that year (£290,839). The Western Jumna Canal measures 433 miles, with an aggregate of 259 miles of distributing channels, besides private watercourses, irrigating an area of 374,243 acres, with a revenue of £74,606, or 8·4 per cent on a capital outlay to 1883 of £884,952. The four Ganges and Jumna Canals, therefore, already irrigate an aggregate area of over two million acres, and will eventually irrigate over three millions. Among many other irrigation enterprises in Upper India are the Agra, Bari Doab, Rohilkhand and Bijnor, Betwa, and the Sutlej Chenab and Indus Inundation Canals.

The Indian rivers form, moreover, as we have seen, the great highways of the country. They supply cheap transit for the collection, distribution, and export of the agricultural staples. What the arteries are to the living body, the rivers are to the plains of Bengal. But the very potency of their energy sometimes causes terrible calamities. Scarcely a year passes without floods, which sweep off cattle and grain stores and the thatched cottages, with anxious families perched on their roofs.

The Rivers
as highways

The Rivers
as destroyers

In their upper courses, where their water is carried by canals to the fields, the rich irrigated lands breed fever, and are in places rendered sterile by a saline crust called *reh*. Farther down, the uncontrollable rivers wriggle across the face of the country, deserting their old beds, and searching out new channels for themselves, sometimes at a distance of many miles. Their old banks, clothed with trees and dotted along their route with villages, run like high ridges through the level rice fields, and mark the deserted course of the river.

It has been shown how the Brahmaputra deserted its main channel of the last century, and now rushes to the sea by a

Changes
of river-
beds.

new course, far to the westwards. Such changes are on a vast a scale, and the eroding power of the current is so insistent, that it is perilous to build large or permanent structures on the margin. The ancient sacred stream of the Gange is now a dead river, which ran through the Districts of Hooghly and the 24 Parganás. Its course is marked by a line of tanks and muddy pools, with temples, shrines, and burning ghats along high banks overlooking its deserted bed.

Deserted
river-
capitals.

Many decayed or ruined cities attest the alterations in river beds within historic times. In our own days, the Ganges passed close under Rájmahal, and that town, once the Muhammadan capital of Bengal, was (1850-55) selected as the site where the railway should tap the river system. The Ganges has now turned away in a different direction, and left the town high and dry, 7 miles from the bank. In 1787-88, the Tistá, a great river of Northern Bengal, broke away from its ancient bed. The *ATRAI*, or the old channel, by which the Tistá waters found their way into the Ganges, has dwindled into a pebble stream, which, in the dry weather, just suffices for boats or carts burthened; while the Tistá has branched to the eastward and now pours into the Brahmaputra. In 1870, the *RAVI*, one of the Five Rivers of the Punjab, carried away the famous shrine of the Sikhs near *DERA NANAK*, and still threatens the town.

If we go back to a more remote period, we find that the whole ancient geography of India is obscured by changes in the courses of the rivers. Thus, Hastinápur, the Ganges capital of the Pándavas, in the *Mahábhárata*, is with difficulty identified in a dried-up bed of the Ganges, 57 miles north-east of the present Delhi. The once splendid capital *KANAUJ*, which also lay upon the Ganges, now moulders in desolation 4 miles away from the modern river-bank. The remnant of its inhabitants live for the most part in huts built up against the ancient walls.

A similar fate on a small scale has befallen Kushtia, the river terminus of the Eastern Bengal Railway. The channel silted up (1860-70), and the terminus had to be removed to *Goálanda*, farther down the river. On the *HUGLI* river¹ a succession of emporia and river-capitals have been ruined from the same cause, and engineering efforts are required to secure the permanence of *CALCUTTA* as a great port.

The bore

An idea of the forces at work may be derived from a single well-known phenomenon of the *Húgli* and the *Meghná*, the *bore*. The tide advances up their broad estuaries until checked

¹ See article *HUGLI RIVER*, *The Imperial Gazetteer of India*.

by a rapid contraction of the channel. The obstructed influx, no longer able to spread itself out, rises into a wall of waters from 5 to 30 feet in height, which rushes onwards at a rate nearly double that of a stage-coach. Rennel stated that the *Hugli bore* ran from Hugli Point to Hugli Town, a distance of about 70 miles, in four hours. The native boatmen fly from the bank (against which their craft would otherwise be dashed) into the broad mid channel when they hear its approaching roar. The *bore* of the Meghna is so 'terrific and dangerous' that no boat will venture down certain of the channels at spring tide.

The Indian rivers not only desert the cities on their banks, ^{Hamlets} but they sometimes tear them away. Many a hamlet and ^{torn away} rice field and ancient grove of trees is remorselessly eaten up each autumn by the current. A Bengal proprietor has often to look on helplessly while his estate is being swept away, or converted into the bed of a broad, deep river. An important branch of Indian legislation deals with the proprietary changes thus caused by alluvion and diluvion.

The rivers have a tendency to straighten themselves out. ^{River} Their course consists of a series of bends, in each of which the ^{win lines} current sets against one bank, which it undermines, while it leaves still water on the other bank, in which new deposits of land take place. By degrees these twists become sharper and sharper, until the intervening land is almost worn away, leaving only a narrow tongue between the bends. The river finally bursts through the slender strip of soil, or a canal is cut across it by human agency, and direct communication is thus established between points formerly many miles distant by the windings of the river. This process of eating away soil from the one bank, against which the current sets, and depositing silt in the still water along the other bank, is constantly at work. Even in their quiet moods, therefore, the rivers steadily steal land from the old owners, and give it to new ones.

During the rains these forces work with uncontrollable fury. ^{A railway} We have mentioned that the first terminus of the Eastern Bengal ^{terminus} Railway at Kushtia had been partially deserted by the Ganges ^{swept} ^{away}. Its new terminus at Goalanda has suffered from an opposite but equally disastrous accident. Up to 1875, the Goalanda station stood upon a massive embankment near the water's edge, protected by masonry spurs running out to the river. About £130,000 had been spent upon these protective works, and it was hoped that engineering skill had conquered the violence of the Gangetic floods. But in August 1875, the

solid masonry spurs, the railway station, and the magistrate's court, were all swept away; and deep water covered their site. A new Goálanda terminus had to be erected two miles inland from the former river-bank. Higher up the Ganges, fluvial changes on so great a scale have been encountered at the river-crossing, where the Northern Bengal Railway begins and the Eastern Bengal Railway ends, that no costly or permanent terminus has yet been attempted. Throughout the long courses of the Ganges and Brahmaputra, the mighty currents each autumn undermine and then rend away many thousand acres of solid land. They afterwards deposit their spoil in their channels farther down, and thus, as has been shown, leave high and dry in ruin many an ancient city on their banks.

Poetry of
Indian
river-
names.

Their work, however, is on the whole beneficent; and a poem of Ossian might be made out of the names which the Indian peasant applies to his beloved rivers. Thus, we have the Goddess of Flowing Speech (*Saraswatí*), or, according to another derivation, the River of Pools; the Streak of Gold (*Suvarna-rekhá*); the Glancing Waters (*Chitra*); the Dark Channel (*Kála-nadí*), or the Queen of Death (*Káli-nadí*); the Sinless One (*Pápagíní* = *Pápalíní*); the Arrowy (*Sharavatí*); the Golden (*Suvarnamatí*); the Stream at which the Deer Drinks (*Haringhátá*); the Forest Hope (*Banás*); the Old Twister (*Burabalang*); besides more common names, such as the All-Destroyer, the Forest King, the Lord of Strength, the Silver Waters, and the Flooder.

Crops of
the river
plains.

Throughout the river plains of Northern India, two harvests, and in some Provinces three, are reaped each year. These crops are not necessarily taken from the same land; but in most Districts the best situated fields yield two harvests within the twelve months. In Lower Bengal, pease, pulses, oil-seeds, and green crops of various sorts, are reaped in spring; the early rice crops in September; and the great rice harvest of the year in November and December. Before the last has been gathered in, it is time to prepare the ground for the spring crops, and the husbandman knows no rest except during the hot weeks of May, when he is anxiously waiting for the rains. Such is the course of agriculture in Lower Bengal. But it should always be remembered that rice is the staple crop in a limited area of India, and that it forms the everyday food of only about 70 millions, or under one-third of the population. It has been estimated that, in the absence of irrigation, the rice crop requires an annual rainfall of at least 36 inches; and an

The three
harvests
of the
year.

Rice.

Indian District requires an average fall of not less than 40 to 60 inches in order to grow rice as its staple crop. A line might almost be drawn across Behar, to the north of which rice ceases to be the staple food of the people, its place being taken by millets, and in a less degree by wheat. There are, indeed, rice growing tracts in well watered or low lying Districts of Northern India, and in the river valleys or deltas and level strips around the southern coast. But speaking generally, throughout North Western, Central, and Southern India (except in the coast strip), rice is consumed only by the richer classes.

The products of each Province are carefully enumerated in the separate provincial articles in *The Imperial Gazetteer of India*, and an account of the most important will be found under the heading of Agriculture in the present volume. They are here referred to only so far as is necessary to give a general idea of the scenery of the river plains. Along the upper and middle courses of the Bengal rivers, the country rises gently from their banks in fertile undulations, dotted with mud villages and adorned with noble trees. Mango groves scent the air with their blossom in spring, and yield their abundant fruit in summer. The spreading banyan, with its colonnades of hanging roots, the stately *pipal*, with its green masses of foliage, the wild cotton tree, glowing white still leafless with heavy crimson flowers, the tall, daintily shaped tamarind, and the quick growing *babul* rear their heads above the crop fields. As the rivers approach the coast, the palm trees take possession of the scene. The ordinary landscape in the delta is a flat stretch of rice fields, fringed round with an evergreen border of bamboos, cocoa nuts, date trees, areca, and other coronetted palms. This densely peopled tract seems at first sight bare of villages, for each hamlet is hidden away amid its own grove of plantains and wealth giving trees. The bamboo and cocoa nut play a conspicuous part in the industrial life of the people, and the numerous products derived from them, including rope, oil, food, fodder, fuel, and timber, have been dwelt on with admiration by many writers.

The crops also change as we sail down the rivers. In the north, the principal grains are wheat, barley, Indian corn, and a variety of millets, such as *jowar* (*Sorghum vulgare*) and *bajra* (*Pennisetum typhoideum*). In the delta, on the other hand, rice is the staple crop, and the universal diet. In a single District, Rangpur, there are 295 separate kinds of rice known to the peasant,¹ who has learned to grow his favourite

¹ *Statistical Account of Bengal*, vol. vii pp 234-237

crop in every locality, from the comparatively dry ground, which yields the *áman* harvest, to the swamps 12 feet deep, on the surface of whose waters the rice ears may be seen struggling upwards for air. Sugar-cane, oil-seeds, flax, mustard, sesamum, palma-christi, cotton, tobacco, indigo, safflower and other dyes, ginger, coriander, red pepper, capsicum, cummin, and precious spices, are grown both in the Upper Provinces, and in the moister valleys and delta of Lower Bengal.

Drugs,
fibres, oil-
seeds, etc.

A whole pharmacopœia of medicines, from the well-known aloe and castor-oil, to obscure but valuable febrifuges, is derived from shrubs, herbs, and roots. Resins, gums, varnishes, india-rubber, perfume-oils, and a hundred articles of commerce or luxury, are obtained from the fields and the forests. Vegetables, both indigenous and imported from Europe, largely enter into the food of the people. The melon and huge yellow pumpkin spread themselves over the thatched roofs: fields of potato, *brinjal*, and yams are attached to the homesteads. The tea-plant is reared on the hilly ranges which skirt the plains both in the North-West and in Assam; the opium poppy about half-way down the Ganges, around Benares and in Behar; the silkworm mulberry still farther down in Lower Bengal; while the jute fibre is essentially a crop of the delta, and would exhaust any soil not fertilized by river floods. Even the jungles yield the costly lac and the *tasar* silk cocoons. The *mahuá*, also a gift of the jungle, produces the fleshy flowers which form a staple article of food in many districts, and when distilled supply a cheap spirit. The *sál*, *sissu*, *tún*, and many other indigenous trees yield excellent timber. Flowering creepers, of gigantic size and gorgeous colours, festoon the jungle; while each tank bears its own beautiful crop of the lotus and water-lily. Nearly every vegetable product which feeds and clothes a people, or enables it to trade with foreign countries, abounds.

Jungle
products.

Third
Region of
India—
The
Southern
Tableland.

Having described the leading features of the Himálayas on the north, and of the great river plains at their base, we come now to the third division of India, namely, the three-sided table-land which covers the southern half or more strictly peninsular portion of India. This tract, known in ancient times as the Deccan (Dakshin), literally *The South*, comprised, in its widest application, the CENTRAL PROVINCES, BERAR, MADRAS, BOMBAY, MYSORE, with the Native Territories of the Nizám, Sindhia, Holkar, and other Feudatory chiefs. It had in 1881 an aggregate population of about 100 millions. For

the sake of easy remembrance, therefore, we may take the inhabitants of the river plains in the north at about 150 millions, and the inhabitants of the southern table land at 100 millions

The Deccan, in its local acceptation, is restricted to the high inland tract between the Narbada (Nerbudda) and the Kistna rivers, but the term is also loosely used to include the whole country south of the Vindhya as far as Cape Comorin. Taken in this wide sense, it slopes up from the southern edge of the Gangetic plains. Three ranges of hills support its northern, its eastern, and its western side, the two latter meeting at a sharp angle near Cape Comorin.

The Deccan

Its three support n_o mountain walls

The northern side is buttressed by confused ranges, with a general direction of east to west, popularly known in the aggregate as the Vindhya mountains. The Vindhya, however, are made up of several distinct hill systems. Two sacred peaks stand as outposts in the extreme east and west, with a succession rather than a series of ranges stretching 800 miles between. At the western extremity, Mount Abu, famous for its exquisite Jain temples, rises, as a solitary outlier of the Aravalli hills, 5653 feet above the Rájputana plains, like an island out of the sea. Beyond the southern limits of that plain, the Vindhya range of modern geography runs almost due east from Gujarat, forming the northern wall of the Narbada valley. The Satpura mountains stretch, also east and west, to the south of the Narbadá river, and form the watershed between it and the Tápti. Towards the heart of India, the eastern extremities of the Vindhya and Sápuras end in the highlands of the Central Provinces. Passing still east, the hill system finds a continuation in the Kaimur range and its congeners. These in their turn end in the outlying peaks and spurs that mark the western boundary of Lower Bengal, and about on the old course of the Ganges under the name of the Rajmahal hills. On the extreme east, Mount Parasnath—like Mount Abu on the extreme west, sacred to Jain rites—rises to 4479 feet above the Gangetic plain.

The Vindhya mountains,

their various ranges

The various ranges of the Vindhya, from 1500 to over 4000 feet high, form, as it were, the northern wall and buttresses which support the central table land. But in this sense the Vindhya must be taken as a loose convenient generalization for the congeries of mountains and table lands between the Gangetic plains and the Narbadá valley. Now pierced by road and railway, they stood in former times as a barrier of mountain and jungle between Northern and Southern India, and formed one of the main difficulties in welding the

the ancient barrier between Northern and Southern India.

whole into an empire. They consist of vast masses of forests, ridges, and peaks, broken by cultivated tracts of the rich cotton-bearing black soil, exquisite river valleys, and high-lying grassy plains.

- The Gháts. The other two sides of the elevated southern triangle are known as the Eastern and Western GHATS. These ranges start southwards from the eastern and western extremities of the Vindhya, and run along the eastern and western coasts of India. The Eastern Gháts stretch in fragmentary spurs and ridges down the Madras Presidency, receding inland and leaving broad level tracts between their base and the coast.
- Eastern Gháts.
- Western Gháts. The Western Gháts form the great sea wall of the Bombay Presidency, with a comparatively narrow strip between them and the shore. Some of them rise in magnificent precipices and headlands out of the ocean, and truly look like colossal 'landing-stairs' (*gháts*) from the sea. The Eastern or Madras Gháts recede upwards to an average elevation of 1500 feet.
- The upheaved southern angle. The Western or Bombay Gháts ascend more abruptly from the sea to an average height of about 3000 feet, with peaks up to 4700, along the coast; rising to 7000 feet and even 8760 feet in the upheaved angle where they unite with the Eastern Gháts, towards their southern extremity.
- The central triangular plateau. The inner triangular plateau thus enclosed lies from 1000 to 3000 feet above the level of the sea. But it is dotted with peaks and seamed with ranges exceeding 4000 feet in height. Its best known hills are the Nilgiris (Blue Mountains), with the summer capital of Madras, Utakamand, over 7000 feet above the sea. Their highest point is Dodábeta peak, 8760 feet, in the upheaved southern angle. The interior plateau is approached by several famous passes from the level coast-strip on the western side. The Bhor-Ghát, for example, ascends a tremendous ravine about 40 miles south-east of Bombay city, to a height of 2027 feet. In ancient times it was regarded as the key to the Deccan, and could be held by a small band against any army attempting to penetrate from the coast. A celebrated military road was constructed by the British up this pass, and practically gave the command of the interior to the then rising port of Bombay. A railway line has now been carried up the gorge, twisting round the shoulders of mountains, tunnelling through intervening crags, and clinging along narrow ledges to the face of the precipice. At one point the zigzag is so sharp as to render a circuitous turn impossible, and the trains have to stop and reverse their direction on a levelled terrace. The Thall Ghát (1912 feet), to the north-
- Passes from the coast; the Bhor-Ghát

east of Bombay, has in like manner been served both by road and railway. Another celebrated pass, farther down the coast, connects the military centre of Belgaum with the little port of Vengurla. ^{Thall Ghat}

These 'landing stairs' from the sea to the interior present scenes of rugged grandeur. The trap rocks stand out, after ages of denudation, like circular fortresses flanked by round towers and crowned with nature's citadels, from the mass of hills behind, natural fastnesses, which in the Maratha times were rendered impregnable by military art. In the south of Bombay, the passes climb up from the sea through thick forests, the haunt of the tiger and the mighty bison. Still farther down the coast the western mountain wall dips deep into the Palghát valley—a remarkable gap, 20 miles broad, and leading by an easy route, only 1000 feet in height, from the seaboard to the interior. ^{The hill fort} A third railway and military road penetrate by this passage from Beypur, and cross the peninsula to Madras. A fourth railway starts inland from the coast at the Portuguese Settlement of Goa. ^{The hill fort}

On the eastern side of India, the Ghats form a series of spurs and buttresses for the elevated inner plateau rather than a continuous mountain wall. They are traversed by a number of broad and easy passages from the Madras coast. Through these openings, the rainfall of the southern half of the inner plateau reaches the sea. The drainage from the northern or Vindhyan edge of the three sided table land falls into the Ganges. The Nerbada (Nerbudda) and Tapti carry the rainfall of the southern slopes of the Vindhyas and of the Satpura Hills, by two almost parallel lines, into the Gulf of Cambay. But from Surat, in lat $21^{\circ} 28'$, to Cape Comorin, in lat $8^{\circ} 4'$, no great river succeeds in piercing the Western Gháts, or in reaching the Bombay coast from the interior table land. ^{The river of the inner plateau}

The Western Gháts form, in fact, a lofty unbroken barrier between the waters of the central plateau and the Indian Ocean. The drainage has therefore to make its way across India to the eastwards, now foaming and twisting sharply round projecting ridges, then tumbling down ravines, roaring through rapids, or rushing along valleys, until the rain which the Bombay sea breeze has dropped on the ridges of the Western Ghats finally falls into the Bay of Bengal. In this way, the three great rivers of the Madras Presidency, viz. the Godávari, the Kistna (Krishna), and the Káveri (Cauvery), rise in the mountains overhanging the Bombay coast, and traverse the whole breadth of the central ^{its drainage eastwards}

table-land before they reach the sea on the eastern shores of India.

Historical
signifi-
cance of
the Eastern
and West-
ern Ghâts ;

and of the
rainfall.

The physical geography and the political destiny of the two sides of the Indian peninsula have been determined by the characteristics of the mountain ranges on either coast. On the east, the Madras country is comparatively open, and was always accessible to the spread of civilisation. On the east, therefore, the ancient dynasties of Southern India fixed their capitals. Along the west, only a narrow strip of lowland intervenes between the barrier range and the Bombay seaboard. This western tract long remained apart from the civilisation of the eastern coast. To our own day, one of its ruling races, the Nairs, retain land tenures and social customs, such as polyandry, which mark a much ruder stage of human advancement than Hinduism, and which in other parts of India only linger among isolated hill tribes. On the other hand, the people of this western or Bombay coast enjoy a bountiful rainfall, unknown in the inner plateau and the east. The monsoon dashes its rain-laden clouds against the Western Ghâts, and pours from 100 to 200 inches of rain upon their maritime slopes from Khândesh down to Malabár. By the time the monsoon has crossed the Western Ghâts, it has dropped the greater part of its aqueous burden ; and central Districts, such as Bangalore, obtain only about 35 inches. The eastern coast also receives a monsoon of its own ; but, except in the neighbourhood of the sea, the rainfall throughout the Madras Presidency is scanty, seldom exceeding 40 inches in the year. The deltas of the three great rivers along the Madras coast form, however, tracts of inexhaustible fertility ; and much is done by irrigation to husband and utilize both the local rainfall and the accumulated waters which the rivers bring down.

The Four
Forest
Regions of
Southern
India.

The ancient Sanskrit poets speak of Southern India as buried under forests. But much of the forest land has gradually been denuded by the axe of the cultivator, or in consequence of the deterioration produced by unchecked fires and the grazing of innumerable herds of cattle, sheep, and goats. Roughly speaking, Southern India consists of four forest regions—First, the Western Ghâts and the plains of the Konkan, Malabár, and Travancore between them and the sea ; second, the Karnátik, with the Eastern Ghâts, occupying the lands along the Coromandel coast and the outer slopes of the hill ranges behind them ; third, the Deccan, comprising the high plateaux of Haidarábád, the Ceded Districts, Mysore,

Coimbatore, and Salem, fourth, the forests of the Northern Circars in the Madras Presidency

Each of these Districts has its own peculiar vegetation. That of the first region, or Western Ghats, largely consists of virgin forests of huge trees, with an infinite variety of smaller shrubs, epiphytic and parasitic plants, and lianas or tangled creepers which bind together even the giants of the forest. The king of these forests is the teak (*Tectona grandis*, Linn.) This prince of timber is now found in the greatest abundance in the forests of Kanara, in the Wynad, and in the Anamalai Hills of Coimbatore and Cochin. The *pun* tree (*Calophyllum inophyllum*, Linn.) is more especially found in the southernmost forests of Travancore and Tinneveli, where tall straight stems, fit for the spars and masts of seagoing ships, are procured. The jack fruit (*Artocarpus integrifolia*, Linn.) and its more common relation the *ain* (*Artocarpus hirsuta*, Lam.), furnish a pretty yellow coloured timber, the blackwood (*Dalbergia latifolia*, Roxb.) yields huge logs excellent for carved furniture. The *Terminalias* (*T. tomentosa* and *T. paniculata*, W and A.) with the bentek (*Lagerstroemia microcarpa*, Wight) supply strong wood suitable for the well built houses of the prosperous population of Malabar and Travancore. The dammer tree or Indian copal (*Vateria indica*, Linn.) yields its useful resin. The ground vegetation supplies one of the most valuable of Indian exports, the cardamom. To enumerate all the important trees and products of the Western Ghats would, however, be impossible.

In the Karnatik region, the forests rarely consist of large timber, in consequence of the drier climate and the shorter monsoon rains. Nor are they of a wide area. Most of the forests consist of what is known as 'Evergreen Scrub,' in which the prominent trees are the *Eugenia jambolana*, Lam., *Mimusops indica*, Linn., and the strychnine (*Strychnos nux vomica*, Linn.). On the slopes of the hills deciduous forest appears with teak, *Terminalias*, *Anogeissus*, and occasional red sanders.

The Deccan region, which gets a share of both monsoons (namely the monsoon from the south west from June to September, and that from the north-east from September to January), has still some large areas covered with fine forest, and yielding good timber. Chief among these areas are the Nallamalai Hills of Karnul, the Palkonda Hills of Cuddapah, the Collegal Hills of Coimbatore, and the Shevaroy and Javadi ranges of Salem and North Arcot. In the Nallamalai Hills, *byssil* (*Pterocarpus Marsupium*, Roxb.) and *saj* (Ter

minalia tomentosa, *IV. and A.*) are the prevailing timbers; the valuable red sanders-wood (*Pterocarpus santalinus*, *Linn.*) has its home in the Pálkonda and adjoining ranges of Cuddapah, while the growth on the hills of Coimbatore includes the precious sandal-wood (*Santalum album*, *Linn.*). In the drier country of Bellary and Penukonda, the chief tree is the *anjan* (*Hardwickia binata*, *Roxb.*), furnishing the hardest and heaviest of Indian woods.

Forests of
Northern
Madras.

The fourth forest region is that of the Northern Circars. It stretches from the Kistna river up to the Chilka lake, and includes fine forests of almost untouched *sál* (*Shorea robusta*, *Gacrt.*), the iron-wood (*Nylia dolabriformis*, *Benth.*), the satin-wood (*Chloroxylon Swietenia*, *D.C.*), and many other timbers of value.

Scenery of
southern
hill
country.

In wild tropical beauty nothing can surpass the luxuriance of an untouched Coorg forest, as viewed from one of the peaks of the Western Gháts. A waving descent of green, broken into terraces of varying heights, slopes downward on every side. North and south run parallel ranges of mountains, wooded almost to the summit; while to the west, thousands of feet below, the view is bounded by the blue line of the Arabian Sea. Wild animals of many kinds breed in the jungle, and haunt the grassy glades. The elephant, the tiger, and the leopard, the mighty bison, the stately *sámbar* deer, and the jungle sheep, with a variety of smaller game, afford adventure to the sportsman. During the rains magnificent cataracts dash over the precipices. The Gersappa falls, in the Western Gháts, have a descent of 830 feet.

Crops of
Southern
India.

In the valleys, and upon the elevated plains of the central plateau, tillage is driving back the jungle to the hilly recesses, and fields of wheat and many kinds of smaller grain or millets, tobacco, cotton, sugar-cane, and pulses, spread over the open country. The black soil of Southern India, formed from the detritus of the trap mountains, is proverbial for its fertility; while the level strip between the Western Gháts and the sea rivals even Lower Bengal in its fruit-bearing palms, rice harvests, and rich succession of crops. The deltas of the rivers which issue from the Eastern Gháts are celebrated as rice-bearing tracts. But the interior of the table-land is liable to droughts. The cultivators here contend against the calamities of nature by varied systems of irrigation—by means of which they store the rain brought during a few months by the monsoon, and husband it for use throughout the whole year. Great tanks or lakes, formed by damming up the valleys, are a striking

feature of Southern India. The food of the common people consists chiefly of small grains, such as *joar*, *bayra*, and *ragi*. The great export is cotton, with wheat from the northern Districts of the table land. The pepper trade of Malabár dates from far beyond the age of Sindbad the Sailor, and reaches back to Roman times. Cardamoms, spices of various sorts, dyes, and many medicinal drugs, are also grown. It is on the interior table land, and among the hilly spurs Mineral which project from it, that the mineral wealth of India lies hid. Coal mining now forms a great industry on the Coal north-eastern side of the table land, in Bengal, and also in Iron the Central Provinces. Beds of iron ore and limestone have been worked in several places, and hold out a possibility of a new era of enterprise to India in the future. Many districts are rich in building stone, marble, and the easily worked laterite. Copper and other metals exist in small quantities. Golconda was long famous as the central mart for the produce of the diamond districts, which now yield little more than a bare living to the workers. Gold dust has from very ancient times been washed out of the river beds, and quartz crushing for gold is being attempted on scientific principles in Madras and Mysore.

We have now briefly surveyed the three regions of India. Recapitulation of the Three Regions of India. The first, or the Himalayan, lies for the most part beyond the British frontier, but a knowledge of it supplies the key to the climatic and social conditions of India. The second region, or the River Plains in the north, formed the theatre of the ancient race movements which shaped the civilisation and political destinies of the whole Indian peninsula. The third region, or the Triangular Table land in the south, has a character quite distinct from either of the other two divisions, and a population which is now working out a separate development of its own. Broadly speaking, the Himalayas are their peoples by Turanian tribes, although to a large extent ruled by Aryan immigrants. The great River Plains of Bengal are still the possession of the Indo Aryan race. The Triangular Table land has formed an arena for a long struggle between the Aryan civilisation from the north, and what is known as the Dravidian stock in the south.

To this vast Empire the English have added BRITISH British BURNI, consisting of the lower valley of the Irrawaddy (Irra Burni addy) with its delta, and a long flat strip stretching down the

eastern side of the Bay of Bengal. Between the narrow maritime tract and the Irawadi valley runs a backbone of low ranges. These ranges, known as the Yoma (Roma) mountains, are covered with dense forests, and separate the Irawadi valley from the strip of coast. The Yoma ranges have peaks exceeding 4000 feet, and culminate in the Bhamo Mountain, 7100 feet. They are crossed by passes, one of which, the An or Aeng, rises to 4517 feet above the sea-level. A thousand creeks indent the seaboard; and the whole of the low level country, both on the coast and in the Irawadi valley, forms one vast rice-field. The rivers float down an abundant supply of teak and bamboos from the north. Tobacco, of an excellent quality, supplies the cigars which all Burmese (men, women, and children) smoke, and affords an important product of increasing value. Arakan and Pegu, or the Arakan Provinces of the coast strip, and also the Irawadi valley, contain mineral oil-springs. Tenasserim forms a long narrow maritime Province, running southward from the mouths of the Irawadi to Point Victoria, where the British territory adjoins Siam. Tenasserim is rich in tin mines, and contains iron-ore equal to the finest Swedish; besides gold and copper in smaller quantities, and a very pure limestone. Rice and teak timber form the staple exports of Burma; and rice is as much the universal food of the people. British Burma, including Tenasserim, has an area of over 87,000 square miles; and a population, in 1881, of $3\frac{3}{4}$ million persons. It is fortunate that it is still possessing wide areas of yet uncultivated land to meet the wants of its rapidly increasing people.¹

Annexation of Upper Burma, 1886.

Since these sheets went to press, the persistent misconduct of King Thebaw in Upper Burma, his obstinate denial of justice, and his frustration of Lord Dufferin's earnest endeavours to arrive at a conciliatory settlement, compelled the British Government to send an expedition against him. A British force under General Prendergast advanced up the Irawadi valley with little opposition, and occupied Mandalay. King Thebaw surrendered, and was removed to honourable confinement in British India. His territories were annexed to the British Empire, by Lord Dufferin's Proclamation, on the 1st of January 1886.

¹ *vide post*, pp. 47, 50.

CHAPTER II

THE PEOPLE

THE POPULATION OF INDIA, with British Burma, amounted in 1881 to 256 millions, or, as already mentioned, more than double the number which Gibbon estimated for the Roman Empire in the height of its power. But the English Government has respected the possessions of native chiefs, and one third of the country still remains in the hands of its hereditary rulers. Their subjects make about one-fifth of the whole Indian people. The British territories, therefore, comprise only two thirds of the area of India, and about four fifths of its inhabitants.

The native princes govern their States with the help of certain English officers, whom the Viceroy stations in native territory. Some of the Chiefs reign almost as independent sovereigns, others require more assistance, or a stricter control. They form a magnificent body of feudatory rulers, possessed of revenues and armies of their own. The more important of these princes exercise the power of life and death over their subjects, but the authority of each is limited by usage, or by treaties or engagements, acknowledging their subordination to the British Government. That Government, as Suzerain in India, does not allow its feudatories to make war upon each other, or to have any relations with foreign States. It interferes when any chief misgoverns his people, rebukes, and if needful removes, the oppressor, protects the weak, and firmly imposes peace upon all.

The British possessions are distributed into twelve governments, each with a separate head, but all of them under the orders of the supreme Government of India, consisting of the Governor General in Council. The Governor General, who also bears the title of Viceroy, holds his court and government at Calcutta in the cold weather, and during summer at Simla, an outer spur of the Himalayas, 7000 feet above the level of the sea. The Viceroy of India, and the Governors of Madras and Bombay, are usually British statesmen appointed in England by the Queen. The heads of the other ten Provinces are selected for their merit from the

General
survey of
the People

The Feudatory
Chiefs

Their
various
powers

British
India—the
Twelve
Provinces,

how
governed

Anglo-Indian services, and are nominated by the Viceroy, subject in the case of the Lieutenant-Governorships to approval by the Secretary of State.

Census of
1881 and
of 1872.

The Census of 1881 returned a population of 256,396,646 souls for all India. The following tables give an abstract of the area and population of each of the British Provinces, and

THE TWELVE GOVERNMENTS OR PROVINCES OF BRITISH INDIA, IN 1881.

NAME OF PROVINCE (Exclusive of the Native States attached to it).	Area in Square Miles.	Total Population.	Number of Persons per Square Mile.
1. Government of Madras, ¹	141,001	31,170,631	221
2. Government of Bombay, with Sind, .	124,122	16,454,414	133
3. Lieutenant-Governorship of Bengal, ² .	150,588	66,691,456	443
4. Lieutenant-Governorship of the Punjab,	106,632	18,850,437	177
5. Lieutenant-Governorship of the North- Western Provinces, .	106,111	44,107,869	416
6. Chief-Commissionership of Oudh, ³ }			
7. Chief-Commissionership of the Central Provinces, .	84,445	9,838,791	117
8. Chief-Commissionership of British Burma, .	87,220	3,736,771	43
9. Chief-Commissionership of Assam, ⁴ .	46,341	4,881,426	105
10. Commissionership of Berar, ⁵ .	17,711	2,672,673	151
11. Commissionership of Ajmere, .	2,711	460,722	170
12. Commissionership of Coorg, .	1,583	178,302	113
Total for British India, ⁶ .	868,465	199,043,492	229

¹ Including the three petty States of Pudukota, Banganapalli, and Sandhūr.

² Exclusive of 5576 square miles of unsurveyed and half-submerged Sundarbans along the sea face of the Bay of Bengal. The Imperial Census Report does not distinguish between the Feudatory States and British territory in the returns for Bengal. The figures given above are taken from the Provincial Census Report, and refer to British territory only. The area and population of the Native States of Bengal are shown in the table on the next page.

³ Oudh has been incorporated, since 1877, with the North-Western Provinces. The Lieutenant-Governor of the North-Western Provinces is also Chief-Commissioner of Oudh.

⁴ Assam was separated from the Lieutenant-Governorship of Bengal in 1874, and erected into a Chief-Commissionership. The area includes an estimate for the unsurveyed tracts in the Cachar, Nágá, and Lakhimpur Hills.

⁵ Berar consists of the six 'Assigned Districts' made over to the British administration by the Nizám of Haidarábád for the maintenance of the Haidarábád Contingent, which he was bound by treaty to maintain, and in discharge of other obligations.

⁶ These figures are exclusive of the population of the British Settlement of Aden in Arabia (34,860), and of the Andaman Islands in the Bay of Bengal (14,628). These places have not been included in the tables of the Imperial Census Report, as being outside the geographical limits of India.

groups of Native States, together with the French and Portuguese possessions in India. The population in 1872 was as follows—British India, 186 millions, Feudatory States, over 54 millions, French and Portuguese possessions, nearly $\frac{1}{4}$ of a million, total for all India, 240,931,521 in 1872

THE THIRTEEN GROUPS OF NATIVE STATES FORMING
FEUDATORY INDIA, IN 1881

NAME OF STATE		Total Area in Square Miles	Total Population	Number of Persons per Square Mile
Under the Governor or Council in Council Under the Local Governments	1 Rajputana	129 750	10 268 392	79
	2 Hyderabad (Nizam's Dominions)	71,771	9 845 594	137
	3 Central Indian Agency and Bundelkhand	75 079	9 261 907	123
	4 Baroda	8 570	2 185 005	255
	5 Mysore ¹	24 723	4 186 188	169
	6 Kashmir ²	80 900	1 534 972	19
	7 Manipur	8 000	221 000	27
	8 Native States under Bombay Government	73 753	6 941 249	94
	9 Native States under Madras Government	8 091	3 001 436	370
	10 Native States under Bengal Government	36 634	2 845 405	78
	11 Native States under Punjab Government	35 817	3 861 683	108
	12 Native States under North Western Provinces	5 125	741 750	145
	13 Native States under Central Provinces	28 834	1 709 700	59
Total for Feudatory India		587 047	56 604 371	96

If to the foregoing figures we add the French and Portuguese possessions, we obtain the total for all India. Thus—

ALL INDIA, INCLUDING BRITISH BURMA.

(Based chiefly on the Census of 1881)

	Area in Square Miles	Population	Number of Persons per Square Mile
British India	868 465	199 043 492	229
Feudatory India	587 047	56 604 371	96
Portuguese Settlements	2 365	475 172	201
French Settlements	203	273 611	135
Total for all India including British Burma	1 458 080	256 396 646	176

¹ Mysore was under direct British administration from 1830 to 1881 when it was restored to native rule on its young chief attaining his majority

² The Kashmir figures relate to the year 1873.

Density of the population, compared with France and England. British India, therefore, supports a population much more than twice as dense as that of the Native States. If we exclude the outlying and lately-acquired Provinces of British Burma and Assam, the proportion is nearly three-fold, or 260 persons to the square mile. How thick this population is, may be realized from the fact that France had in 1876 only 180 people to the square mile; while even in crowded England, wherever the density approaches 200 to the square mile it ceases to be a rural population, and has to live, to a greater or less extent, by manufactures, mining, or city industries.¹ Throughout large areas of Bengal, two persons have to live on the proceeds of each cultivated acre, or 1280 persons to each cultivated square mile. The Famine Commissioners reported in 1880, that over 6 millions of the peasant holdings of Bengal, or two-thirds of the whole, averaged from 2 to 3 acres a-piece. Allowing only four persons to the holding, for men, women, and children, this represents a population of 24 millions struggling to live off 15 million acres, or a little over half an acre a-piece.

Absence of large towns. Unlike England, India has few large towns, and no great manufacturing centres. Thus, in England and Wales 42 per cent., or nearly one-half of the population in 1871, lived in towns with upwards of 20,000 inhabitants, while in British India only 4½ per cent., or not one-twentieth of the people, live in such towns. India, therefore, is almost entirely a rural country; and many of the so-called towns are mere groups of villages, in the midst of which the cattle are driven a-field, and ploughing and reaping go on. Calcutta itself has grown out of a cluster of hamlets on the bank of the Húgli; and the term 'municipality,' which in Europe is only applied to towns, often means in India a 'rural union,' or collection of homesteads for the purposes of local government.

Over-crowded Districts. We see, therefore, in India, a dense population of husbandmen. Wherever their numbers exceed 1 to the acre, or 640 to the square mile,—excepting in suburban districts or in irrigated tracts,—the struggle for existence becomes hard. At half an acre a-piece that struggle is terribly hard. In such Districts, a good harvest yields just sufficient food for the people; and thousands of lives depend each autumn on a few inches more or less of rainfall. The Government may, by great efforts, feed the starving in time of actual famine; but it cannot stop the yearly work of disease and death among a steadily underfed people. In these overcrowded tracts the

¹ Report on the Census of England and Wales for 1871.

population reaches the stationary stage. For example, in Allah ábád District during twenty years, the inhabitants increased by only 6 persons in 10,000 each year. During the nine years from 1872 to 1881, the annual increase was 8 persons in 10,000. In still more densely peopled localities upon the line of railway, facilities for migration have drained off the excessive population, and their total number in 1872 was less than it had been twenty years before. On the other hand, in thinly peopled Provinces the inhabitants quickly multiply. Under Thus, when we obtained the District of Amherst in 1824 from the king of Burma, it had been depopulated by savage native wars. The British established their firm rule, people began to flock in, and by 1829 there were 70,000 inhabitants. In fifty years the population had increased by more than four fold, or to 301,086 in 1881.

In some parts of India, therefore, there are more husband men than the land can feed, in other parts, vast tracts of fertile soil still await the cultivator. In England the people would move freely from the overpopulated districts to the thinly inhabited ones, but in India the peasant clings to his hereditary homestead long after his family has outgrown his fields. If the Indian races will only learn to migrate to tracts where spare land still abounds, they will do more than the utmost efforts of Government can accomplish to prevent famines.

The facts disclosed by the Census in 1872 and 1881 prove, indeed, that the Indian peasant has lost something of his old immobility. The general tendency of the population in Bengal is south and east to the newly formed delta, and north-east to the thinly peopled valleys of Assam. In 1881, it was ascertained that out of a specified population of 247 millions, nearly 6½ millions were living in Provinces in which they had not been born. But the clinging of the people to their old villages in spite of hardship and famine still forms a most difficult problem in India.

Throughout many of the hill and border tracts, land is so plentiful that it yields no rent. Any one may settle on a patch which he clears of jungle, exhausts the soil by a rapid succession of crops, and then leaves it to relapse into forest. In such tracts no rent is charged, but each family of wandering husbandmen pays a poll tax to the chief, or to the Government under whose protection it dwells. As the inhabitants increase, this nomadic system of cultivation gives place to regular tillage. Through out British Burma we see both methods at work side by side, while on the thickly peopled plains of India the 'wandering

Districts the pastures have been brought under the plough, to the detriment of the cattle. The people can no longer afford to leave sufficient land fallow, or under grass, for their oxen and cows.

It will be readily understood that in a country where, almost down to the present day, there was more land than there were people to till it, a high value was set upon the cultivating class. In tracts where the nomadic system of husbandry survives, no family is permitted by the native chief to quit his territory. For each household there pays a poll tax. In many parts of India, we found the lower classes attached to the soil in a manner which could scarcely be distinguished from predial slavery. In spite of our legislative enactments, this system lingered on during nearly a century of British rule. Our early officers in South Eastern Bengal, especially in the great island of Sandwip almost raised a rebellion by their attempts to liberate the slaves. Indeed, in certain tracts where we found the population very depressed, as in Behar, the courts have in our own day occasionally brought to light the survival of serfdom. A feeling still survives in the minds of some British officers against migrations of the people from their own Districts to adjoining ones, or to Native States.

If we except the newly annexed Provinces of Burma and Assam, the population of British India is nearly three times more dense than the population of Feudatory India. This great disproportion cannot be altogether explained by differences in the natural capabilities of the soil. It would be for the advantage of the people that they should spread themselves over the whole country, and so equalize the pressure throughout. The Feudatory States lie interspersed among British territory, and no costly migration by sea is involved. That the people do not thus spread themselves out, but crowd together within our Provinces, is partly due to their belief that, on the whole they are less liable to oppression under British rule than under native chiefs. But any outward movement of the population, even from the most densely peopled English Districts, would probably be regarded with pain by the local officers. Indeed, the occasional exodus of a few cultivators from the overcrowded Province of Behar into the thinly peopled frontier State of Nepal, has formed a subject of sensitive self reproach. In proportion as we can enforce good government under the native chiefs of India, we should hope to see a gradual movement of the people into the Feudatory States. There is plenty of land in India for the whole

serfdom
in India

Unequal
pressure of
the popula-
tion on the
land

THE ETHNICAL HISTORY OF INDIA —The statistical elucidation of the races and Provinces of India can only be effected by tabular forms. At the end of this volume, therefore, will be found a series of ten statements dealing with the various aspects of the Indian population¹. The briefest summary of the ethnological elements which compose that population is all that can be here attempted.

European writers formerly divided the Indian population into two races—the Hindus and the Muhammadans. But when we look more closely at the people, we find that they consist of four well marked elements. These are, first, the recognised non Aryan Tribes, called the Aborigines, and their half Hinduized descendants, numbering over 17½ millions in British India in 1872. Second, the comparatively pure offspring of the Aryan or Sanskrit speaking Race (the Brahmans and Rājputs), about 16 millions in 1872. Third, the great Mixed Population, known as the Hindus, which has grown out of the Aryan and non Aryan elements (chiefly from the latter), 111 millions in 1872. Fourth, the Muhammadans, 41 millions. These made up the 186 millions of people under British rule in 1872. The same four fold division applied to the population of the 54 millions in Feudatory India in 1872, but we do not know the numbers of the different classes.

The figures for 1872 are reproduced in the last paragraph, as the Census of 1881 adopted a different classification, which

Portuguese Possessions is due to more accurate enumeration in 1881, cannot be exactly ascertained.

¹ Viz.—Table I Area, villages, houses, and population, etc., in each Province of British India in 1881.

- „ II Distribution into town and country, or ‘towns and villages in British India.’
- „ III Cultivated, cultivable, and uncultivable land in Provinces for which returns exist.
- „ IV Population of British India classified according to age and sex.
- „ V Population of British India classified according to religion.
- „ VI Asiatic non Indian population of British India classified according to birth place.
- „ VII Non-Asiatic population of British India classified according to birth place.
- „ VIII Town population of India, being a list of the 149 towns of British India, of which the population exceeds 20,000.
- „ IX Population of British India according to education.
- „ X Population of British India, classified according to caste, sect, and nationality.

CHAPTER III

THE NON ARYAN RACES.

THE present chapter treats of the lower tribes, an obscure people, who, in the absence of a race name of their own, may be called the non Aryans or Aborigines. They have left no written records, indeed, the use of letters, or of any simplest hieroglyphs, was to them unknown. The sole works of their hands which have come down to us are rude stone circles, and the upright slabs and mounds, beneath which, like the primitive peoples of Europe, they buried their dead. From these we only discover that, at some far distant but unfixed period, they knew how to make round pots of hard, thin earthenware, not inelegant in shape, that they fought with iron weapons, and wore ornaments of copper and gold. Coins of Imperial Rome have been dug up from their graves. Still earlier remains prove that, long before their advent, India was peopled as far as the depths of the Central Provinces, by tribes unacquainted with the metals, who hunted and warred with polished flint axes and other deftly wrought implements of stone, similar to those found in Northern Europe. And even these were the successors of yet ruder beings, who have left their agate knives and rough flint weapons in the Narbadá valley. In front of this far stretching background of the early Metal and Stone Ages, we see the so called Aborigines being beaten down by the newly arrived Aryan race.

The struggle is commemorated by the two names which the victors gave to the early tribes, namely, the Dasyus, or 'enemies,' and the Dásas, or 'slaves.' The new-comers from the north prided themselves on their fair complexion, and their Sanskrit word for 'colour' (*varna*) came to mean 'race' or 'caste.' Their earliest poets, 3000 years ago, praised in the Rig Veda their bright gods, who, 'slaying the Dasyus, protected the Aryan colour,' who 'subjected the black skin to the Aryan man.' They tell us of their 'stormy deities, who rush on like furious bulls and scatter the black skin.' The sacrificer gave thanks to his god for 'dispersing the slave bands of black descent,'

The Non-
ARYANS
or Abori-
gines

Kistvaen-
builders

Flint
weapons

The Non-
victors as
described
by the
Aryans.

The
'Black
skin'

Among the rudest fragments of mankind are the isolated The Andaman Andaman islanders in the Bay of Bengal. The old Arab and European voyagers described them as dog faced man eaters. The English officers sent to the islands in 1855 to establish a Settlement, found themselves surrounded by naked cannibals of a ferocious type, who daubed themselves when festive with red earth, and mourned in a suit of olive coloured mud. They used a noise like *crying* to express friendship or joy, bore only names of common gender, which they received before birth, and which therefore had to be applicable to either sex, and their sole conception of a god was an evil spirit, who spread disease. For five years they repulsed every effort at intercourse with showers of arrows, but our officers slowly brought them to a better frame of mind by building sheds for them near the British Settlement, where these poor beings might find shelter from the tropical rains, and receive medicines and food.

The Anamalai Hills, in Southern Madras, form the refuge Anamalai hillmen of a whole series of broken tribes. Five hamlets of long haired, wild looking Pulhars were found living on jungle products, mice, or any small animals they could catch, and worshipping demons. The Mundavars shrink from contact with the outside world, and possessed no fixed dwellings, but wandered over the inner most hills with their cattle, sheltering themselves under little leaf sheds, and seldom remaining in one spot more than a year. The thick lipped, small bodied Kaders, 'Lords of the Hills,' are a remnant of a higher race. These hills, now almost uninhabited, abound in the great stone monuments (kistvaens and dolmens) which the primitive tribes erected over their dead. The Nairs, or aborigines of South Western India, still The Nairs, practise polyandry, according to which one woman is the wife of several husbands, and a man's property descends not to his own but to his sister's children. This system also appears among the Himalayan tribes.

In the Central Provinces, the aboriginal races form a large Non Aryan tribes of the Central Provinces proportion of the population. In certain Districts, as in the State of Bastar, they amounted in 1872 to three fifths of the inhabitants. Their most important race the Gonds, have made some advances in civilisation, but the wilder tribes still cling The Gonds to the forest, and live by the chase. Some of them are reported to have used, within our own times, flint points for their arrows. The Mánás wield bows of great strength, which they hold with their feet while they draw the string with both hands. A still wilder tribe, the Márís, fled from their grass built

subsistence by plundering the more civilised hamlets of the Assam valley, a means of livelihood which they have but slowly given up under British rule. Some of the wildest of them, like the independent Abars, are now engaged as a sort of irregular police, to keep the peace of the border, in return for a yearly gift of cloth, hoes, and grain. Their very names bear witness to their former wild life. One tribe, the Akas of Assam, is divided into two clans, known respectively as 'The eaters of a thousand hearths,' and 'The thieves who lurk in the cotton field' Akas of Assam

Many of the aboriginal tribes, therefore, remain in the same early stage of human progress as that ascribed to them by the Vedic poets more than 3000 years ago. But others have made great advances, and form communities of a well developed type. It must here suffice to briefly describe two such races, the Santals and the Kandhs who inhabit the north eastern edge of the central plateau. The Santals have their home among the hills which abut on the Ganges in Lower Bengal. The Kandhs live 150 to 350 miles to the south, among the high lands which look down upon the Orissa delta and Madras coast More advanced non Aryan tribes

The Santals dwell in villages in the jungles or among the mountains, apart from the people of the plains. They numbered about a million in 1872, and give their name to a large District, the SANTAL PARGANAS, 140 miles north west of Calcutta. Although still clinging to many customs of a hunting forest tribe, they have learned the use of the plough, and settled down into skilful husbandmen. Each hamlet is governed by its own head man, who is supposed to be a descendant of the original founder of the village, and who is assisted by a deputy head man and a watchman. The boys of the hamlet have their separate officers, and are strictly controlled by their own head and his deputy till they enter the married state. The Santals know not the cruel distinctions of Hindu caste, but trace their tribes, usually numbering seven, to the seven sons of the first parents. The whole village feasts, hunts, and worships together, and the Santal had to take his wife, not from his own tribe, but from one of the six others. So strong is the bond of race, that expulsion from the tribe was the only Santal punishment. A heinous criminal was cut off from 'fire and water' in the village, and sent forth alone into the jungle. Minor offences were forgiven upon a public reconciliation with the tribe, to effect which the guilty one provided a feast, with much rice beer, for his clansmen The Santals
Santal village government
No castes, but strong tribal feeling

subsistence by plundering the more civilised hamlets of the Assam valley, a means of livelihood which they have but slowly given up under British rule. Some of the wildest of them, like the independent Abars, are now engaged as a sort of irregular police, to keep the peace of the border, in return for a yearly gift of cloth, hoes, and grain. Their very names bear witness to their former wild life. One tribe, the Akas of Assam, is divided into two clans, known respectively as 'The Akas of eaters of a thousand hearths, and 'The thieves who lurk in the Assam cotton field'.

Many of the aboriginal tribes, therefore, remain in the same early stage of human progress as that ascribed to them by the Vedic poets more than 3000 years ago. But others have made great advances, and form communities of a well developed type. It must here suffice to briefly describe two such races, the Santals and the Kandhs who inhabit the north eastern edge of the central plateau. The Santals have their home among the hills which abut on the Ganges in Lower Bengal. The Kandhs live 150 to 350 miles to the south, among the high lands which look down upon the Orissa delta and Madras coast.

The Santals dwell in villages in the jungles or among the untains, apart from the people of the plains. They numbered about a million in 1872, and give their name to a District, the SANTAL PARGANAS, 140 miles north west of Calcutta. Although still clinging to many customs of a forest tribe, they have learned the use of the plough, and settled down into skilful husbandmen. Each hamlet is

by its own head man, who is supposed to be a Santal, the original founder of the village, and who is aided by a deputy head man and a watchman. The boys of the village have their separate officers, and are strictly controlled by their own head and his deputy till they enter the

The Santals know not the cruel distinctions of caste, but trace their tribes, usually numbering seven, to sons of the first parents. The whole village feasts, worships together, and the Santal had to take not from his own tribe, but from one of the six

so strong is the bond of race, that expulsion from the village was the only Santal punishment. A heinous criminal was expelled from 'fire and water' in the village, and sent forth to the jungle. Minor offences were forgiven upon a feast with the tribe, to effect which the guilty man gave a feast, with much rice beer, for his clansmen.

Tax-gathering among the Máris. huts on the approach of a stranger. Once a year a messenger came to them from the local Rájá to take their tribute, which consisted chiefly of jungle products. He did not, however, enter their hamlets, but beat a drum outside, and then hid himself. The shy Máris, placed what they had to give in an appointed spot, and then crept back into their retreats.

The Juáangs or 'Leaf-wearers' of Orissa Hill States ;	Farther to the north there is a tribe of leaf-wearers, on the hill States ;	States of Orissa, Juáangs or Patuas, wear leaf-clothes. The few strings of beads tied before, and in the back, are, in the States of Orissa, Chi-
clothed by Government.	clothed by Government.	Chi-

subsistence by plundering the more civilised hamlets of the Assam valley, a means of livelihood which they have but slowly given up under British rule. Some of the wildest of them, like the independent Abars, are now engaged as a sort of irregular police, to keep the peace of the border, in return for a yearly gift of cloth, hoes, and grain. Their very names bear witness to their former wild life. One tribe, the Akas of Assam, is divided into two clans, known respectively as 'The eaters of a thousand hearths,' and 'The thieves who lurk in the cotton field.'

Many of the aboriginal tribes, therefore, remain in the same early stage of human progress as that ascribed to them by the Vedic poets more than 3000 years ago. But others have made great advances, and form communities of a well developed type. It must here suffice to briefly describe two such races, the Santals and the Kandhs who inhabit the north eastern edge of the central plateau. The Santals have their home among the hills which abut on the Ganges in Lower Bengal. The Kandhs live 150 to 350 miles to the south, among the high lands which look down upon the Orissa delta and Madras coast.

The Santals dwell in villages in the jungles or among the mountains, apart from the people of the plains. They numbered about a million in 1872, and give their name to a large District, the SANTAL PARGANAS, 140 miles north west of Calcutta. Although still clinging to many customs of a hunting forest tribe, they have learned the use of the plough, and settled down into skilful husbandmen. Each hamlet is governed by its own head man, who is supposed to be a descendant of the original founder of the village, and who is assisted by a deputy head man and a watchman. The boys of the hamlet have their separate officers, and are strictly controlled by their own head and his deputy till they enter the married state. The Santals know not the cruel distinctions of Hindu caste, but trace their tribes, usually numbering seven, to the seven sons of the first parents. The whole village feasts, hunts, and worships together, and the Santal had to take his wife, not from his own tribe, but from one of the six others. So strong is the bond of race, that expulsion from the tribe was the only Santal punishment. A heinous criminal was cut off from 'fire and water' in the village, and sent forth alone into the jungle. Minor offences were forgiven upon a public reconciliation with the tribe, to effect which the guilty one provided a feast, with much rice-beer, for his clansmen.

Akas of Assam

More advanced non Arjan tribes

The Santals

Santal village govern ment

No castes, but strong tribal feeling

The six
Santál
cere-
monies.

The chief ceremonies in a Santál's life, six in number, vary in different parts of the country, but are all based upon this strong feeling of kinship. The first is the admission of the newly-born child into the family,—a secret rite, one act of which consists in the father placing his hand on the infant's head and repeating the name of the ancestral deity. The second, the admission of the child into the tribe, is celebrated three or five days after birth,—a more public ceremony, at which the child's head is shaved, and the clansmen drink beer. The third ceremony, or admission into the race, takes place about the fifth year; when all friends, whatever may be their tribe, are invited to a feast, and the child is marked on his right arm with the Santál spots. The fourth consists of the union of his own tribe with another by marriage, which does not take place till the young people can choose for themselves. At the end of the ceremony, the girl's clanswomen pound burning charcoal with the household pestle, in token of the breaking up of her former family ties, and then extinguish it with water, to signify the separation of the bride from her clan. The Santáls respect their women, and seldom or never take a second wife, except for the purpose of obtaining an heir. The fifth ceremony consists of the dismissal of the Santál from the race, by the solemn burning of his body after death. The sixth is the reunion of the dead with the fathers, by floating three fragments of the skull down the Dámodar river (if possible), the sacred stream of the race.

Santál
marriages.

Santál
religion.

The Santál had no conception of bright and friendly gods, such as the Vedic singers worshipped. Still less could he imagine one omnipotent and beneficent Deity, who watches over mankind. Hunted and driven back before the Hindus and Muhammadans, he did not understand how a Being could be more powerful than himself without wishing to harm him. 'What,' said a Santál to an eloquent missionary, who had been discoursing on the Christian God—'what if that strong One should eat me?' Nevertheless, the earth swarms with spirits and demons, whose ill-will he tries to avert. His religion consists of nature-worship, and offerings to the ghosts of his ancestors; and his rites are more numerous even than those of the Hindus. First, the Race-god; next, the Tribe-god of each of the seven clans; then the Family-god, requires in turn his oblation. But besides these, there are the spirits of his forefathers, river-spirits, forest-spirits, well-demons, mountain-demons, and a mighty host of unseen beings, whom he must keep in good humour. He seems also to have borrowed from the Hindus some rites of sun-worship. But his own gods

Race-god ;
Tribe-
god ;
Family-
god ;
Demons.

dwelt chiefly in the ancient *sil* trees which shade his hamlets. There he propitiates by offerings of blood, with goats, cocks, and chickens. If the sacrificer cannot afford an animal, it is with a red flower, or a red fruit, that he draws near to his gods. In some hamlets, the people dance round every tree, so that they may not by evil chance miss the one in which the village-spirits happen to be dwelling.

Until nearly the end of the last century, the Santals were the pests of the neighbouring plains. Regularly after the December harvest, they sallied forth from their mountains, plundered the lowlands, levied black mail, and then retired with their spoil to their jungles. But in 1789, the British Government granted the proprietary right in the soil to the landholders of Bengal under the arrangements which four years later became the Permanent Settlement. Forthwith every landholder tried to increase the cultivated area on his estate, now become his own property. The Santals and other wild tribes were tempted to issue from their fastnesses by high wages or rent free farms. 'Every proprietor,' said a London newspaper, the *Morning Chronicle*, in 1792, 'is collecting his bandmen from the hills to improve his lowlands.' The English officers found they had a new race to deal with, and gradually won the highlanders to peaceful habits by grants of land and 'exemption from all taxes.' They were allowed to settle disputes 'among themselves by their own customs,' and they were used as a sort of frontier police, being paid to deliver up any of their own people who committed violent crimes. Such criminals, after being found guilty by their countrymen, were handed over for punishment to the English judge. The Santals gained confidence in us by degrees, and came down in great numbers within the fence of stone pillars, which the British officers set up in 1832 to mark off the country of the hill people from the plains.

The Santals under British rule

They come forth from the hills

The Hindu money lender soon made his appearance in their settlements, and the simple hillmen learned the new luxury of borrowing. Our laws were gradually applied to them, and before the middle of this century most of the Santal hamlets were plunged in debt. Their strong love of kindred prevented them from running away, and the Hindu usurers reduced them to a state of practical slavery, by threatening the terrors of a distant jail. In 1848, three whole villages threw up their clearings, and fled in despair to the jungle. In June 1855, the southern Santals started in a body, 30,000 strong, with their bows and arrows, to walk 140 miles to Calcutta and

The Santals sink into debt to the Hindus

Santál
rising,
1855.

lay their condition before the Governor-General. At first they were orderly; but the way was long, and they had to live. Robberies took place; quarrels broke out between them and the police; and within a week they were in armed rebellion. The rising was put down, not without mournful bloodshed; and their wrongs were carefully inquired into. A very simple form of administration was introduced, according to which their village head-men were brought into direct contact with the English officer in charge of the District, and acted as the representatives of the people. Our system of justice and government has been adapted to their primitive needs, and the Santáls have for years been among the most prosperous of the Indian races.

The
Kandhs or
Kondhs.

The Kandhs, literally 'The Mountaineers,' a tribe about 100,000 strong in 1872, inhabit the steep and forest-covered ranges which rise inland from the Orissa delta, and the Madras Districts of Ganjám and Vizagapatam. They form one of a group of non-Aryan races who still occupy the position assigned to them by the Greek geographers 1500 years ago. Before that early date, they had been pushed backwards by the advancing Aryans from the fertile delta which lies between the mountains and the sea. One section of the Kandhs was completely broken up, and has sunk into landless low-castes among the Aryan or Hindu communities at the foot of the hills. Another section stood its ground more firmly, and became a peasant militia, holding grants of land from the Hindu chiefs in return for military service. A third section fell back into the fastnesses of the mountains, and was recognised as a wild but free race. It is of this last section that the present chapter treats.

Breaking
up of the
race.

Kandh
patri-
archal
govern-
ment.

The Kandh idea of government is purely patriarchal. The family is strictly ruled by the father. The grown-up sons have no property during his life, but live in his house with their wives and children, and all share the common meal prepared by the grandmother. The clan consists of a number of families, sprung from a common father; and the tribe is made up in like manner from a number of clans who claim descent from the same ancestor. The head of the tribe is usually the eldest son of the patriarchal family; but if he be not fit for the post he is set aside, and an uncle or a younger brother appointed. He enters on no undertaking without calling together the heads of clans, who in their turn consult the heads of families.

Kandh
wars and
punish-
ments.

According to the Kandh theory of existence, a state of war might lawfully be presumed against all neighbours with

whom no express agreement had been made to the contrary Murders were punished by blood revenge, the kinsmen within a certain degree being one and all bound to kill the slayer, unless appeased by a payment of grain or cattle. The man who wounded another had to maintain the sufferer until he recovered from his hurt. A stolen article must be returned, or its equivalent paid, but the Kandh twice convicted of theft was driven forth from his tribe, the greatest punishment known to the race. Disputes were settled by combat, or by the ordeal of boiling oil or heated iron, or by taking a solemn oath on an ant hill, or on a tiger's claw, or a lizard's skin. When a house father died, leaving no sons, his land was parcelled out among the other male heads of the village, for no woman nor indeed any Kandh, was allowed to hold land who could not with his own hand defend it.

The Kandh system of tillage represented a stage half way between the migratory cultivation of the ruder non Aryan tribes and the settled agriculture of the Hindus. They did not, on the one hand, merely burn down a patch in the jungle, take a few crops off it, and then move on to fresh clearings. Nor, on the other hand, did they go on cultivating the same fields from father to son. When their lands showed signs of exhaustion, they deserted them, and it was a rule in some of their settlements to change their village sites once in fourteen years. Caste is unknown, and, as among the Santals, marriage between relations, or even within the same tribe is forbidden. A Kandh wedding consisted of forcibly carrying off the bride in the middle of a feast. The boy's father paid a price for the girl, and usually chose a strong one, several years older than his son. In this way, Kandh maidens were married about fourteen, Kandh boys about ten. The bride remained as a servant in her new father in law's house till her boy husband grew old enough to live with her. She generally acquired a great influence over him, and a Kandh may not marry a second wife during the life of his first one, except with her consent.

The Kandhs

all other inhabitants of a lower race, who were not allowed to hold land, to go forth to battle, or to join in the village worship. These poor people did the dirty work of the hamlet, and supplied families of hereditary weavers, blacksmiths, potters, herds men and distillers. They were kindly treated, and a portion of each feast was left for them. But they could never rise in the

social scale. No Kandh could engage in their work without degradation, nor eat food prepared by their hands. They can give no account of their origin, but are supposed to be the remnants of a ruder race whom the Kandhs found in possession of the hills when they themselves were pushed backwards by the Aryans from the plains.

Kandh
human
sacrifices.

The Kandhs, like the Santáls, have many deities, race-gods, tribe-gods, family-gods, and a multitude of malignant spirits and demons. But their great divinity is the Earth-god, who represents the productive energy of nature. Twice each year, at sowing-time and at harvest, and in all seasons of special calamity, the Earth-god required a human sacrifice (*meriah*). The duty of providing the victims rested with the lower race attached to the Kandh village. Brahmáns and Kandhs were the only classes exempted from sacrifice, and an ancient rule ordained that the offering *must be bought with a price*. Men of the lower race kidnapped the victims from the plains, and a thriving Kandh village usually kept a small stock in reserve, 'to meet sudden demands for atonement.' The victim, on being brought to the hamlet, was welcomed at every threshold, daintily fed, and kindly treated till the fatal day arrived. He was then solemnly sacrificed to the Earth-god, the Kandhs shouting in his dying ear, 'We bought you with a price; no sin rests with us!' His flesh and blood were distributed among the village lands.

The
victims.

The
sacrifice.

The
Kandhs
under
British
rule.

Human
sacrifices
abolished.

In 1835, the Kandhs passed under our rule, and these rites had to cease. The proud Kandh spirit shrank from compulsion; but after many tribal councils, they agreed to give up their stock of victims as a valuable present to their new suzerain. Care was taken that they should not procure fresh ones. The kidnapping of victims for human sacrifice was declared a capital offence; and their priests were led to discover that goats or buffaloes did quite as well for the Earth-god under British rule as human sacrifices. Until 1835, they consisted of separate tribes, always at war with each other and with the world. But under able English administrators (especially Campbell, Macpherson, and Cadenhead), human sacrifices were abolished, and the Kandhs were formed into a united and peaceful race (1837-45). The British officer removed their old necessity for tribal wars and family blood-feuds by setting himself up as a central authority. He adjusted their inter-tribal disputes, and punished heinous crimes. Lieutenant Charters Macpherson, in particular, won over the more troublesome clans to quiet industry, by grants of jungle tracts, of little use to us, but a

The race
won over
to peaceful
industry.

paradise to them, and where he could keep them well under his eye. He made the chiefs vain of carrying out his orders by small presents of cattle, honorific dresses, and titles. He enlisted the whole race on his side by picking out their best men for the police, and drew the tribes into amicable relations among themselves by means of hill fairs. He constructed roads, and taught the Kandhs to trade, with a view to 'drawing them from their fastnesses into friendly contact with other men'. The race has prospered and multiplied under British rule.

Whence came these primitive peoples, whom the Aryan invaders found in the land more than 3000 years ago, and who are still scattered over India, the fragments of a prehistoric world? Written annals they do not possess. Their oral traditions tell us little, but such hints as they yield, feebly point to the north. They seem to preserve dim memories of a time when their tribes dwelt under the shadow of mightier hill ranges than any to be found on the south of the river plains of Bengal. 'The Great Mountain' is the race god of the Santals, and an object of worship among other tribes. Indeed, the Gonds, who numbered 1½ million in the heart of Central India in 1872, have a legend that they were created at the foot of Dewālagiri peak in the Himālayas. Till lately, they buried their dead with the feet turned northwards, so as to be ready to start again for their ancient home in the north.

But the language of the non Aryan races, that record of a nation's past more enduring than rock inscriptions or tables of brass, is being slowly made to tell the secret of their origin. It already indicates that the early peoples of India belonged to three great stocks, known as the Tibeto Burman, the Kolarian, and the Dravidian.

The first stock, or Tibeto Burman tribes, cling to the skirts of the Himalayas and their north-eastern offshoots. They crossed over into India by the north-eastern passes, and in some prehistoric time had dwelt in Central Asia, side by side with the forefathers of the Mongolians and the Chinese. Several of the hill languages in Eastern Bengal preserve Chinese terms, others contain Mongolian. Thus, the Nāgās in Assam still use words for *three* and *water* which might almost be understood in the streets of Canton.¹

¹ The following are the twenty principal languages of the Tibeto Burman group — (1) Cachari or Bodo, (2) Garo, (3) Tipura or Mrung, (4) Tibetan or Bhotia, (5) Gurung, (6) Marma, (7) Newar, (8) Lepcha, (9) Mura, (10) Aka, (11) Mishmi dialects, (12) Dhimal, (13) Kanawari dialects, (14) Mfakir, (15) Singpho, (16) Nāgā dialects, (17) Kuki dialects, (18) Burmese,

- (2) The Kolarians The Kolarians, the second of the three non-Aryan stocks, appear also to have entered Bengal by the north-eastern passes. They dwell chiefly in the north, and along the north-eastern edge, of the three-sided table-land which covers the southern half of India. The Dravidians, or third stock, seem, generally speaking, on the other hand, to have found their way into the Punjab by the north-western passes. They now inhabit the southern part of the three-sided table-land, as far down as Cape Comorin, the southernmost point of India. It appears as if the two streams, namely the Kolarian tribes from the north-east and the Dravidians from the north-west, had converged and crossed each other in Central India. The Dravidians proved the stronger, broke up the Kolarians, and thrust aside their fragments to east and west. The Dravidians then rushed forward in a mighty body to the south.
- (3) The Dravidians. Their convergence in Central India.
- The Kolarians broken up. It thus came to pass that while the Dravidians formed a vast mass in Southern India, the Kolarians survived only as isolated tribes, so scattered as to soon forget their common

(19) Khyeng, and (20) Manipuri. 'It is impossible,' writes Mr. Brandreth, 'to give even an approximate number of the speakers included in this group, as many of the languages are either across the frontier or only project a short distance into our own territory. The languages included in this group have not, with perhaps one or two exceptions, both a cerebral and dental row of consonants, like the South-Indian languages; some of them have aspirated forms of the surds, but not of the sonants; others have aspirated forms of both. All the twenty dialects have words in common, especially numerals and pronouns, and also some resemblances of grammar. In comparing the resembling words, the differences between them consist often less in any modification of the root-syllable than in various additions to the root. Thus in Burmese we have *na*, "ear;" Tibetan, *rna-ba*; Magar, *na-kep*; Newar, *nai-pong*; Dhimal, *na-hathong*; Kiranti dialects, *na-pro*, *na-rék*, *na-phak*; Nágá languages, *te-na-ro*, *te-na-rang*; Manipuri, *na-kong*; Kupui, *ka-na*; Sak, *aka-na*; Karen, *na-khu*; and so on. It can hardly be doubted that such additions as these to monosyllabic roots are principally determinative syllables for the purpose of distinguishing between what would otherwise have been monosyllabic words having the same sound. These determinatives are generally affixed in the languages of Nepál and in the Dhimal language; prefixed in the Lepchá language, and in the languages of Assam, of Manipur, and of the Chittagong and Arakan Hills. Words are also distinguished by difference of tone. The tones are generally of two kinds, described as the abrupt or short, and the pausing or heavy. It has been remarked that those languages which are most given to adding other syllables to the root make the least use of the tones, and, *vice versa*, where the tones most prevail the least recourse is had to determinative syllables.'—This and the following quotations, from Mr. E. L. Brandreth, are condensed from his valuable paper in the *Journal of the Royal Asiatic Society*, New Series, vol. x. (1877), pp. 1-32.

origin We have seen one of the largest of the Kolarian races, the Santáls, dwelling on the extreme eastern edge of the three sided table land, where it slopes down into the Gangetic valley The Kurkus, a broken Kolarian tribe, inhabit a patch of country about 400 miles to the west They have for perhaps thousands of years been cut off from the Santáls by mountains and pathless forests, and by intervening races of the Dravidian and Aryan stocks The Kurkus and Santáls have no tradition of a common origin, yet at this day the Kurkus speak a language which is little else than a dialect of Santali The Savars, once a great Kolarian tribe, mentioned by Pliny and Ptolemy, are now a poor wandering race of woodcutters in Northern Madras and Orissa Yet fragments of them have lately been found deep in Central India, and as far west as Rajputána on the other side The Juangs are an isolated non Aryan remnant among an Aryan and Uriya speaking population They have forgotten, and disclaim, any connection with the Hos or other Kolarian tribes Nevertheless, their common origin is attested by a number of Kolarian words which they have unconsciously preserved ¹

Scattered
Kolarian
fragments

The compact Dravidians in the south, although in after days

¹ The nine principal languages of the Kolarian group are—(1) the Santal, (2) Mundari, (3) Ho, (4) Bhumij, (5) Korwa, (6) Kharia, (7) Juang, (8) Kurku, and perhaps (9) the Sava. Some of them, however, are separated only by dialectical differences 'The Kolarian group of languages,' writes Mr Brandreth, 'has both the cerebral and dental row of letters, and also aspirated forms, which last, according to Caldwell, did not belong to early Dravidian There is also a set of four sounds, which are perhaps peculiar to Santali, called by Skreftsdorf semi consonants and which when followed by a vowel, are changed respectively into *g*, *j*, *d* and *b* Gender of nouns is animate and inanimate, and is distinguished by difference of pronouns, by difference of suffix of a qualifying noun in the genitive relation, and by the gender being denoted by the verb As instances of the genitive suffix, we have in Santali *in ren hopon* "my son," but *in ak orak* "my house" There is no distinction of sex in the pronouns, but of the animate and inanimate gender The dialects generally agree in using a short form of the third personal pronoun suffixed to denote the number, dual and plural, of the noun, and short forms of all the personal pronouns are added to the verb in certain positions to express both number and person, both as regards the subject and object, if of the animate gender, the inanimate gender being indicated by the omission of these suffixes No other group of languages, apparently, has such a logical classification of its nouns as that shown by the genders of both the South Indian groups The genitive in the Kolarian group of the full personal pronouns is used for the possessive pronoun, which again takes all the post positions, the genitive relation being thus indicated by the genitive suffix twice repeated The Kolarian languages generally express grammatical relations by suffixes, and add the post positions directly to the root, without the intervention of an

- (2) The Kolarians The Kolarians, the second of the three non-Aryan stocks, appear also to have entered Bengal by the north-eastern passes. They dwell chiefly in the north, and along the north-eastern edge, of the three-sided table-land which covers the southern half of India. The Dravidians, or third stock, seem, generally speaking, on the other hand, to have found their way into the Punjab by the north-western passes. They now inhabit the southern part of the three-sided table-land, as far down as Cape Comorin, the southernmost point of India. It appears as if the two streams, namely the Kolarian tribes from the north-east and the Dravidians from the north-west, had converged and crossed each other in Central India. The Dravidians proved the stronger, broke up the Kolarians, and thrust aside their fragments to east and west. The Dravidians then rushed forward in a mighty body to the south.
- (3) The Dravidians. Their convergence in Central India.
- The Kolarians broken up. It thus came to pass that while the Dravidians formed a vast mass in Southern India, the Kolarians survived only as isolated tribes, so scattered as to soon forget their common

(19) Khyeng, and (20) Manipuri. 'It is impossible,' writes Mr. Brandreth, 'to give even an approximate number of the speakers included in this group, as many of the languages are either across the frontier or only project a short distance into our own territory. The languages included in this group have not, with perhaps one or two exceptions, both a cerebral and dental row of consonants, like the South-Indian languages; some of them have aspirated forms of the surds, but not of the sonants; others have aspirated forms of both. All the twenty dialects have words in common, especially numerals and pronouns, and also some resemblances of grammar. In comparing the resembling words, the differences between them consist often less in any modification of the root-syllable than in various additions to the root. Thus in Burmese we have *na*, "ear;" Tibetan, *na-ba*; Magar, *na-kep*; Newar, *nai-pong*; Dhimal, *na-hathong*; Kiranti dialects, *na-pro*, *na-rék*, *na-phak*; Nágá languages, *te-na-ro*, *te-na-rang*; Manipuri, *na-kong*; Kupui, *ka-na*; Sak, *aka-na*; Karen, *na-khu*; and so on. It can hardly be doubted that such additions as these to monosyllabic roots are principally determinative syllables for the purpose of distinguishing between what would otherwise have been monosyllabic words having the same sound. These determinatives are generally affixed in the languages of Nepál and in the Dhimal language; prefixed in the Lepchá language, and in the languages of Assam, of Manipur, and of the Chittagong and Arakan Hills. Words are also distinguished by difference of tone. The tones are generally of two kinds, described as the abrupt or short, and the pausing or heavy. It has been remarked that those languages which are most given to adding other syllables to the root make the least use of the tones, and, *vice versa*, where the tones most prevail the least recourse is had to determinative syllables.' — This and the following quotations, from Mr. E. L. Brandreth, are condensed from his valuable paper in the *Journal of the Royal Asiatic Society*, New Series, vol. x. (1877), pp. 1-32.

origin We have seen one of the largest of the Kolarian races, the Santāls, dwelling on the extreme eastern edge of the three sided table land, where it slopes down into the Gangetic valley The Kurkus, a broken Kolarian tribe, inhabit a patch of country about 400 miles to the west They have for perhaps thousands of years been cut off from the Santāls by mountains and pathless forests, and by intervening races of the Dravidian and Aryan stocks The Kurkus and Santāls have no tradition of a common origin, yet at this day the Kurkus speak a language which is little else than a dialect of Santāl The Savars, once a great Kolarian tribe, mentioned by Pliny and Ptolemy, are now a poor wandering race of woodcutters in Northern Madras and Orissa Yet fragments of them have lately been found deep in Central India, and as far west as Rajputāna on the other side The Juangs are an isolated non Aryan remnant among an Aryan and Uriya speaking population They have forgotten, and disclaim, any connection with the Hos or other Kolarian tribes Nevertheless, their common origin is attested by a number of Kolarian words which they have unconsciously preserved ¹

Scattered
Kolarian
fragments.

The compact Dravidians in the south, although in after days

¹ The nine principal languages of the Kolarian group are—(1) the Santāl, (2) Mundari, (3) Ho (4) Bhumij, (5) Korwa, (6) Kharia, (7) Juang, (8) Kurku and perhaps (9) the Savar Some of them, however, are separated only by dialectical differences 'The Kolarian group of languages, writes Mr Brandreth, 'has both the cerebral and dental row of letters, and also aspirated forms, which last, according to Caldwell, did not belong to early Dravidian There is also a set of four sounds, which are perhaps peculiar to Santāl called by Skrefsrud semi consonants and which when followed by a vowel, are changed respectively into *g j d* and *l* Gender of nouns is animate and inanimate and is distinguished by difference of pronouns, by difference of suffix of a qualifying noun in the genitive relation, and by the gender being denoted by the verb As instances of the genitive suffix, we have in Santāl *in ren hopon* 'my son,' but *in ak orak* 'my house' There is no distinction of sex in the pronouns but of the animate and inanimate gender The dialects generally agree in using a short form of the third personal pronoun suffixed to denote the number, dual and plural, of the noun, and short forms of all the personal pronouns are added to the verb in certain positions to express both number and person, both as regards the subject and object, if of the animate gender, the inanimate gender being indicated by the omission of these suffixes No other group of languages, apparently, has such a logical classification of its nouns as that shown by the genders of both the South Indian groups The genitive in the Kolarian group of the full personal pronouns is used for the possessive pronoun, which again takes all the post positions, the genitive relation being thus indicated by the genitive suffix twice repeated The Kolarian languages generally express grammatical relations by suffixes, and add the post positions directly to the root, without the intervention of an

- (2) The Kolarians The Kolarians, the second of the three non-Aryan stocks, appear also to have entered Bengal by the north-eastern passes. They dwell chiefly in the north, and along the north-eastern edge, of the three-sided table-land which covers the southern half of India. The Dravidians, or third stock, seem, generally speaking, on the other hand, to have found their way into the Punjab by the north-western passes. They now inhabit the southern part of the three-sided table-land, as far down as Cape Comorin, the southernmost point of India. It appears as if the two streams, namely the Kolarian tribes from the north-east and the Dravidians from the north-west, had converged and crossed each other in Central India. The Dravidians proved the stronger, broke up the Kolarians, and thrust aside their fragments to east and west. The Dravidians then rushed forward in a mighty body to the south.
- (3) The Dravidians. Their convergence in Central India.
- The Kolarians broken up. It thus came to pass that while the Dravidians formed a vast mass in Southern India, the Kolarians survived only as isolated tribes, so scattered as to soon forget their common

(19) Khyeng, and (20) Manipuri. 'It is impossible,' writes Mr. Brandreth, 'to give even an approximate number of the speakers included in this group, as many of the languages are either across the frontier or only project a short distance into our own territory. The languages included in this group have not, with perhaps one or two exceptions, both a cerebral and dental row of consonants, like the South-Indian languages; some of them have aspirated forms of the surds, but not of the sonants; others have aspirated forms of both. All the twenty dialects have words in common, especially numerals and pronouns, and also some resemblances of grammar. In comparing the resembling words, the differences between them consist often less in any modification of the root-syllable than in various additions to the root. Thus in Burmese we have *na*, "ear;" Tibetan, *rna-ba*; Magar, *na-kep*; Newar, *nai-pong*; Dhimal, *na-hathong*; Kiranti dialects, *na-pro*, *na-rik*, *na-phak*; Naga languages, *te-na-ro*, *te-na-rang*; Manipuri, *na-kong*; Kupui, *ka-na*; Sak, *aka-na*; Karen, *na-khu*; and so on. It can hardly be doubted that such additions as these to monosyllabic roots are principally determinative syllables for the purpose of distinguishing between what would otherwise have been monosyllabic words having the same sound. These determinatives are generally affixed in the languages of Nepal and in the Dhimal language; prefixed in the Lepcha language, and in the languages of Assam, of Manipur, and of the Chittagong and Arakan Hills. Words are also distinguished by difference of tone. The tones are generally of two kinds, described as the abrupt or short, and the pausing or heavy. It has been remarked that those languages which are most given to adding other syllables to the root make the least use of the tones, and, *vice versa*, where the tones most prevail the least recourse is had to determinative syllables.'—This and the following quotations, from Mr. E. L. Brandreth, are condensed from his valuable paper in the *Journal of the Royal Asiatic Society*, New Series, vol. x. (1877), pp. 1-32.

origin We have seen one of the largest of the Kolarian races, the Santáls, dwelling on the extreme eastern edge of the three sided table land, where it slopes down into the Gangetic valley The Kurkus, a broken Kolarian tribe, inhabit a patch of country about 400 miles to the west They have for perhaps thousands of years been cut off from the Santáls by mountains and pathless forests, and by intervening races of the Dravidian and Aryan stocks The Kurkus and Santáls have no tradition of a common origin, yet at this day the Kurkus speak a language which is little else than a dialect of Santali The Savars, once a great Kolarian tribe, mentioned by Pliny and Ptolemy, are now a poor wandering race of woodcutters in Northern Madras and Orissa Yet fragments of them have lately been found deep in Central India, and as far west as Rajputana on the other side The Juangs are an isolated non Aryan remnant among an Aryan and Uriya speaking population They have forgotten, and disclaim, any connection with the Hos or other Kolarian tribes Nevertheless, their common origin is attested by a number of Kolarian words which they have unconsciously preserved ¹

Scattered
Kolarian
fragments

The compact Dravidians in the south, although in after days

¹ The nine principal languages of the Kolarian group are—(1) the Santal (2) Mundáns (3) Ho (4) Bhumij (5) Korwa (6) Kharia, (7) Juang, (8) Kurku and perhaps (9) the Savar Some of them however, are separated only by dialectical differences 'The Kolarian group of languages, writes Mr Brandreth, 'has both the cerebral and dental row of letters, and also aspirated forms which last, according to Caldwell, did not belong to early Dravidian There is also a set of four sounds which are perhaps peculiar to Santali called by Skrefsrud semi consonants and which when followed by a vowel, are changed respectively into *g j l* and *b* Gender of nouns is animate and inanimate and is distinguished by difference of pronouns, by difference of suffix of a qualifying noun in the genitive relation, and by the gender being denoted by the verb As instances of the genitive suffix we have in Santali *in ren hopon* "my son but *in ak oral* my house There is no distinction of sex in the pronouns but of the animate and inanimate gender The dialects generally agree in using a short form of the third personal pronoun suffixed to denote the number, dual and plural of the noun and short forms of all the personal pronouns are added to the verb in certain positions to express both number and person both as regards the subject and object, if of the animate gender the inanimate gender being indicated by the omission of these suffixes No other group of languages, apparently, has such a logical classification of its nouns as that shown by the genders of both the South Indian groups The genitive in the Kolarian group of the full personal pronouns is used for the possessive pronoun, which again takes all the post positions, the genitive relation being thus indicated by the genitive suffix twice repeated The Kolarian languages generally express grammatical relations by suffixes, and add the post positions directly to the root, without the intervention of an

- (2) The Kolarians The Kolarians, the second of the three non-Aryan stocks, appear also to have entered Bengal by the north-eastern passes. They dwell chiefly in the north, and along the north-eastern edge, of the three-sided table-land which covers the southern half of India. The Dravidians, or third stock, seem, generally speaking, on the other hand, to have found their way into the Punjab by the north-western passes. They now inhabit the southern part of the three-sided table-land, as far down as Cape Comorin, the southernmost point of India. It appears as if the two streams, namely the Kolarian tribes from the north-east and the Dravidians from the north-west, had converged and crossed each other in Central India. The Dravidians proved the stronger, broke up the Kolarians, and thrust aside their fragments to east and west. The Dravidians then rushed forward in a mighty body to the south.
- (3) The Dravidians. Their convergence in Central India.
- The Kolarians broken up. It thus came to pass that while the Dravidians formed a vast mass in Southern India, the Kolarians survived only as isolated tribes, so scattered as to soon forget their common

(19) Khyeng, and (20) Manipuri. 'It is impossible,' writes Mr. Brandreth, 'to give even an approximate number of the speakers included in this group, as many of the languages are either across the frontier or only project a short distance into our own territory. The languages included in this group have not, with perhaps one or two exceptions, both a cerebral and dental row of consonants, like the South-Indian languages; some of them have aspirated forms of the surds, but not of the sonants; others have aspirated forms of both. All the twenty dialects have words in common, especially numerals and pronouns, and also some resemblances of grammar. In comparing the resembling words, the differences between them consist often less in any modification of the root-syllable than in various additions to the root. Thus in Burmese we have *na*, "ear;" Tibetan, *na-ba*; Magar, *na-kep*; Newar, *nai-pang*; Dhimal, *na-hathong*; Kiranti dialects, *na-pro*, *na-rék*, *na-phak*; Nágá languages, *te-na-ro*, *te-na-rang*; Manipuri, *na-kong*; Kupui, *ka-na*; Sak, *aka-na*; Karen, *na-khu*; and so on. It can hardly be doubted that such additions as these to monosyllabic roots are principally determinative syllables for the purpose of distinguishing between what would otherwise have been monosyllabic words having the same sound. These determinatives are generally affixed in the languages of Nepál and in the Dhimal language; prefixed in the Lepchá language, and in the languages of Assam, of Manipur, and of the Chittagong and Arakan Hills. Words are also distinguished by difference of tone. The tones are generally of two kinds, described as the abrupt or short, and the pausing or heavy. It has been remarked that those languages which are most given to adding other syllables to the root make the least use of the tones, and, *vice versa*, where the tones most prevail the least recourse is had to determinative syllables.' — This and the following quotations, from Mr. E. L. Brandreth, are condensed from his valuable paper in the *Journal of the Royal Asiatic Society*, New Series, vol. x. (1877), pp. 1-32.

origin We have seen one of the largest of the Kolarian races, the Santáls, dwelling on the extreme eastern edge of the three sided table land, where it slopes down into the Gangetic valley The Kurkus, a broken Kolarian tribe, inhabit a patch of country about 400 miles to the west They have for perhaps thousands of years been cut off from the Santáls by mountains and pathless forests, and by intervening races of the Dravidian and Aryan stocks The Kurkus and Santáls have no tradition of a common origin, yet at this day the Kurkus speak a language which is little else than a dialect of Santali The Savars, once a great Kolarian tribe, mentioned by Pliny and Ptolemy, are now a poor wandering race of woodcutters in Northern Madras and Orissa Yet fragments of them have lately been found deep in Central India, and as far west as Rajputána on the other side The Juangs are an isolated non Aryan remnant among an Aryan and Uriya speaking population They have forgotten, and disclaim, any connection with the Hos or other Kolarian tribes Nevertheless, their common origin is attested by a number of Kolarian words which they have unconsciously preserved ¹

Scattered
Kolarian
fragments.

The compact Dravidians in the south, although in after days

¹ The nine principal languages of the Kolarian group are—(1) the Santal, (2) Mundari, (3) Ho (4) Bhumij, (5) Korwa (6) Kharia, (7) Juang, (8) Kurku and perhaps (9) the Savar Some of them, however, are separated only by dialectical differences 'The Kolarian group of languages, writes Mr Brandreth, 'has both the cerebral and dental row of letters and also aspirated forms, which last, according to Caldwell, did not belong to early Dravidian There is also a set of four sounds, which are perhaps peculiar to Santali, called by Skreftud semi consonants and which, when followed by a vowel, are changed respectively into *g*, *j*, *d*, and *b* Gender of nouns is animate and inanimate and is distinguished by difference of pronouns, by difference of suffix of a qualifying noun in the genitive relation, and by the gender being denoted by the verb As instances of the genitive suffix, we have in Santali *in ren hopon* "my son," but *in ak orak* "my house" There is no distinction of sex in the pronouns, but of the animate and inanimate gender The dialects generally agree in using a short form of the third personal pronoun suffixed to denote the number, dual and plural, of the noun, and short forms of all the personal pronouns are added to the verb in certain positions to express both number and person, both as regards the subject and object, if of the animate gender, the inanimate gender being indicated by the omission of these suffixes No other group of languages, apparently, has such a logical classification of its nouns as that shown by the genders of both the South Indian groups The genitive in the Kolarian group of the full personal pronouns is used for the possessive pronoun, which again takes all the post positions, the genitive relation being thus indicated by the genitive suffix twice repeated The Kolarian languages generally express grammatical relations by suffixes, and add the post positions directly to the root, without the intervention of an

(2) The
Kolarians

(3) The
Dravidi-
ans.

Their con-
vergence
in Central
India.

The Kol-
arians
broken
up.

The Kolarians, the second of the three non-Aryan stocks, appear also to have entered Bengal by the north-eastern passes. They dwell chiefly in the north, and along the north-eastern edge, of the three-sided table-land which covers the southern half of India. The Dravidians, or third stock, seem, generally speaking, on the other hand, to have found their way into the Punjab by the north-western passes. They now inhabit the southern part of the three-sided table-land, as far down as Cape Comorin, the southernmost point of India. It appears as if the two streams, namely the Kolarian tribes from the north-east and the Dravidians from the north-west, had converged and crossed each other in Central India. The Dravidians proved the stronger, broke up the Kolarians, and thrust aside their fragments to east and west. The Dravidians then rushed forward in a mighty body to the south.

It thus came to pass that while the Dravidians formed a vast mass in Southern India, the Kolarians survived only as isolated tribes, so scattered as to soon forget their common

(19) Khyeng, and (20) Manipuri. 'It is impossible,' writes Mr. Brandreth, 'to give even an approximate number of the speakers included in this group, as many of the languages are either across the frontier or only project a short distance into our own territory. The languages included in this group have not, with perhaps one or two exceptions, both a cerebral and dental row of consonants, like the South-Indian languages; some of them have aspirated forms of the surds, but not of the sonants; others have aspirated forms of both. All the twenty dialects have words in common, especially numerals and pronouns, and also some resemblances of grammar. In comparing the resembling words, the differences between them consist often less in any modification of the root-syllable than in various additions to the root. Thus in Burmese we have *na*, "ear;" Tibetan, *rna-ba*; Magar, *na-kep*; Newar, *nai-pong*; Dhimal, *na-hathong*; Kiranti dialects, *na-pro*, *na-rék*, *na-phak*; Nágá languages, *te-na-ro*, *te-na-rang*; Manipuri, *na-kong*; Kupui, *ka-na*; Sak, *aka-na*; Karen, *na-khu*; and so on. It can hardly be doubted that such additions as these to monosyllabic roots are principally determinative syllables for the purpose of distinguishing between what would otherwise have been monosyllabic words having the same sound. These determinatives are generally affixed in the languages of Nepál and in the Dhimal language; prefixed in the Lepchá language, and in the languages of Assam, of Manipur, and of the Chittagong and Arakan Hills. Words are also distinguished by difference of tone. The tones are generally of two kinds, described as the abrupt or short, and the pausing or heavy. It has been remarked that those languages which are most given to adding other syllables to the root make the least use of the tones, and, *vice versa*, where the tones most prevail the least recourse is had to determinative syllables.' — This and the following quotations, from Mr. E. L. Brandreth, are condensed from his valuable paper in the *Journal of the Royal Asiatic Society*, New Series, vol. x. (1877), pp. 1-32.

origin We have seen one of the largest of the Kolarian races, the Santāls, dwelling on the extreme eastern edge of the three sided table land, where it slopes down into the Gangetic valley The Kurkūs, a broken Kolarian tribe, inhabit a patch of country about 400 miles to the west They have for perhaps thousands of years been cut off from the Santāls by mountains and pathless forests, and by intervening races of the Dravidian and Aryan stocks The Kurkūs and Santāls have no tradition of a common origin, yet at this day the Kurkūs speak a language which is little else than a dialect of Santāl Scattered
Kolarian
fragments The Savars, once a great Kolarian tribe, mentioned by Pliny and Ptolemy, are now a poor wandering race of woodcutters in Northern Madras and Orissa Yet fragments of them have lately been found deep in Central India, and as far west as Rajputāna on the other side The Juangs are an isolated non Aryan remnant among an Aryan and Uriya speaking population They have forgotten, and disclaim, any connection with the Hos or other Kolarian tribes Nevertheless, their common origin is attested by a number of Kolarian words which they have unconsciously preserved ¹

The compact Dravidians in the south, although in after days

¹ The nine principal languages of the Kolarian group are—(1) the Santāl, (2) Mundari, (3) Ho, (4) Bhumij, (5) Korwa, (6) Kharia, (7) Juang, (8) Kurkū, and perhaps (9) the Savar Some of them, however, are separated only by dialectical differences The Kolarian group of languages, writes Mr Brandreth, 'has both the cerebral and dental row of letters, and also aspirated forms, which last, according to Caldwell, did not belong to early Dravidian There is also a set of four sounds, which are perhaps peculiar to Santāl, called by Skreftud semi consonants and which, when followed by a vowel, are changed respectively into *g*, *j*, *d* and *b* Gender of nouns is animate and inanimate, and is distinguished by difference of pronouns, by difference of suffix of a qualifying noun in the genitive relation, and by the gender being denoted by the verb As instances of the genitive suffix, we have in Santāl *in ren hapon* "my son," but *in ak orak* "my house" There is no distinction of sex in the pronouns, but of the animate and inanimate gender The dialects generally agree in using a short form of the third personal pronoun suffixed to denote the number, dual and plural, of the noun, and short forms of all the personal pronouns are added to the verb in certain positions to express both number and person, both as regards the subject and object, if of the animate gender, the inanimate gender being indicated by the omission of these suffixes No other group of languages, apparently, has such a logical classification of its nouns as that shown by the genders of both the South Indian groups The genitive in the Kolarian group of the full personal pronouns is used for the possessive pronoun, which again takes all the post positions, the genitive relation being thus indicated by the genitive suffix twice repeated The Kolarian languages generally express grammatical relations by suffixes, and add the post positions directly to the root, without the intervention of an

The compact Dravidians of Southern India;

Their offshoots beyond sea(?)

subdued by the higher civilisation of the Aryan race which pressed in among them, were never thus broken into fragments.¹ Their pure descendants consist, indeed, of small and scattered tribes; but they have given their language to 28 millions of people in Southern India. A theory has been started that some of the islands in the distant Pacific Ocean were peopled either from the Dravidian settlements in India, or from an earlier common source. Bishop Caldwell points out that the aboriginal tribes in Southern and Western Australia use almost the same words for *I, thou, he, we, you*, etc., as the Dravidian fishermen on the Madras coast; and resemble in other ways the Madras hill tribes, as in the use of their national weapon, the boomerang. The civilisation and literature which the Dravidians developed in Southern India will be described in a later chapter on the Indian vernaculars.

oblique form or genitive or other suffix. They agree with the Dravidian in having inclusive and exclusive forms for the plural of the first personal pronoun, in using a relative participle instead of a relative pronoun, in the position of the governing word, and in the possession of a true causal form of the verb. They have a dual, which the Dravidians have not, but they have no negative voice. Counting is by twenties, instead of by tens, as in the Dravidian. The Santáli verb, according to Skrefsrud, has 23 tenses, and for every tense two forms of the participle and a gerund.

¹ Bishop Caldwell recognises twelve distinct Dravidian languages:— (1) Tamil, (2) Malayálam, (3) Telugu, (4) Kanarese, (5) Tulu, (6) Kudugu, (7) Toda, (8) Kota, (9) Gond, (10) Kandh, (11) Uráon, (12) Rájmahal. 'In the Dravidian group,' writes Mr. Brandreth, 'there is a rational and an irrational gender of the nouns, which is distinguished in the plural of the nouns, and sometimes in the singular also, by affixes which appear to be fragmentary pronouns, by corresponding pronouns, and by the agreement of the verb with the noun, the gender of the verb being expressed by the pronominal suffixes. To give an instance of verbal gender, we have in Tamil, from the root *sey*, "to do," *seyd-an*, "he (rational) did;" *seyd-ál*, "she (rational) did;" *seyd-adu*, "it (irrational) did;" *seyd-ar*, "they (the rationals) did;" *seyd-a*, "they (the irrationals) did;" the full pronouns being *avan*, "he;" *aval*, "she;" *adu*, "it;" *avar*, "they;" *avei*, "they." This distinction of gender, though it exists in most of the Dravidian languages, is not always carried out to the extent that it is in Tamil. In Telugu, Gond, and Kandh, it is preserved in the plural, but in the singular the feminine rational is merged in the irrational gender. In Gond, the gender is further marked by the noun in the genitive relation taking a different suffix, according to the number and gender of the noun on which it depends. In Uráon, the feminine rational is entirely merged in the irrational gender, with the exception of the pronoun, which preserves the distinction between rationals and irrationals in the plural; thus, *as*, "he," referring to a god or a man; *ad*, "she" or "it," referring to a woman or an irrational object; but *ar*, "they," applies to both men and women; *abra*, "they," to irrationals only. The rational gender, besides human beings, includes the celestial and infernal deities; and it is further

The following is a list of 142 of the principal non Aryan languages and dialects, prepared by Mr Brandreth for the Royal Asiatic Society in 1877, and classified according to their grammatical structure. Mr Robert Cust has also arranged them in another convenient form, according to their geographical habitat

TABLE OF THE NON ARYAN LANGUAGES OF INDIA ¹

Dravidian Group	Dravidian Group—continued
Tamil	<i>Yerukala</i>
Malayalam	<i>Gadaba</i> (Kolarian?)
Telugu	
{ Kanarese	KOLARIAN GROUP
{ Badaga.	Santali
Tulu	{ Mundari
Kudugu or Coorg.	{ Ho or Larka Kol
Toda.	{ Bhumij
Kota.	Korwa
Gond dialects.	Kharria
{ <i>Mahadeo</i>	Juang
{ <i>Rdy</i>	{ Kuri
{ <i>Maria</i>	{ Kurku
Kandh or Ku	Mehto
Uraon or Dhanur	Savara
Pajmahal or Maler	
Miscellaneous Dialects	TIBETO BURMAN GROUP
{ <i>Naskude</i>	I { Kachari or Bodo
{ <i>Kolami</i>	{ Mech
<i>Kekadi</i>	{ Hojai

sub divided, in some of the languages but in the singular only, into masculine and feminine. The grammatical relations in the Dravidian are generally expressed by suffixes. Many nouns have an oblique form, which is a remarkable characteristic of the Dravidian group, still, with the majority of nouns, the post positions are added directly to the nominative form. Other features of this group are—the frequent use of formatives to specialize the meaning of the root, the absence of relative pronouns and the use instead of a relative participle which is usually formed from the ordinary participle by the same suffix as that which Dr Caldwell considers as the oldest sign of the genitive relation, the adjective preceding the substantive, of two substantives the determining preceding the determined, and the verb being the last member of the sentence. There is no true dual in the Dravidian languages. In the Dravidian languages there are two forms of the plural of the pronoun of the first person, one including, the other excluding, the person addressed. As regards the verbs, there is a negative voice but no passive voice, and there is a causal form. For Caldwell's second edition of his great work, the *Comparative Grammar of the Dravidian Languages* (Trubner, 1875), forms in itself an epoch in the department of human knowledge. Mr Beames' *Comparative Grammar of the Modern Aryan Languages of India* (Trubner, 1872) has laid the foundation for the accurate study of North Indian languages. Dr Dalton's *Ethnology of Bengal* (Calcutta, 1872), and Sir George Campbell's *Specimens of the Languages of India* (Bengal Secretariat Press, 1872) have also shed new and valuable light on the questions at issue.

¹ Brackets refer to dialects that are very closely related to those beyond the circle of the Indian languages. (See also p. 68.)

Tibeto-Burman Group—*continued*.

- Gáro.
Páni-Koch.
Deori-Chutia.
Tipura or Mrung.
II. { Tibetan or Bhutiá.
{ Sarpa.
{ Lhopa or Bhutáni.
Changlo.
Twang.
III. { Gurung.
{ Murmi.
Tháksya.
{ Newar.
{ Palri.
Magar.
IV. Lepchá.
V. Daphlá.
Miri.
Abar.
Bhutiá of Lo.
VI. Aka.
VII. Mishmi dialects.
Chulikata.
Taying or Dígaru.
Mijhu.
VIII. Dhimal.
IX. Kanáwari dialects.
{ *Milchan.*
{ *Tibarskad.*
{ *Sumchu.*
X. { Kiranti.
{ Limbu.
Sunwár.
Brámu.
Chepang.
Váyu.
Kusunda.
XI. Nágá dialects.
Namsang or Fáipuria.
{ *Banpára* or *Joboka.*
{ *Mithan.*
{ *Tablung.*
{ *Mulung.*
XII. Nágá dialects.
Kharí.
{ *Naungdon.*
{ *Tengsa.*
Lhota.
XIII. Nágá dialects.
Angámi.
Rengma.
{ *Arung.*
{ *Kutcha.*
Liyang or Kaieng.
Marám.
XIV. Mikir.
XV. { Singpho.
{ Jili.
XVI. Burmese.
XVII. Kuki dialects.
Khyeng.

Tibeto-Burman Group—*continued*.

- { *Thado.*
{ *Lushai.*
{ *Hallami.*
Manipuri.
{ Maring.
{ Khoibu.
Kupui.
Tangkhu.
Luhupa.
Khungui.
Phadang.
Champhung.
Kupome.
Takaini.
Andro and Sengmai.
Chairel.
Anal and Namfau.
XVIII. { Kumi.
{ Kami.
Mru.
{ Banjogi or Lungkhe.
{ Pankho.
Shendu or Poi.
Sak.
Kyau.
XIX. Karen dialects.
Sgau.
Bghai.
Red Karen.
Pwo.
Taiu.
Mopgha.
Kay or *Gaikho.*
Taungthu.
†Lísaw.
†Gyarung.
†Takpa.
†Manyak.
†Thochu.
†Horpa.

KHASI.

Khási.

TAI.

{ Siamese or Thai.
{ Lao.
{ Shan.
{ Ahom.
{ Khamti.
{ Aiton.
†Tai Mow or Chinese Shan.

MON-ANAM.

Mon.
†Kambojan.
†Anamese.
†Paloung.

NON ARYAN CENSUS OF INDIA

69

We discern, therefore, long before the dawn of history, masses of men moving uneasily over India, and violently pushing in among still earlier tribes. They crossed the snows of the Himalayas, and plunged into the tropical forests in search of new homes. Of these ancient races, fragments now exist almost in exactly the same stage of human progress as they were described by Vedic poets more than 3000 years ago. Some are dying out, such as the Andaman islanders, among whom in 1869 only one family had as many as three children. Others are increasing like the Santals, who have doubled themselves under British rule. But they all require special and anxious care in adapting our complex administration to their primitive condition and needs. Taken as a whole, and including certain half-Hinduized branches, they numbered 17,627,758 in 1872, then about equal to three quarters of the population of England and Wales. But while the bolder or more isolated of the aboriginal races have thus kept them selves apart, by far the greater portion submitted in ancient times to the Aryan invaders, and now make up the mass of the Hindus.

The following table shows the distribution of the aboriginal tribes throughout British India in 1872. But many live in Native States, not included in this enumeration, and the Madras Census of 1872 did not distinguish aborigines from low caste Hindus. Their total number throughout all India (British and Feudatory) probably exceeded 20 millions in 1872.

Aboriginal Tribes and Semi-Hinduized Aborigines in 1872
(Madras Presidency and the Feudatory States not included)

Bengal,	11,116,883
Assam,	1,490,888
North Western Provinces,	377,674
Oudh,	90,490
Punjab,	959,720
Central Provinces,	1,669,835
Berar,	163,039
Coorg,	42,516
British Burma,	1,004,991
Bombay,	711,702
	<hr/>
	17,627,758

As already stated, the Census of 1881 adopted a classification which fails to clearly distinguish the aboriginal elements in the Indian population. In the North Western Provinces, Oudh,

Not
separately
returned.

and the Punjab, which returned an aggregate of nearly $1\frac{1}{2}$ millions of aboriginal or non-Aryan castes or tribes in 1872, no separate return of the aboriginal or non-Aryan element was made in 1881. It is merged by the enumerators in the returns of the Hindu low-castes. The same process has affected the returns of other Provinces. In Madras, for example, 27 castes formerly included in the list of aboriginal tribes, were transferred to the Hindu section of the population. In Bengal, the Census officers explain that the non-registration of the aboriginal element is in some cases due to 'radical differences in the system upon which the castes, and especially the sub-divisions of castes, were classified in 1872 and in 1881.' In the North-Western Provinces and Oudh, the special officer states that his system of classification 'is not compatible with the modern doctrine which divides the population of India into Aryan and aboriginal.'

No com-
mon data
for 1872
and 1881.

Hinduiz-
ing ten-
dencies.

Under these circumstances it would be misleading to attempt a comparison between the returns of the aboriginal or non-Aryan population in 1872 and in 1881. On the one hand, there can be no doubt that the aboriginal castes and tribes are, in many parts of the country, tending towards Hinduism; and that many of them, as they rise in the scale of civilisation, lose their identity in the Hindu community. On the other hand, it is evident that the decreased returns of the aboriginal tribes and castes in 1881 are not entirely, or indeed chiefly, due to this process. It would be erroneous, therefore, to infer that the balance of $12\frac{3}{4}$ millions between the $17\frac{1}{2}$ millions of aborigines returned for British India in 1872 and the $4\frac{3}{4}$ millions nominally returned in 1881, had become Hindus.

A Hinduizing process is going on both among the aboriginal low castes in Hindu Provinces, and among the aboriginal tribes who border on such Provinces. But the apparent disappearance of nearly 13 millions of aborigines between 1872 and 1881 is due, not so much to this Hinduizing process, as to differences in the system of classification and registration adopted by the Census officers. That the disappearance of the Indian aborigines is apparent and not real, can be proved. The birth-rate among some of the aboriginal races is unusually high; and, with exceptions, the aboriginal tribes and castes are numerically increasing, although they are partially merging their separate identity in the Hindu community.

In Bengal and Assam, the aboriginal races are divided into

CRUSHED TRIBES, PREDATORY CLANS. 71

nearly 60 distinct tribes¹ In the North Western Provinces, Their principal races in 16 tribes of aborigines were enumerated in the Census of 1872 In the Central Provinces they numbered 1 $\frac{3}{4}$ millions (1872), the 1872 ancient race of Gonds, who ruled the central table land before the rise of the Marathás, alone amounting to 1 $\frac{1}{2}$ millions In British Burma, the Karens, whose traditions have a singularly Jewish tinge, numbered 330,000 in 1872, and 518,294 in 1881

In Oudh, the nationality of the aboriginal tribes has been buried beneath waves of Rájput and Muhammadan invaders For example, the Bhars, formerly the monarchs of the centre and east of that Province and the traditional fort builders to whom all ruins are popularly assigned, were stamped out by Ibráhim Shárkí of Jaunpur, in the 15th century The Gaulis or ancient ruling race of the Central Provinces, the Ahams of Assam, and the Gonds, Chandels, and Bundels of Bundelkhand,² are other instances of crushed races In centres of the Aryan civilisation, the aboriginal peoples have been pounded down in the mortar of Hinduism into the low castes and out castes on which the social fabric of India rests A few of them, how ever, still preserve their ethnical identity as wandering tribes of jugglers, basket weavers, and fortune tellers Thus, the Náts, Bediyas, and other gipsy clans are recognised to this day as distinct from the surrounding Hindu population

The aboriginal races on the plains have supplied the Aboriginal hereditary criminal classes, alike under the Hindus, the Muhammadans, and the British Formerly organized robber tribes communities, they have, under the stricter police of our days, sunk into petty pilferers But their existence is still recognised by the Criminal Tribes Act, passed so lately as 1871, and still enforced within certain localities of Oudh and Northern India

The non Aryan hill races, who appear from Vedic times down Pred wards as marauders, have at length ceased to be a disturbing hill element in India But many of them figure as predatory clans in Muhammadan and early British history They sallied forth from their mountains at the end of the autumn harvest, pillaged and burned the lowland villages, and retired to their fastnesses laden with the booty of the plains The measures

¹ Among them may be noted the Santáls, 850,000 under direct British administration, total about a million in 1872, Kols, 300,000, Uraons or Dhangars, 200,000, and Mundas 175,000—within British territory In Assam—Cacharís, 200,000, Khasís, 95,000 These figures all refer to 1872

² See for the origin of the Bundelas, Mr J Peames' *Races of the Northern Provinces*, vol. 1 p 45 etc (1869)

by which these wild races have been reclaimed, form some of the most honourable episodes of Anglo-Indian rule. Cleveland's Hill-Rangers in the last century, and the Bhils and Mhairs in more recent times, are well-known examples of how marauding races may be turned into peaceful cultivators and loyal soldiers. An equally salutary transformation has taken place in many a remote forest and hill tract of India. The firm order of British rule has rendered their old plundering life no longer a possible one, and at the same time has opened up to them new outlets for their energies. A similar vigilance is now being extended to the predatory tribes in the Native States. The reclamation of the wild Moghias of Central India, and their settlement into agricultural communities, has been effected by British officers within the past five years.

Character
of the
non-Aryan
tribes.

The hill and forest tribes differ in character from the tamer population of the plains. Their truthfulness, sturdy loyalty, and a certain joyous bravery, almost amounting to playfulness, appeal in a special manner to the English mind. There is scarcely a single administrator who has ruled over them for any length of time without finding his heart drawn to them, and leaving on record his belief in their capabilities for good. Lest the traditional tenderness of the Indian Civil Service to the people should weaken the testimony of such witnesses, it may be safe to quote only the words of soldiers with reference to the tribes with which each was specially acquainted.

The non-
Aryan hill
tribes as
soldiers.

'They are faithful, truthful, and attached to their superiors,' writes General Briggs; 'ready at all times to lay down their lives for those they serve, and remarkable for their indomitable courage. These qualities have always been displayed in our service. The aborigines of the Karnatik were the sepoy of Clive and of Coote. A few companies of the same stock joined the former great captain from Bombay, and helped to fight the battle of Plassey in Bengal, which laid the foundation of our Indian Empire. They have since distinguished themselves in the corps of pioneers and engineers, not only in India, but in Ava, in Afghánistán, and in the celebrated defence of Jalálábád. An unjust prejudice against them grew up in the native armies of Madras and Bombay, produced by the feelings of contempt for them existing among the Hindu and Muhammadan troops. They have no prejudices themselves; are always ready to serve abroad and embark on board ship; and I believe no instance of mutiny has ever occurred among them.' Since General Briggs wrote these

HIGH QUALITIES OF NON ARYANS 73

ntences, the non Aryan hill races have supplied some of the
 ravest and most valued of our Indian regiments, particularly
 he gallant little Gurkhas

Colonel Dixon's report, published by the Court of Directors, Colonel
 portrays the character of the Mhair tribes with admirable minute
 Dixon on the
 Mhairs
 ness He dilates on their 'fidelity, truth, and honesty,' their
 determined valour, their simple loyalty, and an extreme and
 almost touching devotion when put upon their honour Strong
 as is the bond of kindred among the Mhairs, he vouches for
 their fidelity in guarding even their own relatives as prisoners
 when formally entrusted to their care For centuries they had
 been known only as exterminators, but beneath the considerate
 handling of one Englishman who honestly set about under
 standing them they became peaceful subjects and well
 disciplined soldiers

Sir James Outram, when a very young man, did the same Outram a
 good work for the Bhils of KHANDESH He made their chiefs work
 his hunting companions, formed the wilder spirits into a Bhil Bhils
 battalion, and laid the basis for the reclamation of this for
 merly intractable race (See also THE DANGS, *Imperial*
Gazetteer of India)

Every military man who has had anything to do with the
 aboriginal races acknowledges that once they admit a claim on
 their allegiance, nothing tempts them to a treacherous or disloyal
 act 'The fidelity to their acknowledged chief, wrote Captain Fidelity of
 Hunter, 'is very remarkable, and so strong is their attach the hill
 races
 ment, that in no situation or condition however desperate, can
 they be induced to betray him If old and decrepit, they will
 convey him from place to place to save him from his enemies
 Their obedience to recognised authority is absolute, and
 Colonel Tod relates how the wife of an absent chieftain pro-
 cured for a British messenger safe conduct and hospitality
 through the densest forests by giving him one of her husband's
 arrows as a token The very officers who have had to act
 most sharply against them speak most strongly, and often not
 without a noble regret and self reproach, in their favour 'It
 was not war,' Major Vincent Jervis writes of the operations
 against the Santals in 1855 'They did not understand
 yielding, as long as their national drums beat, the whole party
 would stand, and allow themselves to be shot down They
 were the most truthful set of men I ever met'

We have seen that India may be divided into three regions—
 the Himálayas on the north, the great River Plains that stretch ra

by which these wild races have been reclaimed, form some of the most honourable episodes of Anglo-Indian rule. Cleveland's Hill-Rangers in the last century, and the Bhils and Mhairs in more recent times, are well-known examples of how marauding races may be turned into peaceful cultivators and loyal soldiers. An equally salutary transformation has taken place in many a remote forest and hill tract of India. The firm order of British rule has rendered their old plundering life no longer a possible one, and at the same time has opened up to them new outlets for their energies. A similar vigilance is now being extended to the predatory tribes in the Native States. The reclamation of the wild Moghias of Central India, and their settlement into agricultural communities, has been effected by British officers within the past five years.

Character
of the
non-Aryan
tribes.

The hill and forest tribes differ in character from the tamer population of the plains. Their truthfulness, sturdy loyalty, and a certain joyous bravery, almost amounting to playfulness, appeal in a special manner to the English mind. There is scarcely a single administrator who has ruled over them for any length of time without finding his heart drawn to them, and leaving on record his belief in their capabilities for good. Lest the traditional tenderness of the Indian Civil Service to the people should weaken the testimony of such witnesses, it may be safe to quote only the words of soldiers with reference to the tribes with which each was specially acquainted.

The non-
Aryan hill
tribes as
soldiers.

'They are faithful, truthful, and attached to their superiors,' writes General Briggs; 'ready at all times to lay down their lives for those they serve, and remarkable for their indomitable courage. These qualities have always been displayed in our service. The aborigines of the Karnatik were the sepoys of Clive and of Coote. A few companies of the same stock joined the former great captain from Bombay, and helped to fight the battle of Plassey in Bengal, which laid the foundation of our Indian Empire. They have since distinguished themselves in the corps of pioneers and engineers, not only in India, but in Ava, in Afghánistán, and in the celebrated defence of Jalálábád. An unjust prejudice against them grew up in the native armies of Madras and Bombay, produced by the feelings of contempt for them existing among the Hindu and Muhammadan troops. They have no prejudices themselves; are always ready to serve abroad and embark on board ship; and I believe no instance of mutiny has ever occurred among them.' Since General Briggs wrote these

ences, the non Aryan hill races have supplied some of the bravest and most valued of our Indian regiments, particularly the gallant little Gurkhas

Colonel Dixon's report, published by the Court of Directors, portrays the character of the Mhair tribes with admirable minuteness. He dilates on their 'fidelity, truth, and honesty,' their determined valour, their simple loyalty, and an extreme and almost touching devotion when put upon their honour. Strong as is the bond of kindred among the Mhairs, he vouches for their fidelity in guarding even their own relatives as prisoners when formally entrusted to their care. For centuries they had been known only as exterminators, but beneath the considerate handling of one Englishman, who honestly set about under standing them, they became peaceful subjects and well disciplined soldiers

Sir James Outram, when a very young man, did the same good work for the Bhils of KHANDESH. He made their chiefs his hunting companions, formed the wilder spirits into a battalion, and laid the basis for the reclamation of this formerly intractable race. (See also THE DANGS, *Imperial Gazetteer of India*)

Every military man who has had anything to do with the aboriginal races acknowledges, that once they admit a claim on their allegiance, nothing tempts them to a treacherous or disloyal act. 'The fidelity to their acknowledged chief, wrote Captain Hunter, 'is very remarkable, and so strong is their attachment, that in no situation or condition, however desperate, can they be induced to betray him. If old and decrepit they will convey him from place to place, to save him from his enemies. Their obedience to recognised authority is absolute and Colonel Tod relates how the wife of an absent chieftain procured for a British messenger safe conduct and hospitality through the densest forests by giving him one of her husband's arrows as a token. The very officers who have had to act most sharply against them speak most strongly, and often not without a noble regret and self reproach, in their favour. 'It was not war,' Major Vincent Jervis writes of the operations against the Santals in 1855. 'They did not understand yielding, as long as their national drums beat, the whole party would stand, and allow themselves to be shot down. They were the most truthful set of men I ever met'

We have seen that India may be divided into three regions—the Himálayas on the north, the great River Plains that stretch

southward from their foot, and the Three-sided Table-land which slopes upwards again from the River Plains, and covers the whole southern half of India. Two of these regions, the Himálayas on the north, and the Three-sided Table-land in the south, still afford retreats to the non-Aryan tribes. The third region, or the great River Plains, became in very ancient times the theatre on which a nobler race worked out its civilisation.

CHAPTER IV

THE ARYANS IN ANCIENT INDIA

THIS nobler race belonged to the ARYAN or Indo Germanic THE stock, from which the Brahman, the Rajput, and the English Aryan man alike descend Its earliest home, visible to history, was Stock in Central Asia From that common camping ground, certain branches of the race started for the east, others for the west. One of the western offshoots founded the Persian kingdom, another built Athens and Lacedæmon, and became the Hellenic nation, a third went on to Italy, and reared the City on the Its Seven Hills, which grew into Imperial Rome A distant European colony of the same race excavated the silver ores of pre branches historic Spain, and when we first catch a sight of ancient England, we see an Aryan settlement fishing in wattle canoes, and working the tin mines of Cornwall Meanwhile, other Its branches of the Aryan stock had gone forth from the primitive Eastern home in Central Asia to the east Powerful bands found their branches way through the passes of the Himalayas into the Punjab, and spread themselves, chiefly as Brahmans and Rajputs, over India.

We know little regarding these Aryan tribes in their early The camping ground in Central Asia From words preserved in Aryans in the languages of their long separated descendants in Europe their and India, scholars infer that they roamed over the grassy home primitive steppes with their cattle, making long halts to rear crops of grain They had tamed most of the domestic animals, were acquainted with a hard metal, probably iron,¹ and silver,² understood the arts of weaving and sewing, wore clothes, and ate cooked food They lived the hardy life of the temperate zone, and the feeling of cold seems to be one of the earliest common remembrances of the eastern and the western branches of the race Ages afterwards, when the Vedic singers in hot

¹ Sanskrit, *ajaj*, iron ore, in a more general sense, metal, including gold but not copper in Sanskrit, Latin, *aes*, *aeris*, copper, bronze, Gothic, *air*, *eisim*, old German, *er*, iron, modern German, *eisen*

² Sanskrit, *kharyura*, silver; Latin, *argentum*, Greek, ἀργυρος, ἄργυρος

India prayed for long life, they still asked for 'a hundred winters.' To this day the November rice in the tropical delta of the Ganges is called the *haimántik* (cf. Latin *hiems*) or crop of the 'snowy' season.

European and Indian languages merely varieties of Aryan speech. The forefathers of the Greek and the Roman, of the Englishman and the Hindu, dwelt together in Asia, spoke the same tongue, worshipped the same gods. The languages of Europe and India, although at first sight they seem wide apart, are merely different growths from the original Aryan speech. This is especially true of the common words of family life. The names for *father*, *mother*, *brother*, *sister*, and *widow* (Sanskrit, *vidhavá*), are the same in most of the Aryan languages, whether spoken on the banks of the Ganges, of the Tiber, or of the Thames. Thus the word *daughter* (Sanskrit, *duhitri*), which occurs in nearly all of them, has been derived from the Sanskrit root *duh*, 'milk,' and preserves the memory of the time when the daughter was the little milkmaid in the primitive Aryan household.

Indo-European words. The words preserved alike by the European and Indian branches of the Aryan race, as heirlooms of their common home in Western Central Asia, include most of the terms required by a pastoral people who had already settled down to the cultivation of the more easily reared crops. Their domesticated animals are represented by names derived from the same root, for cattle, sheep, wool, goats, swine, dogs, horses, ducks, geese; also mice; their agricultural life, by cognate words for corn (although the particular species of the cereal varied), flax or hemp, ploughing and grinding; their implements, by cognate terms for copper or iron, cart or waggon, boat, helm; their household economy and industries, by words from the same roots for sewing and weaving, house, garden, yard; also for a place of refuge, the division of the year into lunar months, and several of the numerals.

Common origin of European and Indian religions. The ancient religions of Europe and India had a similar origin. They were to some extent made up of the sacred stories or myths which our common ancestors had learned while dwelling together in Central Asia. Certain of the Vedic gods were also the gods of Greece and Rome; and the Deity is still adored by names derived from the same old Aryan root (*div*, to shine, hence The Bright One, the Indian *Deva*, Latin *Deus*, or Divinity), by Bráhmans in Calcutta, by the Protestant clergy of England, and by Catholic priests in Peru.

The Indo-Aryans on the march, The Vedic hymns exhibit the Indian branch of the Aryans on their march to the south-east, and in their new homes.

THE RIVER SETTLEMENTS IN PUNJAB 77

earliest songs disclose the race still to the north of the Kábul Pass, in Kábul, the latest ones bring them as far as the Ganges. Their victorious advance eastwards through the intermediate tract can be traced in the Vedic writings almost step by step. One of their famous settlements lay between the two sacred rivers, the Saraswati, supposed to be the modern Sarsuti near Thánesar in the Punjab, and the Drishad vati, or Ghaggar, a day's march from it. This fertile strip of land, not more than 60 miles long by 20 broad, was fondly remembered by the Indo Aryans as their Holy Land (*Brahma varitta*), 'fashioned of God, and chosen by the Creator'. As their numbers increased, they pushed eastwards along the base of the Himálayas, into what they afterwards called the Land of the Sacred Singers (*Brahmarshi desha*). Their settlements included by degrees the five rivers of the Punjab, together with the upper course of the Jumna and perhaps of the Ganges and in their new settlements.

Here the Vedic hymns were composed, and the steady supply of water led the Aryans to settle down from their old state of wandering pastoral tribes into communities of husbandmen. Their Vedic poets praised the rivers which Function enabled them to make this great change—perhaps the most of the important step in the progress of a race. 'May the Indus, Rivers they sang, 'the far famed giver of wealth, hear us, (fertilizing our) broad fields with water'. The Himálayas, through whose offshoots they had reached India, and at whose southern base they long dwelt, made a lasting impression on their memory. The Vedic singer praised 'Him whose greatness the snow ranges, and the sea, and the aerial river declare'. In all its long wanderings through India, the Aryan race never forgot its Recollections of the northern home. There dwelt its gods and holy singers, and their there eloquence descended from heaven among men, while northern heroes, where the kind and the brave for ever repose beyond the mountain wall lay the paradise of deities and home.

The Rig Veda forms the great literary memorial of the early Aryan settlements in the Punjab. The age of this Veda venerable hymnal is unknown. The Hindus believe, without evidence, that it existed 'from before all time,' or at least from 3101 years B.C., nearly 5000 years ago. European scholars have inferred from astronomical dates that its composition was going on about 1400 B.C. But these dates are themselves given in writings of modern origin, and might have been calculated backwards. We know, however, that the Vedic religion had been at work long before the rise of Buddhism in the 6th century B.C. The antiquity of the Rig Veda, although

not to be dogmatically expressed in figures, is abundantly established. The earlier hymns exhibit the Aryans on the north-western frontiers of India, just starting on their long journey. Before the embassy of the Greek Megasthenes, at the end of the 4th century B.C., they had spread at least to the verge of the Gangetic delta, 1500 miles distant. At the time of the *Periplus*, *circa* 70 A.D., the southernmost point of India was apparently a seat of their worship. A temple to the queen of the god Siva stood on Cape Comorin, before the end of the first Christian century; and the inferences of European scholarship point to the composition of at least some of the Vedic psalms at a period not later than twelve to sixteen centuries before the commencement of our era.

Neverthe-
less of
great anti-
quity.

Inspira-
tion of the
Veda.

The Rig-
Veda ;
1017
hymns,
10,580
verses.

Caste not
known to
Rig-Veda,

nor
widow-
burning.

The Brāhmans declare that the Vedic hymns were directly inspired by God. Indeed, in our own times, the young Theistic Church of Bengal, which rejects Brāhmanical teaching, was split into two sects on the question of the divine authority of the Veda. The hymns seem to have been composed by certain families of Rishis or psalmists, some of whose names are preserved. The Rig-Veda is a very old collection of 1017 of these short lyrical poems, chiefly addressed to the gods, and containing 10,580 verses. They show us the Aryans on the banks of the Indus, divided into various tribes, sometimes at war with each other, sometimes united against the 'black-skinned' aborigines. Caste, in its later sense, is unknown. Each father of a family is the priest of his own household. The chieftain acts as father and priest to the tribe; but at the greater festivals he chooses some one specially learned in holy offerings to conduct the sacrifice in the name of the people. The chief, although hereditary, seems to have been partly elected; and his title of Vis-pati, 'Lord of the Settlers,' survives in the old Persian Vis-paiti, and as the Lithuanian Wiéz-patis in central Europe at this day. Women enjoyed a high position, and some of the most beautiful hymns were composed by ladies and queens. Marriage was held sacred. Husband and wife were both 'rulers of the house' (*dampati*); and drew near to the gods together in prayer. The burning of widows on the husbands' funeral pile was unknown; and the verses in the Veda which the Brāhmans afterwards distorted into a sanction for the practice, have the very opposite meaning. 'Rise, woman,' says the sacred text to the mourner; 'come to the world of life. Come to us. Thou hast fulfilled thy duties as a wife to thy husband.'

The Aryan tribes in the Veda are acquainted with most of

Saspatni (*Sasi*), a name for the moon, so called from the marks on the moon being supposed to resemble a hare (*sasa*).

Influence
of the
rainy
season on
Aryan
mytho-
logy.

Indra, or the Aqueous Vapour that brought the precious rain on which plenty or famine depended each autumn, received the largest number of hymns. By degrees, as the settlers realized more and more keenly the importance of the periodical rains to their new life as husbandmen, he became the chief of the Vedic gods. 'The gods do not reach unto thee, O Indra, or men; thou overcomest all creatures in strength.' Agni, the God of Fire (Latin, *igni-s*), ranks next to Indra in the number of hymns in his honour as the friend of man, the guide of the people, the lord and giver of wealth.

Indra and
Agni.

Judging, indeed, from the preponderance of the invocations to Agni, and from the position which the corresponding deity holds in Iranian mythology, it would appear as if Agni and not Indra had been the chief god of the race, while the Indian and old Persian branches still dwelt together. Among the cold heights and on the uplands of Central Asia, to the north-west of the Himálayas, Heat was the great factor of fertility, the giver of human comfort, and the ripener of the crops. When the eastern offshoots of the Aryans descended upon the plains of India, they found, as they advanced southward, that heat was an element of productiveness which might be taken for granted, a constant factor in the husbandry of the Indus and Jumna valleys. Here it was upon moisture rather than on heat that their harvest depended. To the right of their line of march across the five rivers of the Punjab, a rather narrow tract stretched to the foot of the Himálayas, with an ample rainfall, now averaging 35 inches a year. But on the broad plains to their left, the water-supply was less abundant and more capricious. At the present day the tract immediately to the south of the Aryan route receives only 20 to 30 inches per annum, diminishing through successive belts of rainfall down to 10 inches.

Moisture
v. Heat.

As the Aryan immigrants spread south, therefore, it was no longer so necessary to pray for heat, and it became more necessary to pray for moisture. Agni, the heat-giving god, without being discredited, became less important, and receded in favour of Indra, the rain-bringing deity. In the settlements of the Punjab, Indra thus advanced to the first place among the Vedic divinities. He is the cloud compeller, dropping bountiful showers, filling the dried-up rivers from the Himálayas and bringing the rain-storms. His voice is the thunder; with his spear of lightning he smites open the black clouds, and rends the black bodies of the demons who have drunk up the

Agni gives
place to
Indra.

Indra,
the rain-
bringer.

INDRA AND THE RAINFALL

81

shed for rains. He makes the sun to shine forth again 'I sing of the victories of Indra, of the victories won by the god of the Spear,' chanted the Rig Vedic psalmist. 'On the mountains he smote the demon of drought (Ahi), he poured out the waters and let the river flow from the mountains like alves to cows, so do the waters hasten to the sea' 'Thou hast broken open the rain prisons¹ rich in cattle. The bonds of the streams hast thou burnt asunder'²

As the Aryans pushed forward into the middle and lower Indraguies valley of the Ganges, they found themselves in a region of placetothe Triad, copious rainfall brought by the unfailing monsoons. The rain storms of Indra thus became less important. His waterspouts, although well worth praying for in the Punjab, evidently belonged to an inferior grade of divine energy than that which presided over the irresistible, majestically ordered advance of the periodical rains in Bengal. Indra, the God of Heat, and gave shared in his turn the fate of Agni, the God of Heat, and gave way to three deities on a scale commensurate with the vaster of Brahma, forces of nature in the Lower Gangetic valley. We shall see how Vishnu, the abstract but potent conception of Divine energy embodied in the Brâhmanical Triad of the Creator, Preserver, and Destroyer took the place alike of Agni and of Indra, and of the other Vedic gods. But, meanwhile Indra the Giver of Rain, was the most important deity to the Aryan settlers in the Punjab. He stands forth in the Veda as the foremost Shining One.

The Maruts were the Vedic Storm Gods, 'who make the rocks to tremble, who tear in pieces the forest. Ushas the Other High born Dawn' (Greek *Eos*), 'shines upon us like a young wife, rousing every living being to go forth to his work. The Aswins, or 'Fleet Outriders' of the Dawn, are the first rays of sunrise, 'Lords of Lustre. The Solar Orb (Surya Savitri), the Wind (Vayu), the Sunshine or Friendly Day (Mitra), the animating fermented juice of the Sacrificial Plant (Soma), and many other Shining Ones, are invoked in the Veda, in all, about thirty three gods, 'who are eleven in heaven, eleven on earth, and eleven dwelling in glory in mid air'.

The terrible blood drinking deities of modern Hinduism are

¹ Literally, 'Thou hast broken the cave of Vritra the demon who imprisons the rain and causes drought, with whom Indra is constantly waging victorious war.

² The Rig Vedic attributes of Indra are well summarized by Professor Max Duncker, *Ancient History of India*, pp 47-49 (ed 1881), following Kothe and Benfey, and are detailed with completeness by Muir, 'Sanskrit Texts,' pp 76-139, vol 1 (1872)

Attitude of the Vedic singer to his gods. The Aryan settlers lived on excellent terms with their bright gods. They asked for protection with an assured conviction that it would be granted. 'Give me cows, or land, or long life, in return for this hymn or offering;' 'slay my enemy, scatter the black-skin, and I will sacrifice to thee,'—such is the ordinary frame of mind of the singer to his gods. But, at the same time, he was deeply stirred by the glory and mystery of the earth and the heavens. Indeed, the majesty of nature so filled his mind, that when he praises any one of his Shining Gods he can think of none other for the time being, and adores him as the Supreme Ruler. Verses of the Veda may be quoted declaring each of the greater deities to be the One Supreme: 'Neither gods nor men reach unto thee, O Indra;' Soma is 'king of heaven and earth, the conqueror of all.' To Varuna also it is said, 'Thou art lord of all, of heaven and earth; thou art king of all those who are gods, and of all those who are men.' Agni is likewise addressed as the mightiest and as the most beloved of the gods: 'No one can approach thy darting, strong, terrible flames: burn thou the evil spirits, and every enemy.' The more spiritual of the Vedic singers, therefore, may be said to have worshipped One God, although not One Alone.

A Vedic hymn. ‘In the beginning there arose the Golden Child. He was the one born lord of all that is. He established the earth

and this sky. Who is the God to whom we shall offer our sacrifice?

'He who gives life, he who gives strength, whose command all the Bright Gods revere, whose shadow is immortality, whose shadow is death Who is the God to whom we shall offer our sacrifice?

'He who, through his power, is the one king of the breathing and awakening world He who governs all, man and beast. Who is the God to whom we shall offer our sacrifice?

'He through whom the sky is bright and the earth firm, he through whom the heaven was established, nay, the highest heaven, he who measured out the light and the air Who is the God to whom we shall offer our sacrifice?

'He who by his might looked even over the water clouds, he who alone is God above all gods Who is the God to whom we shall offer our sacrifice?'

The yearning for rest in God, that desire for the wings of a 'The dove, so as to fly away and be at rest, with which noble hearts Better have ached in all ages, breathes in several exquisite hymns of Land the Rig Veda 'Where there is eternal light, in the world where the sun is placed,—in that immortal, imperishable world, place me, O Soma! Where life is free, in the third heaven of heavens, where the worlds are radiant,—there make me immortal! Where there is happiness and delight, where joy and pleasure reside, where our desires are attained,—there make me immortal!'

Nor was the sense of sin, and the need of pardon, absent from the minds of these ancient psalmists As a rule, an honourable understanding seems to have existed between the Vedic sacrificer and his bright god the god being equitably pledged to the fulfilment of the sacrificer's prayer in return for the offering, although the wisest might leave it to Indra himself to decide what was best to bestow But even the cheerful worshippers of the Veda at times felt deeply the sinfulness of sin, and the fear of the sins of the father being visited upon the children 'What great sin is it, O Varuna,' says a hymn of the Rig Veda, 'for which thou seekest to slay thy worshipper and friend?' 'Absolve us from the sins of our fathers and from those which we committed in our own persons' 'It was not our own doing that led us astray, O Varuna, it was

¹ Rig Veda x 121, translated by Prof Max Muller, *Hist Anc Sansk.*
It p 569, *Chips*, vol 1 p 29 (ed 1867)
² Rig Veda, ix. 113 7, Max Muller's translation.

Prayers
for pardon. necessity (or temptation); wine, anger, dice, or thoughtlessness. The stronger perverts the weaker. Even sleep bringeth sin.¹ 'Through want of strength, thou strong and bright god,' says another hymn to Varuna, 'have I gone wrong: have mercy, almighty, have mercy. I go along trembling like a cloud driven before the wind: have mercy, almighty, have mercy. Through want of power (to do right) have I transgressed, O bright and mighty god: have mercy, almighty, have mercy. Whenever we men, O Varuna, commit an offence before the heavenly host, whenever we break the law through thoughtlessness, have mercy, almighty, have mercy.'²

Primitive
Aryan
burial. The very ancient Aryans in Central Asia buried their dead, although cremation seems also to have been resorted to. In Iran the custom of burial eventually gave place to that of exposing the corpse on a mountain to the birds of heaven; a custom still practised in the Pārsi Towers of Silence at Bombay and elsewhere. We have seen that Agni, god of heat, appears to have been the chief deity of the Aryan race in Iran; and fire was regarded by the ancient Persian as too sacred an element to be polluted by a human corpse. The Aryan settlers in India for a time retained the custom of burial. 'Let me not, O Varuna, go to the house of clay,' says one hymn of the Rig-Veda.³ 'O earth, be not too narrow for him,' says another hymn, 'cover him like the mother who folds her son in her garment.'⁴ But in time the Indo-Aryans substituted the fire for the grave; and the burning of the corpse became a distinctive feature of the race, as contrasted with the ruder and more primitive peoples whom they found in the Punjab.

Burning
of the
dead. While the aboriginal tribes buried their dead under rude stone monuments, the Aryan—alike in India, in Greece, and in Italy—made use of the funeral-pyre as the most solemn method of disposing of the mortal part of man. As the Indo-Aryan derived his natural birth from his parents; and a partial regeneration, or second birth, from the performance of his religious duties; so the fire, by setting free the soul from the body, completed the third or heavenly birth. His friends

¹ Rig-Veda, vii. 86; translated in Muir's 'Sanskrit Texts,' vol. v. p. 66 (1872).

² Rig-Veda, vii. 89. Max Müller's beautiful translation is reproduced by Professor Duncker, *Ancient History of India*, p. 53 (1881). See also Muir's translation, 'Sanskrit Texts,' vol. v. p. 67 (1872).

³ Rig-Veda, vii. 89. 1. Muir's 'Sanskrit Texts,' vol. v. p. 67 (1872).

⁴ Rig-Veda, x. 18. Roth's rendering in Duncker, *Ancient History of India*, p. 63 (1881).

ood round the pyre as round a natal bed, and commanded his eye to go to the sun, his breath to the wind, his limbs to the earth, the water and plants whence they had been derived. But 'as for his unborn part, do thou, Lord (Agni), quicken it with thy heat, let thy flame and thy brightness quicken it, convey it to the world of the righteous.'

For the lonely journey of the soul after its separation from Aryan the body, the Aryans, both in Asia and Europe, provided faithful guides (the *Sarameyas* in Sanskrit *Hermias* in Greek) ^{legend of King Yama, or Death}. According to the Zend or old Aryan legend in Persia, Yama was a monarch in the old time when sorrow and sickness were unknown. By degrees sin and disease crept into the world, the slow necessity of death hastened its step, and the old king retired, with a chosen band from the polluted earth into a better country, where he still reigns. The Indian version of the story makes Yama to be the first man who passed through death into immortality. Having discovered the way to the pompos, or guide of the Aryan dead. He became the nekro (*Sarameyas*)—'black and spotted, 'broad of nostril, and 'with a hunger never to be satisfied—wander as his messengers among men. 'Worship with an offering King Yama, the Assembler of Men, who departed to the mighty waters, who found out the road for many.'

Several exquisite hymns bid farewell to the dead—'Depart thou, depart thou by the ancient paths to the place whither our fathers have departed. Meet with the Ancient Ones, meet with the Lord of Death. Throwing off thine imperfections, go to thy home. Become united with a body, clothe thyself in a shining form.' 'Let him depart to those for whom flow the rivers of nectar. Let him depart to those who, through meditation, have obtained the victory, who, by fixing their thoughts on the unseen, have gone to heaven. Let him depart to the mighty in battle, to the heroes who have laid down their lives for others, to those who have bestowed their goods on the poor.' The doctrine of transmigration was unknown. The circle round the funeral pile sung with a firm assurance that their friend went direct to a state of blessedness and reunion with the loved ones who had gone before. 'Do thou conduct

¹ Rig Veda, x 14 1. See Dr John Muir's 'Sanskrit Texts,' and his essay on 'Yama,' *Journal of the Royal Asiatic Society*, part II, 1865, whence many of the above quotations are derived. See also Max Muller's essay on the 'Funeral Rites of the Brāhmins,' on which the following paragraph is based.

Vedic
concep-
tions of
immor-
tality.

us to heaven,' says a hymn of the later Atharva-Veda; 'let us be with our wives and children.' 'In heaven, where our friends dwell in bliss,—having left behind the infirmities of the body, free from lameness, free from crookedness of limb,—there let us behold our parents and our children.' 'May the water-shedding spirits bear thee upwards, cooling thee with their swift motion through the air, and sprinkling thee with dew.' 'Bear him, carry him; let him, with all his faculties complete, go to the world of the righteous. Crossing the dark valley which spreadeth boundless around him, let the unborn soul ascend to heaven. Wash the feet of him who is stained with sin; let him go upwards with cleansed feet. Crossing the gloom, gazing with wonder in many directions, let the unborn soul go up to heaven.'

The
Aryans
advance
into the
Middle
Land

The hymns of the Rig-Veda were composed, as we have seen, by the Aryans in their colonies along the Indus, and on their march eastwards towards the Jumna and upper Ganges. The growing numbers of the settlers, and the arrival of fresh Aryan tribes from behind, still compelled them to advance. From 'The Land of the Sacred Singers,' in the Eastern Punjab (*Brahmarshi-desha*, ante, p. 77), Manu describes them as spreading through 'The Middle Land' (*Madhya-desha*). This comprised the river system of the Ganges as far east as Oudh and Allahábád, with the Himálayas as its northern, and the Vindhya ranges as its southern boundary.

The
Ganges.

The Ganges is only twice mentioned, and without special emphasis, in the Rig-Veda. The conquest of the Middle Land seems, therefore, not to have commenced till the close of the Rig-Vedic era. It must have been the work of many generations, and it will be referred to when we come to examine the historical significance of the two great Sanskrit epics. Between the time when the Aryans descended from Central Asia upon the plains of the Indus and the age when they passed the Ganges, they had conquered many of the aboriginal races, left others behind on their route, and had begun to wage inter-tribal wars among themselves, under rival Aryan heroes and rival Vedic priests. During this advance, the simple faith of the Rig-Vedic singers was first adorned with stately rites, and then extinguished beneath them. The race progressed from a loose confederacy of tribes into several well-knit nations, each bound together by the strong central force of kingly power, directed by a powerful priesthood, and organized on a firm basis of caste.

Slow
advance
into the
Middle
Land.

Whence arose this new constitution of the Aryan tribes into

ions, with castes, priests, and kings? We have seen that The Arjan
though in their earlier colonies on the Indus each father was tribes
test in his family, yet the Chieftain, or Lord of the Settlers, organized
alled in some man specially learned in holy offerings to into
conduct the greater tribal sacrifices Such men were highly kingdoms
honoured, and the famous quarrel which runs throughout the
whole Veda sprang from the claims of two rival sages,
Vasishtha and Viswamitra, to perform one of these ceremonies
The art of writing was unknown, and the hymns and sacrificial
formulæ had to be handed down by word of mouth from
father to son

It thus came to pass that the families who knew these Origin of
holy words by heart became the hereditary owners of the priestly
liturgies required at the most solemn offerings to the gods families
Members of such households were chosen again and again
to conduct the tribal sacrifices, to chant the battle hymn, to
implore the divine aid, or to pray away the divine wrath Even
the early Rig Veda recognises the importance of these sacrifices
'That king,' says a verse, 'before whom marches the priest, he
alone dwells well established in his own house, to him the
people bow down The king who gives wealth to the priest,
he will conquer, him the gods will protect' The tribesmen
first hoped, then believed, that a hymn or prayer which had
once acted successfully, and been followed by victory, would
again produce the same results The hymns became a valu
able family property for those who had composed or learned
them The Rig Veda tells how the prayer of Vasishtha pre
vailed 'in the battle of the ten kings,' and how that of Viswa
mitra 'preserves the tribe of the Bharats.' The potent prayer
was termed *brahman* (from the root *brh* = *irih*, to increase)
and he who offered it, *brahman* Woe to him who despised
either! 'Whosoever,' says the Rig Veda, 'scoffs at the prayer
which we have made, may hot plagues come upon him, may
the sky burn up that hater of Brâhman'

Certain families thus came to have not only a hereditary Growing
claim to conduct the great sacrifices, but also the exclusive numbers
knowledge of the ancient hymns, or at any rate of the traditions of priest
which explained their symbolical meaning They naturally
tried to render the ceremonies solemn and imposing By
degrees a vast array of ministrants grew up around each of the
greater sacrifices There were first the officiating priests and

¹ The following pages are largely indebted to Professor Weber's
History of Indian Literature (Trubner, 1878),—a debt very gratefully
acknowledged

and companions of the king formed an important class among the early Aryan tribes in India, as they certainly did among the mediæval branches of the race in Europe, and still do at the petty courts of India. Their old Sanskrit names, *Kshatriya*, *Rājanya*, and *Rājansi*, mean 'connected with the royal power,' or 'of the royal line;' their usual modern name *Rājput* means 'of royal descent.' In process of time, when the Aryans settled down, not as mere fighting clans, but as powerful nations, in the Middle Land along the Jumna and Ganges, this warrior class grew in numbers and in power. The black races had been reduced to serfdom, or driven back towards the Himalayas and the Vindhya, on the north and on the south of the central tract. The incessant fighting, which had formed the common lot of the tribes on their actual migration eastwards from the Indus, now ceased.

The cultivating caste (Vaiśyas).

A section of the people accordingly laid aside their arms, and, devoting themselves to agriculture or other peaceful pursuits, became the *Vaiśyas*. The sultry heats of the Middle Land must have abated their old northern energy, and inclined them to repose. Those who, from family ties or from personal inclination, preferred a soldier's life, had to go beyond the frontier to find an enemy. Distant expeditions of this sort could be undertaken much less conveniently by the husbandman than in the ancient time, when his fields lay on the very border of the enemy's country, and had just been wrested from it. Such expeditions required and probably developed a military class; endowed with lands, and with serfs to till the soil during the master's absence at the wars. The old companions and kinsmen of the king formed a nucleus round which gathered the more daring spirits. They became in time a distinct military caste.

The four castes :
(1) Brāhmanas,
(2) Kshatriyas,
(3) Vaiśyas,

The Aryans on the Ganges, in the 'Middle Land,' thus found themselves divided into three classes—first, the priests, or Brāhmanas; second, the warriors and king's companions, called in ancient times Kshatriyas, at the present day Rājputs; third, the husbandmen, or agricultural settlers, who retained the old name of Vaiśyas, from the root *viś*, which in the Vedic period had included the whole 'people.' These three classes gradually became separate castes; intermarriage between them was forbidden, and each kept more and more strictly to its hereditary employment. But they were all recognised as belonging to 'Twice-born,' or Aryan race; they were all present at the great national sacrifices; and all worshipped the same Bright Gods.

(4) Śūdras. Beneath them was a fourth or servile class, called Śūdras, the

remnants of the vanquished aboriginal tribes whose lives had been spared. These were 'the slave bands of black descent,' the *Dásas* of the *Veda*. They were distinguished from their 'Twice-born' Aryan conquerors as being only 'Once-born,' and by many contemptuous epithets. They were not allowed to be present at the great national sacrifices, or at the feasts which followed them. They could never rise out of their servile condition, and to them was assigned the severest toil in the fields, and all the hard and dirty work of the village community.

Of the four Indian castes, three had a tendency to increase. As the Aryan conquests spread more aboriginal tribes were reduced to serfdom as *Sudras*. The warriors, or *Kshatriyas*, would constantly receive additions from wealthy or enterprising members of the cultivating class. When an expedition or migration went forth to subdue new territory, the whole colonists would for a time lead a military life, and their sons would probably all regard themselves as *Kshatriyas*. In ancient times, entire tribes, and at the present day the mass of the population throughout large tracts, thus claim to be of the warrior or *Rájpüt* caste. Moreover, the kings and fighting men of aboriginal races who, without being conquered by the Aryans, entered into alliance with them, would probably assume for themselves the warrior or *Kshatriya* rank. We see this process going on at the present day among many of the aboriginal peoples. The *Bráhmans*, in their turn, appear at first to have received into their body distinguished families of *Kshatriya* descent. In later times, too, we find that sections of aboriginal races were also 'manufactured wholesale into *Brahmans*. Unmistakeable cases of such manufactures' or ethnical syncretisms are recorded, and besides the upper class agricultural *Brahmans*, there are throughout India many local castes of *Bráhmans* who follow the humble callings of fishermen, blacksmiths, ploughmen, and potato growers.¹

The *Vaisya* or cultivating caste did not tend, in this manner, to increase. No one felt ambitious to win his way into it, except perhaps the enslaved *Sudras*, to whom any change of condition was forbidden. The *Vaisyas* themselves tended in early times to rise into the more honourable warrior class, and at a later period, to be mingled with the labouring multitude of *Sudras*, or with the castes of mixed descent. In many Provinces they have now almost disappeared as a distinct caste. In ancient India, as at the present day, the three conspicuous castes were (1) the priests and (2) warriors of

¹ See Hunter's *Oriya*, vol. I. pp. 239-264 (1872)

Aryan birth, and (3) the serfs or Súdras, the remnants of earlier races. The Súdras had no rights; and, once conquered, ceased to struggle against their fate. But a long contest raged between the priests and warriors for the chief place in the Aryan commonwealth.

Struggle
between
priestly
and
warrior
castes.

In order to understand this contest, we must go back to the time when the priests and warriors were simply fellow-tribesmen. The Bráhma caste seems to have grown out of the families of Rishis who composed the Vedic hymns, or who were chosen to conduct the great tribal sacrifices. In after-times, the whole Bráhma population of India pretended to trace their descent from the Seven Rishis, heads of the seven priestly families to whom the Vedic hymns were assigned. But the composers of the Vedic hymns were sometimes kings or distinguished warriors rather than priests; indeed, the Veda itself speaks of these royal Rishis (*Rájarshis*). When the Bráhmans put forward their claim to the highest rank, the warriors or Kshattriyas were slow to admit it; and when the Bráhmans went a step further, and declared that only members of their families could be priests, or gain admission into the priestly caste, the warriors seem to have disputed their pretensions. In later ages, the Bráhmans, having the exclusive keeping of the sacred writings, effaced from them, as far as possible, all traces of their struggle with the Kshattriyas. The Bráhmans taught that their caste had come forth from the mouth of God, divinely ordained to the priesthood from the beginning of time. Nevertheless, the Vedic and Sanskrit texts record a long contest, perhaps representing a difference in race or separate waves of Aryan migrations.

Rising
pretension
of the
Bráhmans.

Viswá-
mítra and
Vasishtha

The quarrel between the two sages Viswámítra and Vasishtha, which, as has been mentioned, runs through the whole Veda, is typical of this struggle. Viswámítra stands as a representative of the royal-warrior rank, who claims to perform a great public sacrifice. The white-robed Vasishtha represents the Bráhmans or hereditary priesthood, and opposes the warrior's claim. In the end, Viswámítra established his title to conduct the sacrifice; but the Bráhmans explain this by saying that his virtues and austerities won admission for him into the priestly family of Bhrigu. He thus became a Bráhma, and could lawfully fill the priestly office. Viswámítra serves as a typical link, not only between the priestly and the worldly castes, but also between the sacred and the profane sciences. He was the legendary founder of the art of war, and his equally legendary son Susruta is quoted as the earliest authority on

Indian medicine These two sciences of war and medicine, together with music and architecture, form *upa Vedas*, or supplementary sections of the divinely inspired knowledge of the Brahmans

Another famous royal Rishi, Vitahavya, 'attained the condition of Bráhmaṇhood, venerated by mankind,' by a word of the saintly Bhṛigu. Parasu Rama, the Divine Champion of the Brahmans, was of warrior descent by his mother's side. Manu, 'their legislator, sprang from the warrior caste, and his father is expressly called 'the seed of all the Kshatriyas' But when the Brahmans had firmly established their supremacy, they became reluctant to allow the possibility of even princes finding an entrance into their sacred order. King Ganaka was more learned than all the Brahmans at his court, and performed terrible penances to attain to Brahmanhood. Yet the legends leave it doubtful whether he gained his desire. The still more holy, but probably later, Matanga, wore his body to skin and bone by a thousand years of austerities, and was held up from falling by the hand of the god Indra himself. Nevertheless he could not attain to Brahmanhood. Gautama Buddha, who in the 6th century before Christ overthrew the Brahman supremacy, and founded a new religion, was a prince of warrior descent, perhaps born in too late an age to be adopted into, and utilized by, the Brahman caste.

Among some of the Aryan tribes the priests apparently failed to establish themselves as an exclusive order. Indeed, the four castes, and especially the Brahman caste seem only to have obtained their full development amid the plenty of the Middle Land (*Madhya desha*), watered by the Jumna and the Ganges. The early Aryan settlements to the west of the Indus long remained outside the caste system, the later Aryan offshoots to the south and east of the Middle Land only partially carried that system with them. But in the Middle Land itself, with Delhi as its western capital, and the great cities of Ajodhya (Oudh) and Benares on its eastern frontier, the Brahmans grew by degrees into a compact, learned, and supremely influential body, the makers of Sanskrit literature. Their language, their religion, and their laws, became in after times the standards aimed at throughout all India. They naturally denounced all who did not submit to their pretensions, and they stigmatized the other Aryan settlements who had not accepted their caste system as lapsed tribes or outcasts (*Vṛishalas*). Among the lists of such fallen races we read the name afterwards applied to the Ionians or Greeks (*Yavanas*). The Bráhmans of the Middle

Other cases of Kshatriyas attaining to Brahmanhood

The 'Middle Land, the focus of Brahmanism

Aryan tribes beyond the Brahmanical pale

Land had not only to enforce their supremacy over the powerful warriors of their own kingdoms; they had also to extend it among the outlying Aryan tribes who had never fully accepted their caste system. This must have been a slow work of ages, and it seems to have led to bitter feuds.

There were moments of defeat, indeed, when Bráhmaṇ leaders acknowledged the superiority of the warrior caste. 'None is greater,' says the Brihad Aranyaka Upanishad, 'than the Kshattriya; therefore the Bráhmaṇ, under the Kshattriya, worships at the royal sacrifice (*rájasūya*).'¹ It seems likely that numbers of the Vaisyas or cultivators would take part with the Kshattriyas, and be admitted into their caste. That the contest was not a bloodless one is attested by many legends, especially that of Parasu-Ráma, or 'Ráma of the Axe.' This hero, who was divinely honoured as the sixth Incarnation of Vishnu, appeared on the scene after alternate massacres by Bráhmaṇs and Kshattriyas had taken place. He fought on the Bráhmaṇ side, and covered India with the carcasses of the warrior caste. 'Thrice seven times,' says the Sanskrit epic, 'did he clear the earth of the Kshattriyas,' and so ended in favour of the Bráhmaṇs the long struggle.

It is vain to search into the exact historical value of such legends. They suffice to indicate an opposition among the early Aryan kingdoms to the claims of the Bráhmaṇs, and the mingled measures of conciliation and force by which that opposition was overcome. The Bráhmaṇ caste, having established its power, made a wise use of it. From the ancient Vedic times its leaders recognised that if they were to exercise spiritual supremacy, they must renounce earthly pomp. In arrogating the priestly function, they gave up all claim to the royal office. They were divinely appointed to be the guides of nations and the counsellors of kings, but they could not be kings themselves. As the duty of the Súdra was to serve, of the Vaisya to till the ground and follow middle-class trades or crafts, so the business of the Kshattriya was with

¹ It is easy to exaggerate the significance of this passage, and dangerous to generalize from it. The author has to thank Prof. Cowell and the late Dr. John Muir for notes upon its precise application. Weber, *Hist. Ind. Lit.* p. 54 (1878), describes the *rájasūya* as 'the consecration of the king.' The author takes this opportunity of expressing his many obligations to Dr. John Muir, his first teacher in Sanskrit. Dr. Muir, after an honourable career in the Bengal Civil Service, devoted the second half of his life to the study of ancient Indian literature; and his five volumes of *Original Sanskrit Texts* form one of the most valuable and most permanent contributions to Oriental learning made in our time.

Bráhmaṇ
discomfi-
tures.

The Bráhmaṇ
supremacy
estab-
lished.

They
make a
wise use
of it.

the public enemy, and that of the Brahmans with the national gods

While the Bráhmaṇ leaders thus organized the occupations of the commonwealth, they also laid down strict rules for their own caste. They felt that as their functions were mysterious and above the reach of other men, so also must be their lives. Each day brought its hourly routine of ceremonies, studies, and duties. Their whole life was mapped out into four clearly defined stages of discipline. For their existence, in its full religious significance, commenced not at birth, but on being invested at the close of childhood with the sacred thread of the Twice Born. Their youth and early manhood were to be spent in learning by heart from some Brahman sage the inspired Scriptures, tending the sacred fire and serving their preceptor. Having completed his long studies, the young Bráhmaṇ entered on the second stage of his life, as a householder. He married and commenced a course of family duties. When he had reared a family, and gained a practical knowledge of the world, he retired into the forest as a recluse for the third period of his existence, feeding on roots or fruits and practising his religious rites with increased devotion. The fourth stage was that of the ascetic or religious mendicant wholly withdrawn from earthly affairs, and striving to attain a condition of mind which, heedless of the joys, or pains or wants of the body is intent only on its final absorption into the deity. The Brahman, in this fourth stage of his life, ate nothing but what was given to him unasked, and abode not more than one day in any village, lest the vanities of the world should find entrance into his heart. Throughout his whole existence he practised a strict temperance, drinking no wine, using a simple diet, curbing the desires, shut off from the tumults of war, and his thoughts fixed on study and contemplation. 'What is this world?' says a Bráhmaṇ sage. 'It is even as the bough of a tree, on which a bird rests for a night, and in the morning flies away.'

It may be objected that so severe a life of discipline could never be led by any large class of men. And no doubt there have been at all times worldly Bráhmaṇs, indeed, the struggle for existence in modern times has compelled the great majority of the Bráhmaṇs to betake themselves to secular pursuits. But the whole body of Sanskrit literature bears witness to the fact that this ideal life was constantly before their eyes, and that it served to the whole caste as a high standard in its two really essential features of self-culture and self-restraint.

Incidents in the history of Buddha, in the 6th century before Christ, show that numbers of Bráhmans at that time lived according to this rule of life. Three hundred years later, the Greek ambassador, Megasthenes, found the Bráhmans discoursing in their groves, chiefly on life and death. The Chinese travellers, down to the 10th century A.D., attest the survival of the Bráhmanical pattern of the religious life. The whole monastic system of India, and those vast religious revivals which have given birth to the modern sects of Hinduism, are based on the same withdrawal from worldly affairs. At this day, Bráhman colleges, called *tois*, are carried on without fees on the old model, at Nadiyá in Bengal, and elsewhere. The modern visitor to these retreats can testify to the stringent self-discipline, and to the devotion to learning for its own sake, often protracted till past middle-life, and sometimes by grey-haired students.

Bráhman
rule of
life.

Its here-
ditary
results on
the caste.

The
Bráhman
type.

The Bráhmans, therefore, were a body of men who, in an early stage of this world's history, bound themselves by a rule of life the essential precepts of which were self-culture and self-restraint. As they married within their own caste, begat children only during their prime, and were not liable to lose the finest of their youth in war, they transmitted their best qualities in an ever-increasing measure to their descendants. The Bráhmans of the present day are the result of nearly 3000 years of hereditary education and self-restraint; and they have evolved a type of mankind quite distinct from the surrounding population. Even the passing traveller in India marks them out, alike from the bronze-cheeked, large-limbed, leisure-loving Rájput or warrior caste of Aryan descent; and from the dark-skinned, flat-nosed, thick-lipped low-castes of non-Aryan origin, with their short bodies and Lullet heads. The Bráhman stands apart from both; tall and slim, with finely modelled lips and nose, fair complexion, high forehead, and somewhat cocoa-nut shaped skull—the man of self-centred refinement. He is an example of a class becoming the ruling power in a country, not by force of arms, but by the vigour of hereditary culture and temperance. One race has swept across India after another, dynasties have risen and fallen, religions have spread themselves over the land and disappeared. But since the dawn of history, the Bráhman has calmly ruled; swaying the minds and receiving the homage of the people, and accepted by foreign nations as the highest type of Indian mankind.

The paramount position which the Bráhmans won, resulted, in no small measure, from the benefits which they bestowed.

For their own Aryan countrymen, they developed a noble language and literature. The Bráhmans were not only the priests and philosophers. They were also the lawgivers, the statesmen, the administrators, the men of science, and the poets of their race. Their influence on the aboriginal peoples, the hill and forest races of India, was not less important. To these rude remnants of the flint and bronze ages they brought in ancient times a knowledge of the metals and of the gods. Within the historical period, the Brahman have incorporated the mass of the backward races into the social and religious organization of Hinduism. A system of worship is a great comfort to a tropical people hemmed in by the uncontrolled forces of nature as it teaches them how to propitiate those mysterious powers and so tends to liberate their minds from the terrors of the unseen.

The work done by the Bráhmans for India

The reflective life of the Middle Land (*Madhya-desh*) led the Bráhmans to see that the old gods of the Veda were in reality not supreme beings but poetic fictions. For when they came to think the matter out they found that the sun, the aqueous vapour, the encompassing sky, the wind and the dawn, could not each be separate and supreme creators but must have all proceeded from one First Cause. They did not shock the religious sense of the less speculative castes by any public rejection of the Vedic deities. They accepted the old 'Shining Ones' of the Veda as beautiful manifestations of the divine power, and continued to decorously conduct the sacrifices in their honour. But among their own caste, the Bráhmans distinctly enunciated the unity of God. To the Veda, the Bráhmanas, and the Sutras, they added a vast body of theological literature, composed at intervals between 800 B.C. and 1000 A.D. The Upanishads, meaning according to their great Bráhman expounder, 'The Science of God and His identity with the soul,' the Aranyakas, or 'Tracts for the Forest Recluse,' and the much later Puranas or 'Traditions from of Old,'—contain mystic and beautiful doctrines inculcating the unity of God and the immortality of the soul, mingled with less noble dogmas, popular tales, and superstitions. The mass of the people were left to believe in four castes, four Vedas, and many deities. But the higher thinkers among the Bráhmans recognised that in the beginning there was but one caste, one Veda, and one God.

Brahman theology

Its esoteric and exoteric sides

The old 'Shining Ones' of the Vedic singers were, indeed, no longer suitable deities, either for the life which the Aryans led after they advanced into Southern Bengal, or for the country

Rise of the post Vedic Gods

The vast
forces of
nature,

in Bengal.

The Hindu
Triad :

Brahmá ;

Vishnu ;

Siva.

Bráhma-
philoso-
phy.

in which they lived. The Vedic gods were the good 'friends' of the free-hearted warring tribes in Northern India, settled on the banks of fordable streams or of not overpowering rivers. In Central and South-Eastern Bengal, the Bráhmans required deities whose nature and attributes would satisfy profoundly reflective minds, and at the same time would be commensurate with the stupendous forces of nature amid which they dwelt. The storm-gods (*Maruts*) of the Veda might suffice to raise the dust-whirlwinds of the Punjab, but they were evidently deities on a smaller scale than those which wielded the irresistible cyclones of Bengal. The rivers, too, had ceased to be merely bountiful givers of wealth, as in the north. Their accumulated waters came down in floods, which buried cities and drowned provinces; wrenching away the villages on their banks, destroying and reproducing the land with an equal balance. The High-born Dawn, the Genial Sun, the Friendly Day, and the kindly but confused old groups of Vedic deities, accordingly gave place to the conception of one god in his three solemn manifestations as Brahmá the Creator, Vishnu the Preserver, and Siva the Destroyer and Reproducer.

Each of these highly elaborated gods had his prototype among the Vedic deities; and they remain to this hour the three persons of the Hindu Triad. Brahmá, the Creator, was too abstract an idea to be a popular god; and in a journey through India, the traveller comes on only one great seat of his worship at the present day, on the margin of the sacred lake PUSHKARA, near Ajmere. A single day of Brahmá is 2160 millions of man's years. Vishnu, the Preserver, was a more useful and practical deity. In his ten incarnations, especially in his seventh and eighth, as Ráma and Krishna, under many names and in varied forms, he took the place of the bright Vedic gods. Siva, the third person of the Triad, embodied, as Destroyer and Reproducer, the profound Bráhmanical conception of death as a change of state and an entry into new life. He thus obtained, on the one hand, the special reverence of the mystic and philosophic sects among the Bráhmans; while, on the other, his terrible aspects associated him alike with the Rudra, or 'God of Roaring Tempests' of the Veda, and with the blood-loving deities of the non-Aryan tribes. Vishnu and Siva, in their diverse male and female shapes, now form, for practical purposes, the gods of the Hindu population.

The truth is, that the Aryans in India worshipped—first, as they feared; then, as they admired; and finally, as they reasoned. Their earliest Vedic gods were the stupendous phenomena of

the visible world, these deities became divine heroes in the epic legends, and they were spiritualized into abstractions by the philosophical schools. From the Vedic era downward—that is to say, during a period which cannot be estimated at less than 3000 years—the Brahmans have slowly elaborated the forces and splendid manifestations of nature into a harmonious godhead, and constructed a system of belief and worship for the Indian people. They also pondered deeply on the mysteries of life. Whence arose this fabric of the visible world, and whence came we ourselves—we who with conscious minds look out upon it? It is to these questions that philosophy has, among all races, owed her birth, and the Brāhmans arranged their widely diverse answers to them in six great systems or *darsanas*, literally ‘mirrors of knowledge’.

The present sketch can only touch upon the vast body of speculation which thus grew up, at least 500 years before Christ. The universal insoluble problems of thought and being, of mind and matter, and of soul as apart from both, of the origin of evil, of the *summum bonum* of life, of necessity and freewill, and of the relations of the Creator to the creature, are in the six schools of Brāhmanical philosophy endlessly discussed.

The Sāṅkhya system of the sage Kapila explains the visible world by assuming the existence of a primordial matter from all eternity, out of which the universe has, by successive stages, evolved itself. The Yoga school of Patanjali assumes the existence of a primordial soul, interior to the primeval matter, and holds that from the union of the two the spirit of life (*mahatma*) arose. The two Vedānta schools ascribe the visible world to a divine act of creation, and assume an omnipotent god as the cause of the existence, the continuance, and the dissolution of the universe. The Nyāya or logical school of Gautama enunciates the method of arriving at truth, and lays special stress on the sensations as the source of knowledge. It is usually classed together with the sixth school, the Vaiśeṣika, founded by the sage Kanada, which teaches the existence of a transient world composed of eternal atoms. All the six schools had the same starting point, *ex nihilo nihil fit*. Their sages, as a rule, struggled towards the same end, namely the liberation of the human soul from the necessity of existence and from the chain of future births, by its absorption into the Supreme Soul, or primordial Essence of the universe.¹

¹ Any attempt to fuse into a few lines the vast conflicting masses of Hindu philosophical doctrines must be unsatisfactory. Objections may be taken to compressing the sub-divisions and branching doctrines of each

Summary
of Brah-
man
religion.

The Brāhman, therefore, treated philosophy as a branch of religion. Now the universal functions of religion are to lay down a rule of conduct for this life, and to supply some guide to the next. The Brāhman solutions to the problems of practical religion, were self-discipline, aims, sacrifice to and contemplation of the deity. But besides the practical questions of the spiritual life, religion has also intellectual problems, such as the compatibility of evil with the goodness of God, and the unequal distribution of happiness and misery in this life. Brāhman philosophy exhausted the possible solutions of these difficulties, and of most of the other great problems which have since perplexed Greek and Roman sage, mediæval schoolman, and modern man of science. The various hypotheses of Creation, Arrangement, and Development were each elaborated; and the views of physiologists at the present day are a return, with new lights, to the evolution theory of Kapila. His Sāṅkhya system is held by Weber to be the oldest of the six Brāhman schools, and certainly dates from not later than 500 B.C. The works on Religion published in the native languages in India in 1877 numbered 1192, besides 56 on Mental and Moral Philosophy. In 1882, the totals had risen to 1545 on Religion, and 153 on Mental and Moral Philosophy.

Brahman
science.

The Brāhman had also a circle of sciences of their own. The Science of Language, indeed, had been reduced in India to fundamental principles at a time when the grammarians of the West still treated it on the basis of accidental resemblances; and modern philology dates from the study of Sanskrit by

Sanskrit
grammar.

European scholars. Pāṇini was the architect of Sanskrit grammar: but a long succession of grammarians must have laboured before he reared his enduring fabric. The date of Pāṇini has been assigned by his learned editor Bōhtlingk to about 350 B.C. Weber, reasoning from a statement made (long afterwards) by the Chinese pilgrim Hiuen Tsiang, sug-

Pāṇini

gests that it may have been later. The grammar of Pāṇini stands supreme among the grammars of the world, alike for its precision of statement, and for its thorough analysis of the roots of the language and of the formative principles of words. By employing an algebraic terminology it attains a sharp succinctness unrivalled in brevity, but at times enigmatical. It arranges, in logical harmony, the whole phenomena school into a single sentence. But space forbids a more lengthy disquisition. The foregoing paragraphs endeavour to fairly condense the accounts which H. H. Wilson, Albrecht Weber, Professor Dowson, and the Rev. H. M. Banerji give of the Six *Darśanas* or Schools.

which the Sanskrit language presents, and stands forth as one of the most splendid achievements of human invention and industry. So elaborate is the structure, that doubts have arisen whether its complex rules of formation and phonetic change, its polysyllabic derivatives, its ten conjugations with their multiform aorists and long array of tenses, could ever have been the spoken language of a people. This question will be discussed in the chapter on the modern vernaculars of India.

It is certain that a divergence had taken place before the time of Pāṇini (350 B.C.), and that the spoken language, or *Prākṛita bhāṣa*, had already assumed simpler forms by the assimilation of consonants and the curtailment of terminals. The *Sanskṛita bhāṣa*, literally, the 'perfected speech,' which Pāṇini stereotyped by his grammar, developed the old Aryan tendency to accumulations of consonants with an undiminished, or perhaps an increased array of inflections. In this highly elaborated Sanskrit the Brahmans wrote. It became the literary language of India,—isolated from the spoken dialects, but prescribed as the vehicle for philosophy, science, and all poetry of serious aim or epic dignity. As the Aryan race mingled with the previous inhabitants of the land, the spoken Prakrits adopted words of non-Aryan origin and severed themselves from Sanskrit, which for at least 2000 years has been unintelligible to the common people of India. The old synthetic spoken dialects, or Prakrits underwent the same decay as Latin did, into analytic vernaculars, and about the same time. The noble parent languages alike in India and in Italy, died, but they gave birth to families of vernaculars which can never die.

An intermediate stage of the process can be traced in the *Hindu drama*, in which persons of good birth speak in Prākṛitized Sanskrit, and the low castes in a *bhāṣā*, or patois, between the old Prākṛit and the modern dialects. It is chiefly under the popularizing influences of British rule that the Indian vernaculars have become literary languages. Until the last century, Sanskrit, although as dead as Latin so far as the mass of the people were concerned, was the vehicle for all intellectual and artistic effort among the Hindus, their local ballads and the writings of religious reformers excepted. In addition, therefore, to other sources of influence, the Brahmans were the interpreters of a national literature written in a language unknown to the people.

The priceless inheritance thus committed to their charge they handed down, to a great extent, by word of mouth. Partly

Sanskrit
and
Prakrit
speech

manu
scripts.

No very
ancient
Indian
MSS.

from this cause, but chiefly owing to the destructive climate of India, no Sanskrit manuscripts of remote antiquity exist. A fairly continuous series of inscriptions on rocks, pillars, and copper-plates, enable us to trace back the Indian alphabets to the 3rd century B.C. But the more ancient of existing Sanskrit manuscripts are only four hundred years old, very few have an age exceeding five centuries, and only two date as far back as 1132 and 1008 A.D.¹ The earliest Indian MS. (1008 A.D.) comes from the cold, dry highlands of Nepál.² In Kashmír, birch-bark was extensively used: a substitute for paper also employed in India before 500 A.D., and still surviving in the amulets with verses on them which hang round the neck of Hindus.³ Indeed, birch-bark is to this day used by some native merchants in the Simla Hills for their account books.

Palm-leaf
MSS. of
Japan.

The palm-leaf was, however, the chief writing material in ancient and mediæval India. Two Sanskrit manuscripts on this substance have been preserved in the Monastery of Horiûzi in Japan since the year 609 A.D. It seems probable that these two strips of palm-leaf were previously the property of a Buddhist monk who migrated from India to China in 520 A.D.⁴ At any rate, they cannot date later than the first half of the 6th century; and they are the oldest Sanskrit manuscripts yet discovered. They were photographed in the *Anecdota Oxoniensia*, 1884.

520 A.D. ?

The
Indian
Alphabets.

With regard to the origin of the Indian alphabets, the evidence is still too undigested to safely permit of cursory statement. Of the two characters in which the Asoka inscriptions were written (250 A.D.), the northern variety, or Ariano-Páli, is now admitted to be of Phœnician, or at any rate of non-Indian,

¹ Footnote 198a to Weber's *Hist. Ind. Lit.* p. 182 (1878), quoting the report of Rájendrá Lálá Mitra (1874), and Dr. Rost's letter (1875). Mr. R. Cust, in a note for *The Imperial Gazetteer of India*, assigns the year 883 A.D. as the date of the earliest existing Sanskrit MS. at Cambridge. But this remains doubtful. For very interesting information regarding the age of Indian MSS. see the official reports of the Search for Sanskrit Manuscripts in Bengal, Bombay, and Madras; particularly Dr. G. Bühler's (extra number of the *Journal of the Bombay Branch of the Royal Asiatic Society*, No. xxxiv.A, vol. xii. 1877), and Professor P. Peterson's (extra numbers of the same Journal, xli. 1883, and xlv. 1884).

² The present author has printed and sent to the India Office Library, for public reference, a catalogue of the 332 Sanskrit Buddhist MSS. collected by Mr. B. H. Hodgson in Nepál.

³ Dr. Bühler's *Tour in Search for Sanskrit MSS.*, *Journal Bombay Asiatic Society*, xxxiv.A, p. 29, and footnote. 1877.

⁴ *Anecdota Oxoniensia*, Aryan Series, p. 64, vol. i. Part III. (1884.) See also Part I. of the volume, and pp. 3, 4 of Part III.

parentage The southern variety, or Indo Pāli, is believed by some scholars to be of Western origin, while others hold it to be an independent Indian alphabet An attempt has even been made to trace back its letters to an indigenous system of picture writing, or hieroglyphs, in pre historic India¹ Quintus Curtius mentions that the Indians wrote on leaves in the time of Alexander (326 B C)² They do so to this hour Few, if any, Indian manuscripts on paper belong to a period anterior to the 16th century A D The earliest Indian writings are on copper or stone, the medæval ones generally on strips of palm leaves General Cunningham possesses a short inscription, written with ink in the inside of a lid made of soapstone, dating from the time of Asoka, or 256 B C The introduction of paper as a writing material may be studied in the interesting collection of Sanskrit manuscripts at the Deccan College, Poona.

Sanskrit literature was the more easily transmitted by word of mouth, from the circumstance that it was almost entirely written in verse A prose style, simple and compact, had grown up during the early age following that of the Vedic hymns But Sanskrit literature begins with the later, although still ancient, stage of Aryan development, which superseded the Vedic gods by the Brahmanical Triad of Brahmā, Vishnu, and Siva When Sanskrit appears definitely on the scene in the centuries preceding the birth of Christ, it adopted once and for all a rhythmic versification alike for poetry, philosophy, science, law, and religion, with the exception of the Beast Fables and the almost algebraic strings of aphorisms in the Sūtras The Buddhist legends adhered more closely to the spoken dialects of ancient India, *prākṛita bhāṣa*, and they also have retained a prose style But in classical Sanskrit literature, prose became an arrested development, the *śloka* or verse reigned supreme, and nothing can be clumsier than the attempts at prose in later Sanskrit romances and commentaries Prose

Sanskrit
writings
almost
entirely in
verse

Prose, a
forgotten
art.

¹ By General Cunningham, *Corpus Inscriptionum Indicarum*, pp 52 et seq The attempt cannot be pronounced successful Dr Burnell's *Palaography of Southern India* exhibits the successive developments of the Indian alphabet For the growth of the Indian dialects, see Mr Beames' *Comparative Grammar of the Modern Aryan Languages of India*, Dr Rudolph Hoernle's *Comparative Grammar of the Gaudian Languages*, two excellent papers, by Mr E L Brandreth, on the Gaudian Languages, in the *Journ Roy Asi Soc*, vols xi xii, and Mr R N Cust's *Linguistic and Oriental Essays*, pp 144-171, Trubner, 1880. For a compendious view of the Indian alphabets see Faulmann's *Buch der Schrift*, 119-158, Vienna, 1880

² *Alexander in India*, lib viii cap 9, v 15

writing was practically a lost art in India during eighteen hundred years.

Sanskrit
diction-
aries.

Sanskrit dictionaries are a more modern product than Sanskrit grammars. The oldest Indian lexicographer whose work survives, Amara-Sinha, ranked among the 'nine gems' at the court of Vikramāditya, one of several monarchs of the same name—assigned to various periods from 56 B.C. to 1050 A.D. The particular Vikramāditya under whom the 'nine gems' are said to have flourished, appears from evidence in Hiuen Tsiang's travels to have lived about 500 to 550 A.D. A well-known memorial verse makes Amara-Sinha a contemporary of Varāha-Mihira, the astronomer, 504 A.D. The other Sanskrit lexicons which have come down belong to the 11th, 12th, and subsequent centuries A.D. Those centuries, indeed, seem to mark an era of industry in Sanskrit dictionary-making; and there is little inherent evidence in Amara-Sinha's work (the Amara-kosha) to show that, in its present form, it was separated from them by any wide interval. The number of works on language published in 1877 in the Indian tongues, was 604; and in 1882, 738.

The
Amara-
kosha,
550 A.D. ?

Brāhman
astronomy.

Indepen-
dent
period, to
500 B.C.

The astronomy of the Brāhmins has formed alternately the subject of excessive admiration and of misplaced contempt. The truth is, that there are three periods of Sanskrit astronomy (*Jyoti-sāstra*). The first period belongs to Vedic times, and has left a moderate store of independent observations and inferences worked out by the Brāhmins. The Vedic poets had arrived at a tolerably correct calculation of the solar year; which they divided into 360 days, with an intercalary month every five years. They were also acquainted with the phases of the moon; they divided her pathway through the heavens into 27 or 28 lunar mansions; and they had made observations of a few of the fixed stars. The order in which the lunar mansions are enumerated is one which must have been established 'somewhere between 1472 and 536 B.C.' (Weber). The planets were also an independent, although a later discovery, bordering on the Vedic period. At first seven, afterwards nine in number, they bear names of Indian origin; and the generic term for planet, *graha*, the seizer, had its source in primitive Sanskrit astrology. The planets are mentioned for the first time, perhaps, in the Taittirīya-Aryanaka. The Laws of Manu, however, are silent regarding them; but their worship is inculcated in the later code of Yājñavalkya. The zodiacal signs and the Jyotisha, or so-called Vedic Calendar,—with its solstitial points referring to 1181 B.C., or to a period still more remote,—seem to have

been constructed, or at any rate completed, in an age long subsequent to the Veda. The influence of the Chinese observers upon Indian astronomy, especially with regard to the lunar mansions, is an undecided but a pregnant question

The second period of Brahman astronomy dates from the Greek and Greco Bactrian invasions of India, during the three centuries before Christ. The influence of Greece infused new life into the astronomy of the Hindus. The Indian astronomers of this period speak of the Yavanas or Greeks, as their instructors and one of their five systems is entitled the Romaka Siddhanta¹. Their chief writer in the 6th century, Varāha Mihira 504 A D, gives the Greek names of the planets side by side with their Indian appellations and one of his works bears a Greek title *Hori Sastra* (ὥρη). The Greek division of the heavens into zodiacal signs decans and degrees, enabled the Brāhmins to cultivate astronomy in a scientific spirit, and they elaborated a new system of their own. They rectified the succession of the Sanskrit lunar mansions which had ceased to be in accordance with the actual facts transferring the two last of the old order to the first two places in the new.

In certain points the Brāhmins advanced beyond Greek astronomy. Their fame spread throughout the West and found entrance into the *Chronicon Paschale* (commenced about 330 A D, revised, under Heraclius 610–641 A D). In the 8th and 9th centuries, the Arabs became their disciples borrowed the lunar mansions in the revised order from the Hindus and translated the Sanskrit astronomical treatises *Siddhāntas* under the name of *Sindhends*. The Brahman astronomer of the 6th century, Varāha Mihira, was followed by a famous sage Brahma Gupta, in the 7th (664 A D), and by a succession of distinguished workers, ending with Bhāskara, in the 12th (1150 A D).

The Muhammadan conquest of India then put a stop to further independent progress. After the death of Bhāskara, Indian astronomy gradually decayed, and owed any occasional impulse of vitality to Arabic science. Hindu observers of note arose at rare intervals. In the 18th century (1710–1735), Rājā Jai Singh II constructed a set of observatories at his capital Jaipur, and at Delhi, Benares, Muttra, and Ujjain. His observations enabled him to correct the astronomical tables

Second period,
Greek influences
327 B C to
1000 A D

Best age of
Brahman
astronomy

6th century
A D

Third
period
decay
under
Muham-
madan
rule—
1150–1800
A D
Jai Singh's
observa-
tories,
1728

¹ That is, the Grecian Siddhānta. Another the Paulisa Siddhānta, is stated by Al Biruni to have been composed by Paulus al Yunani and is probably to be regarded, says Weber, as a translation of the *Εκταγμα* of Paulus Alexandrinus. But see Weber's own footnote, No 277, p 253 *Hist Ind Lit* (1878)

Rájá of
Jaipur's
observa-
tories,
1728.

of De la Hire, published in 1702, before the French accepted the Newtonian Astronomy. The Rájá left, as a monument of his skill, lists of stars collated by himself, known as the Tij Muhammad Sháhi, or Tables of Muhammad Sháh, the Emperor of Delhi, by whose command he undertook the reformation of the Indian Calendar. His observatory at Benares survives to this day; and elsewhere, his huge astronomical structures testify, by their ruins, to the ambitious character of his observations. Nevertheless, Hindu astronomy steadily declined. From Vedic times it had linked omens and portents with the study of the heavens. Under the Muhammadan dynasties it degenerated into a tool of trade in the hands of almanac-makers, genealogists, astrologers, and charlatans. It is doubtful how far even Rájá Jai Singh's observations were conducted by native astronomers. It is certain that the Catholic missionaries contributed greatly to his reputation; and that since the sixteenth century the astronomy of the Hindus, as of the Chinese, is deeply indebted to the science of the Jesuits.

Bráhma-
man
mathe-
matics.

In algebra and arithmetic, the Bráhmans attained to a high degree of proficiency independent of Western aid. To them we owe the invention of the numerical symbols on the decimal system; the Indian figures 1 to 9 being abbreviated forms of the initial letters of the numerals themselves,¹ and the zero, or 0, representing the first letter of the Sanskrit word for empty (*śūnya*). The correspondence of the numeral figures with the initial letters of their Indian names, can be clearly traced in the Lúndi character, a cursive form of writing still used in the Punjab, especially among the hereditary trading castes. The Arabs borrowed these figures from the Hindus, called them the 'Indian cyphers,' and transmitted them to Europe. The Arabian mathematicians, indeed, frequently extol the learning of the Indians; and the Sanskrit term for the apex of a planet's orbit seems to have passed into the Latin translations of the Arabic astronomers.² The works on mathematics and mechanical science, published in the native languages in India in 1877, numbered 89; and, in 1882, 166.

Bráhma-
man
medicine.

The medical science of the Bráhmans was also an independent development. The national astronomy and the national medicine of India alike derived their first impulses from the exigencies of the national worship. Observations of the

¹ Dr. Burnell, however, questioned this generally accepted view, and suggested that the old cave numerals of India are themselves of Greek origin.

² The Sanskrit *uccha* has become the *aux* (gen. *augis*) of the Latin translators (Reinaud, p. 525; Weber, p. 257).

heavenly bodies were required to fix the dates of the recurring festivals, anatomical knowledge took its origin in the dissection of the victim at the sacrifice, with a view to dedicating the different parts to the proper gods. The Hindus ranked their medical science as an *upa veda*, or a supplementary revelation, under the title of *Ayur Veda*, and ascribed it to the gods. But their earliest medical authorities belong to the Sutra period, or later scholastic development, of the Yájur Veda. The specific diseases whose names occur in Pāṇini's Grammar indicate that medical studies had made progress before his time (350 B.C.). The chapter on the human body in the earliest Sanskrit dictionary, the *Amara koṣha* (c. 550 A.D.), presupposes a systematic cultivation of the science. The works of the great Indian physicians Charak and Susruta, were translated into Arabic not later than the 8th century.

Its independent development, 4th century B.C. to 8th century A.D.

Unlike the astronomical treatises of the Brāhmins, the Hindu medical works never refer to the Yavanas, or Greeks, as authorities, and, with one doubtful exception, they contain no names which point to a foreign origin. The chief seat of the science was at Benares, far to the east of Greek influence in India. Indeed, Indian pharmacy employed the weights and measures of Provinces still farther to the south east, namely, Magadha and Kalinga. Arabic medicine was founded on the translations from the Sanskrit treatises made by command of the Kaliphs of Bagdad 750-960 A.D. European medicine, down to the 17th century, was based upon the Arabic, and the name of the Indian physician Charaka repeatedly occurs in the Latin translations of Avicenna (Ibn Sina), Rhazes (Al Rasi) and Serapion (Ibn Serabi).

The basis of Arabic and European medicine

Indian medicine dealt with the whole area of the science. It described the structure of the body, its organs, ligaments, muscles, vessels, and tissues. The *materia medica* of the Hindus embraces a vast collection of drugs belonging to the mineral, vegetable, and animal kingdoms, many of which have been adopted by European physicians. Their pharmacy contained ingenious processes of preparation, with elaborate directions for the administration and classification of medicines. Much attention was devoted to hygiene, to the regimen of the body, and to diet.

Scope of Indian medicine

The surgery of the ancient Indian physicians appears to have been bold and skilful. They conducted amputations, arresting the bleeding by pressure, a cup-shaped bandage, and boiling oil. They practised lithotomy, performed operations in the abdomen and uterus, cured hernia, fistula, piles, set broken

Indian surgery

Nose-
making.

bones and dislocations; and were dexterous in the extraction of foreign substances from the body. A special branch of surgery was devoted to rhinoplasty, or operations for improving deformed ears and noses, and forming new ones; a useful operation in a country where mutilation formed part of the judicial system, and one which European surgeons have borrowed. It is practised with much success in the Residency Hospital at Indore, Holkar's capital; as jealous husbands in Native States still resort, in spite of more humane laws, to their ancient remedy against a suspected or unfaithful wife. This consists in throwing the woman violently down on the ground and slashing off her nose.

Operation
for neu-
algia.

The ancient Indian surgeons also mention a cure for neuralgia, analogous to the modern cutting of the fifth nerve above the eyebrow. They devoted great care to the making of surgical instruments, and to the training of students by means of operations performed on wax spread out on a board, or on the tissues and cells of the vegetable kingdom, and upon dead animals. They were expert in midwifery, not shrinking from the most critical operations; and in the diseases of women and children. Their practice of physic embraced the classification, causes, symptoms, and treatment of diseases,—diagnosis and prognosis. The maladies thus dealt with have been arranged into 10 classes, namely—those affecting (1) the humours; (2) the general system, including fevers; (3 to 9) the several organs and parts of the body; and (10) trivial complaints. Considerable advances were also made in veteri-

Veterinary
surgery.

nary science, and monographs exist on the diseases of horses and elephants.

Best age
of Indian
medicine,
250 B.C. to
750 A.D.

The best era of Indian medicine was contemporary with the ascendancy of Buddhism (250 B.C. to 750 A.D.), and did not long survive it. The science was studied in the chief centres of Buddhist civilisation, such as the great monastic university of Nalanda, near Gayá. The ancient Brāhmans may have derived the rudiments of anatomy from the dissection of the sacrifice; but the public hospitals which the Buddhist princes established in every city were probably the true schools of Indian medicine. A large number of cases were collected in them for continuous observation and treatment; and they supplied opportunities for the study of disease similar to those which the Greek physicians obtained at their hospital camps around the mineral springs. Hippokrates was a priest-physician, indeed the descendant of a line of priest-physicians, practising at such a spring; and Charaka was in many ways his Indian

Buddhist
public
hospitals.

counterpart To the present day, works on Hindu medicine frequently commence their sections with the words, 'Charaka says' This half-mythical authority, and Susruta, furnish the types of the ancient Indian physician, and probably belong, so far as they were real personages, to about the commencement of the Christian era Both appear as Brahmins, Susruta being, according to tradition, the son of the sage Viswamitra (p. 92), and Charaka, of another 'Veda learned Muni.'

As Buddhism passed into modern Hinduism (750-1000 A.D.), and the shackles of caste were reimposed with an iron rigour, the Brahmins more scrupulously avoided contact with blood or morbid matter They withdrew from the medical profession, and left it entirely in the hands of the Vaidyas, a lower caste, sprung from a Brahmin father and a mother of the Vaisya or cultivating class These in their turn shrank more and more from touching dead bodies, and from those ancient operations on 'the carcase of a bullock,' etc., by which alone surgical skill could be acquired The abolition of the public hospitals on the downfall of Buddhism, must also have proved a great loss to Indian medicine The series of Muhammadan conquests, commencing about 1000 A.D., brought in a new school of foreign physicians, who derived their knowledge from the Arabic translations of the Sanskrit medical works of the best period These Musalman doctors or *hakims* monopolized the patronage of the Muhammadan princes and nobles of India The decline of Hindu medicine went on until it has sunk into the hands of the village *kabiraj*, whose knowledge consists of jumbled fragments of the Sanskrit texts, and a by no means contemptible pharmacopœia, supplemented by spells, fasts, and quackery While the dissection of the human body under Vesalius and Fabricius was giving birth to modern medicine in the 17th century, the best of the Hindu physicians were working upon the recollections of a long past age without any new lights

Decline of
Hindu
medicine,

750 to
1850 A.D.

The
village
kabiraj

On the establishment of medical colleges in India by the British Government, in the middle of the present century, the Muhammadan youth took advantage of them in disproportionately large numbers But the Brahmins and intellectual classes of the Hindus soon realized that those colleges were the doors to an honourable and a lucrative career Having accepted the change, they strove with their characteristic industry and acuteness to place themselves at the head of it In 1879, of the 1661 pupils in British medical schools throughout India, 950 were Hindus and 284 were

English
medical
colleges
in India

Revival of
medicine
in India. Muhammadans, while the remaining 427 included Christians, Pársis, and all others. Of three Indian youths studying medicine at the University of Edinburgh during the same year, one belonged to the Káyasth or Hindu writer caste, another to the Vaidya or hereditary physician caste, and the third was a Bráhmaṇ. The number of medical works published in the native languages of India in 1877 amounted to 130; and in 1882 to 212, besides 87 on natural science, not including mathematics and mechanics.¹

Hindu art
of war. The Bráhmaṇs regarded not only medicine, but also the arts of war, music, and architecture as *upa-vedas*, or supplementary parts of their divinely-inspired knowledge. Viswámitra, the Vedic sage of royal warrior birth, who in the end attained to Bráhmaṇhood (p. 92), was the first teacher of the art of war (*dhanur-veda*). The Sanskrit epics prove that strategy had attained to the position of a recognised science before the birth of Christ, and the later Agni Purána devotes long sections to its systematic treatment.

Indian
music. The Indian art of music (*gándharva-veda*) was destined to exercise a wider influence. A regular system of notation had been worked out before the age of Pánini (350 B.C.), and the seven notes were designated by their initial letters. This notation passed from the Bráhmaṇs through the Persians to Arabia, and was thence introduced into European music by Guido d'Arezzo at the beginning of the 11th century.² Some, indeed, suppose that our modern word *gamut* comes not from the Greek letter gamma, but from the Indian *gáma* (in Prákrit; in Sanskrit, *gráma*), literally 'a musical scale.'

Hindu music, after a period of excessive elaboration, sank under the Muhammadans into a state of arrested development. Of the 36 chief musicians in the time of Akbar, only 5 were Hindus. Not content with tones and semi-tones, the Indian

¹ For monographs on this interesting branch of Indian science, see the articles of Dr. E. Haas, 'Ueber die Ursprünge der Indischen Medizin, mit besonderem Bezug auf Susruta,' and 'Hippokrates und die Indische Medizin des Mittelalters,' *Zeitschrift der Deutschen Morgenländischen Gesellschaft* for 1876, p. 617, and 1877, p. 647; the 'Indische Medizin, Karaka,' of Professor Roth in the *Zeitschrift der Deutschen Morgenländischen Gesellschaft* for 1872, p. 441; the *Review of the History of Medicine among the Asiatics*, by T. A. Wise, M.D., 2 vols., 1867; H. H. Wilson's little essay, *Works*, iii. 269 (ed. 1864); the excellent summary in Weber's *History of Indian Literature*, Trübner, 1878; and Dr. Watts' *Dict. Economic Products of India* (Calcutta, 1885).

² Von Bohlen, *Das Alte Indien*, ii. 195 (1830); Benfey's *Indien* (Ersch & Gruber's *Encyclopædic*, xvii., 1840); quoted by Weber, *Hist. Ind. Lit.*, p. 272, footnote 315 (1878).

musicians employ a more minute sub division, together with a number of sonal modifications, which the Western ear neither recognises nor enjoys. Thus they divide the octave into 22 sub tones, instead of the 12 tones and semi tones of the European scale. This is one of several fundamental differences, but it alone suffices to render Indian music barbaric to us, giving it the effect of a Scotch ballad in a minor key, sung intentionally a little out of tune.

Melodies which the Indian composer pronounces to be the perfection of harmony, and which have for ages touched the hearts and fired the imagination of Indian audiences, are condemned as discord by the European critic. The Hindu ear has been trained to recognise modifications of sound which the European ear refuses to take pleasure in. Our ears, on the other hand, have been taught to expect harmonic combinations for which Indian music substitutes different combinations of its own. The Indian musician declines altogether to be judged by the few simple Hindu airs which the English ear can appreciate. It is, indeed, impossible to adequately represent the Indian system by the European notation, and the full range of its effects can only be rendered by Indian instruments—a vast collection of sound producers, slowly elaborated during 2000 years to suit the special requirements of Hindu music. The complicated structure of its musical modes (*rāgs*) rests upon three separate systems, one of which consists of five, another of six, and the other of seven notes. It preserves in a living state some of the early forms which puzzle the student of Greek music, side by side with the most complicated developments.

Patriotic Hindus have of late endeavoured to bring about a musical revival upon the old Sanskrit basis. Within the past fifteen years, Rājā Sir Surendra Mohan Tagore of Calcutta has published a series of interesting works on Indian music in the English tongue, adopting as far as possible the European notation. He has organized an orchestra to illustrate the art, and presented complete collections of Hindu instruments to the Conservatoire at Paris, and to other institutions in Europe. One of the earliest subjects which the new movement took as its theme, was the celebration of the Queen of England and her ancestors, in a Sanskrit volume entitled the *Victoria Gītika* (Calcutta, 1875). No Englishman has yet brought an adequate acquaintance with the *technique* of Indian instrumentation to the study of Hindu music. The art still awaits investigation by some eminent

Its peculiar
artistic

Revival of
Hindu
music

Western professor; and the contempt with which Europeans in India regard it, merely proves their ignorance of the system on which Hindu music is built up.

Indian
architec-
ture.

Indian architecture (*artha-sāstra*¹), although also ranked as an *upa-veda* or supplementary part of inspired learning, derived its development from Buddhist rather than from Bráhmānical impulses. A brick altar sufficed for the Vedic ritual. The Buddhists were the great stone-builders of India. Their monasteries and shrines exhibit the history of the art during twenty-two centuries, from the earliest cave structures and rock-temples, to the latest Jain erections, dazzling in stucco and overcrowded with ornament. It seems not improbable that the churches of Europe owe their steeples to the Buddhist topes. The Greco-Bactrian kingdom profoundly influenced architecture and sculpture in Northern India; the Musalmán conquerors brought in new forms and requirements of their own. Nevertheless, Hindu art powerfully asserted itself in the imperial works of the Mughals, and has left memorials which extort the admiration and astonishment of our age.

Greco-
Bactrian
and

Muham-
madan
influences.

The Hindu builders derived from the Muhammadans a lightness of structure which they did not formerly possess. The Hindu palace-architecture of Gwalior, the Indian-Muhammadan mosques and mausoleums of Agra and Delhi, with several of the older Hindu temples of Southern India, stand unrivalled for grace of outline and elaborate wealth of ornament. The Táj-Mahal at Agra justifies Heber's exclamation, that its builders had designed like Titans, and finished like jewellers. The open-carved marble windows and screens at Ahmadábád furnish examples of the skilful ornamentation which beautifies every Indian building, from the cave monasteries of the Buddhist period downward. They also show with what plasticity the Hindu architects adapted their Indian ornamentation to the structural requirements of the Muhammadan mosque.

Indian
decorative
art.

English decorative art in our day has borrowed largely from Indian forms and patterns. The exquisite scrolls on the rock-temples at Karli and Ajanta, the delicate marble tracery and flat wood-carving of Western India, the harmonious blending of forms and colours in the fabrics of Kashmír, have contributed to the restoration of taste in England. Indian art-work, when faithful to native designs, still obtains the highest honours at the international exhibitions of Europe. In pictorial art, the Hindus never

¹ Specifically, *nirmāna-silpam*, or *nirmāna-vidyā*.

made much progress, except in miniature painting, for which Indian perspective is not required. But some of the book illustrations, ^{Indian painting} executed in India under Persian impulses, are full of spirit and beauty. The Royal library at Windsor contains the finest existing examples in this by path of art. The noble manuscript of the *Shāh Jahān Namah*, purchased in Oudh for £1200 in the last century, and now in possession of Her Majesty, will itself amply repay a visit. The specimens at the South Kensington Museum do not adequately represent Indian painting (1882). But they are almost everything that could be desired as regards Indian ornamental design, including Persian book binding, and several of the minor arts.

While the Brāhmans claimed religion, theology, and philosophy as their special domain, and the chief sciences and arts as supplementary sections of their divinely inspired knowledge, they secured their social supremacy by codes of law. Their earliest Dharma sāstras, or legal treatises, belong to the Grihya ^{Brāhman law} Sūtra period, a scholastic outgrowth from the Veda. But their two great digests, upon which the fabric of Hindu jurisprudence has been built up, are of later date. The first of these, the code of Manu, is separated from the Vedic era by a series of ^{Grihya Sūtras, 500 B.C. (?)} Brāhmanical developments, of which we possess only a few of ^{The code of Manu} the intermediate links. It is a compilation of the customary law, current probably about the 5th century B.C., and exhibits the social organization which the Brāhmans, after their successful struggle for the supremacy, had established in the Middle Land of Bengal. The Brāhmans, indeed, claim for their laws a divine origin, and ascribe them to the first Manu or Aryan man, 30 millions of years ago. But as a matter of fact, the laws of Manu are the result of a series of attempts to codify the usages of some not very extensive centre of Brāhmanism in Northern India. They form a metrical digest of local customs, condensed by degrees from a legendary mass of 100,000 couplets (*ślokas*) into 2685. They may possibly have been reduced to a written code with a view to securing the system of caste against the popular movement of Buddhism, and they seem designed to secure a rigid fixity for the privileges of the Brāhmans.

The date of the code of Manu has formed a favourite ^{The age of Manu} subject for speculation from the appearance of Sir William Jones' translation¹ downwards. The history of those speculations is typical of the modernizing process which scholarship

¹ Calcutta, 1794, followed by Hattner's translation into German, 1797

has applied to the old pretensions of Indian literature. The present writer has refrained from anything approaching to dogmatic assertion in regard to the dates assigned to Vedic and Sanskrit works ; as such assertions would involve disquisitions quite beyond the scope of this volume.

Date of
Manu ?

Older
prose code
500-200
B.C. (?)

Present
metrical
code
100-500
A.D.

Probably
500 A.D.

Code of
Yājña-
valkya.

6th cen-
tury A.D. ?

It may, therefore, be well to take the code of Manu as a single instance of the uncertainty which attaches to the date of one of the best known of Indian treatises. Sir William Jones accepted for it a fabulous antiquity of 1250 to 500 B.C. Schlegel was confident that it could not be later than 1000 B.C. Professor Monier Williams puts it at 500 B.C., and Johaentgen assigns 350 B.C. as the lowest possible date. Dr. Burnell, in his posthumous edition of the code,¹ discusses the question with admirable learning, and his conclusions must, for the present, be accepted as authoritative. As indicated in a recent paragraph, the code of Manu, or Mánava-Dharmasástra, is not in its existing metrical form an original treatise, but a versified recension of an older prose code. In its earlier shape it belonged to the Súra period, probably extending from the sixth to the second century B.C. Dr. Burnell's investigations show that our present code of Manu was a popular work intended for princes or Rájás, and their officials, rather than a technical treatise for the Bráhmans. They also prove that the present code must have been compiled between 100 and 500 A.D. ; and they indicate the latter date as the most probable one, viz. 500 A.D. 'It thus appears,' concludes Dr. Burnell, 'that the text belongs to an outgrowth of the Bráhmanical literature, which was intended for the benefit of the kings, when the Bráhmanical civilisation had begun to extend itself over the south of India.'²

The second great code of the Hindus, called after Yājñavalkya, belongs to a period when Buddhism had established itself, and probably to a territory where it was beginning to succumb to the Bráhmanical reaction. It represents the Bráhmanical side of the great controversy (although a section of it deals with the organization of Buddhist monasteries), refers to the execution of deeds on metal plates, and altogether marks an advance in legal precision. It refers more especially to the customs and state of society in the kingdom of Mithila, now the Tirhút and Purniyá Districts, after the Aryans had securely settled themselves in the Gangetic Provinces to the

¹ *The Ordinances of Manu*, by the late Arthur Coke Burnell, Ph.D., C.I.E., of the Madras Civil Service. Trübner. 1884. Pp. xv.-xlvii.

² *Idem*, xxvii.

cast and south east of their old Middle Land of Bengal. The Mitaksharā commentary of the law which bears the name of ^{Mitakshara} Yajñavalkya is in force over almost all India except Lower Bengal Proper, and the Hindus, as a whole, allow to Yajñavalkya an authority only second to that of Manu. Yajñavalkya's code was compiled apparently not later than the 6th or 7th century A.D. It is right again to mention that much earlier periods have been assigned both to Manu and Yajñavalkya than those adopted here. Duncker still accepts the old date of 600 B.C. as that at which Manu's code 'must have been put together and written down' ¹.

These codes deal with Hindu law in three branches, ^{Scope of Hindu law} namely—(1) domestic and civil rights and duties, (2) the administration of justice, (3) purification and penance. They stereotyped the unwritten usages which regulated the family life and social organization of the old Aryan communities in the Middle Land of Bengal. They did not pretend to supply a body of law for all the numerous races of India, but only for Hindu communities of the Brāhmanical type. It is doubtful whether they correctly represented the actual customary law even among the Hindu communities in the Middle Land of the Ganges. For they were evidently designed to assert and maintain the special privileges of the Brahmins. This they effected by a rigid demarcation of the employments of the people, each caste or division of a caste having its own hereditary occupation assigned to it, by stringent rules against the intermingling of the castes in marriage, by forbidding the higher castes, under severe penalties, to eat or drink or hold social intercourse with the lower, and by punishing the lower castes with cruel penances, for defiling by their touch the higher castes, or in any way infringing their privileges. ^{Its rigid caste system}

They exhibit the Hindu community in the four ancient ^{Legal division of the people} classes of priests, warriors, cultivators, and serfs (*sūdras*). But they disclose that this old Aryan classification failed to represent the actual facts even among the Aryan communities in Northern India. They admit that the mass of the people did not belong to any one of the four castes, and they very inadequately ascribe it to concubinage or illicit connections. The ancient Brāhmanical communities in Northern India, as revealed by the codes, consisted—First, of an Aryan ^{The actual division of the people} element divided into priests, warriors, and cultivators, all of whom bore the proud title of the Twice Born, and wore the sacred thread. Second, the subjugated races, 'the once born'

¹ *Ancient History of India*, 1, Professor Max Duncker, p. 195, ed. 1881.

Súdras. Third, a vast residue termed the Varna-sankara, literally the 'mingled colours;' a great but uncertain number of castes, exceeding 300, to whom was assigned a mixed descent from the four recognised classes. The first British Census of India, in 1872, proved that the same division remains the fundamental one of the Hindu community to this day.

Growth of
Hindu
law.

As the Bráhmans spread their influence eastwards and southwards from the Middle Land of Bengal, they carried their codes with them. The number of their sacred law-books (Dharma-sástras) amounted to at least fifty-six, and separate schools of Hindu law sprang up. Thus the Dáyabhága version of the Law of Inheritance prevails in Bengal; while the Mitákshará commentary on Yájñavalkya is current in Madras and throughout Southern and Western India. But all modern recensions of Hindu law rest upon the two codes of Manu or of Yájñavalkya; and these codes, as we have seen, only recorded the usages of certain Bráhmanical centres in the north, and perhaps did not fairly record even them.

Based on
customary
law.

As the Bráhmans gradually moulded the population of India into Hinduism, such codes proved too narrow a basis for dealing with the rights, duties, and social organization of the people. Later Hindu legislators accordingly inculcated the recognition of the local usages or land-law of each part of the country, and of each class or tribe. While binding together, and preserving the historical unity of, the Aryan twice-born castes by systems of law founded on their ancient codes, they made provision for the customs and diverse stages of civilisation of the ruder peoples of India, over whom they established their ascendancy. By such provisions, alike in religion and in law, the Bráhmans incorporated the Indian races into that loosely coherent mass known as the Hindu population.

Plasticity
of Hindu-
ism.

It is to this plastic element that Hinduism owes its success; and it is an element which English administrators have sometimes overlooked. The races of British India exhibit many stages of domestic institutions, from the polyandry of the Nairs to the polygamy of the Kulin Bráhmans. The structure of their rural organization varies, from the nomadic husbandry of the hillmen, to the long chain of tenures which in Bengal descends from the landlord through a series of middle-men to the actual tiller of the soil. Every stage in industrial progress is represented; from the hunting tribes of the central plateau to the rigid trade-guilds of Gujarát. The Hindu legislators recognised that each of these diverse stages of social development had its own usages and unwritten law. Even

the code of Manu acknowledged custom as a source of law, and admitted its binding force when not opposed to express law. <sup>Incor-
poration
of local
customs
into
Hinduism</sup> Vrihaspati says, 'The laws (*dharma*) practised by the various countries, castes, and tribes, they are to be preserved, other wise the people are agitated' Devala says, 'What gods there are in any country, and whatsoever be the custom and law anywhere, they are not to be despised there, the law there is such' Varāha Mihira says, 'The custom of the country is first to be considered, what is the rule in each country, that is to be done' A learned English judge in Southern India thus summed up the texts 'By custom only can the *Dharma śāstra* [Hindu law] be the rule of others than Brahmins [only one thirtieth of the population of Madras] and even in the case of Brahmins it is very often superseded by custom' ¹

The English, on assuming the government of India, wisely declared that they would administer justice according to the customs of the people. But our High Courts enforce the <sup>Perils of
modern
codifica-
tion</sup> Brāhminical codes with a comprehensiveness and precision unknown in ancient India. Thus in Bengal, the non Hindu custom of *sagai*, by which deserted or divorced wives among the lower castes marry again, was lately tried according to 'the spirit of Hindu law,' while in Madras, judges have pointed out a serious divergence between the Hindu law as now administered, and the actual usages of the people. Those usages are unwritten and uncertain. The Hindu law is printed in many accessible forms,² and Hindu barristers are ever pressing its principles upon our courts. The Hindu law is apt to be applied to non Hindu, or semi Hindu, customs.

Efforts at comprehensive codification in British India are thus surrounded by special difficulties. For it would be improper to give the fixity of a code to all the unwritten half fluid usages current among the 300 unhomogeneous castes of Hindus, while it might be fraught with future injustice to exclude any of them. Each age has the gift of adjusting

¹ Dr. Burnell's *Dśa vidhāgha*, Introd. p. xv. See also *Hindu Law as administered by the High Court of Judicature at Madras*, by J. Nelson, M.A., District Judge of Cuddapah, chaps. iii and iv (Madras, 1877), and *Jurnal Roy. Asi. Soc.*, pp. 208-236 (April 1881).

² For the latest treatment of Hindu law from the philosophical, scholarly, and practical points of view, see the third edition of West and Buhler's *Digest of the Hindu Law of Inheritance, Parturition, and Adoption*, 2 vols. Bombay 1884. From the writings of Mayne, Burnell, and Nelson in Madras, and those of the Honourable Raymond West and Dr. Bühler in Bombay, a new and more just conception of the character of Hindu law and of its relations to Indian custom may be said to date.

Codes *versus* survival of fittest customs. its institutions to its actual wants, especially among tribes whose customs have not been reduced to written law. Many of those customs will, if left to themselves, die out. Others of them, which prove suited to the new social developments under British rule, will live. A code should stereotype the survival of the fittest; but the process of natural selection must be the work of time, and not an act of conscious legislation.

Restricted scope of Indian codification. This has been recognised from time to time by the ablest of Anglo-Indian codifiers. They restrict the word code to the systematic arrangement of the rules relating to some well-marked section of juristic rights, or to some executive department of the administration of justice. 'In its larger sense,' write the Indian Law Commissioners in 1879, 'of a general assemblage of all the laws of a community, no attempt has yet been made in this country to satisfy the conception of a code. The time for its realization has manifestly not arrived.' The number of works on Law, published in the native languages of India in 1877, was 165; and in 1882, 181, besides 157 in English; total, 338 works on law published in India in 1882.

Secular literature of the Hindus. The Bráhmans were not merely the depositaries of the sacred books, the philosophy, the science, and the laws of the ancient Hindu commonwealth; they were also the creators and custodians of its secular literature. They had a practical monopoly of Vedic learning, and their policy was to trace back every branch of knowledge and of intellectual effort to the Veda. In this policy they were aided by the divergence which, as we have seen, arose at a very early date between the written and spoken languages of India. Sanskrit literature, apart from religion, philosophy, and law, consists mainly of two great epics, the drama, and a vast body of legendary, erotic, and mystical poetry.

Its chief branches. The venerable epic of the Mahábhárata ranks first. The orthodox legend ascribes it to the sage Vyása, who, according to Bráhman chronology, compiled the inspired hymns into the four Vedas, nearly five thousand years ago (3101 B.C.). But one beauty of Sanskrit is that every word discloses its ancient origin in spite of mediæval fictions, and Vyása means simply the 'arranger,' from the verb 'to fit together.' No fewer than twenty-eight Vyásas, incarnations of Brahma and Vishnu, came down in successive astronomical eras to arrange and promulgate the Vedas on earth. Many of the legends in the Mahábhárata are of Vedic antiquity, and the main story

deals with a period assigned, in the absence of conclusive evidence, to about 1200 B.C., and certainly long anterior to the time of Buddha, 543 B.C. But its compilation into its present form seems to have taken place many centuries later.

Panini (350 B.C.) makes no clear reference to it. The inquisitive Greek ambassador and historian, Megasthenes, does not appear to have heard of it during his stay in India, 300 B.C. Dion Chrysostomos supplies the earliest external evidence of the existence of the Mahābhārata, *circa* 75 A.D. The arrangement of its vast mass of legends must probably have covered a long period. Indeed, the present poem bears traces of three separate eras of compilation during which its collection of primitive folk tales grew from 8800 *stokas* or couplets, into a cyclopædia of Indian mythology and legendary lore extending over eighteen books and 220,000 lines. The twenty-four books of Homer's *Iliad* comprise only 15,693 lines, the twelve books of Virgil's *Aeneid*, only 9868. Its date
growth

The central story of the Mahābhārata occupies scarcely one-fourth of the whole, or about 50,000 lines. It narrates a prehistoric struggle between two families of the Lunar race for a patch of country near Delhi. These families, alike descended from the royal Bharata, consisted of two brotherhoods, cousins to each other, and both brought up under the same roof. The five Pāṇḍavas were the miraculously born sons of King Pandu, who, smitten by a curse, resigned the sovereignty to his brother Dhṛitaraṣṭra, and retired to a hermitage in the Himālayas, where he died. The ruins of his capital, Hastināpura, or the 'Elephant City,' are pointed out beside a deserted bed of the Ganges, 57 miles north-east of Delhi, at this day. His brother Dhṛitaraṣṭra ruled in his stead, and to him one hundred sons were born, who took the name of the Kauravas from an ancestor, Kuru. Dhṛitaraṣṭra acted as a faithful guardian to his five nephews, the Pāṇḍavas, and chose the eldest of them as heir to the family kingdom. His own sons resented this act of supersession, and so arose the quarrel between the hundred Kauravas and the five Pāṇḍavas which forms the main story of the Mahābhārata. The nucleus of the legend probably belongs to the period when the Aryan immigrants were settling in the upper part of the triangle of territory between the Jumna and the Ganges, and before they had made any considerable advances beyond the latter river. It is not unreasonable to assign this period to about the 12th century B.C. Central
story of
the Maha-
bhārata
12th cen-
tury B.C.

The hundred Kauravas forced their father to send away their

offered to her, and seem quite unaware that a later age would deem her position one which required explanation.¹

The rest of the Mahābhārata. The struggle for the kingdom of Hastināpura forms, however, only a fourth of the Mahābhārata. The remainder consists of later additions. Some of these are legends of the early Aryan settlements in the Middle Land of Bengal, tacked on to the central story; others are mythological episodes, theological discourses, and philosophic disquisitions, intended to teach the military caste its duties, especially its duty of reverence to the Brāhmins. Taken as a whole, the Mahābhārata may be said to form the cyclopædia of the Heroic Age in Northern India, with the struggle of the Pāndavas and Kauravas as its original nucleus; and the submission of the military power to priestly domination as its later didactic design.

The Rāmāyana. The second great Indian epic, the Rāmāyana, recounts the advance of the Aryans into Southern India. Unlike the Mahābhārata, its composition is assigned not to a compiler (*ryāsa*) in the abstract, but to a named poet, Vālmīki. On the other hand, the personages and episodes of the Rāmāyana have an abstract or mythological character, which contrasts with the matter-of-fact stories of the Mahābhārata. The heroine of the Rāmāyana, Sītā, is literally the 'field-furrow,' to whom the Vedic hymns and early Aryan ritual paid divine honour. She represents Aryan husbandry, and has to be defended against the raids of the aborigines by the hero Rāma, an incarnation of the Aryan deity Vishnu, and born of his divine nectar. Rāma is regarded by Weber as the analogue of Balarāma, the 'Ploughbearer' (*halabhrīt*). From this abstract point of view, the Rāmāyana exhibits the progress of Aryan plough-husbandry among the mountains and forests of Central and Southern India; and the perils of the agricultural settlers from the non-ploughing nomadic cultivators and hunting tribes.

Its allegorical character. The abduction of Sītā by an aboriginal or demon prince, who carried her off to Ceylon; her eventual recovery by Rāma; and the advance of the Aryans into Southern India, form the central story of the Rāmāyana. It differs therefore from the central legend of the Mahābhārata, as commemorating a period when the main arena of Aryan enterprise had extended itself far

¹ The beautiful story of Sāvitrī, the wife faithful to the end, is told in the Mahābhārata by the sage Mārkaṇḍeya in answer to Yudishthira's question, whether any woman so true and noble as Draupadī had ever been known. Sāvitrī, on the loss of her husband, dogged the steps of Yama, King of Death, until she wrung from him, one by one, many blessings for her family, and finally the reluctant restoration of her husband to life.

ance, but goes in quest of Ráma to bring him back as rightful heir. A contest of fraternal affection takes place. Bharata at length returns to rule the family kingdom in the name of Ráma, until the latter shall come to claim it at the end of the fourteen years of banishment appointed by their late father.

The
abduction
of Sítá.

Her
rescue.

So far, the Rámáyana merely narrates the local chronicles of the court of Ajodhya. In the third book the main story begins. Rávana, the demon or aboriginal king of the far south, smitten by the fame of Sítá's beauty, seizes her at the hermitage while her husband is away in the jungle, and flies off with her in a magical chariot through the air to Lanka or Ceylon. The next three books (4th, 5th, and 6th) recount the expedition of the bereaved Ráma for her recovery. He makes alliances with the aboriginal tribes of Southern India, under the names of monkeys and bears, and raises a great army. The Monkey general, Hanumán, jumps across the straits between India and Ceylon, discovers the princess in captivity, and leaps back with the news to Ráma. The Monkey troops then build a causeway across the narrow sea,—the Adam's Bridge of modern geography,—by which Ráma marches across and, after slaying the monster Rávana, delivers Sítá. The rescued wife proves her unbroken chastity, during her stay in the palace of Rávana, by the ancient ordeal of fire. Agni, the god of that element, himself conducted her out of the burning pile to her husband; and, the fourteen years of banishment being over, Ráma and Sítá return in triumph to Ajodhya. There they reigned gloriously; and Ráma celebrated the great horse sacrifice (*aswa-medha*) as a token of his imperial sway over India. But a famine having smitten the land, doubts arose in Ráma's heart as to his wife's purity while in her captor's power at Ceylon. He banishes the faithful Sítá, who wanders forth again to Válmiíki's hermitage, where she gives birth to Ráma's two sons. After sixteen years of exile, she is reconciled to her repentant husband, and Ráma and Sítá and their children are at last reunited.¹

Later San-
skrit epics.

Raghu-
vansa.

The Mahábhárata and the Rámáyana, however overlaid with fable, form the chronicles of the kings of the Middle Land of the Ganges, their family feuds, and their national enterprises. In the later Sanskrit epics, the legendary element is more and more overpowered by the mythological. Among them the Raghu-vansa and the Kumára-sambhava, both assigned to Kálidása, take the first rank. The Raghu-vansa

¹ Respectful mention should here be made of Growse's translation of the Hindi version of the *Rámáyana* by Tulsí Dás. (4to. Allahábád, 1883.)

celebrates the solar line of Raghu, King of Ajodhya, more particularly the ancestry and the life of his descendant Rama. The Kumāra sambhava recounts the birth of the War god ¹ Kumāra sambhava. It is still more didactic and allegorical, abounding in sentiment and in feats of prosody. But it contains passages of exquisite beauty of style and elevation of thought. From the astrological data which these two poems furnish, Jacobi infers that they cannot have been composed before 350 A.D.

The name of Kālidāsa has come down, not only as the ^{Kalidasa} composer of these two later epics, but as the father of the Sanskrit drama. According to Hindu tradition, he was one of the 'Nine Gems' or distinguished men at the court of Vikramaditya. This prince is popularly identified with the King of Ujjain who gave his name to the *Samrat era*, commencing in the year 57 B.C. But, as Holtzmann points out, it may be almost as dangerous to infer from this latter circumstance that Vikramaditya lived in 57 B.C., as to ^{King Vikramaditya} place Julius Cæsar in the first year of the so called Julian Calendar, namely, 4713 B.C. Several Vikramādityas figure in Indian history. Indeed, the name is merely a title, 'A very Sun in Prowess,' which has been borne by victorious monarchs of many of the Indian dynasties. The date of Vikramāditya has been variously assigned from 57 B.C. to 1050 A.D., and the works of the poets and philosophers who formed the ^{550 A.D.?} 'Nine Gems' of his court, appear from internal evidence to have been composed at intervals during that long period. The Vikramaditya, under whom Kālidasa and the 'Nine Gems' are said to have flourished, ruled over Malwa probably from 500 to 550 A.D.

In India, as in Greece and Rome, scenic representations ^{Age of the Sanskrit drama} seem to have taken their rise in the rude pantomime of a very early time, possibly as far back as the Vedic ritual, and the Sanskrit word for the drama, *nataka*, is derived from *nata*, a dancer. But the Sanskrit dramas of the classical age which have come down to us, probably belong to the period between the 1st century B.C. and the 8th century A.D. They make mention of Greek slaves, are acquainted with Buddhism in its full development, and disclose a wide divergence between Sanskrit and the dialects used by the lower classes. The Mahā

¹ Translated into spirited English verse by Mr. Ralph T. H. Griffith, M.A., who is also the author of a charming collection of 'Idylls from the Sanskrit,' based on the Mahabharata, Rāmāyana, Raghu vamsa, and Kālidasa's Seasons.

bhārata and Rámáyana appear in the Sanskrit drama as part of the popular literature,—in fact, as occupying very much the same position which they still hold. No dramas are known to exist among the works which the Hindus who emigrated to Java, about 500 A.D., carried with them to their new homes. Nor have any dramas been yet found among the Tibetan translations of the Sanskrit classics.

Sakuntalá. The most famous drama of Kálidása is Sakuntalá, or the 'Lost Ring.' Like the ancient epics, it divides its action between the court of the king and the hermitage in the forest. Prince Dushyanta, an ancestor of the noble Lunar race, weds by an irregular marriage a beautiful maiden, Sakuntalá, at her father's hermitage in the jungle. Before returning to his capital, he gives his bride a ring as a pledge of his love; but smitten by a curse from a holy man, she loses the ring, and cannot be recognised by her husband till it is found. Sakuntalá bears a son in her loneliness, and sets out to claim recognition for herself and child at her husband's court. But she is as one unknown to the prince, till, after many sorrows and trials, the ring comes to light. She is then happily reunited with her husband, and her son grows up to be the noble Bharata, the chief founder of the Lunar dynasty whose achievements form the theme of the Mahábhārata. Sakuntalá, like Sitá, is the type of the chaste and faithful Hindu wife; and her love and sorrow, after forming the favourite romance of the Indian people for perhaps eighteen hundred years, have furnished a theme for the great European poet of our age. 'Wouldst thou,' says Goethe,

'Wouldst thou the young year's blossoms, and the fruits of its decline,
And all by which the soul is charmed, enraptured, feasted, fed,—
Wouldst thou the earth and heaven itself in one sole name combine?
I name thee, O Sakuntalá! and all at once is said.'

Other
dramas;

Sakuntalá has had the good fortune to be translated by Sir William Jones (1789), and to be sung by Goethe. But other of the Hindu dramas and domestic poems are of almost equal interest and beauty. As examples of the classical period; may be taken the Mrichchakatí, or 'Toy Cart,' a drama in ten acts, on the old theme of the innocent cleared and the guilty punished; and the poem of Nala and Damayanti, or the 'Royal Gambler and the Faithful Wife.' Such plays and poems frequently take an episode of the Mahábhārata or Rámáyana for their subject; and in this way the main incidents in the two great epics have been gradually dramatized or reduced to the still more popular form of household song. The modern

Sanskrit,

drama was one of the first branches of literature which accepted the spoken dialect and thus it has formed the best, indeed the only, school in which a man can acquaint himself with the modern vernacular.

In our own day there has been a great increase in India new plays in the vernacular tongue coming from the press, and societies of patriotic young men have thrown themselves into dramatic companies, especially in Calcutta and Bombay. Many of the pieces are very interesting of stories from the Sanskrit epics and dramas. Several have a political significance, and deal with the process of development upon which India has entered under the influence of British rule. One Bengali play, the *Nil-darpan* or the Indigo Factory, became the subject of a celebrated trial in Calcutta while others—such as *Ekti ki Kule Samant*—this what you call civilisation?—suggests many serious thoughts to a candid English mind. In 1877 102 dramas were published in India in the native tongues and in 1880 245.

Closely allied to the drama is the prose romance. In 1825 Dr H. H. Wilson intimated that Hindu literature contained collections of domestic narrative to an extent surpassing those of any other people. The vast growth of European fiction since that date renders this statement no longer accurate. But Wilson's translations from the *Vrihat katha* may still be read with interest,² and the Sanskrit Beast stories now occupy an even more significant place in the history of Indo-European literature than they did then. Many fables of animals found their way to the western world, from the time of Æsop downwards, from their original home in India. The relation between the lion and the jackal in the Greek versions has no reality in nature. It is based however upon the actual relation between the lion and the jackal, in the Sanskrit stories.³ Weber found complete cycles of Indian fables may have existed in the time of Pāṇini (350 B.C.). It is known that the Sanskrit *Hitopadesha* or Book of Good Advice, was translated into Persian as early as the 6th century A.D., and from thence into all the subsequent versions in Asia Minor and Europe have been derived. The most ancient animal fables of the

¹ Literally The Mirror of Indigo.

² *Oriental Quarterly Magazine* Calcutta, March 1825, vol. 1, of Wilson's Collected Works, pp. 156-768. London.

³ See however Weber's elaborate footnote No. 11 in *Ind. Lit.* p. 211. Max Müller's *Conception of Fables* (*CPJ* vol. IV pp. 145-109) suggests that a well-known story from the East to the West.

the present day the nursery stories of England and America: The graceful Hindu imagination delighted also in fairy tales; and the Sanskrit compositions of this class are the original source of many of the fairy tales of Persia, Arabia, and Christendom. The works of fiction published in the native languages in India in 1877 numbered 196; and in 1882, 237.

Sanskrit
lyric
poetry.

In mediæval India, a large body of poetry, half-religious, half-amorous, grew up around the legend of the youthful Krishna (the eighth incarnation of Vishnu) and his loves with the shepherdesses, the playmates of his sweet pastoral life. Kālidāsa, according to Hindu tradition, was the father of the erotic lyric, as well as a great dramatic and epic poet. In his Megha-dūta or 'Cloud Messenger,' an exile sends a message by a wind-borne cloud to his love, and the countries beneath its long aerial route are made to pass like a panorama before the reader's eye. The Gīta Govinda, or Divine Herdsman of Jayadeva, is a Sanskrit 'Song of Solomon' of the 12th century A.D. A festival once a year celebrates the birthplace of this mystical love-poet, in the Birbhūm District of Lower Bengal; and many less famous compositions of the same class now issue from the vernacular press throughout India. In 1877, no fewer than 697 works of poetry were published in the native languages in India; and in 1882, 834.

The
Purānas,
8th to 16th
century
A.D.

The mediæval Brāhmins displayed a marvellous activity in theological as well as in lyric poetry. The Purānas, literally 'The Ancient Writings,' form a collection of religious and philosophical treatises in verse, of which the principal ones number eighteen. The whole Purānas are said to contain 1,600,000 lines. The really old ones have either been lost or been incorporated in new compilations; and the composition of the existing Purānas probably took place from the 8th to the 16th century A.D. As the epics sang the wars of the Aryan heroes, so the Purānas recount the deeds of the Brāhman gods. They deal with the creation of the universe; its successive dissolutions and reconstructions; the stories of the deities and their incarnations; the reigns of the divine Manus; and the chronicles of the Solar and Lunar lines of kings who ruled, the former in the east and the latter in the west of the Middle Land (Madhya-desh).

Contents
of the
Purānas.

Their
sects.

The Purānas belong to the period after the mass of the people had split up into their two existing divisions, as worshippers of Vishnu or of Siva, *post*, 700 A.D. They are

devoted to the glorification of one or other of these two rival gods, and thus embody the sectarian theology of Brāhmanism. While claiming to be founded on Vedic inspiration, they practically superseded the Veda, and have formed during ten centuries the sacred literature on which Hinduism rests¹ Their influence

An idea of the literary activity of the Indian mind at the present day may be formed from the fact, that 4890 works were published in India in 1877, of which 4346 were in the native languages. Only 436 were translations, the remaining 4454 being original works or new editions. The number of Indian publications constantly increases. In 1882, 6198 works were published in India, 5543 being in the native languages. The translations numbered 720, and the original works, including new editions, 5478. These figures only show the publications officially registered under the Act. A large number of unregistered pamphlets or brochures must be added, together with the daily and weekly issue of vernacular newspapers, exceeding 230 in number and circulating over 150,000 copies Indian works published in 1877 and 1882

This chapter has attempted to trace the intellectual and religious development of the early Aryans in India, and their constitution into castes and communities. Regarding their territorial history, it has said almost nothing. It has, indeed, indicated their primeval line of march from their Holy Land among the seven rivers of the Punjab, to their Land of the Sacred Singers between the upper courses of the Jumna and the Ganges, and thence to their more extensive settlements in the Middle Land of Bengal (*Madya-desha*) stretching to beyond the junction of these two great rivers. It has also told very briefly the legend of their advance into Southern India, in the epic rendering of the Rāmāyana. But the foregoing pages have refrained from attempts to fix the dates or to fill in the Absence of territorial history

¹ The foregoing pages have very briefly reviewed the most important branches of Sanskrit literature, the influence of that literature upon Hinduism will be dealt with in a subsequent chapter. To fully appreciate the connection between ancient thought and present practice in India, the student may also refer to Professor Monier Williams' *Modern India and the Indians* (Trubner, 1879). That work unites the keen observation of a traveller new to the country with the previous learning acquired during a lifetime devoted to Oriental studies. Professor Monier Williams is thus enabled to correlate the existing phenomena of Indian life with the historical types which underlie them.

details of these movements. For the territorial extension of the Aryans in India is still a battle-ground of inductive history.

Its inductive data.

Even for a much later period of Indian civilisation, the data continue under keen dispute. This will be amply apparent in the following chapters.¹ These chapters will open with the great upheaval of Buddhism against Bráhmānism in the 6th century before Christ. They will summarize the struggles of the Asiatic races in India during a period of twenty-three hundred years. They will close with the great military revival of Hinduism under the Maráthá Bráhmans in the 18th century of our era. An attempt will then be made, from the evidence of the vernacular literature and languages, to present a view of Indian thought and culture, when the European nations came in force upon the scene.

The Bráhmans in Indian history.

Meanwhile, the history of India, so far as obscurely known to us before the advent of the Greeks, 327 B.C., is essentially a literary history, and the memorials of its civilisations are mainly literary or religious memorials. The more practical aspects of those long ages, which were their real aspects to the people, found no annalist. From the commencement of the post-Vedic period, the Bráhmans strove with increasing success to bring the Aryan life and civilisation of India more and more into accord with their own priestly ideas.

The six attacks on Bráhmānism, 6th century B.C. to 19th century A.D.

In order to understand the long domination of the Bráhmans, and the influence which they still wield, it is necessary also to keep in mind their position as the great literary caste. Their priestly supremacy has been repeatedly assailed, and was during a space of nearly a thousand years overpowered by Buddhism. But throughout twenty-two centuries the Bráhmans have been the counsellors of Hindu princes and the teachers of the Hindu people. They still represent the early Aryan civilisation of India. Indeed, the essential history of India is a narrative of the attacks upon the continuity of their civilisation,—that is to say, of attacks upon the Bráhmānical system of the Middle Land, and of the modifications and compromises to which that system has had to submit.

¹ Namely, on Buddhism, the Greeks in India, the Scythic Inroads, the Rise of Hinduism, Early Muhammadan Rulers, the Mughal Empire, and the Maráthá Power. We still await the complete evidence of coins and inscriptions; although valuable materials have been already obtained from these silent memorials of the past. Mr. K. T. Telang's *Introduction to the Mudrárákshasa*, with Appendix, shows what can be gathered from a minute and critical examination of the historical data incidentally contained in the Hindu drama.

Those attacks mark out six epochs. First the religious up-¹ *Buddh*
 rising of the non Aryan and the partially Brahmanized Aryan ^{ism}
 tribes on the east of the Middle Land of Bengal, initiated by
 the preaching of Buddha in the 6th century B.C., culminating in
 the Buddhist kingdoms about the commencement of our era,
 and melting into modern Hinduism about the 8th century A.D.
 Second, warlike inroads of non Bráhmanical Aryans and Scythic ^{2. Greeks}
 races from the west strongly exemplified by the Greek invasions ^{and}
 in the 4th century B.C. and continuing under the Greco Bactrian ^{Scythians}
 empire and its Scythic rivals to probably the 5th century A.D.
 Third the influence of the so-called aborigines or non Aryan ^{3 Non}
 tribes of India and of the non Aryan low castes incorporated ^{Aryan}
 into the Hindu community—an influence ever at work—indeed ^{tribes.}
 by far the most powerful agent in dissolving Bráhmanism into
 Hinduism, and specially active after the decline of Buddhism
 about the 7th century A.D.

Fourth, the reaction against the low beliefs, priestly oppres- ^{4 Hindu}
 sion, and bloody rites which resulted from this compromise ^{sects}
 between Bráhmanism and aboriginal worship. The reaction
 received an impetus from the preaching of Sankar Achárya,
 who founded his great Siváite sect in the 8th century A.D.
 It obtained its full development under a line of ardent
 Vishnuite reformers from the 12th to the 16th centuries A.D.
 The fifth solvent of the ancient Bráhmanical civilisation of ^{5 Muham}
 India was found in the Muhammadan invasions and the rule ^{madans}
 of Islam, 1000 to 1765 A.D. The sixth, in the English ^{6 English}
 supremacy, and in the popular upheaval which it has produced
 in the 18th and 19th centuries. Each of these six epochs will
 so far as space permits, receive separate treatment in the
 following chapters.

CHAPTER V.

BUDDHISM IN INDIA (543 B.C. TO 1000 A.D.).

Buddhism. THE first great solvent of Bráhmaism was the teaching of Gautama Buddha. The life of this celebrated man has three sides,—its personal aspects, its legendary developments, and its religious consequences upon mankind. In his own person, Buddha appears as a prince and preacher of ancient India. In the legendary developments of his story, Buddha ranks as a divine teacher among his followers, as an incarnation of Vishnu among the Hindus, and as a saint of the Christian church, with a day assigned to him in both the Greek and Roman calendars. As a religious founder, he left behind a system of belief which has gained more disciples than any other creed in the world ; and which is now more or less accepted by 500 millions of people, or nearly one-half the human race. According to the Páli texts, Buddha was born 622 B.C., and died 543 B.C.¹ Modern calculations fix his death about 480 B.C.²

Gautama Buddha. The story of Buddha's earthly career is a typical one. It is based on the old Indian ideal of the noble life which we have seen depicted in the Sanskrit epics. Like the Pándavas in the Mahábhárata, and like Ráma in the Rámáyana, Buddha is the miraculously born son of a king, belonging to one of the two great Aryan lines, the Solar and the Lunar ; in Buddha's case, as in Ráma's, to the Solar. His youth, like that of the epic heroes, is spent under Bráhma tutors, and like the epic heroes he obtains a beautiful bride after a display of unexpected prowess with the bow ; or, as the northern Buddhists relate, at an actual *svayam-vara*, by a contest in arms for the princess. A period of voluntary exile follows an interval of married happiness, and Buddha retires like Ráma to a Bráhma's hermitage in the forest.

Buddha and Ráma. The sending back of the charioteer to the bereaved father's capital forms an episode in the story of both the young princes. As in the Rámáyana, so in the legend of Buddha, it is to the

¹ Childers' *Dictionary of the Páli Language*, s.v. Buddho, p. 96.

² Oldenberg's *Buddha, Sein Leben* etc. (Hoey's excellent translation, p. 197). *Vide post*, p. 153.

jungles on the south of the Ganges, lying between the Aryan settlements and the aboriginal races, that the royal exile repairs. After a time of seclusion, the Pándavas, Ráma, and Buddha alike emerge to achieve great conquests, the two former by force of arms, the last by the weapons of the Spirit. Up to this point the outline of the three stories has followed the same type; but henceforth it diverges. The Sanskrit epics depict the ideal Aryan man as prince, hermit, and hero. In the legend of Buddha, that ideal has developed into prince, hermit, and saint.

The
Indian
legend

Gautama, afterwards named Buddha, 'The Enlightened,' and Siddhártha, 'He who has fulfilled his end,' was the only son of Suddhodana, King of Kapilavastu. This prince, the chief of the Sákya clan, ruled over an outlying Aryan settlement on the north eastern border of the Middle Land, about a hundred miles to the north of Benares, and within sight of the snow topped Himálayas. A Gautama Rájput of the noble Solar line, he wished to see his son grow up on the warlike model of his race. But the young prince shunned the sports of his playmates, and retired to solitary day dreams in nooks of the palace garden. The king tried to win his son to a practical career by marrying him to a beautiful and talented girl, and the youthful Gautama unexpectedly proved his manliness by a victory over the flower of the young chiefs at a tournament. For a while he forgot his solemn speculations on the unseen, in the sweet realities of early married life.

Parentage
of Gau-
tama
Budh

622 B C

His lonely
youth, at
1-19

But in his drives through the city he deeply reflected on the types of old age, disease, and death which met his eye, and he was powerfully impressed by the calm of a holy man, who seemed to have raised his soul above the changes and sorrows of this world. After ten years, his wife bore to him an only son, and Gautama, fearing lest this new tie should bind him too closely to the things of earth, retired about the age of thirty to a cave among the forest-clad spurs of the Vindhya. The story of how he turned away from the door of his wife's lamp-lit chamber, denying himself even a parting caress of his new born babe lest he should wake the sleeping mother, and galloped off into the darkness, is one of the many tender episodes in his life. After a gloomy night ride, he sent back his one companion, the faithful charioteer, with his horse and jewels to his father. Having cut off his long Rájput locks, and exchanged his princely raiment for the rags of a poor passer by, he went on alone a homeless beggar. This abandonment of earthly pomp and power, and of loved

His mar-
ried life,
at 19-29

His Great
Renuncia-
tion, at
29-30.

wife and new-born son, is the Great Renunciation which forms a favourite theme of the Buddhist scriptures in Sanskrit, Pāli, Tibetan, and Chinese. It has furnished, during twenty centuries, the type of self-sacrifice which all Indian reformers must follow if they are to win the trust of the people.

Buddha's
forest life,
et. 30-36
or 29-34.

588 B.C.

His spiri-
tual crisis.

His tempta-
tion.

His 'En-
lighten-
ment.'

For a time Buddha studied under two Bráhmaṇ recluses, near RAJAGRIHA, in Patná District, learning from them that the path to divine knowledge and tranquillity of soul lies through the subjection of the flesh. He then buried himself deeper in the south-eastern jungles, which at that time covered Gayá District, and during six years wasted himself by austerities in company with five disciples. The temple of BUDDH-GAYA marks the site of his long penance. But instead of earning peace of mind by fasting and self-torture, he reached a crisis of religious despair, during which the Buddhist scriptures affirm that the enemy of mankind, Māra, wrestled with him in bodily shape. Torn with doubts as to whether, after all his penance, he was not destined to perdition, the haggard ascetic, in a final paroxysm, fell senseless to the earth.

When he recovered, the mental struggle had passed. He felt that the path to salvation lay not in self-torture in a mountain cave, but in preaching a higher life to his fellow-men. His five disciples, shocked by his giving up penance, forsook him; and Buddha was left in solitude to face the question whether he alone was right and all the devout minds of his age were wrong. The Buddhist scriptures depict him as sitting serene under a fig-tree, while the great Enemy and his crew whirled round him with flaming weapons. 'When the conflict began between the Saviour of the World and the Prince of Evil,' says one of their sacred texts,¹ the earth shook; the sea uprose from her bed, the rivers turned back to the mountains, the hill-tops fell crashing to the plains, the sun was darkened, and a host of headless spirits rode upon the tempest. From his temptation in the wilderness, the ascetic emerged with his doubts for ever laid at rest, seeing his way clear, and henceforth to be known as Buddha, literally 'The Enlightened.'²

This was Buddha's second birth; and the *pipal* fig or Bo (Bodhi), literally the Tree of the Enlightenment, under whose spreading branches its pangs were endured, has become

¹ The Madhurattha-Vilāsini, *Journal of the Bengal Asiatic Society*, vol. vii. p. 812. Rhys Davids' *Buddhism*, p. 36.

² According to the Ceylonese texts, Buddha 'obtained Buddhahood' in 588 B.C. This would make him 34, not 36 years of age. Childers' *Pāli Dictionary*, s.v. Buddhō.

the sacred tree of 500 millions of mankind. It is the *Ficus religiosa* of Western science. The idea of a second birth was familiar to the twice born Aryan castes of ancient India, and was represented by their rite ceremony of investing the boy at the close of childhood with the sacred thread. In this as in its other features, the story of Buddha adheres to ancient Aryan types but gives to them a new spiritual significance. Having passed through the three prescribed stages of the Aryan saintly life,—as learner, householder, and forest recluse—he now entered on its fourth stage as a religious mendicant. But he developed from the old Brahmanical model of the wandering ascetic, intent only on saving his own soul, the nobler type of the preacher, striving to bring deliverance to the souls of others.

His story follows the old Aryan types

Two months after his temptation in the wilderness, Buddha commenced his public teaching in the Deer Forest, on the outskirts of the great city of Benares. Unlike the Brahmins, he addressed himself, not to one or two disciples of the sacred caste, but to the mass of the people. His first converts were laymen, and among the earliest were women. After three months of ministry, he had gathered around him sixty disciples, whom he sent forth to the neighbouring countries with these words: 'Go ye now and preach the most excellent Law.' The essence of his teaching was the deliverance of man from the sins and sorrows of life by self-renunciation and inward self-control. While the sixty disciples went on their missionary tour among the populace, Buddha converted certain celebrated hermits and fire-worshippers by an exposition of the philosophical side of his doctrine. With this new band he journeyed on to Rājāgrīha, where the local king and his subjects joined the faith, but where also he first experienced the fickleness of the multitude. Two thirds of each year he spent as a wandering preacher. The remaining four months of the rainy season he abode at some fixed place, often near Rājāgrīha, teaching the people who flocked around his little dwelling in the bamboo grove. His five old disciples, who had forsaken him in the time of his sore temptation in the wilderness, penitently rejoined their master. Princes, merchants, artificers, Brahmins and hermits, husbandmen and serfs, noble ladies and repentant courtesans, were yearly added to those who believed.

Public teaching of Buddha at 36-80

He sent forth the Sixty

He converts the people

Buddha preached throughout a large part of Behar, in the Oudh, and the adjacent Districts in the North Western Provinces. In after ages monasteries marked his halting

in the Gangetic valley

gence which the Northern or Tibetan Buddhists give to the legend of the life and to the teaching of their Master. The southern texts dwell upon the early career of Buddha up to the time of his Enlightenment in his 34th or 36th year. The incidents of that period have a peculiar pathos, and appeal to the most sacred experiences of humanity in all ages. They form the favourite episodes of European works on Buddhism. But such works are apt to pay perhaps too little attention to the fact that the first thirty-four years of Buddha's life were only a self-preparation for a social and religious propaganda prolonged to an extreme old age.

The forty-six years of intense personal labour, during which Buddha traversed wide regions, converted nations, withstood kings, eluded assassins, and sifted out false disciples, receive more attention in the northern legends. These legends have lately been compiled from the Tibetan texts into a work which furnishes a new and most interesting view of Buddha's life.¹ The best authority on the Southern Buddhism of Burma states that the history of the Master 'offers an almost complete blank as to what regards his doings and preachings during a period of nearly twenty-three years.'²

The texts of the Northern Buddhists fill up this blank. Southern Buddhism modelled its biographies of the Master

to Ceylonese scribes, *circa* 450 A.D. The first part of it was published by Fausboll in 1875 (Copenhagen), and Mr Rhys Davids' translation, with valuable introduction and notes, appeared under the title of *Buddhist Birth Stories* in 1880 (Trübner, London). Mr Childers' *Dictionary of the Idli Language* is a storehouse of original materials from Ceylonese sources, and has been used for verifying all statements in the present chapter. A compendious view of Southern Buddhism ancient and modern, will be found in Spence Hardy's *Manual of Buddhism*, translated from Singalese MSS. The Burmese branch of Southern Buddhism is well represented by Bishop Bigandet's *Life or Legend of Gaudama* (third edition, 2 vols., Trübner, 1880), and by Mr Alabaster's *The Wheel of the Law*, a translation or paraphrase of the Siamese *Pathama Sambodhiyan*. Mr Rhys Davids' *Buddhism*, and his *Hibbert Lectures*, give an excellent review of the faith. The French works, the original authorities in Europe, have (in some respects) been superseded by Oldenberg's *Buddha, Sein Leben* etc.

¹ *The Life of the Buddha, and the Early History of his Order, derived from Tibetan Works in the Bhahgyur and Bstan-hgyur*, translated by W. Woodville Rockhill, Second Secretary to the United States Legation in China (Trübner & Co., London 1884). Mr Beal's *Siyuki, or Buddhist Records of the Western World*, translated from the Chinese of Huen Tsiang, throws curious side-lights upon the traditions which the Chinese pilgrim brought with him or heard in India regarding the local incidents of Buddha's life.

² I from the fifty-sixth to the seventy-ninth year of his life. Bishop Bigandet's *Life or Legend of Gaudama*, vol. i. p. 260, and footnote.

The
Indian
epic type ;

upon the Indian epic type. Such biographies, as already stated, reproduce the three stages in the life of an Aryan hero, depicted by the Mahábhárata and Rámáyana ; except that the three ideal stages have developed from those of prince, hermit, and warrior, to those of prince, hermit, and saint. In the northern conditions of China and Tibet, Buddha appears by no means as an Aryan hero. He is rather the representative of a race with birth-customs and death-rites of its own—of a race dwelling amid the epic Aryan kingdoms of India, but with traces of a separate identity in the past. He is a Sakya (perhaps a Scythic) prince, whose clan had settled to the south of the Himálayas, and preserved relics of a non-Aryan type.

The
Tibetan
type.

The philo-
sophical
type

The artificial character which the southern legends give to the life of Buddha, arose from their tendency to assimilate him with epic Indian types. It was intensified by the equally Indian tendency to convert actual facts into philosophical abstractions. Gautama or Sakya-Muni became only a link in a long series of just men made perfect. According to the Ceylonese texts, a Buddha is a human being who has obtained perfect self-control and infinite knowledge. Having attained Enlightenment himself, he spends the rest of his life in preaching the truth to others. At his death he is reabsorbed into the Divine Essence, and his religion flourishes for a certain period until it dies out, and a new Buddha appears to preach anew the lost truth. The attainment of Buddhahood is the final result of virtue and self-sacrifice during many previous lives. Innumerable Buddhas have been born in this world ; 24 of whom are separately named. Gautama was only the latest, and his doctrine is destined to give place to the Metteya Buddha, or Buddha of Kindness, who is next to come.¹

of the
Southern
Buddha.

The
northern
concrete
type.

The Buddha of the northern legends is a reformer of a more concrete type. The Tibetan texts give prominence to the political aspects of his Reformation. Incidentally, indeed, they amplify several of the touching episodes familiar to Southern Buddhism. The 'great Fear' which impelled the young prince forth from his palace into the darkness to seek a higher life ; the dirt and stones thrown at the wanderer by the village girls ; the parables of the Mango-tree, the Devout Slave, and many others ; the rich young man who left all for the faith and was *not* exceeding sorry ; and Buddha's own retirement from Benares to avoid the gifts and honours which were being thrust upon him,—receive fresh illustration from the Tibetan texts.²

¹ Mr. Childers' *Páli Dictionary*, p. 96. Sanskrit, *Maitraya*.

² The materials for the following paragraphs are derived mainly from Mr. Rockhill's work (1884), already cited.

But it is from the political and historical aspects that the Tibetan life of Buddha possesses its special value. We learn that Buddhism was in its origin only one of many conflicting sects, indeed, that alike to its royal patrons and opponents it appeared at first in the light of a new order rather than in the light of a new faith¹. The early struggles of Buddhism were neither with the old Aryan gods, nor with the Bráhmans as a caste, but with rival orders of philosophers or ascetics, and with schismatics among its own followers. The gods of the Veda, Brahma, Indra, and the Shining Ones, appear in friendly relations with Buddha and attend upon him in more than one crisis of his life. The Brahman were no longer a caste altogether devoted to a spiritual life. The Tibetan texts disclose them as following partly religious, partly secular vocations, and as among 'the great nobles' of an Indian kingdom. The Brahman attitude to the new faith was by no means one of confederate hostility. The main body of Brahman continued non-Buddhist, and taught their doctrines at royal courts. But many conspicuous converts were drawn from among them, and the Tibetan texts almost uniformly speak of Bráhmans with respect.

The opponents of the Tibetan Buddha were rival sects whom he found in possession of the field and the false brethren who rose among his own disciples. The older hostile sects were confuted, sometimes by fair discussion but more often by superior magical feats. Indeed, transformations and miraculous appearances seem for a time to have furnished the most potent arguments of the new faith. But eventually Buddha forbade resort to such testimonies, and magic became to the orthodox Buddhist an unholy art. In his later years, Buddha more than once insists that his doctrine is essentially one to be understood of the people, that he was keeping back no secret for an initiated few, and that he was the preacher of a strictly popular religion without any esoteric side.

It was from among his own disciples that his bitterest enemies came. The Sakya race of Kapilavastu had adopted his teaching as a nation, without much pretence of individual conversion. Buddha's modest beginnings, first with the five followers, then with the sixty, then with the thousand, now took a national development. In the fervour of the new movement, the Sakyas proclaimed that one man out of every family must enter the Buddhist mendicant order, and it was from this ordinance, to which Buddha was compelled to give a reluctant assent, that the troubles of his later life arose.

¹ Rockhill, *op. cit.* Also Rhys Davids *His first Lectures*, p. 156

Schism of
Devadatta.

The discontent among the forced disciples found a leader in Buddha's own cousin, Devadatta, who aspired by superior asceticism to the headship. For the schism which he created, Devadatta won the support of the Heir-apparent of Magadha. A struggle, partly religious partly political, ensued. Devadatta was for a time triumphant. He abetted the murder of the Magadha king, the father of his ally; forced the aged Buddha into retirement; and plundered and oppressed the people. The miraculous deliverances of 'the Blessed One' from the catapult, and from the wild elephant let loose against him in a narrow street, mark, however, the turning-point in the fortunes of the schism. Devadatta was confuted by magical arts, and his royal patron was converted to the true faith. The traitor disciple having thus failed to usurp the spiritual leadership of the Sakyas, attempted to seduce the wife whom Buddha had left in solitude. The apostate hoped with her aid to stand forth as the king or temporal leader of the Sakya race. His contemptuous rejection by the loyal Sakya princess, his acts of despairing cruelty, and his fall into hell with a lie in his mouth, fitly close the career of the first great schismatic.

His fall
into hell.

Buddha,
the Sakya
prince.

Throughout the Tibetan texts, Buddha figures as a typical Sakya; first as a young Kshatriya or prince of the royal line, and then as a saintly personage who turns back an army sent against his nation by the force of his piety alone. Such spiritual weapons, however, proved a feeble defence in early India. Eventually, the Sakya capital was attacked by overwhelming numbers. For a time the enemy were repulsed without the Buddhists incurring the sin of taking life. But their firm adherence to their Master's commandment, 'Thou shalt not kill,' in the end decided the fate of the Sakya city. Some escaped into exile and founded settlements in distant parts as far as the other side of the Punjab frontier. The fall of the city ended in the slaughter of 77,000 Sakyas, and in the dispersion of the remnants of the race. The story of the five hundred Sakya youths and five hundred Sakya maidens who were carried into captivity is a pathetic one. The five hundred youths were massacred in cold blood; and the faithful Sakya maidens, having refused to enter the harem of their conqueror, were exposed to the populace with their hands and feet chopped off. How Buddha came to them in their misery, dressed their wounds, and comforted them with the hope of a better life, 'so that they died in the faith,' is affectingly told.

Disasters
of his race.

The foregoing narrative touches only on one or two aspects of the Tibetan texts. It suffices to show the characteristic

divergences between the northern and the southern legend. In the northern, there is a gradually developed contrast between two main figures, the traitor Devadatta and his brother Ananda, the Beloved Disciple. The last year of Buddha's ministry is dwelt on by both. But its full significance and its most tender episodes are treated with special unction in the northern version of the Book of the Great Decease. The Fo wei kuan king,¹ or 'Dying Instruction of Buddha,' translated into Chinese between 397 and 415 A.D. from a still earlier Sanskrit text, gives to the last scene a peculiar beauty. 'It was now in the middle of the night,' it says, 'perfectly quiet and still for the sake of his disciples, he delivered a summary of the law.' After laying down the rules of a good life, he revealed the inner doctrines of his faith. From these a few sentences may be taken. 'The heart is lord of the senses govern, therefore, your heart, watch well the heart.' 'Think of the fire that shall consume the world, and early seek deliverance from it.' 'Lament not my going away, nor feel regret. For if I remained in the world, then what would become of the church? It must perish without fulfilling its end. From henceforth all my disciples, practising their various duties, shall prove that my true Body, the Body of the Law (*Dharmakaya*), is everlasting and imperishable. The world is fast bound in fetters, I now give it deliverance, as a physician who brings heavenly medicine. Keep your mind on my teaching, all other things change, this changes not. No more shall I speak to you. I desire to depart. I desire the eternal rest (*Nirvana*). This is my last exhortation.'

The secret of Buddha's success was that he brought spiritual deliverance to the people. He preached that salvation was equally open to all men, and that it must be earned, not by propitiating imaginary deities, but by our own conduct. His doctrines thus cut away the religious basis of caste, impaired the efficiency of the sacrificial ritual, and assailed the supremacy of the Bráhmans as the mediators between God and man. Buddha taught that sin, sorrow, and deliverance, the state of a man in this life, in all previous and in all future lives, are the inevitable results of his own acts (*Karma*). He thus applied the inexorable law of cause and effect to the soul. What a man sows, he must reap.

As no evil remains without punishment, and no good deed without reward, it follows that neither priest nor God can prevent

¹ Translated in Appendix to the Catalogue of the Manuscripts presented by the Japanese Government to the Secretary of State for India and now in the India Office.—Concluding letter of Mr. Beal to Dr. Rost, dated 1st September 1874 sec. 5.

each act bearing its own consequences. Misery or happiness in this life is the unavoidable result of our conduct in a past life; and our actions here will determine our happiness or misery in the life to come. When any creature dies, he is born again in some higher or lower state of existence, according to his merit or demerit. His merit, or demerit, that is his character, consists of the sum total of his actions in all previous lives.

By this great law of *Karma*, Buddha explained the inequalities and apparent injustice of man's estate in this world as the consequence of acts in the past; while Christianity compensates those inequalities by rewards in the future. A system in which our whole well-being, past, present, and to come, depends on ourselves, theoretically leaves little room for the interference, or even existence, of a personal God.¹ But the atheism of Buddha was a philosophical tenet, which so far from weakening the sanctions of right and wrong, gave them new strength from the doctrine of *Karma*, or the Metempsychosis of Character.

The liberation of the soul.

Nirvāna.

To free ourselves from the thralldom of desire and from the fetters of selfishness, was to attain to the state of the perfect disciple, *Arahat* in this life, and to the everlasting rest after death, *Nirvāna*. Some Buddhists explain *Nirvāna* as absolute annihilation, when the soul is blown out like the flame of a lamp. Others hold that it is merely the extinction of the sins, sorrows, and selfishness of individual life. The fact is, that the doctrine underwent processes of change and development, like all theological dogmas. 'But the earliest idea of *Nirvāna*,' says one of the greatest authorities on Chinese Buddhism, 'seems to have included in it no more than the enjoyment of a state of rest consequent on the extinction of all causes of sorrow.'² The great practical aim of Buddha's teaching was to subdue the lusts of the flesh and the cravings of self; and *Nirvāna* has been taken to mean the extinction of the sinful grasping condition of heart which, by the inevitable law of *Karma*, would involve the penalty of renewed individual existence. As the Buddhist strove to reach a state of quietism or holy meditation in this world, namely, the

¹ 'Buddhism,' says Mr. Beal, *Catena of Buddhist Scriptures*, p. 153, 'declares itself ignorant of any mode of personal existence compatible with the idea of spiritual perfection, and so far, it is ignorant of God.'

² Beal, *Catena of Buddhist Scriptures from the Chinese*, p. 157, ed. 1871; and the *Buddhist Tripitaka*, App., Letter to Dr. Rost, sec. 6. Max Müller deals with the word from the etymological and Sanskrit side in his *Chips from a German Workshop*, vol. i. pp. 279, 290, ed. 1867. But see, specially, Childers' *Pāli Dictionary*, s.v. *Nibbānam*, pp. 265-274.

state of the perfect disciple or *Arahat*, so he looked forward to an eternal calm in a world to come, *Nirvāṇa*

Buddha taught that this end could only be attained by the Moral practice of virtue. He laid down eight precepts of morality, code with two more for the religious orders making ten commandments (*dasa sīla*) in all. He arranged the besetting faults of mankind into ten sins, and set forth the special duties applicable to each condition of life to parents and children, to pupils and teachers to husbands and wives, to masters and servants, to laymen and the religious orders. In place of the Brahman rites and sacrifices Buddha prescribed a code of practical morality as the means of salvation. The four essential features of that code were—reverence to spiritual teachers and parents control over self kindness to other men, and reverence for the life of all sentient creatures.

He urged on his disciples that they must not only follow the true path themselves but that they should preach it to all mankind. Buddhism has from the first been a missionary religion. One of the earliest acts of Buddha's public ministry was to send forth the Sixty and he carefully formulated the four chief means of conversion. They were companionship with the good listening to the Law reflection upon the truths heard, and the practice of virtue. He also instituted a religious Order, one of whose special duties it was to go forth and preach to the nations. While therefore the Brahmins kept their ritual for the twice born Aryan castes Buddhism addressed itself not only to those castes and to the lower mass of the people but to all the non Aryan races throughout India, and eventually to almost the whole Asiatic world. Two features of the Buddhist Order were its fortnightly meetings and public confession, or Disburdenment of sins. On the death of Buddha, five hundred of his disciples met in a vast cave near Rājagṛha to gather together his sayings. This was the First Council. They chanted the lessons of their master in three great divisions—the words of Buddha to his disciples,¹ his code of discipline² and his system of doctrine.³ These became the Three Collections⁴ of Buddha's teaching, and the word for a Buddhist Council⁵ means literally 'a singing together'. A century afterwards, a Second Council, of seven hundred, was held at Vaisali, to settle disputes between the more and the less strict followers of Buddhism. It condemned a system of ten 'Indulgences' which had grown

¹ *Sūtras*

² *Vinaya*

³ *Abhidharma*

⁵ *Sangha* in Pali

The First Council, 543 B.C. (?)

Second Council, 443 B.C. (?)

The Ten Commandments

aspects of Buddhism

up; but it led to the separation of the Buddhists into two hostile parties, who afterwards split into eighteen sects.

Third
Buddhist
Council,

244 B.C. (?)

During the next two hundred years Buddhism spread over Northern India, perhaps receiving a new impulse from the Greek kingdoms in the Punjab. About 257 B.C., Asoka, the King of Magadha or Behar, became a zealous convert to the faith.¹ Asoka was grandson of the Chandra Gupta whom we shall meet as an adventurer in Alexander's camp, and afterwards as an ally of Seleukos. Asoka is said to have supported 64,000 Buddhist priests; he founded many religious houses, and his kingdom is called the Land of the Monasteries (Vihāra or Behar) to this day.

The work
of Asoka.

Asoka did for Buddhism what Constantine afterwards effected for Christianity; he organized it on the basis of a State religion. This he accomplished by five means—by a Council to settle the faith, by edicts promulgating its principles, by a State Department to watch over its purity, by missionaries to spread its doctrines, and by an authoritative revision or canon of the Buddhist scriptures. In 244 B.C., Asoka convened at Patná the Third Buddhist Council, of one thousand elders. Evil men, taking on them the yellow robe of the Order, had given forth their own opinions as the teaching of Buddha. Such heresies were now corrected; and the Buddhism of Southern Asia practically dates from Asoka's Council.

(1) His
Great
Council.

¹ Much learning has been expended upon the age of Asoka, and various dates have been assigned to him. But, indeed, all Buddhist dates are open questions, according to the system of chronology adopted. The middle of the 3rd century B.C. may be taken as the era of Asoka. The following table from General Cunningham's *Corpus Inscriptionum Indicarum*, p. vii. (1877), exhibits the results of the latest researches on this subject:—

B.C. 264	ASOKA, Struggle with brothers, 4 years.
260	Comes to the throne.
257	Conversion to Buddhism.
256	Treaty with Antiochus.
255	Mahindo ordained.
251	Earliest date of rock edicts.
249	Second date of rock edicts.
248	Arsakes rebels in Parthia.
246	Diodotus rebels in Bactria.
244	Third Buddhist Council under Mogaliputra.
243	Mahindo goes to Ceylon.
242	Barábar cave inscriptions.
234	Pillar edicts issued.
231	Queen Asandhimitta dies.
228	Second Queen married.
226	Her attempt to destroy the Bodhi tree.
225	Asoka becomes an ascetic.
224	Issues Rúpnáth and Sasseram edicts.
223	Dies.
215	DASARATHA's cave inscriptions, Nágárajuni.

In a number of edicts, before and after the synod, he published (2) His edicts throughout India the cardinal principles of the faith. Such edicts are still found graven deep upon pillars, caves, and rocks, from the Yusafzai valley beyond Peshawar on the north western frontier, through the heart of Hindustán and the Central Provinces, to Káthiáwar in the west, and Orissa in the east coast of India. Tradition states that Asoka set up 84,000 memorial columns or topes. The Chinese pilgrims came upon them in the inner Himálayas. Forty-two inscriptions still surviving show how widely these royal sermons were spread over India itself¹.

In the year of the Council, Asoka founded a State Department to watch over the purity, and to direct the spread, of the faith. A Minister of Justice and Religion (Dharma Mahámátra) directed its operations and, as one of its first duties was to proselytize, this Minister was charged with the welfare of the aborigines among whom his missionaries were sent. Asoka did not think it enough to convert the inferior races, without looking after their material interests. Wells were to be dug and trees planted, along the roads, a system of medical aid was

¹ Major General Cunningham, Director General of the Archaeological Survey of India, enumerates 14 rock inscriptions, 17 cave inscriptions, and 11 inscribed pillars. The rock inscriptions are at—(1) Shahjizgarhi in the Yusafzai country, 40 miles east north east of Peshawar, (2) Khalat on the west bank of the Jumna, (3) Gurnar in Káthiáwar, 40 miles north of Sonmáth, (4 to 7) Dháuli in Cuttack, midway between Cuttack and Puri, and Jaugada in Ganjam District, 18 miles north north west of Barhampur,—two inscriptions at each, virtually identical, (8) Vasseram, at the north east end of the Kámtur range, 70 miles south east of Benares, (9) Rupnath, a famous place of pilgrimage, 35 miles north of Jabalpur, (10 and 11) Bairát, 41 miles north of Jaipur, (12) the Khandgiri Hill near Dháuli in Cuttack, (13) Deotek, 50 miles south east of Nagpur, (14) Mansera, north west of Rawal Pinli, inscribed in the Bactrian character. The cave inscriptions, 17 in number, are found at—(1, 2, 3) Barabar, and (4, 5, 6) Nagarjuni Hills, both places 15 miles north of Gaya, (7 to 15) Khandgiri Hill in Cuttack, and (16 and 17) Kamgarh in Surguja. The eleven inscribed pillars are—(1) the Delhi Siwalik, at Delhi, (2) the Delhi Meerut, at Delhi, (3) the Allahabád, (4) the Lauriya Araraj, at Lauriya, 77 miles north of Patna, (5) the Lauriya Navandgarh, at another Lauriya, 15 miles north north west of Bettua, (6 and 7) two additional edicts on the Delhi Siwalik, not found on any other pillar, (8 and 9) two short additional edicts on the Allahabad pillar, peculiar to itself, (10) a short mutilated record on a fragment of a pillar at Sanchi, near Bhilsa, (11) at Rámpura in the Tarai, north-east of the second Lauriya, near Bettua. The last named pillar and the rock inscription at Mansera (No. 14) are recent discoveries since the first edition of this work was published. The Mansera rock inscription is interesting as being the second in the Bactrian character, and for its recording twelve Edicts complete.

established throughout his kingdom and the conquered Provinces, as far as Ceylon, for man and beast.¹ Officers were appointed to watch over domestic life and public morality,² and to promote instruction among the women as well as the youth.

(4) Missionary efforts.

Asoka recognised proselytism by peaceful means as a State duty. The Rock Inscriptions record how he sent forth missionaries 'to the utmost limits of the barbarian countries,' to 'intermingle among all unbelievers,' for the spread of religion. They shall mix equally with soldiers, Bráhmans, and beggars, with the dreaded and the despised, both within the kingdom 'and in foreign countries, teaching better things.'³ Conversion is to be effected by persuasion, not by the sword. Buddhism was at once the most intensely missionary religion in the world, and the most tolerant. This character of a proselytizing faith, which wins its victories by peaceful means, so strongly impressed upon it by Asoka, has remained a prominent feature of Buddhism to the present day. Asoka, however, not only took measures to spread the religion, he also endeavoured to secure its orthodoxy. He collected the body of doctrine into an authoritative version, in the Mágadhí language or dialect of his central kingdom in Behar; a version which for two thousand years has formed the canon (*pitakas*) of the Southern Buddhists. In this way, the Mágadhí dialect became the Páli or sacred language of the Ceylonese.

(5) Reformed canon of Buddhist scriptures.

Edicts of Asoka.

Mr. Robert Cust thus summarizes Asoka's Fourteen Edicts:—

1. Prohibition of the slaughter of animals for food or sacrifice.
2. Provision of a system of medical aid for men and animals, and of plantations and wells on the roadside.
3. Order for a quinquennial humiliation and re-publication of the great moral precepts of the Buddhist faith.
4. Comparison of the former state of things, and the happy existing state under the king.
5. Appointment of missionaries to go into various countries, which are enumerated, to convert the people and foreigners.
6. Appointment of informers (or inspectors) and guardians of morality.
7. Expression of a desire that there may be uniformity of religion and equality of rank.
8. Contrast of the carnal pleasures of previous rulers with the pious enjoyments of the present king.
9. Inculcation of the true happiness to be found in virtue, through which alone the blessings of heaven can be propitiated.

¹ Rock Inscriptions, Edict ii., General Cunningham's *Corpus Inscriptionum*, p. 118.

² Rock Inscriptions, Edict vi. etc., *Corpus Inscriptionum*, p. 120. These Inspectors of Morals are supposed to correspond to the Sixth Caste of Megasthenes, the 'Ἐπίσκοποι of Arrian.

³ Rock Inscriptions, Edict v. etc., *Corpus Inscriptionum*, p. 120.

- 10 Contrast of the vain and transitory glory of this world with the reward for which the king strives and looks beyond
- 11 Inculcation of the doctrine that the imparting of *dharma* or teaching of virtue to others is the greatest of charitable gifts
- 12 Address to all unbelievers
- 13 (Imperfect), the meaning conjectural
- 14 Summing up of the whole

The fourth and last of the great Buddhist Councils was held under King Kanishka, according to one tradition four centuries after Buddha's death. The date of Kanishka is still uncertain, but, from the evidence of coins and inscriptions, his reign has been fixed in the 1st century after Christ, or, say, 40 A.D.¹ Kanishka, the most famous of the Saka conquerors, ruled over North Western India, and the adjoining countries. His authority had its nucleus in Kashmir, but it extended to both sides of the Himalayas, from Yarkand and Khokand to Agra and Sind.

Kanishka's Council of five hundred drew up three commentaries on the Buddhist faith. These commentaries supplied in part materials for the Tibetan or Northern Canon, completed at subsequent periods. The Northern Canon, or, as the Chinese proudly call it, the 'Greater Vehicle of the Law,' includes many later corruptions or developments of the Buddhism which was originally embodied by Asoka in the 'Lesser Vehicle,' or Canon of the Southern Buddhists (244 B.C.).² The Buddhist Canon of China, a branch of the 'Greater Vehicle,' was gradually arranged between 67 and 1285 A.D. It includes 1440 distinct works, comprising 5586 books. The ultimate divergence between the Canons is great. They differ not only, as we have seen, in regard to the legend of Buddha's life, but also as to his teaching. With respect to doctrine, one example will suffice. According to the Northern or 'Greater Vehicle,' Buddhist monks who transgress wilfully after ordination may yet recover themselves, while to such castaways the Southern or 'Lesser Vehicle' allowed no room for repentance.²

The original of the Northern Canon was written in the Sanskrit language, perhaps because the Kashmiri and northern priests, who formed Kanishka's Council, belonged to isolated Himalayan settlements which had been little influenced by the

¹ The latest efforts to fix the date of Kanishka are little more than records of conflicting authorities. See Dr James Fergusson's paper in the *Journal of the Royal Asiatic Society*, Article ix., April 1880, and Mr E. Thomas' comprehensive discussion on the Saka and Gupta coins, pp. 18-79 of the *Report of the Archaeological Survey of Western India for 1874-75*, 4th ed., London, 1876.

² Peal, *Critica*, p. 253.

growth of the Indian vernacular dialects. In one of these dialects, the Mágadhí of Behar, the Southern Canon had been compiled by Asoka and expanded by commentators. Indeed, the Buddhist compilations appear to have given the first literary impulse to the Prákrits or spoken Aryan dialects in India; as represented by the Páli or Mágadhí of the Ceylonese Buddhist scriptures, and the Maháráshtri of the ancient sacred books of the Jains. The northern priests, who compiled Kanishka's Canon, preferred the 'perfected' Sanskrit, which had become by that time the accepted literary vehicle of the learned throughout India, to the Prákrit or 'natural' dialects of the Gangetic valley. Kanishka and his Kashmír Council (40 A.D.?) became to the Northern or Tibeto-Chinese Buddhists, what Asoka and his Patná Council (244 B.C.) had been to the Buddhists of Ceylon and the South.

Buddhism
as a
national
religion;

Buddhism was thus organized as a State religion by the Councils of Asoka and Kanishka. It started from Bráhma-
manical doctrines; but from those doctrines, not as taught in hermitages to clusters of Bráhma-
man disciples, but as vitalized by a preacher of rare power in the capital cities of India. Buddha did not abolish caste. On the contrary, reverence to Bráhma-
mans and to the spiritual guide ranked among the four great sets of duties, with obedience to parents, control over self, and acts of kindness to all men and animals. He introduced, however, a new classification of mankind, on the spiritual basis of believers and unbelievers.

its religious
orders;

The former took rank in the Buddhist community,—
at first, according to their age and merit; in later times, as laity¹ and clergy² (*i.e.* the religious orders). Buddhism carried transmigration to its utmost spiritual use, and proclaimed our own actions to be the sole ruling influence on our past, present, and future states. It was thus led into the denial of any external being or god who could interfere with the immutable law of cause and effect as applied to the soul. But, on the other hand, it linked together mankind as parts of one universal whole, and denounced the isolated self-seeking of the human heart as 'the heresy of individuality.'³ Its mission was to make men more moral, kinder to others, and happier themselves; not to propitiate imaginary deities. It accordingly founded its teaching on man's duty to his neighbour, instead of on his obligations to God; and constructed its

¹ *Uṇṣáka*.

² *Sramana*, *bhikṣu* (monk or religious mendicant), *bhikṣuní* (nun).

³ *Saśúyaditthi*.

ritual on the basis of relic worship or the commemoration of good men, instead of on sacrifice. Its sacred buildings were not temples to the gods, but monasteries (*vihāras*) for the religious orders, with their bells and rosaries, or memorial shrines,¹ reared over a tooth or bone of the founder of the faith and practical morality.

The missionary impulse given by Asoka quickly bore fruit. In the year after his great Council at Patna (244 B.C.), his son Mahindo² carried Asoka's version of the Buddhist scriptures in the Māgadhī language to Ceylon. He took with him a band of fellow missionaries, and soon afterwards, his sister, the princess Sanghamitta, who had entered the Order, followed with a company of nuns. It was not, however, till six hundred years later (410-432 A.D.) that the Ceylonese Canon was written out in Pali, the sacred Māgadhī language of the Southern Buddhists. About the same time missionaries from Ceylon finally established the faith in Burma (450 A.D.). The Burmese themselves assert that two Buddhist preachers landed in Pegu as early as 207 B.C. Indeed, some Burmese date the arrival of Buddhist missionaries just after the Patna Council, 244 B.C., and point out the ruined city of Tha-tun, between the Sittaung (Tsit taung) and Salween estuaries, as the scene of their pious labours. Siam was converted to Buddhism in 638 A.D., Java received its missionaries direct from India between the 5th and the 7th centuries, and spread the faith to Bali and Sumatra.³ Spread of Buddhism. In the South, Ceylon, etc., 244 B.C. to 638 A.D.

While Southern Buddhism was thus wafted across the ocean, another stream of missionaries had found their way by Central Asia into China. Their first arrival in the Chinese empire is said to date from the 2nd century B.C., although it was not till 65 A.D. that Buddhism there became the established religion. The Greco-Bactrian kingdoms in the Punjab, and beyond it, afforded a favourable soil for the faith. The Scythian dynasties who succeeded the Greco-Bactrians accepted Buddhism, and the earliest remains which recent discovery has In the North China, etc., 2nd century B.C. to 552 A.D.

¹ *Stūpas, toṣas*, literally 'heaps or tumuli,' *dagobas* or *dhatu gopas*, 'relic preservers,' *chatras*.

² Sanskrit Mahendra.

³ All these dates are uncertain. They are founded on the Singalese chronology, but the orthodox in the respective countries place their national conversion at remoter periods. Occasionally, however, the dates can be tested from external sources. Thus we know from the Chinese traveller Fa Hien that up to about 414 A.D. Java was still unconverted. Fa Hien says, 'Heretics and Brahmins were numerous there, and the law of Iudha is in nowise entertained.' The Burmese chronicles go back to a time when the duration of human life was ninety millions of years, and when a single dynasty ruled for a period represented by a unit followed by 140 cyphers. See *The Imperial Gazetteer of India*, Article Siamoway.

unearthed in Afghánistán are Buddhist. Kanishka's Council, soon after the commencement of the Christian era, gave the great impetus to the faith beyond the Himálayas. Tibet, South Central Asia, and China, lay along the regular missionary routes of Northern Buddhism; the Kirghiz are said to have carried the religion as far west as the Caspian; on the east, Buddhism was introduced into the Corea in 372 A.D., and thence into Japan in 552.

Buddhist
influence
on Chris-
tianity.

Buddhist doctrines are believed to have deeply affected religious thought in Alexandria and Palestine. The question is yet undecided as to how far the Buddhist ideal of the holy life, with its monks, nuns, relic-worship, bells, and rosaries, influenced Christian monachism; and to what extent Buddhist philosophy aided the development of the Gnostic heresies, particularly those of Basilides and Manes, which rent the early church. It is certain that the analogies are striking, and have been pointed out alike by Jesuit missionaries in Asia, and by oriental scholars in Europe.¹ The form of abjuration for those who renounced the Gnostic doctrines of Manes, expressly mentions *Bóddha* and the *Σκυθιανός* (Buddha and the Scythian or Sákya)—seemingly, says Weber, a separation of Buddha the Sákya into two. At this moment, the Chinese in San Francisco assist their devotions by pictures of the Buddhist Goddess of Mercy, imported on thin paper from Canton, which the Irish Roman Catholics identify as the Virgin Mary with the Infant in her arms, an aureole round her head, an adoring figure at her feet, and the Spirit hovering in the form of a bird.²

But it is right to point out that the early Nestorian Christians in China may have been the source of some of these resemblances. The liturgy of the Goddess of Mercy, Kwan-yin, in which the analogies to the Eastern Christian office are most strongly marked, have been traced with certainty only as far back as 1412 A.D. in the Chinese Canon.³ Professor Max

¹ For the latter aspect of the question, see Weber, founding on Lassen, Renan, and Beal, *Hist. Ind. Lit.*, p. 309, note 363, ed. 1878.

² See also *post*, p. 153. Polemical writers, Christian and Chinese, have with equal injustice accused Buddhism and Christianity of consciously plagiarizing each other's rites. Thus Kuang-Hsien, the distinguished member of the Astronomical Board, who brought about the Chinese persecution of the Christians from 1665 to 1671, writes of them: 'They pilfer this talk about heaven and hell from the refuse of Buddhism, and then turn round and revile Buddhism.'—*The Death-blow to the Corrupt Doctrines of T'ien-chu* (i.e. Christianity), p. 46 (Shanghai, 1870). See also the remarks of Jao-chow—'The man most distressed in heart'—in the same collection.

³ For an excellent account from the Chinese texts of the worship and liturgy of Kwan-yin, 'the Saviour,' or in her female form as the Goddess of Mercy, see Beal's *Catena of Buddhist Scriptures*, 383-397 (Trübner, 1871).

Muller endeavoured to show that Buddha himself is the original of Saint Josaphat, who has a day assigned to him by both the Greek and Roman churches¹

Professor Muller's Essay² has led to an examination of the whole evidence bearing on this subject³. The results may be thus summarized. The Roman Martyrology at the end of the saints for the 27th November, states 'Apud Indos Persis finitimos sanctorum Barlaam et Josaphat (commemoratio), quorum actus mirandos Joannes Damascenus conscripsit'. *Among the Indians who border on Persia Saints Barlaam and Josaphat, whose wonderful works have been written of by St John of Damascus*. The story of these two saints is that of a young Indian prince, Josaphat who is converted by a hermit, Barlaam. Josaphat undergoes the same awakening as Buddha from the pleasures of this world. His royal father had taken similar precautions to prevent the youth from becoming acquainted with the sorrows of life. But Josaphat, like Buddha, is struck by successive spectacles of disease, old age, and death, and abandons his princely state for that of a Christian devotee. He converts to the faith his father, his subjects, and even the magician employed to seduce him. For this magician Theudas, the Buddhist schismatic Devadatta is supposed to have supplied the original, while the name of Josaphat is itself identified by philologists with that of Boddhisattwa, the complete appellation of Buddha⁴.

Buddha as a Christian Saint

Legend of Saints Barlaam and Josaphat

This curious transfer of the religious teacher of Asia to the Christian Martyrology has an equally curious history. Saint John of Damascus wrote in the 8th century in Greek, and an Arabic translation of his work, belonging to the 11th century, still survives. The story of Josaphat was popular in the Greek Church, and was embodied by Simeon the Metafrast in the lives of the saints, *circa* 1150 A.D. The Greek form of the name is Ιωσαφάβ⁵. By the 12th century, the

Early stages of the story

¹ *Chips from a German Workshop*, vol. iv. p. 177-189 ed. 1875

² *Contemporary Review*, July 1870

³ For a list of the authorities and an investigation of them from the Roman Catholic side by Emmanuel Cosquin see *Revue des Questions Historiques*, lvi pp. 579-600, Paris October 1880

⁴ The earliest form of Josaphat was Iosaspis in Greek and Ioudasf in Arabic, an evident derivation from the Sanskrit Boddhisattwa through the Persian form Boudasp (Weber). The name of the magician Theudas is in like manner an accurate philological reproduction of Devadatta or Thevdat

⁵ See the valuable note in Colonel Yule's *Marco Polo*, vol. ii. pp. 302-309 (2nd ed. 1875)

Life of Barlaam and Josaphat had already reached Western Europe in a Latin form. During the first half of the 13th century, Vincent de Beauvais inserted it in his *Speculum Historiale*; and in the latter half of that century it found a place in the Golden Legend of Jacques de Voragine. Meanwhile, it had also been popularized by the troubadour, Guy de Cambrai. From this double source, the Golden Legend of the Church and the French poem of the people, the story of Barlaam and Josaphat spread throughout Europe. German, Provençal, Italian, Polish, Spanish, English, and Norse versions carried it from the southern extremity of the Continent to Sweden and Iceland.

In 1583, the legend was entered in the Roman Martyrology for the 27th day of November, as we have already seen, upon the alleged testimony of St. John of Damascus. A church in Palermo still (1874) bears the dedication, *Divo Iosaphat*.¹ The Roman Martyrology of Gregory XIII., revised under the auspices of Urban VIII., has a universal acceptance throughout Catholic Christendom; although from the statements of Pope Benedict XIV., and others, it would appear that it is to be used for edification, rather than as a work resting on infallible authority.² However this may be, the text of the two legends, and the names of their prominent actors, place beyond doubt the identity of the Eastern and the Western story.

A Japanese temple; its analogies to Hinduism and Christianity.

It is difficult to enter a Japanese Buddhist temple without being struck by analogies to the Christian ritual on the one hand, and to Hinduism on the other. The chantings of the priests, their bowing as they pass the altar, their vestments, rosaries, bells, incense, and the responses of the worshippers, remind one of the Christian ritual. 'The temple at Rokugo,' writes a recent traveller to a remote town in Japan, 'was very beautiful, and, except that its ornaments were superior in solidity and good taste, differed little from a Romish church. The low altar, on which were lilies and lighted candles, was draped in blue and silver; and on the high altar, draped in crimson and cloth of gold, there was nothing but a closed shrine, an incense-burner, and a vase of lotuses.'³ In a Buddhist temple at Ningpo, the Chinese goddess of mercy,

¹ Yule, *op. cit.* p. 308.

² This aspect of the question is discussed at considerable length by Emmanuel Cosquin, pp. 583-594. He gives the two legends of Buddha and of Barlaam-Josaphat in parallel columns, pp. 590-594 of the *Revue des Questions Historiques*, vol. lvi., already cited.

³ Miss Bird's *Unbeaten Tracks in Japan*, vol. i. p. 295 (ed. 1880).

Kwan yin, whose resemblance to the Virgin Mary and Christ's Serpent has already been mentioned (p. 150), is seen standing on a serpent, bruising his head with her heel.

The Hindus, while denouncing Buddha as a heretic, have been constrained to admit him to a place in their mythology. They regard him as the ninth, and hitherto last, incarnation of Vishnu,—the Lying Spirit let loose to deceive men until the tenth or final descent of Vishnu, on the white horse, with a flaming sword like a comet in his hand, for the destruction of the wicked and the renovation of the world.

While on the one hand a vast growth of legends has arisen around Buddha, tending to bring out every episode of his life into strong relief, efforts have been made on the other hand to explain away his personal identity. No date can be assigned with certainty for his existence on this earth. The Northern Buddhists have fourteen different accounts, ranging from 622 B.C. to 546 B.C.¹ The Southern Buddhists agree in setting from the 1st of June 543 B.C. as the day of Buddha's death. This latter date, 543 B.C., is usually accepted by European writers; but Indian chronology, as worked back from inscriptions and coins,² gives the date *circa* 480. Some scholars have argued that Buddhism is merely a rational development of the Brâhmanical Sankhya philosophy of Kapila (see p. 151); that Buddha's birth is placed at a purely arbitrary era, the *kalpa*, 'the abode of Kapila' that has arisen "after the devî, in reference to the Mâtrî doctrine of Kapila's system; and that his own two names are *satyâkama* and *brahmacari* 'he who has fulfilled his end,' and Buddha, 'the enlightened.'

Buddhism and Brahmanism are unquestionably united by intermediate links. Certain of the *Upanishads* of the *Upanishad* Brahmins, particularly the *Upanishad* *Aranyakas* and the *Upanishad* of the Yoga system, teach doctrines which are essentially Buddhist. According to Wilson and others, Buddha had possibly no personal existence;³ Buddhism

¹ Cosma de Moraes, on the authority of Tibetan sources, *Tibetan Grammar*, p. 199. A debt long overdue has at length been paid to one of the most single minded of oriental scholars by the publication of *The Thirteenth Duke's Life and Works of Alexander Cosma de Moraes*. (Trilochan, 1885.)

² General Cunningham works back the date of Buddha's death to 478 B.C., and takes this as his starting point in the *Coins of the Indian Empire*, p. vii. The subject is admirably discussed by Mr. E. Davis in the *International Numismatic Review* (Oxford, 1887), pp. 35-56. He arrives at 412 B.C. as the most probable date. Dr. O. H. Olberg fixes it at about 480 B.C.

³ Professor H. H. Wilson went so far as to say, 'I cannot see...

Buddhism was merely the Sāṅkhya philosophy widened into a national religion; and the religious life of the Buddhistic orders was the old Brāhmanical type popularized.¹ The theory is at any rate so far true, that Buddhism was not a sudden invention of any single mind, but a development on a broader basis of a philosophy and religion which preceded it. Such speculations, however, leave out of sight the two great traditional features of Buddhism—namely, the preacher's appeal to the people, and the undying influence of his beautiful life. Senart's still more sceptical theory of Buddha as a Solar Myth, has completely broken down under the critical examination of Oldenberg.

Buddhism never ousted Brāhmanism from any large part of India. The two systems co-existed as popular religions from the death of Buddha during thirteen hundred years (543 B.C. to about 800 A.D.), and modern Hinduism is the joint product of both. The legends of Buddha, especially those of the Northern Canon,² bear witness to the active influence of Brāhmanism during the whole period of Buddha's life. After his death, certain kings and certain eras were intensely Buddhistic; but the continuous existence of Brāhmanism is abundantly proved from the time of Alexander (327 B.C.) downwards. The historians who chronicled Alexander's march, and the Greek ambassador Megasthenes, who succeeded them (300 B.C.) in their literary labours, bear witness to the predominance of Brāhmanism in the period immediately preceding Asoka. Inscriptions, local legends, Sanskrit literature, and the drama, disclose the survival of Brāhman influence during the next six centuries (244 B.C. to 400 A.D.). From 400 A.D. we have the evidence of the Chinese pilgrims, who toiled through Central Asia into India to visit the birthplace of their faith.³

'Never did more devoted pilgrims,' writes the greatest living

that Sākya Muni is an unreal being, and that all that is related of him is as much a fiction as is that of his preceding migrations and the miracles that attended his birth, his life, and his departure.' The arguments are dealt with by Weber, *Hist. Ind. Lit.*, pp. 284-290, ed. 1878.

¹ Dr. Oldenberg's *Buddha, Sein Leben*, contains valuable evidence on this subject (Hoey's transl. pp. 46, 48 to 59, etc.). See also *The Sāṅkhya Aphorisms of Kapila*, Sanskrit and English, with illustrative texts from the Commentaries by Dr. Ballantyne, formerly Principal of the Benares College, 3rd ed. (Trübner, 1885.)

² See the *Life of the Buddha and the Early History of his Order*, derived from the Tibetan texts, by Mr. Woodville Rockhill of the U. S. Legation in China; also Oldenberg's *Buddha*.

³ The *Si-yu-ki, or Buddhist Records of the Western World*, translated from the Chinese, by Samuel Beal (Trübner, 2 vols. 1884), has completed

student of their lives,¹ 'leave their native country to encounter the perils of travel in foreign and distant lands, never did disciples more ardently desire to gaze on the sacred vestiges of their religion, never did men endure greater sufferings by desert, mountain, and sea, than these simple minded, earnest Buddhist priests.' Fa Hian entered India from Afghánistán, Fa Hian, and journeyed down the whole Gangetic valley to the Bay of Bengal in 399-413 A.D. He found Brahman priests equally honoured with Buddhist monks, and temples to the Indian gods side by side with the religious houses of the Buddhist faith

Huen Tsiang, a still greater pilgrim, also travelled to India from China by the Central Asia route, and has left a fuller record of the state of the two religions in the 7th century. His wanderings extended from 629 to 645 A.D. Everywhere throughout India he found the two systems eagerly competing for the suffrages of the people. By this time, indeed, Brahmanism was beginning to reassert itself at the expense of the Buddhist religion. The monuments of the great Buddhist monarchs, Asoka and Kanishka, confronted him from the moment he neared the Punjab frontier, but so also did the temples of Siva and his 'dread' queen Bhima. Throughout North Western India he found Buddhist convents and monks surrounded by 'swarms of heretics,' i.e. Brahmanical sects

The political power was also divided, though Buddhist sovereigns still predominated. A Buddhist monarch ruled over ten kingdoms in Afghánistán. At Peshawar, the great monastery built by Kanishka was deserted, but the populace remained faithful. In Kashmir, the king and people were devout Buddhists, under the teaching of 500 monasteries and

and perfected the work begun by Julien and Remusat. Mr. Beal's new volumes throw a flood of light on the social, religious, and political condition of India from the 5th to 7th centuries A.D. The older authorities are Foe Koue Ki *ou Relation des Royaumes Bouddhiques, Voyages dans la Tartarie, l'Afghanistan et l'Inde à la fin du IV^e siècle, par Chi Fa Hian*, translated by A. Remusat, reviewed by Klaproth and Landresse, 1836. Mr. Beal's *Travels of the Buddhist Pilgrim Fa Hian*, translated with Notes and Prolegomena, 1869. Julien's *Voyages des Pèlerins Bouddhistes, t. 1, Histoire de la Vie de Houen Tsiang et de ses Voyages dans l'Inde transcrits from the Chinese 1853 t. II and III, Mémoires sur les Contrées Centrales, par Houen Tsiang* translated from the Chinese, 1857-59. C. J. Neumann's *Pilgerfahrten Buddhistischer Priester von China nach Indien, aus dem Chinesischen übersetzt*, 1883, of which only one volume is published. General Cunningham's *Ancient Geography of India*, and his *Reports of the Archaeological Survey of India* (various dates)

¹ Si-yu ki, Mr. Beal's Introduction, pp. ix, x

5000 monks. In the country identified with Jaipur, on the other hand, the inhabitants were devoted to heresy and war.

Buddhism
in India,
629-645
A.D.

Buddhist influence in Northern India seems, during the 7th century A.D., to have centred in the fertile plain between the Jumna and the Ganges, and in Behar. At Kanauj (Kanyákubja), on the Ganges, Hiuen Tsiang found a powerful Buddhist monarch, Śílāditya, whose influence reached from the Punjab to North-Eastern Bengal, and from the Himálayas to the Narbadá river. Here flourished 100 Buddhist convents and 10,000 monks. But the king's eldest brother had been lately slain by a sovereign of Eastern India, a hater of Buddhism; and 200 temples to the Bráhmaṇ gods reared their heads under the protection of the devout Śílāditya himself.

Council of
Śílāditya,
634 A.D.

Śílāditya appears as an Asoka of the 7th century A.D., and he practised with primitive vigour the two great Buddhist virtues of spreading the faith and charity. The former he attempted by means of a general Council in 634 A.D. Twenty-one tributary sovereigns attended, together with the most learned Buddhist monks and Bráhmaṇs of their kingdoms. But the object of the convocation was no longer the undisputed assertion of the Buddhist religion. It dealt with the two phases of the religious life of India at that time. First, a discussion between the Buddhists and Bráhmaṇ philosophers of the Sánkhyā and Vaiseshika schools; second, a dispute between the Buddhist sects who followed respectively the Northern and the Southern Canons, known as 'the Greater and the Lesser Vehicle of the Law.' The rites of the populace were of as composite a character as the doctrines of their teachers. On the first day of the Council, a statue of Buddha was installed with great pomp; on the second, an image of the Sun-god; on the third, an idol of Siva.

Śílāditya's
charity.

Śílāditya held a solemn distribution of his royal treasures every five years. Hiuen Tsiang describes how on the plain near Allahábád, where the Ganges and the Jumna unite their waters, the kings of the Empire, and a multitude of people, were feasted for seventy-five days. Śílāditya brought forth the stores of his palace, and gave them away to Bráhmaṇs and Buddhists, to monks and heretics, without distinction. At the end of the festival, he stripped off his jewels and royal raiment, handed them to the bystanders, and, like Buddha of old, put on the rags of a beggar. By this ceremony, the monarch commemorated the Great Renunciation of the founder of the Buddhist faith. At the same time, he discharged the highest duty inculcated alike by the Buddhist and Bráhmaṇical religions,

namely almsgiving. The vast monastery of Nalanda¹ formed a seat of learning which recalls the universities of Medieval Europe. Ten thousand monks and novices of the eighteen Buddhist schools here studied theology, philosophy, law, science, especially medicine, and practised their devotions. They lived in lettered ease supported from the royal funds. But even this stronghold of Buddhism furnishes a proof that Buddhism was only one of two hostile creeds in India. During the brief period with regard to which the Chinese records afford information it was three times destroyed by the enemies of the faith.²

Hsuen Tsiang travelled from the Punjab to the mouth of the Ganges and made journeys into Southern India. But every where he found the two religions mingled. Buddh Gaya, which holds so high a sanctity in the legends of Buddha, had already become a great Brāhman centre. On the east of Bengal, Assam had not been converted to Buddhism. In the south west, Orissa was a stronghold of the Buddhist faith. But in the seaport of Tamruk at the mouth of the Hughli, the temples to the Brāhman gods were five times more numerous than the monasteries of the faithful. On the Madras coast, Buddhism flourished, and indeed throughout Southern India, the faith seems still to have been in the ascendant, although struggling against Brāhman heretics and their gods.

During the 8th and 9th centuries A.D., Brahmanism became the ruling religion. There are legends of persecutions instigated by Brāhman reformers, such as Kumarila Bhaṭṭa and Sankara Achārya. But the downfall of Buddhism seems to have resulted from natural decay, and from new movements of religious thought, rather than from any general suppression by the sword. Its extinction is contemporaneous with the rise of Hinduism and belongs to a subsequent chapter.

In the 11th century, it was chiefly on the Sāles, Idā Kashmir and Orissa, that remained faithful. When the Muhammadans came permanently upon the scene, Buddhism as a popular faith has almost disappeared from the interior Provinces of India. Magadha, the cradle of the religion still continued Buddhist under the Pal Rajas down to the Muhammadan conquest of Bakhtiyar Khilji in 1199 A.D.

¹ Identified with the modern Baragani near Gaya. The site can be traced by a mass of brick ruins 1500 ft. long by 40 ft. wide. General Cunningham's *Antiquities of India* pp. 458-460.

² *India's Career of Buddhism* See p. 122 from the Chinese records.

³ MS. materials sent to the Asiatic Society by General Cunningham.

Buddhism
an exiled
religion,
1000 A.D.

Its foreign
conquests.

During nearly a thousand years, Buddhism has been a banished religion from its native home. But it has won greater triumphs in its exile than it could have ever achieved in the land of its birth. It has created a literature and a religion for nearly half the human race, and has affected the beliefs of the other half. Five hundred millions of men, or forty per cent. of the inhabitants of the world, still acknowledge, with more or less fidelity, the holy teaching of Buddha. Afghánistán, Nepál, Eastern Türkistán, Tibet, Mongolia, Manchuria, China, Japan, the Eastern Archipelago, Siam, Burma, Ceylon, and India, at one time marked the magnificent circumference of its conquests. Its shrines and monasteries stretched in a continuous line from what are now the confines of the Russian Empire to the equatorial islands of the Pacific. During twenty-four centuries, Buddhism has encountered and outlived a series of powerful rivals. At this day it forms, with Christianity and Islám, one of the three great religions of the world; and the most numerous followed of the three.

Buddhist
survivals
in India.

In India its influence has survived its separate existence. The Buddhist period not only left a distinct sect, the Jains; but it supplied the spiritual basis on which Bráhmaism finally developed from the creed of a caste into the religion of the people. A later chapter will show how important and how permanent have been Buddhistic influences on Hinduism. The Buddhists in British India in 1881 numbered nearly $3\frac{1}{2}$ millions, of whom $3\frac{1}{4}$ millions were in British Burma; and 166,892 on the Indian continent, almost entirely in North-Eastern Bengal and Assam. Together with the Jain sect, the Buddhist subjects of the Crown in British India amount to close on four millions (1881).¹ The revival of Buddhism is always a possibility in India. This year (1885) an excellent Buddhist journal has been started in Bengali, at Chittagong.

The Jains.

The Jains number about half a million in British India. Like the Buddhists, they deny the authority of the Veda, except whose Archæological Reports and kind assistance this volume is deeply indebted.

¹ The Buddhists proper were returned in 1881 for British India at 3,418,476; of whom 3,251,584 were in British Burma; 155,809 in the Lieutenant-Governorship of Bengal; and 6563 in Assam. The Jains proper were returned at 448,897 in British India by the Census of 1881. But except in a few spots, chiefly among the spurs of the Himálayas and in Assam and South-Eastern Bengal, the Indian Buddhists may be generally reckoned as Jains.

in so far as it agrees with their own doctrines. They disregard sacrifice, practise a strict morality, believe that their past and future states depend upon their own actions rather than on any external deity, and scrupulously reverence the vital principle in man and beast. They differ from the Buddhists chiefly in their ritual and objects of worship. The veneration of good men departed is common to both, but the Jains have expanded and methodized such adoration on lines of their own.

The Buddhists admit that many Buddhas have appeared in successive lives upon earth, and attained *Nirvana* or beatific extinction, but they confine their reverence to a comparatively small number. The Jains divide time into Jain doc-
successive eras, and assign twenty four *Jinas*, or just men made trines
perfect, to each¹. They name twenty four in the past age, twenty four in the present, and twenty four in the era to come, and place colossal statues of white or black marble to this great company of saints in their temples. They adore above all the two latest, or twenty third and twenty fourth *Jinas* of the present era—namely, *Parsvanáth*² and *Mahavira*.

The Jains choose wooded mountains and the most lovely Jain
retreats of nature for their places of pilgrimage, and cover them temple
with exquisitely carved shrines in white marble or stucco cities
Párasnáth Hill in Bengal, the temple city of *Palitána* in *Káthiawár*, and *Mount Abu*, which rises with its gems of architecture like a jewelled island from the *Rájpútána* plains, form well known scenes of their worship. The Jains are a wealthy community, usually engaged in banking or wholesale commerce, devoid indeed of the old missionary spirit of Buddhism, but closely knit together among themselves. Their charity is boundless, and they form the chief supporters of the beast hospitals, which the old Buddhistic tenderness for animals has left in many of the cities of India.

Jainism is, in its external aspects, Buddhism equipped with Relation
a mythology—a mythology, however, not of gods, but of saints of Jainism
But in its essentials, Jainism forms a survival of beliefs to Buddh
ism
anterior to *Asoka* and *Kanishka*. According to the old view, the Jains are a remnant of the Indian Buddhists who saved themselves from extinction by compromises with Hinduism, and so managed to erect themselves into a recognised caste.

¹ Under such titles as *Jagata prabhu* 'lord of the world,' *Kṣhīnakarma*, 'freed from ceremonial acts,' *Sarvajña*, 'all knowing,' *Adhishwara*, 'supreme lord,' *Tirthankara*, 'he who has crossed over the world,' and *Jina* 'he who has conquered the human passions.'

² Popularly rendered *Parsvanath*.

Jains
earlier
than
Buddhists?

According to the later and truer view, they represent in an unbroken succession the Nigantha sect of the Asoka edicts. The Jains themselves claim as their founder, Mahāvīra, the teacher or contemporary of Buddha; and the Niganthas appear as a sect independent of, indeed opposed to, the Buddhists in the Rock Inscriptions of Asoka and in the Southern Canon (*pitakas*).

Mahāvīra, who bore also the spiritual name of Vardhamāna, 'The Increaser,' is the 24th Jina or 'Conqueror of the Passions,' adored in the present age of Jain chronology. Like Buddha, he was of princely birth, and lived and laboured in the same country and at the same time as Buddha. According to the southern Buddhist dates, Buddha 'attained rest' 543 B.C., and Mahāvīra in 526 B.C. According to the Jain texts, Mahāvīra was the predecessor and teacher of Buddha.

Antiquity
of the
Jains.

A theory has accordingly been advanced that the Buddhism of Asoka (244 B.C.) was in reality a later product than the Nigantha or Jain doctrines.¹ The Jains are divided into the Svetāmbaras, 'The White Robed,' and the Digambaras, 'The Naked.' The Tibetan texts make it clear that sects closely analogous to the Jains existed in the time of Buddha, and that they were antecedent and rival orders to that which Buddha established.² Even the Southern Buddhist Canon preserves recollections of a struggle between a naked sect like the Jain Digambaras, and the decently robed Buddhists.³ This Digambara or Nigantha sect (Nirgrantha, 'those who have cast aside every tie') was very distinctly recognised by Asoka's edicts; and both the Svetāmbara and Digambara orders of the modern Jains find mention in the early copper-plate inscriptions of Mysore, *circa* 5th or 6th century A.D. The Jains in our own day feel strongly on this subject, and the head of the community at Ahmadābād has placed many arguments before the writer of the present work to prove that their faith was anterior to Buddhism.

Until quite recently, however, European scholars did not admit the pretensions of the Jains to pre-Buddhistic antiquity.

¹ This subject was discussed in Mr. Edward Thomas' *Jainism, or the Early Faith of Asoka*; in Mr. Rhys Davids' article in *The Academy* of 13th September 1879; in his *Hibbert Lectures*, p. 27; and in the *Numismata Orientalia* (Ceylon fasciculus), pp. 55, 60.

² Mr. Woodville Rockhill's *Life of the Buddha*, from the Bkah-Hgyur and Bstan-Hgyur in *various locis*. 1884.

³ See for example the curious story of the devout Buddhist bride from the Burmese sacred books, in Bishop Bigandet's *Life of Gaudama*, pp. 257-259, vol. i. ed. 1882.

H. H. Wilson questioned their importance at any period earlier than twelve centuries ago¹. Weber regarded 'the Jains as merely one of the oldest sects of Buddhism,' and Lassen believed that they had branched off from the Buddhists². M. Barth, after a careful discussion of the evidence, still thought that we must regard the Jains 'as a sect which took its rise in Buddhism'³. On the other hand, Oldenberg, who brings the latest light from the Pali texts to bear on the question, accepts the identity of the Jain sect with the Niganthas 'into whose midst the younger brotherhood of Buddha entered'⁴.

The learned Jacobi has now investigated this question from the Jain texts themselves⁵. Oldenberg had proved, out of the Buddhist scriptures, that Buddhism was a true product of Bráhmán doctrine and discipline. Jacobi shows that both 'Buddhism and Jainism must be regarded as religions developed out of Bráhmanism not by a sudden reformation, but prepared by a religious movement going on for a long time'⁶. And he brings forward evidence for believing that Jainism was the earlier outgrowth, that it was probably founded by Pársynath, now revered as the 23rd Jina, and merely reformed by Mahavira, the contemporary of Buddha⁷. The outfit of the Jain monk, his alms bowl, rope, and water vessel, was practically the equipment of the previous Bráhmán ascetic⁸. In doctrine, the Jains accepted the Bráhmán pantheistic philosophy of the *Átman*, or Universal Soul. They believed that not only animals and plants, but the elements themselves, earth, fire, water, and wind, were endowed with souls. Buddha made a further divergence. He combated the Brahman doctrine of the Universal Soul, and the Jain dogma, of the elements and

Jacobi's investigation of the question

Jainism older than Buddhism

¹ *Essays and Lectures on the Religion of the Hindus*, by H. H. Wilson, Dr. Reinhold Kost's edition, p. 329 vol. 1 (1863).

² Weber's *Indische Studien* xxi. 210, and Lassen's *Indische Alterthums Kunde* iv. 763 et seq.

³ Barth's *Religions of India*, ed. 1882, p. 151. also Barth's *Lehrbuch der Geschichte des Hinduismus*, iii. 90.

⁴ *Ju'tha, his Life and Doctrine, his Order*, by Prof. Hermann Oldenberg. Hoey's translation (1882), p. 67. See also his pp. 66 and (footnote) 77, and 175.

⁵ *Jaina Sutras, Part I, the Achārāṅga Sutra, and the Kalpa Sutra* by Hermann Jacobi, forming vol. xxii of Max Müller's *Sacred Books of the East*. Clarendon Press, 1884.

⁶ Jacobi *op. cit.* Introduction xxxi.

⁷ *Op. cit.* xxxii.

⁸ For slight differences, see Jacobi, *op. cit.* xxxii.

minerals being endowed with souls, finds no place in Buddhist philosophy.¹

Date of
the Jain
Scripture.

Jacobi believes that the Jain texts were composed or collected at the end of the 4th century B.C.; that the origin of the extant Jain literature cannot be placed earlier than about 300 B.C.; and that their sacred books were reduced to writing in the 5th century A.D.² He thinks that the two existing divisions of the Jains, the Svetambaras and the Digambaras, separated from each other about two or three hundred years after the death of the Founder; but 'that the development of the Jain church has not been at any time violently interrupted.'

Jains an
independ-
ent sect.

That, 'in fact, we can follow this development from its true beginning through its various stages, and that Jainism is as much independent from other sects, especially from Buddhism, as can be expected from any sect.'³

Modern
Jainism.

In its superficial aspects, modern Jainism may be described as a religion allied in doctrine to ancient Indian Buddhism, but humanized by saint-worship, and narrowed from a national religion to the exclusive requirements of a sect.

Survivals
of Buddh-
ism in
India.

The noblest survivals of Buddhism in India are to be found, however, not among any peculiar body, but in the religion of the people; in that principle of the brotherhood of man, with the assertion of which each new revival of Hinduism starts; in the asylum which the great Vaishnav sect affords to women who have fallen victims to caste rules, to the widow and the outcast; in that gentleness and charity to all men, which take the place of a poor-law in India, and give a high significance to the half-satirical epithet of the 'mild' Hindu.

¹*Op. cit.* xxxiii. ² Jacobi, *op. cit.* xxxv and xlii. ³ *Op. cit.* xlii.

CHAPTER VI

THE GREEKS IN INDIA (327 TO 161 B.C.)

RELIGION AND PHILOSOPHY have been the great contributions of India to the world. We now come to deal with India, not as a centre of influence upon other nations, but as acted on by them.

THE EXTERNAL HISTORY OF INDIA commences with the Greek invasion in 327 B.C. Some indirect trade between India and the Mediterranean seems to have existed from very ancient times. Homer was acquainted with tin,¹ and other articles of Indian merchandise, by their Sanskrit names, and a list has been made of Indian products mentioned in the Bible. The ship captains of Solomon and Hiram not only brought Indian apes, peacocks, and sandal wood to Palestine, they also brought their Sanskrit names.² This was about 1000 B.C. The Assyrian monuments show that the rhinoceros and elephant were among the tribute offered to Shulmaneser II (859-823 B.C.).³ But the first Greek historian who speaks clearly of India is Hekataios of Miletos (549-486 B.C.), the knowledge of Herodotos (450 B.C.) ended at the Indus, and Ktesias, the physician (401 B.C.), brought back from his residence in Persia only a few facts about the products of India, its dyes and fabrics, monkeys and parrots. India to the east of the Indus was first made known to Europe by the historians and men of science who accompanied Alexander the Great in 327 B.C. Their narratives, although now lost, furnished materials to Strabo, Pliny, and Arrian. Soon afterwards, Megasthenes, a Greek

External
sources of
the history
of India

Early
Greek
writers—
549-401
B.C.

Megasthenes,
306-295
B.C.

¹ Greek, Kassiteros, Sanskrit, Kastīra, hence, the Kassiterides the Tin or Scilly Islands. Elephas, ivory, through the Arabian *eleph* (from Arabic *el*, the, and Sanskrit *il*), domestic elephant), is also cited.

² Sir G. Lindwood's *Handbook to the British Indian Section of the Paris Exhibition of 1878*, pp. 22-35. For economic intercourse with ancient India, see Del Mar's *History of Money in Ancient Countries*, chaps. iv and v (1885).

³ Helrew, Kophim, tukijim, almugim = Sanskrit, कर्पूर, नखल, -अलङ्कार

⁴ Professor Max Duncker's *Ancient History of India*, p. 13 (ed. 1881)

ambassador resident at a court in the centre of Bengal (306-298 B.C.), had opportunities for the closest observation. The knowledge of the Greeks concerning India practically dates from his researches, 300 B.C.¹

Alexander's expedition, 327-325 B.C.

Alexander the Great entered India early in 327 B.C.; crossed the Indus above Attock, and advanced, without a struggle, over the intervening territory of the Taxiles² to the Jehlam (Jhelum) (Hydaspes). He found the Punjab divided into petty kingdoms jealous of each other, and many of them inclined to join an invader rather than to oppose him. One of these local monarchs, Porus, disputed the passage of the Jehlam with a force which, substituting chariots for guns, about equalled the army of Ranjít Singh, the ruler of the Punjab in the present century.³ Plutarch gives a vivid description of the battle from Alexander's own letters. Having drawn up his troops at a bend of the Jehlam, about 14 miles west of the modern field of Chilianwála,⁴ the Greek general crossed under cover of a tempestuous night. The chariots hurried out by Porus stuck in the muddy margin of the river. In the engagement which followed, the elephants of the Indian prince refused to face the

¹ The fragments of the *Indika* of Megasthenes, collected by Dr. Schwanbeck, with the first part of the *Indika* of Arrian; the *Periplus Maris Erythræi*, with Arrian's account of the voyage of Nearkhos; the *Indika* of Ktesias; and Ptolemy's chapters relating to India, have been edited in four volumes with prolegomena by Mr. J. W. M'Crindle, M.A. (Trübner, 1877, 1879, 1882, and 1885). They originally appeared in the *Indian Antiquary*, to which this volume and the whole *Imperial Gazetteer of India* are much indebted. General Cunningham's *Ancient Geography of India*, with its maps, and his *Reports of the Archaeological Survey*, Vincent's *Commerce and Navigation of the Ancients* (2 vols. 4to, 1807), and the series of maps, on an unfortunately small scale, in General-Lieutenant von Spruner's *Historisch-Geographischen Atlas* (Gotha), have also been freely availed of.

² The Takkas, a Turanian race, the earliest inhabitants of RAWAL PINDI DISTRICT. They gave their name to the town of Takshásila or Taxila, which Alexander found 'a rich and populous city, the largest between the Indus and Hydaspes,' identified with the ruins of DERI SHAHAN. Taki or Asarúr, on the road between Lahore and Pindi Bhatiyán, was the capital of the Punjab in 633 A.D. When names are printed in capitals, the object is to refer the reader to the fuller information given in the *Imperial Gazetteer of India*.

³ Namely, '30,000 efficient infantry; 4000 horse; 300 chariots; 200 elephants' [Professor Cowell]. The Greeks probably exaggerated the numbers of the enemy. Alexander's army numbered 'about 50,000, including 5000 Indian auxiliaries under Mophis of Taxila.'—General Cunningham, *Anc. Geog. of India*, p. 172. See his lucid account of the battle, with an excellent map, pp. 159-177, ed. 1871.

⁴ And about 30 miles south-west of Jehlam town.

Greeks, and, wheeling round, trampled his own army under foot. His son fell early in the onset, Porus himself fled wounded, but on tendering his submission, he was confirmed in his kingdom, and became the conqueror's trusted friend. Alexander built two memorial cities on the scene of his victory, —Bucephala on the west bank, near the modern JALALPUR, named after his beloved charger, Bucephalus, slain in the battle and Nikaia, the present MONG, on the east side of the river.

Alexander advanced south east through the kingdom of the younger Porus to Amritsar and after a sharp bend backward to the west, to fight the Kathaci at Sangala, he reached the Beas (Hyphasis). Here, at a spot not far from the modern battle field of Sobrion he halted his victorious standards.¹ He had resolved to march to the Ganges but his troops were worn out by the heats of the Punjab summer, and their spirits broken by the hurricanes of the south west monsoon. The native tribes had already risen in his rear and the Conqueror of the World was forced to turn back, before he had crossed even the frontier Province of India. The Sutlej the eastern Districts of the Punjab and the mighty Jumna, still lay between him and the Ganges. A single defeat might have been fatal to his army, if the battle on the Jehlam had gone against him not a Greek would probably have reached the Afghan side of the passes. Yielding at length to the clamour of his men he led them back to the Jehlam. He there embarked 8000 of his troops in boats previously prepared, and floated them down the river, the remainder marched in two divisions along the banks.

The country was hostile, and the Greeks held only the land on which they encamped. At Multan then as now the capital of the Southern Punjab, Alexander had to fight a pitched battle with the Malli, and was severely wounded in taking the city. His enraged troops put every soul within it to the sword. Farther down, near the confluence of the five rivers of the Punjab, he made a long halt, built a town,—Alexandria, the modern Uchh,—and received the submission of the neighbouring States. A Greek garrison and Satrap, whom he here left behind, laid the foundation of a more lasting influence. Having constructed a new fleet, suitable for the greater rivers on which he was now to embark, he proceeded southwards through Sind, and followed the course of the Indus until he reached

¹ The change in the course of the Sutlej has altered its old position relative to the Beas at this point. The best small map of Alexander's route is No. v. in General Cunningham's *Anc. Geog. of India*, p. 104, ed. 1871.

Leaves
India,
August
325 B.C.

the ocean. In the apex of the delta he founded or refounded a city—Patala—which survives to this day as Haidarábád, the native capital of Sind.¹ At the mouth of the Indus, Alexander beheld for the first time the majestic phenomenon of the tides. One part of his army he shipped off under the command of Nearkhos to coast along the Persian Gulf; the other he himself led through Southern Baluchistán and Persia to Susa, where, after terrible losses from want of water and famine on the march, he arrived in 325 B.C.²

Results of
Greek ex-
pedition,
327-325
B.C.

During his two years' campaign in the Punjab and Sind, Alexander captured no province, but he made alliances, founded cities, and planted Greek garrisons. He had transferred much territory from the tribes whom he had half-subdued, to the chiefs and confederations who were devoted to his cause. Every petty court had its Greek faction; and the detachments which he left behind at various positions from the Afghán frontier to the Beas, and from near the base of the Himálayas to the Sind delta, were visible pledges of his return. At Taxila (DERI-SHAHAN) and Nikaia (MONG) in the Northern Punjab; at Alexandria (UCHH) in the Southern Punjab; at Patala (HAIDARABAD) in Sind; and at other points along his route, he established military settlements of Greeks or their allies. A body of his troops remained in Bactria. In the partition of the Empire after Alexander's death in 323 B.C., Bactria and India eventually fell to Seleukos Nikator, the founder of the Syrian monarchy.

Seleukos,
323-312
B.C.

Chandra
Gupta,
326 B.C.;

Meanwhile, a new power had arisen in India. Among the Indian adventurers who thronged Alexander's camp in the Punjab, each with his plot for winning a kingdom or crushing a rival, Chandra Gupta, an exile from the Gangetic valley, seems to have played a somewhat ignominious part. He tried to tempt the wearied Greeks on the banks of the Beas with

¹ For its interesting appearances in ancient history, see General Cunningham's *Anc. Geog. of India*, pp. 279-287, under Patala or Nirankot. It appears variously as Pattala, Pattalene, Pitasila, etc. It was formerly identified with Tatta (Thatha), near to where the western arm of the Indus bifurcates. See also M'Crindle's *Commerce and Navigation of the Erythrean Sea*, p. 156 (Trübner, 1879). An excellent map of Alexander's campaign in Sind is given at p. 248 of Cunningham's *Anc. Geog. of India*.

² The stages down the Indus and along the Persian coast, with the geographical features and incidents of Nearkhos' *Voyage*, are given in the second part of the Indika of Arrian, chapter xviii. to the end. The river stages and details are of value to the student of the modern delta of the Indus.—M'Crindle's *Commerce and Navigation of the Erythrean Sea*, pp. 153-224 (1879).

schemes of conquest in the rich south eastern Provinces, but having personally offended Alexander, he had to fly the camp (326 B.C.) In the confused years which followed, he managed, with the aid of plundering hordes, to found a kingdom on the ruins of the Nanda dynasty in Magadha, or Behar (316 316 B.C., B.C.)¹ He seized their capital, Pataliputra, the modern Patna, established himself firmly in the Gangetic valley, and compelled the Punjab principalities, Greek and native alike, to acknowledge his suzerainty.² While, therefore, Seleukos Nikator was winning his way to the Syrian monarchy during the eleven years which followed Alexander's death, Chandra Gupta was building up an empire in Northern India. Seleukos reigned in Syria from 312 to 280 B.C., Chandra Gupta in the 312 P.C. Gangetic valley from 316 to 292 P.C. In 312 B.C., the power of both had been consolidated, and the two new sovereignties were soon brought face to face.

About that year, Seleukos, having recovered Babylon, proceeded to re-establish his authority in Bactria and the Punjab. In the Punjab, he found Greek influence decayed. Alexander had left a mixed force of Greeks and Indians at Taxila. But no sooner had he departed from India, than the Indians rose and slew the Greek governor. The Macedonians next massacred the Indians. A new governor, sent by Alexander, murdered the friendly Punjab prince, Porus, and was himself driven out of India, by the advance of Chandra Gupta from the Gangetic valley. Seleukos, after a war with Chandra Gupta, determined to ally himself with the new power in India rather than to oppose it. In return for 500 elephants, he ceded the Greek settlements in the Punjab and the Kabul valley, gave his daughter to Chandra Gupta in marriage, and stationed an ambassador, Megasthenes, at the Gangetic court (306-298 B.C.)³ Chandra Gupta became familiar to the Greeks as Sındrokottos, King of the Prasii and Gangaridae, his capital, Pataliputra,⁴ or Patná, was rendered into Palimbothra. On the other hand, the Greeks and kings of Grecian dynasties appear in the rock-inscriptions under Indian forms.⁵

¹ *Corpus Inscriptionum Indicarum*, i. 7. Jacobi's *Jaina Siltras*, xliii.

² For the dynasty of Chandra Gupta, see *Numismata Orientalia* (Ceylon fasciculus), pp. 41-50.

³ The modern Patna, or Iattana, means simply 'the city'. For its identification with Pataliputra by means of Mr. Ravenshaw's final discoveries, see General Cunningham's *Anc. Geog. of India*, p. 452 et seq.

⁴ The Greeks as *Λόναι* (Λάνας), from the *Ἴωνες* or Ionians. In the Inscriptions of Asoka, five Greek princes appear: Antiochus (of Syria), Ptolemy (Ptolemaios of Egypt), Antigonos (Gonatos of Macedonia),

Petty
kingdoms.

suit, and lived peaceably under their native chiefs. The kingly government is portrayed almost as described in Manu, with its hereditary castes of councillors and soldiers. Megasthenes mentions that India was divided into 118 kingdoms; some of which, such as that of the Prasii under Chandra Gupta, exercised suzerain powers. The village system is well described, each little rural unit seeming to the Greek an independent republic. Megasthenes remarked the exemption of the husbandmen (Vaisyas) from war and public services; and enumerates the dyes, fibres, fabrics, and products (animal, vegetable, and mineral) of India. Husbandry depended on the periodical rains; and forecasts of the weather, with a view to 'make adequate provision against a coming deficiency,' formed a special duty of the Bráhmans. 'The philosopher who errs in his predictions observes silence for the rest of his life.'

Indo-
Greek
treaty,
256 B.C.

Before the year 300 B.C., two powerful monarchies had thus begun to act upon the Bráhmanism of Northern India, from the east and from the west. On the east, in the Gangetic valley, Chandra Gupta (316-292 B.C.) firmly consolidated the dynasty which during the next century produced Asoka (264-223 B.C.), established Buddhism throughout India, and spread its doctrines from Afghánistán to China, and from Central Asia to Ceylon. On the west, the heritage of Seleukos (312-280 B.C.) diffused Greek influences, and sent forth Greco-Bactrian expeditions to the Punjab. Antiochos Theos (grandson of Seleukos Nikator) and Asoka (grandson of Chandra Gupta), who ruled these probably conterminous monarchies, made a treaty with each other, 256 B.C. In the next century, Eukratides, King of Bactria, conquered as far as Alexander's royal city of Patala, the modern Haidarábád in the Sind Delta; and sent expeditions into Cutch and Gujarát, 181-161 B.C. Menander advanced farthest into North-Western India, and his coins are found from Kábul, near which he probably had his capital, as far as Muttra on the Jumna. The Buddhist successors of Chandra Gupta profoundly modified the religion of Northern India from the east; the empire of Seleukos, with its Bactrian and later offshoots, deeply influenced the science and art of Hindustán from the west.

Greeks in
India,
181-161
B.C.

Greek in-
fluence on
Indian art.

We have already seen how much Bráhman astronomy owed to the Greeks, and how the builders' art in India received its first impulse from the architectural exigencies of Buddhism. The same double influence, of the Greeks on the west and of the Buddhists on the east of the Bráhmanical Middle Land of

Bengal, can be traced in many details. What the Buddhists were to the architecture of Northern India, that the Greeks were to its sculpture. Greek faces and profiles constantly occur in ancient Buddhist statuary. They enrich almost all the larger museums in India, and examples may be seen at South Kensington. The purest specimens have been found in the Punjab, where the Greeks settled in greatest force. In the Lahore collection there was, among other beautiful pieces, an exquisite little figure of an old blind man feeling his way with a staff. Its subdued pathos, its fidelity to nature, and its living movement dramatically held for the moment in sculptured suspense, are Greek, and nothing but Greek. It is human misfortune, that has culminated in wandering poverty, age, and blindness—the very curse which Sophocles makes the spurned Teiresias throw back upon the doomed king—

Blind having seen
 Poor having rolled in wealth I e with a staff
 Feeling his way to a strange land shall go

As we proceed eastward from the Punjab the Greek type begins to fade. Purity of outline gives place to lusciousness of form. In the female figures, the artists trust more and more to swelling breasts and towering chignons, and load the neck with constantly accumulating jewels. Nevertheless, the Grecian type of countenance long survived in Indian art. It is perfectly unlike the coarse, conventional ideal of beauty in modern Hindu sculptures, and may perhaps be traced as late as the delicate profiles on the so-called Sun Temple at KANARAH, built in the 12th century A.D. on the Orissa shore.

Not only did the Greek impulse become fainter and fainter in Indian sculpture with the lapse of time, but that impulse was itself gradually derived from less pure and less vigorous sources. The Greek ideal of beauty may possibly have been brought direct to India by the officers and artists of Alexander the Great. But it was from Græco Bactria, not from Greece itself, that the practical masters of Greek sculpture came to the Punjab. Indeed, it seems probable that the most prolific stream of such artistic inspirations reached India from the Roman Empire, and in Imperial times, rather than through even the indirect Grecian channels represented by the Bactrian kingdom.

It must suffice here to indicate the ethnical and dynastic influences thus brought to bear upon India, without attempting to assign dates to the individual monarchs. The chronology of the twelve centuries intervening between the

Greek and
 Hindu
 types of
 sculpture

Greek
 types die
 out

Foreign
 influences
 on India

Græco-Bactrian period and the Muhammadan conquest still depends on a mass of conflicting evidence derived from inscriptions, legendary literature, unwritten traditions, and coins.¹ Four systems of computation exist, based upon the Vikramáditya, Saka, Seleucidan, and Parthian eras.

In the midst of the confusion, we see dim masses moving southwards from Central Asia into India. The Græco-Bactrian kings are traced by coins as far as Muttra on the Jumna. Their armies occupied for a time the Punjab, as far south as Gujarát and Sind. Sanskrit texts are said to indicate their advance through the Middle Land of the Bráhmans (*Madhya-desha*) to Sáketa (or AJODHYA), the capital of Oudh, and to Patná in Behar.² Megasthenes was only the first of a series of Greek ambassadors to Bengal.³ A Grecian princess became the queen of Chandra Gupta at Patná (*circ.* 306 B.C.). Græco-Bactrian girls, or Yavanís, were welcome gifts, and figure in the Sanskrit drama as the personal attendants of Indian kings. They were probably fair-complexioned slaves from the northern regions. It is right to add, however, that the word Yavan has a much wider application than merely to the Greeks or even to the Bactrians. The credentials of the Indian embassy to Augustus in 22-20 B.C. were written on skins; a circumstance which perhaps indicates the extent to which Greek usage had overcome Bráhmanical prejudices. During the century preceding the Christian era, Scythian or Tartar hordes began to supplant the Græco-Bactrian influence in the Punjab.

The 'Yavanas,' The term Yavana, or Yona, formerly applied to any non-Bráhmanical race, and especially to the Greeks, was now extended to the Sakæ or Scythians. It probably includes many various tribes of invaders from the west. Patient effort will be required before the successive changes in the meaning of Yavana, both before and after the Greek period, are worked

¹ Report of the *Archæological Survey of Western India* for 1874-75, p. 49 (Mr. E. Thomas' monograph).

² Goldstucker assigned the Yavana siege of Saketa (AJODHYA), mentioned in the Mahábháshya, to Menander; while the accounts of the Gárgi Sanhitá in the Yuga Purána speak of a Yavana expedition as far as Patná. But, as Weber points out (*Hist. Ind. Lit.*, p. 251, footnote 276), the question arises as to whether these Yavanas were Græco-Bactrians or Indo-Scythians. See, however, *Report of Archæological Survey of Western India* for 1874-75, p. 49, and footnote.

³ Weber, *Hist. Ind. Lit.*, p. 251 (ed. 1878), enumerates four.

out. The word travelled far, and has survived with a strange vitality in out of the way nooks of India. The Orissa chroniclers called the sea invaders from the Bay of Bengal, Yavanas, and in later times the term was applied to the Musalmáns¹. At the present day, a vernacular form of the word is said to have supplied the local name for the Arab settlers on the Coromandel coast.²

¹ *Hunters Orissa*, vol. 1. pp. 25, 85, and 209 to 232 (ed. 1872).

² Bishop Caldwell gives Yavanas (Yonas) as the equivalent of the Sonagas or Muhammadans of the western coast. *Comparative Grammar of the Dravidian Languages* 2nd edition, p. 2 (Trübner, 1875).

was born¹ During the two hundred years before the Christian era the Scythic movements come a little more clearly into sight, and in the first century after Christ those movements culminate in a great Indian sovereignty. About 126 B.C., the Tartar tribe of Su are said to have conquered the Greek dynasty in Bactria and the Greco-Bactrian settlements in the Punjab were overthrown by the Tue Chi²

Two centuries later, we touch solid ground in the dynasty whose chief representative, Kanishka, held the Fourth Buddhist Council *circa* 40 A.D., and became the royal founder of Northern Buddhism. But long anterior to the alleged Tue Chi settlements in the Punjab tribes of Scythic origin had found their way into India, and had left traces of non-Aryan origin upon Indian civilisation. The sovereignty of Kanishka in the first century A.D. was not an isolated effort, but the ripened fruit of a series of ethnical movements.

Certain scholars believe that even before the time of Buddha, there are relics of Scythic origin in the religion of India. It has been suggested that the *Asvamedha*, or Great Horse Sacrifice, in some of its developments at any rate, was based upon Scythic ideas. 'It was in effect,' writes Mr. Edward Thomas, 'a martial challenge, which consisted in letting the victim who was to crown the imperial triumph at the year's end, go free to wander at will over the face of the earth, its sponsor being bound to follow its hoofs and to conquer or conciliate' the chiefs through whose territories it passed. Such a prototype seems to him to shadow forth the life of the Central Asian communities of the horseman class, 'among whom a captured steed had so frequently to be traced from camp to camp, and surrendered or sought for at last.' The curious connection between the Horse Sacrifice and the Man Sacrifice of the pre-Buddhistic religion of India has often been noticed. That connection has been explained from the Indian point of view, by the substitution theory of a horse for a human victim. But among the early shepherd tribes of Tibet, the two sacrifices crossed as inseparable parts of The Great

¹ *Causes of the Buddhist Struggle from the Christian Era to the Present*, 186-187. See also Herodotus 1. 103, 104. Compendium of Indian Literature, 1863. See also H. H. Wilson, *Asiatic Researches*, 212, 213. By Weber, *Hist. Ind. Lit.*, 255, 256, 1858.

² Dr. G. G. Coxe, *Asiatic Researches*, 212, 213. See also Coxe, *Asiatic Researches*, 212, 213.

³ *Causes of the Buddhist Struggle from the Christian Era to the Present*, 186-187. See also Herodotus 1. 103, 104. Compendium of Indian Literature, 1863. See also H. H. Wilson, *Asiatic Researches*, 212, 213. By Weber, *Hist. Ind. Lit.*, 255, 256, 1858.

betan records might settle the point. These hopes have, however, been disappointed, as the earliest Tibetan records prove to be a reflex of foreign influences rather than a deposit

of indigenous traditions. Tibet, Khoten, and other countries to the north of the Himalayas, on adopting Buddhism, more or less unconsciously re-cast their national traditions into Buddhist moulds.¹ These traditions of two distinct streams of civilisation,—the material civilisation of China and the religious civilisation of India. Some of the early Tibetan legends seem to be clumsy copies of the stories of the first Chinese sovereigns recorded in the Bamboo Books.² The Tibetan classics further obscure the historical facts by a tendency to trace the royal lines of Central Asia to the family or early converts of Buddha, as certain medieval families of Europe claimed descent from the Wise Men of the East and noble *saints* of Rome found their ancestors among the heroes of the Trojan war. Thus the first Tibetan monarch derived his line from Prasenadjit, King of Kosala, the life-long friend of Buddha, and the dynasty of Khoten claimed, as its founder a son of King Dharmasoka.

The truth is, that while Tibet obtained much of its material civilisation from China its medicine its mathematics its weights and measures its chronology its clothing its mul-
berries tea, and ardent spirits it received its religion and letters from India, together with its philosophy, and its ideal of the spiritual life. The mission of the seven Tibetan nobles to India to find an alphabet for the yet unwritten language of Tibet, is an historical event of the 7th century A.D. The Indian monastery of Nalanda was reproduced with fidelity in the great Hsamyas, or religious house at Lhasa. The struggle between Chinese and Indian influences disclosed itself alike in the public disputations of the Tibetan sects and in the inner intrigues of the palace. One of the greatest of the Tibetan monarchs married two wives,—an Indian princess who brought Buddhist images from Nepal, and a Chinese princess who brought silk brocades and whisky from China.³ We must therefore receive with caution the evidence as to the original signification of the word Sakya, derived from the records of a nation which was so largely indebted for its ideas and its traditions to later foreign sources.

¹ Early Histories of Tibet and Khoten, in Mr. Rockhill's *Life of the*
Pullika, p. 237 etc.

² *Ibid* p. 203

VOL. VI

³ *Ibid*, pp. 213-215

found both the Northern or Scythic and the Southern forms of Buddhism in full vigour in India. He spent fourteen months at China pati, the town where Kanishka had kept his Chinese hostages in the Punjab; and he records the debates between the Northern and Southern sects of Buddhists in various places. The town of China pati, ten miles west of the Beas river,¹ bore witness to later ages of the political connection of Northern India with the Trans Himalayan races of Central and Eastern Asia. The Scythic influence in India was a Scythic dynastic as well as a religious one. The evidence of coins and the names of Indian tribes or reigning families, such as the Sákas, Huns, and Nágas, point to Scythian settlements as far south as the Central Provinces.²

Some scholars believe that the Scythians poured down upon India in such masses as to supplant the previous population. The Jats or Jats,³ who now number 4½ millions and form one-fifth of the inhabitants of the Punjab, are identified with the Getae, and their great sub-division the Dhe with the Dahae, whom Strabo places on the shores of the Caspian. This view has received the support of eminent investigators, from Professor H. H. Wilson to General Cunningham, the late Director General of the Archaeological Survey of India.⁴ The existing division between the Játas and the Dhe has, indeed, been traced back to the contiguity of the Massa getae or Great Jats, Getae,⁵ and the Dahae, who dwelt side by side in Central Asia, and who may have advanced together during the Scythian movements towards India on the decline of the Græco Bactrian Empire. Without pressing such identifications too closely in the service of particular theories, the weight of authority is in favour of a Scythian origin for the Játas, the most numerous and valuable section of the agricultural population of the Punjab.⁶ A similar descent has been assigned to certain of the Rájput

¹ General Cunningham's *Anc. Geog. of India*, p. 200.

² Muir's *Sanskrit Texts*, chap. v, vol. 1 (1868). Sir C. Grant's *Gazetteer of the Central Provinces*, lxx, etc (Nagpur, 1870). Reports of the *Archæological Survey of India as to Western India*, Professor H. H. Wilson (and Dr. F. Hall), *Vishnu Purána*, ii. 134.

³ The word occurs as Jats and Jats, but the identity of the two forms has been established by reference to the *Aln i Aklarl*. Some are now Hindus, others Muhammadans.

⁴ See among other places, part iv. of his *Archæological Reports*, p. 19.

⁵ *Massi* means 'great' in Pehlevi.

⁶ It should be mentioned, however, that Dr. Trumpp believed them to be of Aryan origin (*Zeitsch. d. Deutsch. Morg. Gesellsch.*, xv. p. 690). See Mr. J. Beames' admirable edition of Sir Henry Elliot's *Glossary of the Races of the North-Western Provinces*, vol. 1 pp. 130-137, ed. 1869.

tribes. Colonel Tod, still the standard historian of Rájásthán, strongly insisted on this point.

(2) The
Rájputs.

The relationship between the Játs and the Rájputs, although obscure, is acknowledged; and although the *jus connubii* no longer exists between them, an inscription seems to show that they intermarried in the 5th century A.D.¹ Professor Cowell, indeed, regards the arguments for the Scythic descent of the Rájputs as inconclusive.² But authorities of weight have deduced, alike from local investigation³ and from Sanskrit literature,⁴ a Scythic origin for the Játs and for certain of the Rájput tribes. The question has lately been discussed, with the fulness of local knowledge, by Mr. Denzil Ibbetson, the chief Census officer for the Punjab in 1881. His conclusions are—First, that the terms Rájput and Ját indicate a difference in occupation and not in origin. Second, that even if they represent distinct waves of migration, separated by an interval of time, ‘they belong to one and the same ethnic stock.’ Third, ‘that whether Játs and Rájputs were or were not originally distinct,’ ‘the two now form a common stock; the distinction between Ját and Rájput being social rather than ethnic.’⁵ We shall see that earlier migrations of Central Asian hordes also supplied certain of the Nágá, or so-called aboriginal, races of India.

Indian
struggle
against the
Scythians.

The Scythic settlements were not effected without a struggle. As Chandra Gupta had advanced from the Gangetic valley, and rolled back the tide of Græco-Bactrian conquest, 312–306 B.C.,

¹ Inscription discovered in Kotah State; No. 1 of Inscription Appendix to Colonel Tod’s *Annals and Antiquities of Rájásthán*, vol. i. p. 701, note 3 (Madras Reprint, 1873). Although Tod is still the standard historian of Rájputána, and will ever retain an honoured place as an original investigator, his ethnical theories must be received with caution.

² Appendix to Elphinstone’s *Hist. Ind.*, pp. 250 *et seq.*, ed. 1866.

³ Tod’s *Rájásthán*, pp. 52, 483, 500, etc., vol. i. (Madras Reprint, 1873).

⁴ Dr. Fitz-Edward Hall’s edition of Professor H. H. Wilson’s *Vishnu Purána*, vol. ii. p. 134. The Húnas, according to Wilson, were ‘the white Huns who were established in the Punjab, and along the Indus, as we know from Arrian, Strabo, and Ptolemy, confirmed by recent discoveries of their coins and by inscriptions.’ ‘I am not prepared,’ says Dr. Fitz-Edward Hall, ‘to deny that the ancient Hindus when they spoke of the Húnas included the Huns. In the Middle Ages, however, it is certain that a race called Húna was understood by the learned of India to form a division of the Kshattriyas.’ Professor Dowson’s *Dict. Hind. Mythology*, etc., p. 122.

⁵ See the ethnographical volume of the Punjab Census for 1881, paras. 421, 422 *et seq.*, by Mr. Denzil Jelf Ibbetson, of the Bengal Civil Service, p. 220 (Government Press, Calcutta, 1883).

so the native princes who stemmed the torrent of Scythian invasion are the Indian heroes of the first century before and after Christ. Vikramāditya, King of Ujjain, appears to have won his paramount place in Indian story by driving out the invaders. An era, the *Samvat*, beginning in 57 B.C., was founded in honour of his achievements. Its date¹ seems at variance with his legendary victories over the Scythian Kanishka in the 1st century after Christ². But the very title of its founder suffices to commemorate his struggle against the northern hordes, as Vikramāditya Sakāri, or Vikramaditya, the Enemy of the Scythians.

The name of Vikramāditya, 'A very Sun in Prowess,' was borne, as we have seen, by several Indian monarchs. In later ages their separate identity was merged in the ancient renown of the Slayer of the Scythians, who thus combined the fame of many Vikramādityas. There was a tendency to assign to his period the most eminent Indian works in science and poetry,—works which we know must belong to a date long after the first century of our era. His reign forms the Augustan era of Sanskrit literature, and tradition fondly ascribed the highest products of the Indian intellect during many later centuries to the poets and philosophers, or Nine Gems, of this Vikramaditya's Court. As Chandra Gupta, who freed India from the Greeks, is celebrated in the drama *Mudrā rākshasa*, so Vikramāditya, the vanquisher of the Scythians, forms the central royal personage of the Hindu stage.

Vikramaditya's achievements, however, furnished no final deliverance, but merely form an episode in the long struggle between the Indian dynasties and new races from the north. Another popular era, the *Saka*, literally the Scythian, takes its commencement in 78 A.D.³ and is supposed to commemorate the defeat of the Scythians by a king of Southern India, Salivahanā⁴. During the seven centuries which followed, three powerful monarchies, the Senas, Guptas, and Valabhis, established themselves

¹ *Samvat* is the 'Year'. The uncertainty which surrounds even this long accepted finger post in Indian chronology may be seen from Dr. J. Ferguson's paper 'On the Saka and Samvat and Gupta eras' (*Journal of Asiatic Soc.*, New Series, vol. xii) especially p. 172.

² The Hushka, Jushka, and Kanishka family of the *Rajya Tarangini* or *Chronicles of Kashmir*, are proved by inscriptions to belong to the 4th century of the Seleucid era, or the 1st century A.D.

³ Monday, 14th March 78 A.D., Julian style.

⁴ General Cunningham, see also Mr. Edw. Thomas' letter, dated 16th September 1874 to *The Asiatic Soc.*, which brings this date within the period of the Kanishka family (212 to 275 A.D.).

Sena (Sah) in Northern and Western India. The Senas and Singhas, or dynasty, 60 B.C. to 235 A.D. Sâtraps of Surâshtra, are traced by coins and inscriptions from 60 or 70 B.C. to after 235 A.D.¹ After the Senas come the Guptas of KANAUJ,² in the North-Western Provinces, the Middle Land of ancient Brâhmanism. The Guptas introduced an era of their own, commencing in 319 A.D.; and ruled in person or by viceroys over Northern India during 150 years, as far to the south-west as Kâthiâwâr. The Gupta dynasty was overthrown by foreign invaders, apparently a new influx of Huns or Tartars from the north-west (450-470 A.D.).

Valabhi dynasty, 480-722 A.D. The Valabhîs succeeded the Guptas, and ruled over Cutch, north-western Bombay,³ and Mâlwa, from 480 to after 722 A.D.⁴ The Chinese pilgrim, Hiuen Tsiang, gives a full account of the court and people of Valabhî (630-640 A.D.). Buddhism was the State religion, but heretics, *i.e.* Brâhmans, abounded; and the Buddhists themselves were divided between the northern school of the Scythian dynasties, and the southern or Indian school of Asoka. The Valabhîs seem to have been overthrown by the early Arab invaders of Sind in the 8th century.

Long struggle against Scythic invaders, 57 B.C. to 544 A.D. The relations of these three Indian dynasties, the Senas, Guptas, and Valabhîs, to the successive hordes of Scythians, who poured down on Northern India, are obscure. There is abundant evidence of a long-continued struggle, but the efforts to affix dates to its chief episodes have not yet produced results which can be accepted as final. Two Vikramâditya Sakâris, or vanquishers of the Scythians, are required for the purposes of chronology; and the great battle of Korûr near Mûltân, in which the Scythian hosts perished, has been shifted backwards and forwards from 78 to 544 A.D.⁵

The truth seems to be that, during the first six centuries of the Christian era, the fortunes of the Scythian or Tartar races rose and fell from time to time in Northern India. They more than once sustained great defeats; and they more than once overthrew the native dynasties. Their presence is popularly

¹ By Mr. Newton. See Mr. E. Thomas on the Coins of the Sâh Kings, *Archæol. Rep. Western India*, p. 44 (1876); and Dr. J. Fergusson, *Journal Roy. As. Soc.*, 1880.

² Now a town of only 16,646 inhabitants in Farukhâbâd District, but with ruins extending over a semicircle of 4 miles in diameter.

³ Lât-deshâ, including the collectorates of SURAT, BROACH, KAIRA, and parts of BARODA territory.

⁴ The genealogy is worked out in detail by Mr. E. Thomas, *ut supra*, pp. 80-82.

⁵ 78 A.D. was the popularly received date, commemorated by the Sâka era; 'between 524 and 544 A.D.' is suggested by Dr. Fergusson (p. 284 of *Journal Roy. As. Soc.*, vol. xii.) in 1880.

attested during the century before Christ by Vikramaditya (571 C ?), during the 1st century after Christ, it is represented by the Kanishka family (2 B.C. to 87 A.D.), it was noted by Cosmas Indicopleustes, about 535 A.D.

A recent writer on the subject¹ believes that it was the white Huns who overthrew the Guptas between 465 and 470 A.D. He places the great battles of Korur and Mraushari, which 'freed India from the Sakas and Hunas,' between 524 and 544 A.D. But these dates still lie in the domain of inductive, indeed almost of conjectural, history. Cosmas Indicopleustes, who traded in the Red Sea about 535 A.D., speaks of the Huns as a powerful nation in Northern India in his days.²

While Greek and Scythic influences had thus been at work in Northern India during nine centuries (327 B.C. to 544 A.D.), another (so-called indigenous) element was profoundly affecting the future of the Indian people. A previous chapter has traced the fortunes, and sketched the present condition, of the pre-Aryan 'aborigines.' The Bráhmínical Aryans never accomplished a complete subjugation of these earlier races. The tribes and castes of non-Aryan origin numbered in 1872 about 18 millions in British territory, while the castes who claim a pure Aryan descent are under 16 millions.³ The pre-Aryans have influenced the popular dialects of every Province, and in Southern India they still give their speech to 28 millions of people.

The Vedic settlements along the five rivers of the Punjab were merely colonies or confederacies of Aryan tribes, who had pushed in among a non-Aryan population. When an Aryan family advanced to a new territory, it had often, as in the case of the Pándava brethren, to clear the forest and drive out the aboriginal people. This double process constantly repeated itself, and as late as 1657, when the Hindu Rájá founded the present city of BAREILLY, his first work was to cut down the jungle and expel the old Katheriyas. The ancient Bráhmínical kingdoms of the Middle Land (*Madhya desha*), in the North-Western Provinces and Oudh, were surrounded by non-Aryan tribes. All the legendary advances beyond the northern centre of Aryan civilisation, narrated in the epic poets, were made into

¹ Dr J. Fergusson, *Journal Roy. As. Soc.*, pp. 282-284 etc. (1880)

² *Tof.ographia Christiani*, lib. xi. p. 338, *apud* Fergusson, *ut supra*

³ This latter number included both Brahmins (10 574 444) and Kshattriyas and Kájpús (5 240 495). But, as we have just seen, some of the Kájpút tribes are believed to be of Scythic origin, while others have been incorporated from confessedly non-Aryan tribes (*vide ante* p. 91). Such non-Aryan Kájpúts more than outnumber any survivals of the Vaisyas of pure Aryan descent.

the territory of non-Aryan races. When we begin to catch historical glimpses of India, we find the countries even around the northern Aryan centre ruled by non-Aryan princes. The Nandas, whom Chandra Gupta succeeded in Behar, appear as a Súdra or non-Aryan dynasty; and according to one account, Chandra Gupta and his grandson Asoka came of the same stock.¹

Pre-Aryan kingdoms in Northern India.

The Buddhist religion did much to incorporate the pre-Aryan tribes into the Indian polity. During the long struggle of the Indo-Aryans against Græco-Bactrian and Scythian inroads (627 B.C. to 544 A.D.), the Indian aboriginal races must have had an increasing importance, whether as enemies or allies. At the end of that struggle, we discover them ruling in some of the fairest tracts of Northern India. In almost every District throughout Oudh and the North-Western Provinces, ruined towns and forts are ascribed to aboriginal races who ruled at different periods, according to the local legends, between the 5th and 11th centuries A.D. When the Muhammadan conquest supplies a firmer historical footing, after 1000 A.D., non-Aryan tribes were still in possession of several of these Districts, and had only been lately ousted from others.

The Takshaks of Ráwal Píndi District.

The Statistical Survey of India has brought together many survivals of these obscure races. It is impossible to follow that survey through each locality; the following paragraphs indicate, with the utmost brevity, a few of the results. Starting from the West, Alexander the Great found RAWAL PÍNDI District in the hands of the Takkas or Takshaks, from whom its Greek name of Taxila was derived. This people has been traced to a Scythian migration about the 6th century B.C.² Their settlements in the 4th century B.C. seem to have extended from the Paropamisan range³ in Afghánistán to deep into Northern India. Their Punjab capital, Takshásila, or Taxila, was the largest city which Alexander met with between the Indus and the Jehlam (327 B.C.).⁴ Salihávana, from whom the Sákā

The Takshaks. Sixth Century B.C.; 327 B.C.

¹ The *Mudrá-rākshasa* represents Chandra Gupta as related to the last of the Nandas; the Commentator of the *Vishnu Purāna* says he was the son of a Nanda by a low-caste woman. Prof. Dowson's *Dict. Hindu Mythology*, etc., p. 68 (Trübner, 1879).

² Such dates have no pretension to be anything more than intelligent conjectures based on very inadequate evidence. With regard to the Takshaks, see Colonel Tod and the authorities which he quotes, *Rājasthán*, vol. i. p. 53 *passim*, pp. 93 *et seq.* (Madras Reprint, 1873).

³ Where Alexander found them as the *Paræ-takæ* — *pahari* or Hill Takæ(?).

⁴ Arrian. The Bráhmaṇ mythologists, of course, produce an Aryan pedigree for so important a person as King Taksha, and make him the son of Bharata and nephew of Ráma-chandra.

or Scythian era took its commencement (78 A D), is held by some authorities to have been of Takshak descent¹ In the 7th century A D, Takī,² perhaps derived from the same race, was the capital of the Punjab The Scythic Takshaks, indeed, are supposed to have been the source of the great Serpent Race, the Takshakas or Nagas, who figure so prominently in Sanskrit literature and art, and whose name is still borne by the Nāga tribes of our own day The Takkas remaining to the present time are found only in the Districts of Delhi and Karnal They number 14,305, of whom about three fourths have adopted the faith of Islām

The words Nāgā and Takshaka in Sanskrit both mean a 'snake,' or tailed monster As the Takshakas have been questionably connected with the Scythian Takkas, so the Nāgās have been derived, by conjecture in the absence of evidence, from the Tartar patriarch Nagas, the second son of Elkhan³ Both the terms, Nagas and Takshakas, seem to have been loosely applied by the Sanskrit writers to a variety of non Aryan peoples in India, whose religion was of an anti Aryan type We learn, for example, how the five Pāndava brethren of the Mahabharata burned out the snake king Takshaka from his primeval Khāndava forest The Takshaks and Nāgās were the tree and serpent worshippers, whose rites and objects of adoration have impressed themselves deeply on the architecture and sculptures of India They included, in a confused manner, several different races of Scythic origin

The chief authority on Tree and Serpent Worship in India has deliberately selected the term 'Scythian' for the anti Aryan elements, which entered so largely into the Indian religions both in ancient and in modern times⁴ The Chinese records give a full account of the Nāga geography of ancient India The Nāgā kingdoms were both numerous and powerful, and Buddhism derived many of its royal converts from them The

¹ Tod, *Asiatic Researches*, vol. 1, p. 95 (ed. 1873)

² Takī or Asarur, 45 miles west of Lahore General Cunningham, *Asiatic Researches*, p. 191, and Map vi (ed. 1871) This Takī lies however, considerably to the south east of the Takshasila of Alexander's expedition

³ Tod, *Asiatic Researches*, vol. 1, p. 53 (ed. 1873), a very doubtful authority

⁴ Dr J. Ferguson's *Tree and Serpent Worship*, pp. 71, 72 (India Museum, 4to, 1865) For the results of more recent local research see Mr. K. C. S. Carnac's papers in the *Journal of the Asiatic Society of Bengal*, 'The Snake Symbol in India,' 'Ancient Sculpturings on Rocks,' 'Stone Carvings at Maijūnāgarī,' etc., the Honourable Rao Sahib Vishvarāks Narayan Mandlik's 'Serpent Worship in Western India,' and other essays in the *Pentagon Asiatic Journal*, also, *Lectures of Archaeology at Surgh*, Western

become
the
Dragon-
races of
China.

Chinese chroniclers, indeed, classify the Nágá princes of India into two great divisions, as Buddhists and non-Buddhists. The serpent-worship, which formed so typical a characteristic of the Indo-Scythic races, led the Chinese to confound those tribes with the objects of their adorations; and the fierce Indo-Scythic Nágás would almost seem to be the originals of the Dragon races of Chinese Buddhism and Chinese art. The compromises to which Buddhism submitted, with a view to winning the support of the Nágá peoples, will be referred to in the following chapter, on the Rise of Hinduism.

The
Ghakkars
of Ráwal
Pindi,
1008-1857
A.D.

As the Greek invaders found Ráwal Pindi District in possession of a Scythic race of Takkas in 327 B.C., so the Musalmán conqueror found it inhabited by a fierce non-Aryan race of Ghakkars thirteen hundred years later. The Ghakkars for a time imperilled the safety of Mahmúd of Ghazní in 1008. Farishta describes them as savages, addicted to polyandry and infanticide. The tide of Muhammadan conquest rolled on, but the Ghakkars remained in possession of their sub-Himálayan tract.¹ In 1205 they ravaged the Punjab to the gates of Lahore; in 1206 they stabbed the Muhammadan Sultán in his tent; and in spite of conversion to Islám by the sword, it was not till 1525 that they made their submission to the Emperor Bábar in return for a grant of territory. During the next two centuries they rendered great services to the Mughal dynasty against the Afghán usurpers, and rose to high influence in the Punjab. Driven from the plains by the Sikhs in 1765 A.D., the Ghakkar chiefs maintained their independence in the Murree (Marri) Hills till 1830, when they were crushed after a bloody struggle. In 1849, Ráwal Pindi passed, with the rest of the Sikh territories, under British rule. But the Ghakkars revolted four years afterwards, and threatened Murree, the summer capital of the Punjab, as lately as 1857. The Ghakkars are now found in the Punjab Districts of Ráwal Pindi, Jehlam, and Hazára. Their total number was returned at 25,789 in 1881. They are described by their British officers as 'a fine spirited race, gentlemen in ancestry and bearing, and clinging under all reverses to the traditions of noble blood.'²

Pre-
Aryans of
Bareilly
District.

The population of Ráwal Pindi District has been selected to illustrate the long-continued presence and vitality of the pre-Aryan element in India. Other parts of the country must be

¹ For a summary of their later history, see article on RAWAL PINDI DISTRICT, *The Imperial Gazetteer of India*.

² *The Imperial Gazetteer of India*, article RAWAL PINDI DISTRICT.

more briefly deal with. Proceeding westward into the North Western Provinces, we everywhere find traces of an early Buddhist civilisation in contact with, or overthrown by, rude non-Aryan tribes. In Bareilly District, for example, the wild Ahirs from the north, the Dail from the south and the Bhars from the east, seem to have expelled highly-civilised Aryan communities at some period before 1000 A.D. Still further to the east, all remains of prehistoric masonry in Oudh and the North Western Provinces are ascribed to the ancient Bhars or to a non-Aryan race of Bhars.

The Bhars appear to have possessed the whole Gangetic The Bhars plains in the centuries coeval with the fall of Buddhism in Oudh. Their kingdoms extended over most of Oudh. lofty mounds covered with ancient groves mark the sites of their former cities, and they are the mysterious 'fort-builders' to whom the peasantry ascribe any ruin of unusual size. In the central valley of the Ganges, their power is said to have been crushed by the Shaka dynasty of Jaunpur in the end In Jaun of the 14th century. In the Districts north of the Gangetic plain, the Bhars figure still more prominently in local traditions, and an attempt has been made to trace their continuous history. In GORAKHPUR DISTRICT, the aboriginal In Gorakhpur Tharus and Bhars seem to have overwhelmed the early outposts of Aryan civilisation several centuries before Christ. Their appearance on the scene is connected with the rise of Buddhism. They became vassals of the Buddhist kingdom of Behar on the south-east, and on the fall of that power, about 550 A.D., they regained their independence. The Chinese pilgrim in the 7th century comments in this region on the large number of monasteries and towers—the latter probably a monument of the struggle with the aboriginal Bhars, who were here finally crushed between the 7th and the 10th centuries A.D. In 1881, the total Bhar population of Oudh and the North Western Provinces numbered 349,113.

As we advance still farther eastwards into Bengal, we find that the non-Aryan races have within historical time supplied a large part of the Hindu population. In the north, the Koch The Koch established their dominion upon the ruins of the Aryan of Northern Kingdom of Kamrup, which the Afghan King of Bengal had Bengal destroyed in 1489. The Koch gave their name to the name Sate of KOCH BEHAR, and their descendants, together In Koch with those of other non-Aryan tribes, form the mass of the Behar people in the neighbouring British Districts, such as RANGPUR. In Rang In 1871, they numbered 1½ million in Northern Bengal and pur

Kuch
Behar
Rájás.

Behar. One part of them got rid of their low origin by becoming Musalmáns, and thus obtained the social equality which Islám grants to all mankind. The rest have merged more or less imperfectly into the Hindu population; and about three-quarters of a million of them claim, in virtue of their position as an old dominant race, to belong to the Kshattriya caste. They call themselves Rájbansís, a term exactly corresponding to the Rájputs of Western India. The Hinduized Rájás of Kuch Behar obtained for their ancestors a divine origin from their Bráhmaṇ genealogists, in order to efface their aboriginal descent; and among the nobility all mention of the Koch tribe was avoided. The present Mahárájá married the daughter of the celebrated theistic apostle, Keshab Chandra Sen, the leader of the Brahmo Samáj. He is an honorary major in the British army, and takes a prominent part in Calcutta and Simla society.

Ahams of
Assam.

Proceeding still eastwards, the adjacent valley of Assam was, until the last century, the seat of another non-Aryan ruling race. The Ahams entered Assam from the south-east about 1350 (?) A.D.; had firmly established their power in 1663; gradually yielded to Hinduism; and were overpowered by fresh Buddhist invasions from Burma between 1750 and 1825, when the valley was annexed to British India. The Ahams have been completely crushed as a dominant race; and their old national priests, to the number of 253,860, have been forced to become tillers of the soil for a living. But the people of Assam are still so essentially made up of aboriginal races and their Hinduized descendants, that not 130,000 persons of even alleged pure Aryan descent can be found in a population exceeding $4\frac{3}{4}$ millions.¹

Pic-
Aryan
element
south of
the
Ganges.

Aborigines
in Central
India;

The foregoing summary has been confined to races north of the Ganges. Passing to the southern Gangetic plain, we find that almost every tract has traditions of a pre-Aryan tribe, either as a once-dominant race or as lying at the root of the local population. The great Division of Bundelkhand contains several crushed peoples of this class, and takes its name from the Bundelas, a tribe of at least semi-aboriginal descent.

¹ The Bráhmans in Assam number only 119,075 (being fewer than the Kalitás or old priests of the Ahams, 253,860), out of a total population in Assam of 4,881,426; while the Koch alone number about 230,382, and even the crushed Ahams 179,314. For further particulars regarding these races, see *The Imperial Gazetteer of India*, article ASSAM.

As we rise from the Gangetic plains into the highlands of the Central Provinces, we reach the abiding home of the non Aryan tribes. One such race after another—Gauls, Nāgis, Gonds, Ahīrs, Bhīls—ruled from the Sātpura plateau.¹ Some of their chiefs and leading families now claim to be Kshatriyas, and a section of one of the lowest races, the Chauhāns, borrowed their name from the noble 'Chauhān Rājputs.

In the Lower Provinces of Bengal, we find the delta in Lower Bengal peopled by masses of pre Aryan origin. One section of them has merged into low-class Hindus, another section has sought a more equal social organization by accepting the creed of Muhammad. But such changes of faith do not alter their ethnical type, and the Musalman of the delta differs as widely in race from the Afghān as the low-caste Hindu of the delta differs from the Brāhman. Throughout Southern India, the non Aryan elements form almost the entire population, and have supplied the great Dravidian family of languages, which are spoken by 28 millions of people. Two of our oldest and most faithful allies in the Madras Presidency, the enlightened dynasty of Travancore and the ancient princes of Pudukotta, are survivals of the time when non Aryan sovereigns ruled over Southern India.

The Scythic inroads, and the ancient Nāgā and so called Scythic aboriginal tribes, have, however, not merely left behind remnants of races in individual Districts. They have affected the character of the whole population, and profoundly influenced the religious beliefs and domestic institutions of India. In the Veda we see highly developed communities of the Aryan stock, worshipping bright and friendly gods, honouring woman, and assigning to her an important position in the family life. Husband and wife were the *Dampati*, or joint rulers of the Indo-Aryan household. Traditions of the freedom of woman among the ancient Aryan settlers survive in the *sakāntāna* or Maiden's Own Choice of a Husband, in the epic poems.

The curtain of Vedic and Post Vedic literature falls upon the scene before the 5th century B.C. When the curtain rises on the domestic and religious life of mediæval India, in the life of

¹ See CENTRAL PROVINCES. *The Imperial Gazetteer of India*. The Gauls are locally believed to have been earlier fort builders than the Gonds (see for example article SADOER), and some of the Gond chiefs trace their descent through 54 generations to a well recorded ancestor assigned to 91 A.D. (see *The Imperial Gazetteer of India*, article SARAYGHAN).

Puránas about the 10th century A.D., a vast change has taken place. The people are no longer sharply divided into civilised Aryans and rude non-Aryans, but into castes of a great mixed population. Their religion is no longer a worship of bright and friendly gods, but a composite product of Aryan spiritual conceptions and non-Aryan superstitions. The position of woman has also altered for the worse. Husband and wife are no longer 'joint rulers' of the household. The Maiden's Own Choice has fallen into disuse, or survived only as a Court pageant; the custom of child-marriage has grown up. The widow has been condemned to a life of privation, or has been taught the merit of extinguishing her existence on her husband's funeral pile.

The
appeal to
the Veda.

The following chapter will exhibit this amorphous growth, popularly known as Hinduism. Orthodox Hindus are unfortunately in the habit of claiming the authority of the Veda for their mediæval institutions, for the evil as well as for the good. As a matter of fact, these institutions are the joint product of non-Aryan darkness and of Aryan light. The Scythic, and Nágá, and so-called aboriginal races, with their indifference to human suffering, their polyandric households, and their worship of fear and blood, have left their mark deep in the Hindu law-codes, in the terrorizing of the Hindu religion, and in the degradation of woman. English scholarship has shown that the worst feature of Hinduism, widow-burning, had no authority in the Veda. When it is equally well understood that the darker features of Hinduism, as a whole, rest not upon the Vedic scriptures, but are the result of a human compromise with non-Aryan barbarism, the task of the Indian reformer will be half accomplished. It is with a true popular instinct that the great religious movements of India in our day reject the authority of mediæval Hinduism, and appeal back to the Veda.

CHAPTER VIII

RISE OF HINDUISM (750 TO 1520 A D)

FROM these diverse races, pre Aryan, Aryan, and Scythic, the population of India has been made up. The task of organizing them fell to the Bráhmans. That ancient caste, which had never quitted the scene even during the height of the Buddhistic supremacy, stepped forward to the front of the stage upon the decay of the Buddhist faith. The Chinese pilgrim, about 640 A D, had found Bráhmanism and Buddhism co existing throughout India. The conflict of creeds brought forth a great line of Bráhman apostles, from the 8th to the 16th century A D, with occasional successors down to our own day. The disintegration of Buddhism, as we have seen, occupied many hundred years, perhaps from 300 to 1000 A D¹

The Hindus take the 8th century as the turning point in the struggle. About 750 A D, arose a holy Bráhman of Bengal, Kumárla Bhatta by name, preaching the old Vedic doctrine of a personal Creator and God. Before this realistic theology, the impersonal abstractions of the Buddhists succumbed, and according to a later legend, the reformer wielded the sword of the flesh not less trenchantly than the weapons of the spirit. A Sanskrit writer, Madhava Achárya, of the 14th century A D, relates how Sudhanwan, a prince in Southern India, 'commanded his servants to put to death the old men and the children of the Buddhists, from the bridge of Ráma [the ridge of reefs which connects India with Ceylon] to the Snowy Mountain let him who slays not, be slain.'²

¹ From the language of the Saddharma Pundarika, translated into Chinese before the end of the 3rd century A D, H H Wilson infers that even at that early date 'the career of the Buddhists had not been one of uninterrupted success, although the opposition had not been such as to arrest their progress' (*Essays*, vol. II p 366, ed 1862). The existence of Buddhism in India is abundantly attested to 1000 A D.

² Quoted by H H Wilson, *ut supra*. See also Lassen's *Indische Alterthumskunde*, vol. II p 708, Colebrooke's *Essays*, p 190.

True value of the legend. It is needless to say that no sovereign existed at that time in India whose power to persecute extended from the Himálayas to Cape Comorin. So far as the legend has any truth, it refers to one of many local religious reprisals which took place at the Indian courts during the struggle between the Buddhists and the Bráhmans. Such reprisals recurred in later days, on a smaller scale, between the rival Hindu sects. The legend of Kumánila is significant, however, as placing on a religious basis the series of many-sided evolutions which resulted in Hinduism. These evolutions were the result of ethnical processes, more subtle than the scheming of any caste of men. The Bráhmans gave a direction to Hinduism, but it was the natural development of the Indian races which produced it.

Twofold basis of Hinduism ; caste and religion. Hinduism is a social organization and a religious confederacy. As a social organization, it rests upon caste, with its roots deep down in the ethnical elements of the Indian people. As a religious confederacy, it represents the coalition of the old Vedic faith of the Bráhmans with Buddhism on the one hand, and with the ruder rites of the pre-Aryan and Indo-Scythic races on the other.

Caste basis of Hinduism. The ethnical basis of caste is disclosed in the fourfold division of the people into the 'twice-born' Aryan castes, including the Bráhmans, Kshattriyas (Rájputs), and Vaisyas; and the 'once-born' non-Aryan Súdras. The Census proves that this classification remains the fundamental one to the present day.

The race-origin of caste. The three 'twice-born' castes still wear the sacred thread, and claim a joint, although an unequal, inheritance in the holy books of the Veda. The 'once-born' castes are still denied the sacred thread, and their initiation into the old religious literature of the Indo-Aryans has only been effected by the secular teaching of our Anglo-Indian schools. But while caste has thus its foundations deep in the distinctions of race, its superstructure is regulated by another system of division, based on the occupations of the people. The early classification of the people may be expressed either ethnically as 'twice-born' Aryans, and 'once-born' non-Aryans; or socially, as priests, warriors, husbandmen, and serfs. On these two principles of classification, according to race and to employment, still further modified by geographical position, has been built up the ethnical and social organization of Indian caste.

Modified by 'occupation' and 'locality.'

Complexity of caste.

From the resulting cross-divisions arises an excessive complexity, which renders any brief exposition of caste superficial. As a rule, it may be said that the Aryan or 'twice-born' castes adhere most closely to the ethnical principle of

division, the 'once born' or distinctly non Aryan to the same principle, but profoundly modified by the concurrent principle of employment, while the mixed progeny of the two are classified solely according to their occupation. But even among the Brāhmins, whose pride of race and continuity of tradition should render them the firmest ethnical unit among the Indian castes, classification by employment and by geographical situation plays a very important part and the Brāhmins, so far from being a compact unit are made up of several hundred castes, who cannot intermarry nor eat food cooked by each other. They follow every employment, from the calm *pandits* of Behar in their stainless white robes, and the haughty priests of Benares, to the potato growing Brāhmins of Orissa, 'half naked peasants, struggling along under their baskets of jams, with a filthy little Brāhmanical thread over their shoulder' ¹

Even the Brāhmins not an ethnical unit

In many parts of India, Brāhmins may be found earning their livelihood as porters, shepherds cultivators, potters, and fishermen, side by side with others who would rather starve and see their wives and little ones die of hunger, than demean themselves to manual labour or allow food prepared by a man of inferior caste to pass their lips. Classification by locality introduces another set of distinctions among the Brāhmins. In Lower Bengal jails a convict Brāhmin from Behar or the North Western Provinces used to be highly valued, as the only person who could prepare food for all classes of Brāhmin prisoners. In 1864 the author saw a Brāhmin felon try to starve himself to death and submit to a flogging rather than eat his food, on account of scruples as to whether the birthplace of the North Western Brāhmin who had cooked it, was equal in sanctity to his own native district. The Brāhmins are popularly divided into ten great septs, according to their locality, five on the north and five on the south of the Vindhya range. But the minor distinctions are innumerable. Thus, the first of the five northern Brāhmin septs, the

The Brāhmin caste analyzed

¹ See Hunter's *Orissa*, vol. 1 pp 238 et seq (ed. 1872) where 25 pages are devoted to the diversities of the Brāhmins in occupation and race. Also *Hindu Tribes and Castes* by the Rev M. A. Sherring, introd. xxi vol. II (40, Calcutta, 1879).

² Thus translated according to a Sanskrit mnemonic *Si' Li —*

1. The five Gauras north of the Vindhya range—

(1) The *Sikhar* *Li*, so called from the country watered by the river Sarawati.

(2) The *Admir* *Li*, so called from the Kanakak or Kanauco river.

Sáraswatas in the Punjab, consist of 469 classes.¹ Sherring enumerated 1886 separate Bráhmañical tribes.² Dr. Wilson, of Bombay, carried his learned work on Caste to the length of two volumes, aggregating 678 pages, before his death; but he had not completed his analysis of even a single caste—the Bráhmans.

The lower
castes still
more com-
plex.

It will be readily understood, therefore, how numerous are the sub-divisions, and how complex is the constitution, of the lower castes. The Rájputs now number 590 separately-named tribes in different parts of India.³ But a process of synthesis as well as of analysis has been going on among the Indian peoples. In many outlying Provinces, we see non-Aryan chiefs and warlike tribes turn into Aryan Rájputs before our eyes.⁴ Well-known legends have been handed down of large bodies of aliens being incorporated from time to time even into the Bráhmañ caste.⁵ But besides these 'manufactured Bráhmans,' and the ethnical syncretisms which they represent, there has been a steady process of amalgamation among the Hindus by mixed marriage.⁶ The Súdras, says Mr. Sherring, 'display a great intermingling of races. Every caste exhibits this confusion. They form a living and practical testimony to the fact that in former times the upper and lower classes of native society, by which I

The build-
ing up of
castes.

(3) The *Gauras* proper, so called from Gaur, or the country of the Lower Ganges.

(4) The *Utkalas*, of the Province of Utkala or Odra (Orissa).

(5) The *Maithilas*, of the Province of Mithila (Tirhut).

II. The five Dravidas south of the Vindhya range—

(1) The *Maháráshtras*, of the country of the Maráthí language.

(2) The *Andhras* or *Tailanjas*, of the country of the Telugu language.

(3) The *Dravidas* proper, of the country of the Dravidian or Tamil language.

(4) The *Karnátas*, of the Karnátika, or the country of the Canarese language.

(5) The *Gurjaras*, of Gurjaráshtra, or the country of the Gujáráti language.

¹ Compiled by Pandit Rádhá Krishna, quoted by Dr. J. Wilson, *Indian Caste*, part ii. pp. 126-133.

² *Hindu Tribes and Castes*, pp. xxii.-xlvi. vol. ii. (4to, Calcutta, 1879).

³ See Sherring, *Hindu Tribes and Castes*, vol. ii. pp. lv.-lxv.

⁴ See Sherring, *Hindu Tribes and Castes*, vol. ii. p. lxvii.

⁵ Hunter's *Orissa*, vol. i. p. 247 (in Oudh), p. 248 (in Bhágalpur), p. 254 (in Malabar), etc.

⁶ See two interesting articles from opposite points of view, on the synthetic aspects of caste, by the Rev. Mr. Sherring, of Benares, and by Jogendra Chandia Ghose, in the *Calcutta Review*, Oct. 1880.

mean the Hindu and non Hindu population of India, formed alliances with one another on a prodigious scale, and that the offspring of these alliances were in many instances gathered together into separate castes and denominated Sudras¹

The Hindu custom now forbids marriage between (1) persons of the same *gotra* or kindred, and (2) persons of different castes. But this precise double rule has been arrived at only after many intermediate experiments in endogamous and exogamous tribal life. The transitions are typified by the polyandry of Draupadi in the *Mahābhārata*, and by many caste customs relating to marriage, inheritance, and the family tie, which survive to this day. Such survivals constitute an important branch of law, in fact, the domestic 'common law' of India² and furnish one of the chief difficulties in the way of Anglo-Indian codification. Thus, to take a single point, the rules regarding marriage exhibit every phase from the compulsory polyandry of the old Nairs, the permissive polyandry of the Punjab Jāts, and the condonement of adultery with a husband's brother or kinsman among the Karakat Vellāls of Madura, to the law of Levirate among the Ahīrs and Nūmīyas, the legal re-marriage of widows among the low caste Hindus, and the stringent provisions against such re-marriages among the higher castes. At this day, the Nairs exhibit several of the stages in the advance from polyandric to monogamous institutions. The conflict between polyandry and the more civilised marriage system of the Hindus is going on before our eyes in Malabar. Among the Kōils, although polyandry is forgotten, the right of disposing of a girl in marriage still belongs, in certain cases to the *maternal* uncle,—a relic of the polyandric system of succession through females. This tribe also preserves the form of marriage by 'capture'.

The slow development of Hindu marriage law

Survivals of the process

The *Brahmanas* indicate that the blood of the Hindus was, even in the early post Vedic period greatly intermingled. The ancient marriage code recognised as lawful, unions of men of higher caste with females from any of the lower ones and their offspring³ had a quite different social status from

Ancient mingling of castes

¹ *Calcutta Review*, vol. p. 275

² Among many treatises on this subject, Arthur Steele's *Law and Custom of Hindu Castes* (1868) deals with Western India. Nelson's *Law of Hindu Law* (1877) and Burnell's *Digest* etc. may be quoted for the Madras Presidency, Beames a admirable edition of Sir Henry Elliot's *Treatise of the North Western Provinces*, and Sherring's *Hindu Treatises* (besides more strictly legal treatises) for Bengal.

³ The *Tuṣṭirīya Prāśnāra* of the Kṛishṇa Yajur Veda (quoted by Dr J. Wilson, *Castes*, p. 127-132) enumerates 159 castes. ⁴ *Asiatic*

the progeny¹ of illicit concubinage. The laws of Manu disclose how widely such connections had influenced the structure of Indian society 2000 years ago; and the Census proves that the mixed castes still form the great body of the Hindu population. In dealing with Indian caste, we must therefore allow, not only for the ethnical and geographical elements into which it is resolvable, but also for the synthetic processes by which it has been built up.

The 'occupation' basis of caste.

Changes of 'occupation' by castes.

The Vaisyas.

Goldsmiths of Madras.

The same remark applies to the other principle of classification on which caste rests, namely, according to the employments of the people. On the one hand, there has been a tendency to erect every separate employment in each separate Province into a distinct caste. On the other hand, there has been a practice (which European observers are apt to overlook) of the lower castes changing their occupation, and in some cases deliberately raising themselves in the social scale. Thus the Vaisya caste, literally the *vis* or general body of the Aryan settlers, were in ancient times the tillers of the soil. They have abandoned this laborious occupation to the Súdra and mixed castes, and are now the merchants and bankers of India. 'Fair in complexion,' writes the most accurate of recent students of caste,² 'with rather delicate features, and a certain refinement depicted on their countenances, sharp of eye, intelligent of face, and polite of bearing,' the Vaisyas 'must have radically changed since the days when their forefathers delved, sowed, and reaped.' Indeed, so great is the change, that a heated controversy is going on in Hindu society as to whether the Bengali *baníyás*, or merchant-bankers, are really of Vaisya descent or of a higher origin.

Such a rise in the social scale is usually the unconscious work of time, but there are also legends of distinct acts of self-assertion by individual castes. In Southern India, the goldsmiths strenuously resisted the rule of the Bráhmans, and for ages claimed to be the true spiritual guides, styling themselves *áčhárýas*, 'religious teachers,' and wearing the sacred thread. Their pretensions are supposed to have given rise to the great division of castes in Madras, into the 'Right-hand,' or the cultivating and trading castes who supported the Bráhmans;

¹ *Pratiloma*. For an arrangement of 134 Indian castes, according to their origin, or 'procession' from (1) regular full marriage by members of the same caste, (2) *anuloma*, (3) *pratiloma*, (4) *Vrátya-Santati*, (5) adultery, (6) incest, (7) degeneration; Wilson, *Indian Caste*, ii. pp. 39-70.

² The Rev. M. A. Sherring (deceased, alas, since the above was written, after a life of noble devotion and self-sacrifice to the Indian people), *Calcutta Review*, October 1880, p. 220.

and the 'Left hand,' chiefly craftsmen who sided with the artisan opposition to Brāhman supremacy ¹

In Bengal, a similar opposition came from the literary class The Dattas, a sept of the Kāyasth or writer caste, re-nounced the position assigned to them in the classification of Hindu society. They claimed to rank next to the Brahmans, and thus above all the other castes. They failed, but a native author² states that one of their body, within the memory of men still living maintained his title, and wore the sacred thread of the pure 'twice born.' The Statistical Survey of India has disclosed many self assertions of this sort, although of a more gradual character and on a smaller scale. Thus, in Eastern Bengal where land is plentiful, the Shahs, a section of the Suris or degraded spirit sellers, have, in our own time, advanced themselves first into a respectable cultivating caste, and then into prosperous traders. Some of the Telis or oil pressers in Dacca District and certain of the Iāmbulls or *pīn* growers in Rangpur have in like manner risen above their hereditary callings and become bankers and grain merchants. These examples do not include the general opening of professions, effected by English education—the great solvent of caste.

The Dattas of Bengal

The Shahs

Teli Tambuls etc

There is therefore a plasticity as well as a rigidity in caste. Its plasticity has enabled caste to adapt itself to widely separated stages of social progress, and to incorporate the various ethnical elements which make up the Indian people. Its rigidity has given strength and permanence to the corporate body thus formed. Hinduism is internally loosely coherent, but it has great powers of resistance to external pressure. Each caste is to some extent a trade-guild, a mutual assurance society, and a religious sect. As a trade union, it insists on the proper training of the youth of its craft, regulates the wages of its members, deals with trade delinquents, and promotes good fellowship by social gatherings. The famous fabrics of medieval India, and the chief local industries in our own day, were developed under the supervision of caste or trade guilds of this sort. Such guilds may still be found in many parts of India, but not always with the same complete development ³.

Plasticity and rigidity in caste

Caste as a system of trade guilds.

¹ This subject is involved in much obscurity. The above sentences embody the explanation given in Nelson's *Life of the Hindu Law as administered by the Court of Madras* p. 140 (Madras 1877).

² Jyotindra Chandra Ghose *Civilization in India* vol. i p. 279 (Oxford 1890).

³ The *Statistical Account of the Districts of the Bombay Presidency* devoted a special section to such trade guilds in every District.

Its regulation of wages. In AHMADABAD DISTRICT¹ each trade forms a separate guild. All heads of artisan households are ranged under their proper guild. The objects of the guild are to regulate competition among the members, and to uphold the interest of the body in disputes with other craftsmen. To moderate competition, the guild appoints certain days as trade holidays, when any member who works is punished by a fine. A special case occurred in 1873 among the Ahmadábád bricklayers. Men of this class sometimes added 3d. to their daily wages by working extra time in the early morning. But several families were thereby thrown out of employment. Accordingly the guild met, and decided that as there was not employment for all, no man should be allowed to work extra time.

Working of the trade-guild. The decisions of the guild are enforced by fines. If the offender refuses to pay, and the members of the guild all belong to one caste, the offender is put out of caste. If the guild contains men of different castes, the guild uses its influence with other guilds to prevent the recusant member from getting work. The guild also acts in its corporate capacity against other crafts. For example, in 1872, the Ahmadábád cloth-dealers resolved among themselves to reduce the rates paid to the sizers or *tágíás*. The sizers' guild refused to prepare cloth at the lower rates, and remained six weeks on strike. At length a compromise was arrived at, and both guilds signed a stamped agreement.

An Indian 'strike.'

Besides its punitive fines, the guild draws an income from fees levied on persons beginning to practise its craft. This custom prevails at Ahmadábád in the cloth and other industries. But no fee is paid by potters, carpenters, and inferior artisans. An exception is made, too, in the case of a son succeeding to his father, when nothing need be paid. In other cases, the amount varies, in proportion to the importance of the trade, from £5 to £50. The revenue from these fees and from punitive fines is expended in feasts to the members of the guild, in the support of poor craftsmen or their orphans, and in charity. A favourite device for raising money in Surat is for the members of a trade to agree to keep a certain date as a holiday, and to shut up all their shops except one. The right to keep open this one shop is let by auction, and the amount bid is credited to the guild-fund.

Guild funds.

Guild charities.

Trade-interests of caste : Within the guild, the interests of the common trade often supersede the race element of the theoretically common caste. Thus, in Surat, each class of craftsmen, although including men

¹ See the article, *The Imperial Gazetteer of India*.

of different castes and races, combine to form a guild, with a council, a head-man, and a common purse for charity and entertainments. In Ahmadâbâd, Broach, and many industrial centres, the trade organization into guilds co exists with, or dominates, the race structure of caste. A twofold organization also appears in the village community. Caste regulates the theoretical position of every family within it, but the low-castes often claim the headship in the village government.

In Bârdâsat Sub district in Bengal, of 5818 enumerated Village Heads, only 15 were Brahmans or Rajputs, 4 were Kâjasths, while 3524 belonged to the Sudra or inferior castes, down to the detested cow skimmers and corpse bearers, the residue being Muhammadans, with 13 native Christians. In Southern India, the Village Head is sometimes of so low a caste that he cannot sit under the same roof with his colleagues in the village government. He therefore hands up his staff, which is set in the place of honour, while he himself squats on the ground outside. The trade-guild in the cities, and the village community throughout the country, act, together with caste, as mutual assurance societies, and under normal conditions allow none of their members to starve. Caste, and the trading or agricultural guilds concurrent with it, take the place of a poor-law in India.

It is obvious that such an organization must have some weapons for defending itself against lazy or unworthy members. The responsibility which the caste discharges with regard to feeding its poor, would otherwise be liable to abuses. As a matter of fact, the caste or guild exercises a surveillance over each of its members, from the close of childhood until death. If a man behaves well, he will rise to an honoured place in his caste; and the desire for such local distinctions exercises an important influence in the life of a Hindu. But the caste has its punishments as well as its rewards. Those punishments consist of fine and excommunication. The fine usually takes the form of a compulsory feast to the male members of the caste. This is the ordinary means of purification, or of making amends for breaches of the caste code.

Excommunication inflicts three penalties: First, an interdict against eating with the fellow members of the caste. Second, an interdict against marriage within the caste. This practically amounts to debarring the delinquent and his family from respectable marriages of any sort. Third, cutting off the delinquent from the general community, by forbidding him the use of the village barber and washerman, and of the

priestly adviser. Except in very serious cases, excommunication is withdrawn upon the submission of the offender, and his payment of a fine. Anglo-Indian law does not enforce caste-decrees. But caste punishments exercise an efficacious restraint upon unworthy members of the community, precisely as caste rewards supply a powerful motive of action to good ones. A member who cannot be controlled by this mixed discipline of punishment and reward is eventually expelled; and, as a rule, an 'out-caste' is really a bad man. Imprisonment in jail carries with it that penalty; but may be condoned after release, by heavy expiations.

Recapitulation of caste.

Such is a brief survey of the nature and operation of caste. But the cross-divisions on which the institution rests; its conflicting principles of classification according to race, employment, and locality; the influence of Islám in Northern India; of the 'right-handed' and 'left-handed' branches in the South;¹ and the modifications everywhere effected by social or sectarian movements, render a short account of caste full of difficulties.

The religious basis of Hinduism.

Hinduism is, however, not only a social organization resting upon caste; it is also a religious federation based upon worship. As the various race elements of the Indian people have been welded into caste, so the simple old beliefs of the Veda, the mild doctrines of Buddha, and the fierce rites of the non-Aryan tribes have been thrown into the melting-pot, and poured out thence as a mixture of alloy and dross to be worked up into the Hindu gods. In the religious as in the social structure, the Bráhmans supplied the directing brain-power. But both processes resulted from laws of human evolution, deeper than the workings of any individual will; and in both, the product has been, not an artificial manufacture, but a natural development. Hinduism merely forms one link in the golden chain of Indian religions. We have seen that the career of Buddha was but a combination of the ascetic and the heroic Aryan life as recorded in the Indian epics. Indeed, the discipline of the Buddhists organized so faithfully the prescribed stages of a Bráhman's existence, that it is difficult to decide whether the *Sarmanai* of Megasthenes were Buddhist clergy or Bráhman recluses. If accurate scholarship cannot accept Buddhism as simply the Sánkhyā philosophy turned into a national religion, it admits that Buddhism is a natural development from Bráhmanism. An early set of

Its stages of evolution.

¹ See Crole's *Statistical Account of Chingleput District*, pp. 33, 34 (1879).

intermediate links is found in the *darsanas*, or philosophical systems, between the Vedic period and the establishment of Buddhism as a national religion under Asoka (1400? to 250 B.C.) A later set is preserved in the compromises effected during the final struggle between Buddhism and Bráhmānism, ending in the re-assertion of the latter in its new form as the religion of the Hindus (700 to 1000 A.D.)

Buddhism not only breathed into the new birth its noble spirit of charity, but bequeathed to Hinduism many of its institutions unimpaired, together with its scheme of religious life, and the material fabric of its worship. At this day, the *mahájān* or bankers guild, in Surat, devotes part of the fees that it levies on bills of exchange to animal hospitals, true survivals of Asoka's second edict, which provided a system of medical aid for beasts, 250 years before Christ. The cenobitic life, and the division of the people into laity and clergy, have passed almost unchanged from Buddhism into the present Hindu sects, such as the Vaishnavs or Vishnuites.

The Hindu monasteries in our own day vie with the Buddhist convents in the reign of Śīlāditya, and Puri is, in many respects, a modern unlettered Nalanda. The religious houses of the Orissa delta, with their revenue of £50,000 a year,¹ are but Hindu developments of the Buddhist cells and rock monasteries, whose remains still honeycomb the adjacent hills.

If we examine the religious life of the Vishnuite communities, we find their rules are Buddhistic, with Bráhmānical reasons attached. Thus the moral code of the Kabír panthis consists of five rules.² First, life, whether of man or beast, must not be violated, because it is the gift of God. Second, humanity is the cardinal virtue, and the shedding of blood, whether of man or beast, a heinous crime. Third, truth is the great principle of conduct, because all the ills of life and ignorance of God are due to original falsehood (*māyā*). Fourth, retirement from the world is desirable, because the desires of the world are hostile to tranquillity of soul, and to the undisturbed meditation on God. Fifth, obedience to the spiritual guide is incumbent on all. This last rule is common to every sect of the Hindus. But the Kabír panthis direct the pupil to examine well his teacher's life and doctrine before

¹ Report by the Committee of native cattle on 11 Oct. 1862, presented to the Orisá *prathak*, dated 25th March 1869, par. 15.

² H. H. Wilson's *Adigraha of the Hindus*, vol. 1, p. 246, 1862.

he resigns himself to his control. If we did not know that Buddhism was itself an outgrowth from primitive Bráhmaism, we might hold this code to be simple Buddhism, with the addition of a personal God. But knowing, as we do, that Bráhmaism and Buddhism were themselves closely connected, and that they combined to form Hinduism; it is impossible to discriminate how far Hinduism was made up by direct transmission from Buddhism or from Bráhmaism.

Buddhist influences on later religions.

Serpent ornamentation :

In Hinduism ;

In Buddhism ;

In Christian art.

Coalition of Buddhism with earlier religions :

The influence of Buddhism on the Christianity of the western world has been referred to at p. 152. Whatever uncertainties may still obscure that question, the effect of Buddhism upon the present faiths of Eastern Asia admits of no doubt. The best elements in the teaching of Buddha have survived in modern Hinduism; and Buddhism carried with it essential doctrines of Bráhmaism to China and Japan, together with certain characteristics of Indian religious art. The snake ornamentation, which figures so universally in the religion of India, is said to have been carried by Buddhism alike to the east and the west. Thus, the canopy or baldachino over Buddha's head delights in twisted pillars and wavy patterns. These wave-like ornaments are conventionalized into cloud curves in most of the Chinese and Japanese canopies; but some of them still exhibit the original figures thus symbolized as undulating serpents or Nágas. A serpent baldachino of this sort may be seen in a monastery at Ningpo.¹ It takes the place of the cobra-headed canopy, which in India shelters the head of Siva, or of Vishnu as he slept upon the waters at the creation of the world. The twisted columns which support the baldachino at St. Peter's in Rome, and the fluted ornamentation so common over Protestant pulpits, are said to have a serpentine origin, and an eastern source. The association of Buddha with two other figures, in the Japanese temples, perhaps represents a recollection of the Bráhma triad. The Bráhmaical idea of trinity, in its Buddhist development as Buddha, Dharma (the Law), and Sangha (the Congregation), deeply penetrates the faith. The Sacred Tooth of Buddha at Ceylon is a reproduction of the phallic *linga* of India.

Buddhism readily coalesced with the pre-existing religions of primitive races. Thus, among the hill tribes of Eastern Bengal, we see the Khyaungthas, or 'Children of the River,'

¹ The authority for this statement is an unpublished drawing by Miss Gordon Cumming.

passing into Buddhists without giving up their aboriginal rites. In India They still offer rice and fruits and flowers to the spirits of hill and stream,¹ and the Buddhist priests, although condemning the custom as unorthodox, do not very violently oppose it. In Japan, a Buddhist saint visited the hill slope of Hotoke Iwa in 767 A.D., declared the local Shinto deity to be only a manifestation of Buddha, and so converted the old idolatrous high place into a Buddhist shrine. Buddhism has thus served as a link between the ancient faiths of India and the modern worship of the eastern world. It has given sanctity to the centres of common pilgrimage to which the great faiths of Asia resort. Thus the Siva worshippers ascend the top of Adam's Peak in Ceylon, to adore the footprint of their phallic god, the *Siva fada*, the Buddhists repair to the spot to revere the same symbol as the footmark of Buddha, and the Muhammadans venerate it as a relic of Adam, the Semitic father of mankind.

Shrines common to various faiths

Adam's Peak

Many common shrines of a similar character exist in India. The famous place of pilgrimage at Sakhi Sarwar crowns the high bank of a hill stream at the foot of the Sulaiman range, in the midst of desert scenery, well adapted to penitents who would mortify the flesh. To this remote spot, the Muhammadans come in honour of a Musalman saint, the Sikhs to venerate a memorial of their theistic founder, Nanak, and the Hindus to perform their own ablutions and rites. The mount near Madras, associated in Catholic legend with the martyrdom of St Thomas, was originally a common hill shrine for Muhammadans, Christians, and Hindus. Such hill-shrines for joint worship are usually either rock fortresses, like Kalinjar in the North Western Provinces and Chunar overhanging the Ganges, or river islands, like the beautiful islet on the Indus just below the new railway bridge at Sakkar. The object of common adoration is frequently a footmark in stone. Thus the Hindus venerate as the footprint of Vishnu or Siva (*Vishnufad* or *Si apad*), while the Muhammadans revere it as the footprint of Muhammad (*Kadamra ul*). The mingled architecture of some of these pilgrimages attests the various races and creeds that combined to build them. Buddhism, which in some respects was at first a relic of a distant Brahman supremacy, has done much to remove the gulf between the ancient and the modern religions of India.

Sakhi Sarwar

Hinduism, however, derived its chief strength merely from
 1 See H. H. Wilson, *Ind. Ant. Soc.*, vol. 1, p. 40, &c.

Non-Aryan elements in Hinduism. the two ancient Aryan faiths, the Bráhmancial and the Buddhist. In its popular aspects, it drew much of its strength, and many of its rites, from the Nágá and other non-Aryan peoples of India. Buddhists and Bráhmans alike endeavoured, during their long struggle, to enlist the masses on their side. The Nágá kingdoms were divided, as we have seen, by the Chinese geographers into those which had accepted Buddhism, and those which had not. A chief feature in Nágá-worship was the reverence for dragons or tailed monsters. This reverence found its way into mediæval Buddhism, and became an important element in Buddhist mythology. The historian of Tree and Serpent worship goes so far as to say that 'Buddhism was little more than a revival of the coarser superstitions of the aboriginal races, purified and refined by the application of Aryan morality.'¹

Nágá rites. Serpent-worship in Hinduism.

The great monastery of Nalanda owed its foundation to the supposed influence of a tailed monster, or Nágá, in a neighbouring tank. Many Hindu temples still support colonies of sacred crocodiles; and the scholar who has approached the subject from the Chinese point of view, comes to the conclusion that 'no superstition was more deeply embedded in the [ancient] Hindu mind than reverence for Nágás or dragons. Buddhism from the first had to contend as much against the under current of Nágá reverence in the popular mind, as against the supercilious opposition of the philosophic Bráhman in the upper current. At last, as it would seem, driven to an extremity by the gathering cloud of persecution, the Buddhists sought escape by closing with the popular creed, and endeavouring to enlist the people against the priests; but with no further success than such a respite as might be included within some one hundred years.'²

Phallic emblems in Hinduism. This conception of the process is coloured by modern ideas, but there can be no doubt that Hinduism incorporated many aboriginal rites. It had to provide for the non-Aryan as well as for the Aryan elements of the population, and it combined the Bráhmanism and Buddhism of the Aryans with the fetish-worship and religion of terror which swayed the non-Aryan races. Some of its superstitions seem to have been brought by Turanian or Scythian migrations from Central Asia. Serpent-worship is closely allied to, if indeed it does

¹ Fergusson's *Tree and Serpent Worship*, pp. 62, with footnote, *et seq.* (4to, 1868). This view must be taken subject to limitations.

² *Catena of Buddhist Scriptures from the Chinese*, pp. 415, 416. By Samuel Beal (Triübner, 1871).

not take its origin in, that reverence for the symbols of human reproduction which formed one of the most widely spread religions of pre historic man. Phallic or generative emblems are on earth what the sun is in the heavens. The sun, as the type of celestial creative energy, was a primitive object of Aryan adoration. Later Brahmanism, and its successor Hinduism, seem to have adopted not only the serpent, but the *linga* and *yoni*, or the terrestrial organs of male and female creative energy, from the non Aryan races. The early Aryan ritual of the Vedas was addressed to the elements particularly to Fire. The Hindu
linga and
yoni

The worship of the phallic emblem or *linga* finds only a doubtful sanction, if any at all, in those ancient scriptures,¹ but the Purānas disclose it in full vigour (1000 A.D.), and the Muhammadans found it in every part of India. It is not only the chief religion to the south of the Vindhya, but it is universally recognised by the Hindus. Such symbolism fitted well into the character of the third person of their triad—Siva, the Reproducer, as well as the All Destroyer. To the Brāhmins it supplied a popular basis for their abstruse doctrines regarding the male and female energy in nature. Phallic worship harmonized also with their tendency to supply each god with a correlative goddess, and furnished an easily understood symbolism for the *Sakta* sects, or worshippers of the divine creative power,² so numerous among the Hindus. For the semi aboriginal tribes and half Hinduized low castes, this conception of Siva as the All Destroyer and Reproducer, organized on a philosophical basis their old religion of propitiation by blood.³ The
creative
energy

The fetish and tree worship of the non Aryan races also entered largely into Hinduism. The first Englishman⁴ who tried to study the natives as they actually are, and not as the Brahmins described them, was struck by the universal prevalence of a worship quite distinct from that of the Hindu deities. A Bengal village has usually its local god, which it adores. Fetish
worship in
Hinduism,

The sakti
grām

¹ H. H. Wilson's *Religion of the Hindus*, vol. 1 p. 270 (ed. 1862)

² *Sakta*

³ The relation of these rites of the semi Hinduized low-castes to the religion of the non Aryan races is treated at considerable length from personal observation, in Hunter's *Annals of Rural Bengal*, pp. 127-136 and 194 5th edition

⁴ Dr. Francis Buchanan, who afterwards took the name of Hamilton. His survey of the North Eastern Districts of Bengal, 1807-13 forms a noble

either in the form of a rude unhewn stone, or a stump, or a tree marked with red-lead. Sometimes a lump of clay placed under a tree does for a deity; and the attendant priest, when there is one, generally belongs to the half-Hinduized low-castes. The rude stone represents the non-Aryan fetish; and the tree seems to owe its sanctity to the non-Aryan belief that it forms the abode of the ghosts, or gods, of the village. We have seen how, in some Santáli hamlets, the worshippers dance round every tree; so that they may not, by any evil chance, miss the one in which the village spirits happen to dwell.

Vishnuite
symbols.

As the non-Aryan phallic emblems were utilized by Hinduism in the worship of Siva, the All-Destroyer and Reproducer, so the household fetish *sálagrám* has supplied a symbol for the rival Hindu deity Vishnu, the Preserver. The *sálagrám* (often an ammonite or curved stone) and the *tulasí* plant are the insignia of Vishnuism, as universally as the *linga* is of Sivaism. In both cases the Bráhmans enriched the popular fetish-worship with deep metaphysical doctrines, and with admirable moral codes. The Sivaite devotee carries round his neck, or hidden about his person, a miniature phallic emblem, *linga*; the *sálagrám* and *tulasí* are the objects of reverence among all the Vishnuite sects.¹

Jungle
rites.

The great Vishnuite festival of Bengal, the *rath-játra*, when Jagannáth, the 'Lord of the World,' is dragged in his car to his garden-house, is of Buddhist origin. But it has many a humbler counterpart in the forest excursions which the Bengal villagers make in their holiday clothes to some sacred tree in the neighbouring grove or jungle. These jungle rites find special favour with the low-castes, and disclose curious survivals of the non-Hinduized element in the worshippers. Blood sacrifices and the eating of flesh have long been banished from the popular Vishnuite sects. But on such forest festivals, the fierce aboriginal instincts even in the mixed castes, who accept in ordinary life the restraints of Hinduism, break loose. Cowherds have been seen to

series of MS. folios in the India Office, much in need of a competent editor. Montgomery Martin made three printed volumes out of them by the process of drawing his pencil through the parts which did not interest him, or which he could not understand. These he published under the title of the *History, Antiquities, Topography, and Statistics of Eastern India* (3 vols., 1838).

¹ See, *inter alia*, pp. 15, 39, 50, 54, 116, 117, 140, 149, 179, 181, 246, vol. i. of H. H. Wilson's *Religion of the Hindus* (ed. 1862).

seed on swine flesh, which at all other times they regard with abhorrence

The ceremonies, where they can pretend to a conscious meaning have a propitiatory or necromantic tinge. Thus, in Birbhūm District the mixed and low castes of the chief town repair once a year to the jungle, and make offerings to a ghost who dwells in a *bel* tree. Buchanan Hamilton describes such sacrifices as 'made partly from fear, and partly to gratify the appetite for flesh'.¹ In examining the western ethnical frontier of Lower Bengal, the rites of the non Aryan hillmen are found to merge into the Hinduism of the plains. The evidence shows that the Hindus derived from non Aryan sources their phallic emblem, the *linga* their household fetish, the *sadlagram*, their village gods, *grām devatas*, with the ghosts and demons that haunt so many trees, and the bloody rites of their national deity, Siva. Among the Hindus, these superstitions are often isolated and unconnected with each other, among the Santals and other non Aryan races, they form riveted links in a ritual of fear and propitiation.

Non Aryan rites merging into Hinduism

The development of Hinduism out of pre-existing religious types, although a natural evolution, bears the impress of human guidance. Until the 12th century A.D., the Brāhmins supplied the directing energy in opposition to the Buddhists, and founded their reforms on a re-assertion of the personality of God. But by that period, Buddhism had ceased to struggle for a separate existence in India, and the mass of the people began to strike out religious sects upon popular rather than on Brahmanical lines. The work of the early Brahman reformers was accordingly carried on after the 12th century, in part by low caste apostles, who popularized the old Brahmanical conception of a personal God, by infusing into it the Buddhist doctrine of the spiritual equality of man. Many of the Hindu sects form brotherhoods, on the Buddhist model, within which the classification by caste gives place to one based on the various degrees of perfection attained in the religious life.

Low caste apostles

Most of the Hindu reformations since the 12th century thus preserve what was best in each of the two ancient faiths of India—namely, the personal God of the Brāhmins, and the spiritual equality of the Buddhists. Among the Hindus, every preacher who would really appeal to the

The Hindu apostolic type

¹ *Hist., etc. of Eastern India*, from the Buchanan MSS., vol. 1 p. 194

² *Hunter's Annals of Kural Bengal*, p. 194 5th edition

popular heart must fulfil two conditions, and conform to a certain type. He must cut himself off from the world by a solemn act, like the Great Renunciation of Buddha; and he must come forth from his solemn communing with a simple message. The message need not be original. On the contrary, it must consist of a re-assertion, in some form, of the personality of God and the equality of men in His sight.

The Hindu
Acta Sancto-
rum.

Hinduism boasts a line of religious founders stretching in almost unbroken succession from about 700 A.D. to the present day. The lives of the mediæval saints and their wondrous works are recorded in the *Bhakta-Mālā*, literally, 'The Garland of the Faithful,' compiled by Nābhājī about three centuries ago.¹ This difficult Hindī work was popularized by later versions and commentaries,² and a vast structure of miracle and fable has been reared upon it. It is the Golden Legend and *Acta Sanctorum* of Hinduism. The same wonders are not recorded of each of its apostles, but divine interpositions abound in the life of all. The greater ones rank as divine incarnations prophesied of old. Some were born of virgins; others overcame lions; raised the dead; their hands and feet when cut off sprouted afresh; prisons were opened to them; the sea received them and returned them to the land unhurt, while the earth opened and swallowed up their slanderers. Their lives were marvellous, and the deaths of some a solemn mystery.

Miracles
of the
religious
founders.

Kabir's
death.

Thus on Kabir's decease, both the Hindus and Musalmāns claimed the body, the former to burn it, the latter to bury it, according to their respective rites. While they wrangled over the corpse, Kabir suddenly stood in the midst, and, commanding them to look under the shroud, vanished. This they did. But under the winding-sheet they found only a heap of beautiful flowers, one-half of which they gave to be burned by the Hindus in their holy city, while the other half was buried in pomp by the Musalmāns. His name lives in the memory of the people; and to this day pilgrims from Upper India beg a spoonful of rice-water from the Kabir Monastery at Purī, at the extreme southern point of Bengal.

¹ H. H. Wilson, writing in the *Asiatic Researches* (Calcutta, 1828), says about '250 years ago.'—See *Journal of the Bombay Branch of the Asiatic Society*, vol. iii. p. 4.

² The best known are those of Nārāyan Dās, about the time of Sháh Jahán (1627–58); the *tiká* of Krishna Dās (1713); and a later version 'in the more ordinary dialect of Hindustán.'—Wilson's *Religions of the Hindus*, vol. i. pp. 9, 10 (ed. 1862).

The first in the line of apostles was Kumārila, a *bhatta* or Brahman of Behar. The legend relates that he journeyed into Southern India, in the 8th century A.D., commanding princes and people to worship one God. He stirred up a persecution against the Buddhists or Jains in the State of Rudrapur,—a local persecution which later tradition magnified into a general extermination of the Buddhists from the Himālayas to Cape Comorin.¹ In Hindu theology he figures as a teacher of the later Mīmāṃsā philosophy, which ascribes the universe to a divine act of creation and assumes an all-powerful God as the cause of the existence, continuance, and dissolution of the world. The doctrine of this personal deity, 'the one existent and universal soul, 'without a second' (*advaita*), embodies the philosophical argument against the Buddhists. Kumārila bequeathed his task to his famous disciple Sankara Achārya in whose presence he is said to have solemnly committed his body to the flames.

With the advent of Sankara Achārya we touch firmer historical ground. Born in Malabar, he wandered over India as an itinerant preacher as far north as Kashmir, and died at Kedarnāth in the Himalayas, aged 32. One of his disciples has narrated his life's work under the title of 'The Victory of Sankara,'² a record of his doctrines and controversial triumphs. Sankara moulded the later Mīmāṃsā or Vedāntic philosophy into its final form, and popularized it as a national religion. It is scarcely too much to say that, since his short life in the 8th or 9th century, every new Hindu sect has had to start with a personal God. He addressed himself to the high caste philosophers on the one hand, and to the low-caste multitude on the other. He left behind, as the twofold result of his life's work, a compact Brāhman sect and a popular religion.

The Brāhman sect are the Smartas, still powerful in Southern India. Sankara taught that there was one sole and supreme God, *Brāhma Para Brahma*, distinct alike from any member of the old Brāhman triad, or of the modern Hindu pantheon, the

¹ The local persecution is recorded by Ananda Giri a disciple of Sankara about the 8th or 9th century A.D., and the author of the *Sankara Iyaya*. The magnified version appears in the *Sarva Darśana Saṅgraha* of Mādhava Achārya in the 14th century. See, however, the Mackenzie MSS. in the India Office Library.

² The *Sankara Iyaya* of Ananda Giri, published in the *Bibliothèque de l'Inde*, and critically examined by Kashinath Trimbal Telang in vol. v of the *Indian Antiquary*. But indeed Sankara is the first great figure in almost every Hindu hagiology, or book of saints, from the *Sarva Darśana Saṅgraha* of Mādhava Achārya downwards.

His religion for the people.

Ruler of the universe and its inscrutable First Cause, to be worshipped, not by sacrifices, but by meditation, and in spirit and in truth. The Smárta Bráhmans follow this philosophic side of his teaching; and of the religious houses which he founded some remain to this day, controlled from the parent monastery perched among the western ranges of Mysore.¹ But Sankara realized that such a faith is for the few. To those who could not rise to so high a conception of the godhead, he allowed the practice of any rites prescribed by the Veda, or by later orthodox teachers, to whatsoever form of the godhead they might be addressed. Tradition fondly narrates that the founders of almost all the historical sects of Hinduism—Sivaïtes, Vishnuïtes, Sauras, Sáktas, Gánapatyas, Bhairavas—were his disciples.² But Siva-worship claims Sankara as its apostle in a special sense. Siva-worship represents the popular side of his teaching, and the piety of his followers has elevated Sankara into an incarnation of Siva himself.³

Growth of Siva-worship;

Nothing, however, is altogether new in Hinduism, and it is needless to say that Siva had won his way high up into the pantheon long before the preaching of Sankara, in the 9th century A.D. Siva is the Rudra of the Vedas, as developed by Bráhman philosophy, and adapted by Sankara and others to popular worship. Rudra, the Storm-God of the Vedic hymns, had grown during this process into Siva, the Destroyer and Reproducer, as the third person of the Bráhman triad. The Chinese pilgrims supply evidence of his worship before the 7th century A.D., while his dread wife had a temple at the southernmost point of India at the time of the Periplus (2nd century A.D.), and gave her name to Cape Comorin.⁴ Siva ranks high in the Mahábhárata, in various passages of uncertain date; but does not reach his full development till the Puránas, probably after the 10th century A.D. His worship in Bengal is said to have been formulated by Paramata Kálanála at Benares;⁵ but Sankara's teaching gave an impulse to it

¹ See SRINGIRI (*The Imperial Gazetteer of India*) for a brief account of the chief-priest of the Smárta sect, which has its head-quarters in this monastery. Also the *Statistical Account of Mysore and Coorg*, by Lewis Rice, vol. ii. p. 413, etc. (Bangalore Government Press, 1876.)

² Wilson's *Religion of the Hindus*, vol. i. p. 28 (1862).

³ This rank is claimed for Sankara by Mádhava Achárya in the 14th century A.D.; indeed, Siva's descent as Sankara is said to have been foretold in the *Skanda Purána*. Sankara is one of the names of Siva.

⁴ From Kumári or Kanyá-kumári, the Virgin Goddess, a name of Durgá, wife of Siva.

⁵ As Visweswara, or Lord of the Universe, under which name Siva is still the chief object of worship at Benares.

SIVA WORSHIP

throughout all India, especially in the south, and later tradition makes Paramata himself a disciple of Sankara

In the hands of Sankara's followers and apostolic successors Siva worship became one of the two chief religions of India. As at once the Destroyer and Reproducer, Siva represented profound philosophical doctrines, and was early recognised as being in a special sense the god of the Bráhmans. To them he was the symbol of death as merely a change of life. On the other hand his terrible aspects reserved in his long list of names from the Korrer (Rudra) of the Veda to the Dread One (Bhima) of the modern Hindu Pantheon well adapted him to the religion of fear and propitiation prevalent among the ruder non Aryan races. Siva in his twofold character thus became the deity alike of the highest and of the lowest castes. He is the Mahadeva or Great God of modern Hinduism and his wife is Devi pre eminently THE Goddess.

His universal symbol is the *li* a the emblem of reproduction his sacred beast the bull connected with the same idea, a trident tops his temples.

His images partake of his double nature. The Brahmanical conception is represented by his attitude as a fair skinned man seated in profound thought the symbol of the fertilizing Ganges above his head and the bull (emblem alike of procreation and of Aryan plough tillage) near at hand. The wilder non Aryan aspects of his character are signified by his necklace of skulls his collar of twining serpents his tiger skin and his club with a human head at the end. His five faces and four arms have also their significance from this double aspect of his character. Aryan and non Aryan. His wife in like manner appears in her Aryan form as Urmá light the type of high born loveliness, in her composite character as Durga a golden coloured woman, beautiful but menacing, riding on a tiger and in her terrible non Aryan aspects, as Kálí a black fury of a hideous countenance dripping with blood, crowned with snakes, and hung round with skulls.

As an Aryan deity, Siva is *Parupati* the Lord of Animals and the Protector of Cows. *Sambhu* the Auspicious. *Mrityun* the Vanquisher of Death. *Vishvanatha* the Monarch of All. In his non Aryan attributes, he is *Aghora* the Horrible, *Virupaksha*, of Misshapen Eyes, *Ugra*, the Fierce. *Kapalamlin*,

¹ A San krit text declares Siva to be the *didava* or special god of the Bráhmans, Vishnu, of the Kshattriyas. Irahma of the Vaisyas, and the ancestor of the Sudras.

² *I* in the root *vi* / weep

Garlanded with Skulls. So also Devī, his female form, as an Aryan goddess is Umā, the lovely daughter of the mountain king, Himavat;¹ Aryā, the Revered; Gaurī, the Brilliant or Gold-coloured; Jagad-gaurī, the World's Fair One; Bhavānī, the Source of Existence; and Jagan-mātā, the Mother of the Universe. Her non-Aryan attributes appear in her names of Kālī or Syāmā, the Black One; Chandī, the Fierce; Bhairavī, the Terrible; Rakta-dantī, the Bloody-Toothed.

Twofold
aspects of
Siva-
worship.

The ritual of Siva-worship preserves, in an even more striking way, the traces of its double origin. The higher minds still adore the Godhead by silent contemplation, as prescribed by Sankara, without the aid of external rites. The ordinary Brāhman hangs a wreath of blossoms around the phallic *linga*, or places before it offerings of flowers and rice. But the low-castes pour out the lives of countless victims at the feet of the terrible Kālī, and until lately, in time of pestilence and famine, tried in their despair to appease the relentless goddess by human blood. During the dearth of 1866, in a temple to Kālī within 100 miles of Calcutta, a boy was found with his neck cut, the eyes staring open, and the stiff clotted tongue thrust out between the teeth. In another temple at Húglī (a railway station only 25 miles from Calcutta), the head was left before the idol, decked with flowers.² Such cases are true survivals of the regular system of human sacrifices which we have seen among the non-Aryan tribes.³ They have nothing to do with the old mystic *purusha-medha* or man-offering, whether real or symbolical, of the ancient Aryan faith;⁴ but they form an essential part of the non-Aryan religion of terror, which demands that the greater the need, the greater shall be the propitiation.

Human
offerings,
1866.

Garlands
of skulls.

Such sacrifices are now forbidden, alike by Hindu custom and English law. H. H. Wilson found evidence that they were regularly offered by the Kāpālika sect of Sivaite Hindus eight centuries ago; and representatives of those

¹ Monarch of the Himālayas.

² The Calcutta *Englishman* of 19th May 1866; *Annals of Rural Bengal*, p. 128, 5th edition.

³ As among the Kandhs, *ante*, chap. iii.

⁴ See Dr. Haug's *Origin of Brāhmanism*, p. 5 (Poona, 1863). The Purusha-sukta of the *Rig Veda*, x. 90, verses 7-15; and the Purusha-medha of the *Satapatha Brāhmana*, i. 2, 3, 6, and xiii. 6, i. 1; and of the *Aitareya Brāhmana*, ii. 8, with other passages quoted throughout Dr. Muir's *Sanskrit Texts*, seem to have an allegorical and mystical significance, rather than to refer to a real sacrifice. See also Wilson's *Essay on Human Sacrifices*, *Journal Roy. As. Soc.*, vol. viii. p. 96 (1852).

hideous votaries of Siva, 'smeared with ashes from the funeral pile, and their necks hung round with human skulls,' survive to this day.¹ Colonel Keatinge mentions that he has seen old sacrificial troughs near Jántiapur, now used only for goats, which exactly fitted the size of a man. The new troughs are reduced to the dimensions of the animals at present offered, and the greater length of the ancient ones is explained by a legend of human sacrifices. The Statistical Survey of India has brought to light many traditions of such offerings. The hill tribes between Sylhet and Assam hunt a monkey at sowing time, and crucify it on the margin of the village lands apparently as a substitute for the Spring man sacrifice.² A human life was sometimes devoted to the preservation of an artificial lake, or of a river embankment—a watchman of aboriginal descent being sacrificed³ or a virgin princess walled up in the breach.⁴

Another Sivaite festival was the Charak Pujá, or Hook Swing. The hook thrust through the muscles of the back and then swung in the air, in honour of Kali. In 1863 the orders of Government for abolishing this festival were carried out in a border District, Bírbum lying between the Hindu plains and the non Aryan highlands. The low castes in reality semi aborigines, and only half Hinduized, assembled round the poles and foretold famine from the loss of their old propitiatory rites. As they thought the Spring ceremonies absolutely essential before commencing tillage, the British officer suggested they might swing a man by a rope round his waist instead with a hook through his back. This compromise was accepted by some, but the better informed cultivators gloomily assured the officer that the ceremonies would have no good effect on the crops without the spilling of blood.⁵

The thirteen chief sects of Siva worshippers faithfully represent the composite character of their god. Sankara Siva left behind him a succession of teachers, many of whom rose to the rank of religious founders. The *Smárta* Bráhmans still maintain their life of calm monastic piety. The *Dandis*,

¹ H. H. Wilson's *Religion of the Hindus*, vol. 1. p. 264.
² As among the Kandhs, *ante*, chap. iii.
³ See SAKRAYPATNA, *The Imperial Gazetteer of India*.
⁴ See ANANTASAGARAM, *The Imperial Gazetteer of India*.

⁵ It is right to say that very little blood was lost, and the wounds caused were slight, indeed, slighter than those sometimes left behind by the skewers which were fixed through the cheek or tongue of the swingers during the performance.

Gradations
of Siva-
worship.

or ascetics, divide their time between begging and meditation. Some of them adore, without rites, Siva as the third person of the Aryan triad. Others practise an apparently non-Aryan ceremony of initiation by drawing blood from the inner part of the novice's knee, as an offering to the god in his more terrible form, Bhairava. The *Dandīs* follow the non-Aryan custom of burying their dead, or commit the body to some sacred stream.¹ The *Yogīs* include every class of devotee, from the speechless mystic who, by long suppressions of the breath, loses the consciousness of existence in an unearthly union with Siva, to the impostor who sits upon air, and the juggler who travels with a performing goat. The thirteen Sivaite sects descend, through various gradations of self-mortification and abstraction, to the *Aghorīs*, whose abnegation extends to eating carrion, or even human corpses, and gashing their own bodies with knives.

Sivaite
corpse-
eaters.

Within the last few years a small Aghorī community took up their abode in a deserted building on the top of a mount near Ujjain. To inspire terror and respect, they descended to the burning *ghāt*, snatched the charred bodies from the funeral pile, and retreated with them to their hill. The horror-stricken mourners complained to the local officer of the Mahārājā Sindhia, but did not dare to defend their dead against the squalid ministers of Siva. In the end, the Mahārājā's officer, by ensuring a regular supply of food for the devotees, put a stop to their depredations.

Non-
Aryan
types,
spiritual-
ized by the

The lowest Sivaite sects follow non-Aryan rather than Aryan types, alike as regards their use of animal food and their bloody worship. These non-Aryan types are, however, spiritualized into a mystic symbolism by the Sivaite *Sāktas*, or worshippers of the creative energy in nature (*Sakti*). The 'right-hand' adorers² follow the Aryan ritual, with the addition of an offering of blood.³ Their *Tantras* or religious works take the form of a dialogue between Siva and his lovely Aryan bride,⁴ in which the god teaches her the true forms of prayer and ceremonial. But the 'left-hand' worship⁵ is an organized five-fold ritual, of incantation, lust, gluttony, drunkenness, and blood. The non-Aryan origin of these secret rites is attested

Sākta or
Tantrik
sect.

¹ Cf. the Santāls and the Dámodar river, *ante*, chap. iii.

² Dakshinas or Bhāktas.

³ The *baḷi*.

⁴ Usually in the form of Umā or Pārvatī.

⁵ Vāmīs or Vāmācharīs, whose worship comprises the five-fold Makāra, 'which taketh away all sin,' namely—*māṃsa* (flesh), *maṣya* (fish, the symbol of ovarian fertility), *madya* (intoxicating spirits), *maithuna* (sexual intercourse), *mudrā* (mystical gesticulations).

by the use of meats and drinks forbidden to all respectable Hindus, perhaps also by the community of women, possibly an unconscious survival of the non Aryan forms of polyandry and primitive marriage by capture.¹ The Kanchuliyas, one of the lowest of the Sivaite sects, not only enforce a community of women, but take measures to prevent the exercise of individual selection, and thus leave the matter entirely to divine chance. Even their orgies, however, are spiritualized into a mystic symbolism, and the Dread Goddess surely punishes the votary who enters on them merely to gratify his lusts.

Siva worship thus became a link between the highest and the lowest castes of Hindus. Vishnu the second person of the Aryan triad supplied a religion for the intermediate classes. Siva, as a philosophical conception of the Bráhmans, afforded small scope for legend and the atrocities told of him and his wife in their terrible forms as adapted to the non Aryan masses were little capable of refined literary treatment. But Vishnu, the Preserver furnished a congenial theme for sacred romance. His religion appealed, not to the fears, but to the hopes of mankind. Siva worship combined the Bráhmānical doctrine of a personal God with non Aryan bloody rites, Vishnu worship in its final form as a popular religion, represents the coalition of the same Bráhmānical doctrine of a personal God, with the Buddhist principle of the spiritual equality of man.

Vishnu had always been a very human god from the time when he makes his appearance in the Veda as a solar myth, the 'Unconquerable Preserver striding across the universe in three steps'.² His later incarnations made him the familiar friend of man. Of these 'descents' on earth ten or twenty two in number, Vishnu worship, with the unerring instinct of

¹ Cf. also the festival of the *Rukmini Parān* at Puri. See Hunter's *Orissa*, vol. 1, p. 131.

² Probably at first connected with the rising, zenith, and setting of the sun in his daily course.

³ *Avataras*. The ten chief ones are (1) the Fish incarnation, (2) the Tortoise, (3) the Boar, (4) the Man Lion, (5) the Dwarf, (6) Parasurama, or Kama with the Axe, (7) Kama or Kama chandra, (8) Krishna, (9) Buddha, and (10) Kalki, the White Horse, yet to come. The first four are mythological beasts, perhaps representing the progress of animal life through the eras of fishes, reptiles, and mammals, developing into a formed man. From another aspect, the Fish represents the *yoni*, or ovarian fertility, the Tortoise, the *linga*, the Boar, the terrestrial fertiliser, and the Man Lion, the celestial. These four appeared in the *Satya Yuga*.

His later
develop-
ments.

a popular religion, chose the two most beautiful and most human for adoration. As Ráma and Krishna, Vishnu attracted to himself innumerable loving legends. Ráma, his seventh incarnation, was the hero of the Sanskrit epic, the Rámáyana. In his eighth incarnation, as Krishna, Vishnu becomes the high-souled prince of the other epic, the Mahábhárata; he afterwards grew into the central figure of Indian pastoral poetry; was spiritualized into the supreme god of the Vishnuite Puránas; and now flourishes as the most popular deity of the Hindus.

The worship of Vishnu, in one phase or another, is the religion of the bulk of the middle classes; with its roots deep down in beautiful forms of non-Aryan nature-worship, and its top sending forth branches among the most refined Bráhmans and literary sets. It is a religion in all things graceful. Its gods are heroes or bright friendly beings, who walk and converse with men. Its legends breathe an almost Hellenic beauty. The pastoral simplicities and exquisite ritual of Vishnu belong to a later age than Siva-worship, with its pandering to the grosser superstitions of the masses. Whatever may be the philosophical priority of the two creeds, Vishnuism made its popular conquests at a later period than Sivaite rites.

The
Vishnu
Purána,
circ. 1045
A.D.

In the 11th century, the Vishnuite doctrines were gathered into a religious treatise. The *Vishnu Purána* dates from about 1045 A.D.,¹ and probably represents, as indeed its name implies, 'ancient' traditions which had co-existed with Sivaism and Buddhism for centuries. It derived its doctrines from the Vedas, not, however, in a direct channel, but filtered through the two great epic poems, the Rámáyana and the Mahábhárata. The *Vishnu Purána* forms one of the eighteen Puránas or Sanskrit theological works, in which the Bráhman moulders of Vishnuism and Sivaism embodied their rival systems. These works especially extol the second and third members of the Hindu triad, now claiming the pre-eminence for Vishnu

The
eighteen
Puranas.

astronomical period anterior to the present world. The fifth or dwarf incarnation represents early man in the Treta Yuga, or second astronomical period, also long anterior to the present mundane one. The next three incarnations represent the Heroic Age; the ninth or Buddha, the Religious Age. The tenth stands for the end of all things, according to the Hindu apocalypse, when Vishnu shall appear on a white horse, a drawn sword, blazing like a comet, in his hand, for the destruction of the wicked and the renovation of the world. The *Bhágavata Purána* gives twenty-two incarnations of Vishnu.

¹ Preface to the *Vishnu Purána*. H. H. Wilson, p. cxii. (ed. 1864).

VISHNU WORSHIP

the sole deity, and now for Siva, but in their higher flights rising to a recognition that both are but forms for representing the one eternal God. Their interminable dialogues are said to run to 1,600,000 lines¹ But they exhibit only the Brahmanical aspect of what were destined to become the two national faiths of India, and they are devoid of any genuine sympathy for the people

The *Vishnu Purana* starts with an intolerance equal to Brahmanism that of the ancient code of Manu It still declares the priests to have sprung from the mouth, and the low castes from the feet, of God Its stately theogony disdains to touch the legends of the people It declares indeed that there is One God, but He is the God of the Brahmins to whom He gives the earth as an inheritance and in His eyes the ruder Indian races are as naught This is the general tenor of its doctrines, although more enlightened perhaps because later, passages occur In the *Vishnu Purana* Buddha is still an arch heretic, who teaches the masses to despise the Veda, but whose disciples are eventually crushed by the bright Aryan gods It is true that in the concluding book, when treating of the last Iron Age to which this world has now come some nobler idea of God's dealing with man gleams forth In that time of universal dissolution and darkness the sage consoles us with the assurance that devotion to Vishnu will suffice for salvation to all persons and to all castes²

Vishnuism had to preach a different doctrine before it could become, as it has for ages been, a religion of the people The first of the line of Vishnuite reformers was Rámanuja, a Bráhman of Southern India In the middle of the 12th century, he led a movement against the Sivaites, proclaiming the unity of God, under the title of Vishnu the Cause and the Creator of all things Prosecuted by the Chola king, who tried to enforce Sivaité conformity throughout his dominions, Rámanuja fled to the Jain sovereign of Mysore This prince he converted to the Vishnuite faith by expelling an evil spirit from his daughter Seven hundred monasteries, of which four still remain, are said to have marked the spread of his doctrine before his death Rámanuja accepted converts from every class, but it was reserved for his successors to formally enunciate the brotherhood of man

At the end of the 13th century A D, according to some

¹ Preface to the *Vishnu Purana*, p. xxiv H. H. Wilson (ed. 1864)

² *Vishnu Purana*, lib. i. cap. vi. p. 89 H. H. Wilson (ed. 1864)

³ *Vishnu Purana*, lib. vi. cap. ii H. H. Wilson, p. cxxxvii.

Rámánand,
1300-1400
A. D.

authorities, or at the end of the 14th, according to others, the great reformation, which made Vishnu-worship a national religion of India, took place. Rámánand stands fifth in the apostolic succession from Rámánuja, and spread his doctrine through Northern India. He had his head-quarters in a monastery at Benares, but wandered from place to place preaching the One God under the name of Vishnu, and choosing twelve disciples, not from the priests or nobles, but among the despised castes. One of them was a leather-dresser, another a barber, and the most distinguished of all was the reputed son of a weaver. The list shows that every caste found free entrance into the new creed.

His low-caste
disciples.

The life of a disciple was no life of ease. He was called upon to forsake the world in a strictly literal sense, and to go about preaching or teaching, and living on alms. His old age found an asylum in some monastery of the brotherhood. Rámánuja had addressed himself chiefly to the pure Aryan castes, and wrote in the language of the Bráhmans. Rámánand appealed to the people, and the literature of his sect is in the dialects familiar to the masses. The Hindi vernacular owes its development into a written language, partly to the folk-songs of the peasantry and the war-ballads of the Rájput court-bards, but chiefly to the literary requirements of the new popular faith. Vishnuism has deeply impressed itself on the modern dialects of Northern India.¹

Kabír,
1380-1420
A. D.

Kabír, one of the twelve disciples of Rámánand, carried his doctrines throughout Bengal. As his master had laboured to gather together all castes of the Hindus into one common faith, so Kabír, seeing that the Hindus were no longer the whole inhabitants of India, tried, about the beginning of the 15th century, to build up a religion that should embrace Hindu and Muhammadan alike. He rejected caste, denounced image-worship, and condemned the hypocrisy and arrogance of the Bráhmans. According to Kabír, the chief end of man is to obtain purity of life, and a perfect faith in God. The writings of his sect acknowledge that the god of the Hindu is also the god of the Musalmán. His universal name is The

His doc-
trines.

¹ The three best known sets of such religious treatises are—(1) the voluminous works ascribed to Kabír (*circa* 1400 A.D.) and his followers, preserved at the head-quarters of his sect, the *Kabír Chaurá* at Benares; (2) the *Granth*, or scriptures of various Bhágats or Vishnuite religious founders, especially of Dadú in Rájputána, and of the Sikh Gurús, beginning with Nának (1469); and (3) the *Bhaktamaldá*, or Roll of the Bhaktas or apostles, the Golden Legend of Vishnuism already referred to.

ner, whether He be invoked as the Ali of the Muhammadans, Co 11 n
as the Râma of the Hindus 'To Ali and to Rama we owe of Vishn
ur life,' say the scriptures of his sect,¹ 'and should show like Islâm
enderness to all who live What avails it to wash your mouth, 1420 A 1
o count your beads to bathe in holy streams to bow in temples
if, whilst you mutter your prayers or journey on pilgrimage
deceitfulness is in your heart? The Hindu fasts every
eleventh day the Musalmân on the Ramzan Who formed
the remaining months and days that you should venerate but
one? If the Creator dwell in tabernacles whose dwelling is
the universe? The city of the Hindu god is to the east The On
[Benares], the city of the Musalmân god is to the west (od 1
[Mecca] but explore your own heart for there is the god
both of the Musalmâns and of the Hindus Behold but One
in all things He to whom the world belongs He is
father of the worshippers like of Ali and of Râma He is
my guide, He is my priest Kabir was preeminently the
Vishnuite apostle to Bengal but his followers are also
numerous in the Central Provinces Cujrat and the Deccan

Kabir's teaching marks another great stride in the Vish Brother
nite reformation His master Ramanand had asserted an hood of
abstract equality of castes because he identified the deity with man
the worshipper He had regarded the devotee as but a man
festation of the divinity and no lowness of birth could degrade
the godhead As Vishnu had taken the form of several of the
inferior animals, such as the Boar and the 1 h incarnation
so might he be born as a man of any caste Kabir accepted
this doctrine, but he warmed it by an intense humanity All
the chances and changes of life the varied lot of man, his
differences in religion his desires hopes fears loves, are but
the work of *Mâjâ*, or illusion To recognise the one Divine
Spirit under these manifold illusions is to obtain emancipation The 1 c
and the Rest of the Soul That Rest is to be reached, not by of the s
burnt-offerings or sacrifices, but, according to Kabir, by faith *Fa 1*
(*bhakti*), by meditation on the Supreme, by keeping His holy
names, Hari, Ram, Govind, for ever on the lips and in the
heart

The labours of Kabir may be placed between 1380 and Cha
1420 A.D. In 1486, Chaitanya was born, who spread the 1486
Vishnuite doctrines, under the worship of Jagannath, through A 1
out the deltas of Penglal and Orissa Signs and wonders

¹ The *Ijtâd* of Ibadat one of Kabir's disciples. The rival claims of
the Hindus and Musalmâns to Kabir's holy have a ready been mer a nel
² S. 142, 141. Abridged from H. H. Wilson's Works i. 81 (ed 1824)

VISHNUITE CENOBITES.

Chutanya has become a sort of family worship throughout Orissa. The landed gentry worship him with a daily ritual in household chapels dedicated to his name. After his death, a sect arose among his followers, who asserted the spiritual independence of women.¹ In their monastic enclosures, male and female cenobites live in celibacy, the women shaving their heads, with the exception of a single lock of hair. The two sexes chant the praises of Vishnu and Chaitanya together, in hymn and solemn dance. One important doctrine of the Vishnuite sects is their recognition of the value of women as instructors of the outside female community. For long, their female devotees were the only teachers admitted into the *sanas* of good families in Bengal. Fifty years ago, they had effected a change for the better in the state of female education and the value of such instruction was assigned as the cause of the sect having spread in Calcutta. Since that time, Vishnuite female ascetics of various sorts have entered the same field. In some instances the bad crept in along with the good and an effort made in 1863 to utilize them in the mechanism of Public Instruction failed.²

The place
I assign
to women

The analogy of woman's position in the Vishnuite sects to that assigned to her by ancient Buddhism is striking. But the analogy becomes more complete when the comparison is made with the extra mural life of the modern Buddhist nun on the Punjab frontier. Thus in LAHUL (Lahul) some of the nuns have not, as in Tibet, cloisters of their own. They are attached to monasteries in which they reside only a few months of the year, and which they may permanently quit, either in order to marry or for other sufficient reasons. In 1868, there were seventy one such Buddhist nuns in Lahul, able to read and write, and very closely resembling in their life and discipline the better orders of Vishnuite female devotees in Bengal. One of them was sufficiently skilled in astronomy to calculate eclipses.³

The death of Chutanya marked the beginning of a spiritual decline in Vishnu worship. About 1520, Vallabha Swami preached in Northern India that the liberation of the soul did not depend upon the mortification of the body, and that

¹ The Spashtha Dayakas

² Wilson's *Religion of Hindus*, vol. 1 p. 171 (ed 1862)

³ The official details of this interesting and once promising experiment at Dacca will be found in Appendix A to the Report of the Director of Public Instruction, Bengal, for 1863-64 pp 83 90, for 1864-65, pp 155-158, and in each subsequent Annual Report to 1869.

⁴ Sterring's *Hindu Triks*, vol. II p 9 (4to, Calcutta)

God was to be sought, not in nakedness and hunger and solitude, but amid the enjoyments of this life. An opulent sect had, from an early period, attached itself to the worship of Krishna and his bride Rádhá ; a mystic significance being, of course, assigned to their pastoral loves. Still more popular among women is the modern adoration of Krishna as the Bála Gopála, or the Infant Cowherd,—a faith perhaps unconsciously stimulated by the Catholic worship of the Divine Child. The sect, however, deny any connection of their Infant god with the babe Jesus, and maintain that their worship is a legitimate and natural development of Vishnuite conceptions. Another influence of Christianity on Hinduism may possibly be traced in the growing importance assigned by the Krishna sects to *bhakti*, or faith, as an ail-sufficient instrument of salvation.

Child-
worship.

Krishna-
worship.

Vallabhi-Swámí was the apostle of Vishnuism as a religion of pleasure. When he had finished his life's work, he descended into the Ganges ; a brilliant flame arose from the spot ; and, in the presence of a host of witnesses, his glorified form ascended to heaven. The special object of his homage was Vishnu in his pastoral incarnation, in which he took the form of the divine youth Krishna, and led an arcadian life in the forest. Shady bowers, lovely women, exquisite viands, and everything that appeals to the sensuousness of a tropical race, are mingled in his worship. His daily ritual consists of eight services, in which Krishna's image, as a beautiful boy, is delicately bathed, anointed with essences, splendidly attired, and sumptuously fed. The followers of the first Vishnuite reformers dwelt together in secluded monasteries, or went about scantily clothed, living upon alms. But the Vallabhi-Swámí sect performs its devotions arrayed in costly apparel, anointed with oil, and perfumed with camphor or sandal. It seeks its converts, not among weavers, or leather-dressers, or barbers, but among wealthy bankers and merchants, who look upon life as a thing to be enjoyed, and upon pilgrimage as a holiday excursion, or an opportunity for trade.

A religion
of pleasure.

In a religion of this sort, abuses are inevitable. It was a revolt against a system which taught that the soul could approach its Maker only by the mortification of the body. It declared that God was present in the cities and marts of men, not less than in the cave of the ascetic. Faith and love were its instruments of salvation, and voluptuous contemplation its approved spiritual state. It delighted to clothe the deity in a beautiful human form, and mystical amorous poems make a

His Bráhma-
manical
and
Buddhist
origin.

ceremony of the Vishnuite faith. Jagannáth, literally 'The Lord of the World,' represents, with unmistakeable clearness, that coalition of Bráhma and Buddhist doctrines which forms the basis of Vishnu-worship. In his temple are three rude images, unconsciously representing the Bráhmañical triad. His Car Festival is probably a once-conscious reproduction of the Tooth Festival of the Buddhists, although its original significance has dropped out of sight. The Chinese pilgrim Fa-Hian gives an account of the yearly procession of Buddha's Sacred Tooth from its chapel to a shrine some way off,¹ and of its return after a stay there. This was in the 5th century A.D.; but the account applies so exactly to the Car Festival at the present day, that Fergusson pronounces the latter to be 'merely a copy.'²

A similar festival is still celebrated with great rejoicing in Japan. As in the Indian procession of Jagannáth, the Japanese use three cars;³ and Buddha sits in his temple, together with two other figures, like the Jagannáth triad of Orissa.³ It is needless to add, that while Jagannáth is historically of Buddhist or composite origin, he is to his true believers the one supreme 'Lord of the World.'

Car Festi-
val of
Jagannáth.

English
calumnies.

The calumnies in which some English writers have indulged with regard to Jagannáth, are exposed in Hunter's work on Orissa. That work carefully examined the whole evidence on the subject, from 1580, when Abul Fazl wrote, through a long series of travellers, down to the police reports of 1870.⁴ It came to the conclusion which H. H. Wilson had arrived at from quite different sources,⁵ that self-immolation was entirely opposed to the worship of Jagannáth, and that the deaths at the Car Festival were almost always accidental. In a closely-packed, eager throng of a hundred thousand men and women at Purí, numbers of them unaccustomed to exposure or hard labour, and all of them tugging and straining to the utmost at the car, under a blazing sun, deaths must occasionally occur.

Self-im-
molation
not prac-
tised.

There were also isolated instances of pilgrims throwing themselves under the wheels in a frenzy of religious excitement. At one time, several unhappy people were killed or injured every year, but they were almost invariably cases

¹ From the chapel at Anurádhapura to Mehentele.

² *History of Architecture*, vol. ii. p. 590 (ed. 1867).

³ See, among many interesting notices by recent travellers, Miss Bird's *Unbeaten Tracks in Japan*, vol. i. pp. 111, 115, etc. (ed. 1880).

⁴ Hunter's *Orissa*, vol. i., particularly pp. 306-308; also pp. 132-136.

⁵ Namely, the descriptions of the Car Festival or *Rath-Játra* in the work of Krishna Dás.

of accidental trampling. At an early period, indeed, the priests at Puri, probably by permitting a midnight sacrifice once a year within their precincts to the wife¹ of Siva, had fallen under suspicion of bloody rites². But such rites arose from the ambition of the priests to make Puri the sacred city of all worships and all sects. The yearly midnight offerings to the Dread Goddess within Jagannáth's sacred precincts represent the efforts made from time to time towards a coalition of the Sivaite and Vishnuite worship, like the *chakra* or sacred disc of Vishnu which surmounts the pre historic temple to Káli at Tamluk³.

Such compromises had nothing to do with the worship of the true Jagannāth. A drop of blood even accidentally spilt in his presence pollutes the officiating priests, the people, and the consecrated food. The few suicides that occurred at the Car Festival were for the most part those of diseased and miserable objects, who took this means to put themselves out of pain.⁴ The official returns now place the facts beyond doubt. Nothing could be more opposed to Vishnu worship than self immolation. Any death within the temple of Jagannāth renders the place unclean. The ritual suddenly stops, and the polluted offerings are hurried away from the sight of the offended god.

According to Chaitanya, the Orissa apostle of Jagannāth, ^{Evidence about Jagannāth} the destruction of the least of God's creatures is a sin against the Creator. Self-slaughter he would have regarded with abhorrence. The copious literature of his sect frequently describes the Car Festival, but makes no mention of self-sacrifice, and contains not a single passage which could be twisted into a sanction for it.⁵ Abul Fazl, the minister of Akbar, who conducted the survey of India for the Mughal Emperor, is silent about self-immolation to Jagannāth, although, from the context, it is almost certain that had he heard of the practice he would have mentioned it. In 1870, the present author compiled an index to all accounts by travellers and others of self-immolation at the Car Festival, ^{again a self-sacrifice} from the 14th century downwards.⁶ It proved that such

¹ Dimala the 'Stainless One'

² See statement from the *Haf iklim* (1483, 1527 A.D.) in Hunter's *Oruz*, vol. 1, p. 306.

² See *The Imperial Collector* article TAMILAK.

⁴ See authorities quoted in *Hunters' Orissa* vol 1 p. 134. Stirling's account *Annals Assam* vol xv p. 324. *Cu'n u h' m'ee* vol x p. 23. *Report of S. u. u. l. C. m'iss'ner to the Government of Bengal*, 1868, part II p. 5. *Surf'ol ee Reports*, *Leut. Lattie's Orissa* 1850.

¹ H. H. Wilson's *Records of the Herodias*, vol. 4, p. 155 (ed. 1862).

⁴ Hurst's *Oris* 1, vol. 1 pp. 305-308.

that there is ample scope for adoring God under other manifestations, or in other shapes. Unless a new sect takes the initiative, by rejecting caste or questioning the authority of the Veda, the Hindu is slow to dispute the orthodoxy of the movement. Even the founder of the Brahma Samáj, or modern theistic church of Bengal, lived and died a Hindu.¹ The Indian vernacular press cordially acknowledges the merits of distinguished Christian teachers, like Dr Duff of Calcutta, or Dr Wilson of Bombay. At first, indeed, our missionaries, in their outburst of proselytizing zeal, spoke disrespectfully of Hinduism, and stirred up some natural resentment. But as they more fully realized the problems involved in conversion, they moderated their tone, and now live on friendly terms with the Brahmans and religious natives.

An orthodox Hindu paper, which had been filling its columns with a vigorous polemic entitled 'Christianity Destroyed,' no sooner heard of the death of the late Mr Sherring, than it published a eulogium on that devoted missionary. It dwelt on 'his learning, affability, solidity, piety, benevolence, and business capacity.' The editor, while a stout defender of his hereditary faith, regretted that 'so little of Mr Sherring's teaching had fallen to his lot.'² The Hindus are among the most tolerant religionists in the world.

Of the three members of the Hindu Triad, the first person, Bráhma, has now but a few scattered handfuls of followers, the second person, Vishnu, supplies a worship for the middle classes, around the third person, Shiva, in his twofold aspects, has grown up that mixture of philosophical symbolism with propitiatory rites professed by the highest and by the lowest castes. But the educated Hindu willingly recognises that, beyond and above his chosen Deity of the Triad, or his favourite incarnation, or his village fetish, or his household *idolgram*, dwells the PARAMESWARA, the One First Cause, whom the eye has not seen, and whom the mind cannot conceive, but who may be worshipped in any one of the forms in which he manifests his power to men.

¹ The best short account of this deeply interesting movement, and of its first leader Kammichan Roy, will be found under the title of *Indian Theistic Reformers*, by Professor Monier Williams, in the *Journal of the Royal Asiatic Society*, Jan. 1881, vol. xiii. See also his *Modern India* (Trübner, 1879), and Miss Collet's *Indians Near East* (Williams & Norgate annually).

² The *Kurish-kin Satya*, quoted in the *Chronicle of the London Missionary Society* for November 1880, p. 792.

CHAPTER IX

CHRISTIANITY IN INDIA (*area 100 TO 1881 A.D.*)

CHRISTIANITY now forms the faith of over two millions of the Indian population. Coeval with Buddhism during the last nine centuries of its Indian history, the teaching of Christ has, after the lapse of another nine hundred years, more than twelve times more followers than the teaching of Buddha upon the Indian continent. Adding Burma, where the doctrines of Gautama still remain the creed of the people, there are over two millions of Christians to under three and a half millions of Buddhists, or to four millions of Buddhists and Jains. Christianity, while a very old religion in India, is also one of the most active at the present day. The Census of 1881 disclosed that the Christians in British and Feudatory India had increased by more than one fifth since 1872, and this increase, while partly the result of more perfect enumeration represents to a large extent a real growth.

The origin of Christianity in India is obscure. Early tradition, accepted popularly by Catholics, and more doubtfully by Protestants, connects it with St. Thomas the Apostle, who is said to have preached in Southern India, on the Malabar and Coromandel coasts, to have founded several churches, and finally, to have been martyred at the Little Mount, near Madras, in 68 A.D. The Catholic tradition narrates further, that a persecution arose not long after, in which all the priests perished, that many years later, the Patriarch of Babylon, while still in communion with Rome, heard of the desolate state of the Indian Church, and sent forth bishops who revived its faith, that about 486 A.D., Nestorianism spread from Babylon into Malabar.

To orthodoxy this tradition has a twofold value. It assigns an apostolic origin to the Christianity of India, and it explains away the fact that Indian Christianity, when it emerges into history, formed a branch of the unorthodox Nestorian Church. Modern criticism has questioned the evidence for the evangelistic labours of the Doubting Apostle in Southern India. It

Christianity coeval with Buddhism for 900 years

Origin of Christianity in India.

The orthodox tradition.

Value of the tradition.

has brought to light the careers of two later missionaries, both bearing the name of Thomas, to whom, at widely separated dates, the honour of converting Southern India is assigned. Gibbon dismisses the question of their respective claims in a convenient triplet:—‘The Indian missionary St. Thomas, an Apostle, a Manichæan, or an Armenian merchant.’¹

Syrian
Christians
of India.

This method of treatment scarcely satisfies the present century; and the Statistical Survey of India has thrown fresh light on the Syrian Christians of the Southern Peninsula. At this day they number 304,410,² or more than double the number of Native Protestants in India in 1861. Indeed, until within the past ten years, the remnants of the ancient Syrian Church had still a larger native following in India than all the Protestant sects put together.³ It would be unsuitable to dismiss so ancient and so numerous a body without some attempt to trace their history. That history forms the longest continuous narrative of any religious sect in India except the Jains.

Their
numbers
and
antiquity.

The Syrian Church of Malabar had its origin in the period when Buddhism was still triumphant; it witnessed the birth of the Hinduism which superseded the doctrine and national polity of Buddha; it saw the arrival of the Muhammadans who ousted the Hindu dynasties; it suffered cruelly from the Roman inquisitors of the Portuguese; but it has survived its persecutors, and has formed a subject of interest to Anglican inquirers during the past eighty years.⁴

The three
Legends
of St.
Thomas.

The three legends of St. Thomas, the missionary of Southern India, may be summarized as follows. According to the Chaldean Breviary and certain Fathers of the Catholic Church,

¹ *Decline and Fall of the Roman Empire* (quarto edition, 1788), vol. iv. p. 599, footnote 122.

² *Census of India*, 1881, vol. ii. pp. 20, 21. The Census officers return the whole as ‘Syrians,’ without discriminating between Jacobites and Syrian Catholics. A statement kindly supplied to the author by the Vicar-Apostolic of Verapoli returns the Syrian Catholics within his jurisdiction at over 200,000, and the Jacobites at about 100,000. The latter are chiefly under the jurisdiction of the Roman vicars-apostolic of Verapoli and Quilon, but are still distinguished as ‘Catholics of the Syrian rite.’

³ See *Protestant Missions in India, Burma, and Ceylon*, Statistical Tables, 1881, drawn up under the authority of the Calcutta Missionary Conference. This valuable compilation returns 138,731 Native Protestant Christians in 1861, and 224,258 in 1871, in India, exclusive of Burma.

⁴ From the time of Claudius Buchanan and Bishop Heber downwards. See *Asiatic Researches*, vol. vii., ‘Account of St. Thomé Christians on the coast of Malabar,’ by Mr. Wrede; Buchanan’s *Christian Researches in Asia*, 4th ed. (1811), pp. 106, 145; Heber’s *Journal*, vol. ii.; Bishop Middleton’s *Life of Le Bas*, chapters ix.–xii. (1831); Hough’s *Hist. of Christianity in India*, 5 vols. (1839–60).

St Thomas the Apostle converted many countries of Asia, and found a martyr's death in India. The meagre tradition of the early Church was expanded by the Catholic writers of the sixteenth and seventeenth centuries. The abstract by Vincenzo Maria makes the Apostle commence his work in Mesopotamia, and includes Bactria, Central Asia, China, 'the States of the Great Mogul,' Siam, Germany, Brazil, and Ethiopia, in the circle of his missionary labours. The apostolic traveller then sailed east again to India, converting the island of Socotra on the way, and after preaching in Malabar, ended his labours on the Coromandel coast.¹ The final development of the tradition fills in the details of his death. It would appear that on the 21st December 68 A.D., at Mailapur, a suburb of Madras, the Brahmans stirred up a tumult against the Apostle, who, after being stoned by the crowd, was finally thrust through with a spear upon the spot now known as St Thomas' Mount.

The second legend assigns the conversion of India to Thomas the Manichean, or disciple of Manes, towards the end of the third century. Another legend ascribes the honour to an Armenian merchant, Thomas Cana, in the eighth century. The story relates that Mar Thomas, the Armenian, settled in Malabar for purposes of trade, married two Indian ladies, and grew into power with the native princes. He found that such Christians as existed before his time had been driven by persecution from the coast into the hill-country. Mar Thomas secured for them the privilege of worshipping according to their faith, led them back to the fertile coast of Malabar, and became their archbishop. On his death, his memory received the gradual and spontaneous honours of canonization by the Christian communities for whom he had laboured, and his name became identified with that of the Apostle.

Whatever may be the claims of the Armenian Thomas as the re-builder of the Church in Southern India, he was certainly not its founder. Apart from the evidence of Patristic literature, there is abundant local proof that Christianity flourished in Southern India long before the eighth century. In the sixth century, while Buddhism was still at the height of its power, Kalyān, on the Bombay coast, was the seat of a Christian bishop from Persia.*

¹ *The Port of St. Marco & the Indian*. Colonel Yule's second ed. on vol. II p. 343, note 4 (1875).

² *Gazetteer of the Madras Presidency*, vol. XXI part 1, Tanjavur District, pp. 66, 200 etc. It is not necessary to dispute whether the seat of this bishopric was the modern Kalyān or Quilon (Culian) as the coast from Bombay's southwards to Quilon bore indefinitely the name of Caliana.

5213 (S
A.D. (?)

First
Legend
St Thomas
the
Apostle
(68 A.D.)

Second
Legend
Thomas
the Mani-
chean (277
A.D.)

Third
Legend
Thomas
the Ar-
menian
(780 A.D.)

The three
Legends
examined

the 1st

the second legend; The claims of Thomas the Manichæan have the European support of the Church historians, La Croze,¹ Tillemont, and others. The local testimony of a cross dug up near Madras in 1547, bearing an inscription in the Pehlvi tongue, has also been urged in his favour. The inscription is probably of the seventh or eighth century A.D., and, although somewhat variously deciphered, bears witness to the sufferings of Christ.²

and the first. For the claims of St. Thomas the Apostle, a longer and more ancient series of authorities are cited. The apocryphal history of St. Thomas, by Abdias, dating perhaps from the end of the first century, narrates that a certain Indian king, Gondaphorus, sent a merchant called Abban to Jesus, to seek a skilful architect to build him a palace. The story continues that the Lord sold Thomas to him as a slave expert in that art.³ The Apostle converted King Gondaphorus, and then journeyed on to another country of India, under King Meodeus, where he

¹ *Histoire du Christianisme des Indes*, 2 vols. 12mo (The Hague, 1758).

² Professor Haug reads it thus : 'Whoever believes in the Messiah, and in God above, and also in the Holy Ghost, is in the grace of Him who bore the pain of the cross.' Dr. Burnell deciphers it more diffidently :— 'In punishment [?] by the cross [was] the suffering of this [one] : [He] who is the true Christ and God above, and Guide for ever pure.' Yule's *Marco Polo*, 2nd ed., p. 345, vol. ii.; also p. 339, where the cross is figured.

³ This legend forms the theme of the *Hymnus in Festo Sancti Thomae Apostoli, ad Vesperum*, in the Mozarabic Breviary, edited by Cardinal Lorenzana in 1775. Its twenty-one verses are given as an appendix in Dr. Kennet's Madras monograph. Three stanzas will here suffice :—

'Nuncius venit de Indis
Quaerere artificem :
Architectum construere
Regium palatium :
In foro deambulabat
Cunctorum venalium.

Habeo servum fidelem,
Locutus est Dominus,
Ut exquiris talem, aptum
Esse hunc artificem :
Abbanes videns, et gaudens,
Suscepit Apostolum.'

The hymn assigns the death of the Apostle to the priest of a sun temple which had been overthrown by St. Thomas :—

'Tunc sacerdos idolorum
Furibundus astitit,
Gladio transverberavit
Sanctum Christi martyrem.
Glorioso passionis
Laureatum sanguine.'

was slain by lances¹ The existence of a King Gondaphorus has been established by coins, which would place him in the last century B.C., or within the first half of the first century of our era² But, apart from difficulties of chronology, it is clear that the Gondaphorus of the coins was an Indo-Scythic monarch, reigning in regions which had no connection with Malabar His coins are still found in numbers in Afghanistan and the Punjab, especially from Peshawar to Ludhiana He was essentially a Punjab potentate

The mention of St. Thomas the Apostle in connection with India by the Fathers, and in the Offices of the Church, does not bring him nearer to Malabar, or to the supposed site of his martyrdom at Madras For the term 'India,' at the period to which these authorities belong, referred to the countries beyond Persia, including Afghanistan and the basins of the Upper Oxus, Indus, and Ganges, rather than to the southern half of the peninsula In the early accounts of the labours of St. Thomas, the vague term India is almost always associated with Persia, Media, or Bactria³ Nor does the appellation of St. Thomas as the Apostle of India in the Commemorations of the Church, help to identify him with the St. Thomas who preached on the Malabar and Coromandel coasts For not only does the indeterminate character of the word still adhere to their use of 'India,' but the area assigned to the Apostles' labours is so wide as to deprive them of value for the purpose of local identification Thus, the Chaldean Breviary of the Malabar Church itself states that 'by St. Thomas were the

Wide
meaning of
'India,'

in the
Fathers,

¹ Colonel Yule's *Marco Polo*, second edition vol. II p. 243 Dr Kennet, in an interesting monograph entitled *St. Thomas, the Apostle of India*, p. 19 (Madras, 1882), says — 'The history of Alodia was published for the first time by Wolfgang Lazius, under the title of *Abdus Bilgomer, Episcopi et Apostolorum Discipuli, de Historia certaminis Afriani, libri decem, Julii Africano Interprete* Basilia 1532

² For the various dates see Colonel Yule's *Marco Polo*, second edition, vol. II p. 343 Colonel Yule's *Cathay* deals with the Chinese and Central Asian aspects of the legend of St. Thomas (2 vols. 1866)

³ Thus the *Fuscal Chronicle* of Bishop Dorotheus (lxix A.D. 254) says — 'The Apostle Thomas, after having preached the gospel to the Parthians, Medes, Persians, Germanians [an agricultural people of Persia mentioned by Herodotus, i. 125], Bactrians, and Magi suffered martyrdom at Calamina, a town of India' Hippolytus, Bishop of Pontus (circa 220 A.D.), assigns to St. Thomas, Parthia, Media, Persia, Hecania, the Bactra, the Mada, and, while ascribing the conversion of India to St. Bartholomew, mentions Calamina, a city of India, as the place of St. Thomas' martyrdom. The Metropolitan Johannes, who attended the Council of Nicea in 325, subscribed as Bishop of 'India Maxima and Persia.' Dr Kennet's monograph (Madras, 1882); Hoagh, i. pp. 30 to 116

the second legend ; The claims of Thomas the Manichæan support of the Church historians, La (others. The local testimony of a cross in 1547, bearing an inscription in t also been urged in his favour. The ins the seventh or eighth century A.D., at variously deciphered, bears witness Christ.²

and the first.

For the claims of St. Thomas the Ap ancient series of authorities are cited. of St. Thomas, by Abdias, dating perha first century, narrates that a certain Inc sent a merchant called Abban to] architect to build him a palace. The Lord sold Thomas to him as a slave ex Apostle converted King Gondaphorus to another country of India, under K

¹ *Histoire du Christianisme des Indes*, 2 vo

² Professor Haug reads it thus : 'Whoever in God above, and also in the Holy Ghost bore the pain of the cross.' Dr. Burnell dec 'In punishment [?] by the cross [was] the suf is the true Christ and God above, and Guide *Polo*, 2nd ed., p. 345, vol. ii.; also p. 339, \

³ This legend forms the theme of the *H Apostoli, ad Vesperum*, in the Mozarabic Lorenzana in 1775. Its twenty-one verses Kennet's Madras monograph. Three stan

' Nuncius venit de
Quaerere artifi
Architectum con
Regium palat
In foro deambu
Cunctorum v

Habeo servum
Locutus est
Ut exquiris ta'
Esse hunc
Abbanes vid
Suscepit

The hymn assigns the death of the which had been overthrown by St. T

' Tunc sace
Furibu
Gladio tr
Sancti
Glorios
Lau

came upon a story of 'a poor and aged *Jattik*, or Christian priest.'¹

Whether the Christians on the coast of Malabar were a direct offshoot of the Nestorian Church of Asia, or the result of an earlier seedling dropped by St Thomas or St Bartholomew on their apostolic travels, it is certain that from their first appearance in local history, the Malabar Christians obeyed bishops from Persia of the Nestorian rite.² By the 7th century, the Persian Church had adopted the name of Thomas Christians and this title would in time be extended to all its branches, including that of Malabar. The early legend of the Manichæan Thomas in the 3rd century, and the later labours of the Armenian Thomas, the rebuilder of the Malabar Church, in the 8th, had endeared that name to the Christians of Southern India. In their isolation and ignorance, they concentrated the three names, and concentrated their legends of the three Thomases in the person of the Apostle.³ Before the 14th century, they had completed the process by believing that St. Thomas was Christ.

The fitness of things soon required that the life and death of the Apostle should be localized by the Southern Indian Church. Patristic literature clearly declares that St Thomas had suffered martyrdom at Calamina, probably in some country east of Persia, or in Northern India itself. The tradition of the Church is equally distinct, that in 394 A.D. the remains of the Apostle were transferred to Edessa in Mesopotamia.⁴ The attempt to localize the death of St Thomas on the south-western coast of India started, therefore, under disadvantages. A suitable site was, however, found at the Mount near Madras, one of the many hill shrines of ancient India which have formed a joint resort of religious persons of diverse faiths,—Buddhist, Muhammadan, and Hindu (*ante*, p. 203).

Marco Polo, the first European traveller who has left an account of the place, gives the legend in its undeveloped form.

¹ Dr. Fellew's 'History of Kasilgar,' in the *Quarterly Report of Sir D. J. Forsyth's Mission*, p. 127 (Quarto, Foreign Office Press, Calcutta, 1875).

² Mr. Campbell's *Political Gazetteer*, Thána District, chap. 11 (Bombay, 1882).

³ The Jacobites or followers of Jacobus Baradaeus prefer in the same way to deduce their name and pedigree from the Apostle James Gibbon (603, footnote (ed. 1788)).

⁴ For the authorities see Dr. Kennet's Malabar monograph, *St. Thomas*, *The Apostle of India* (1852), and Colonel Yule's critical note, *Marco Polo*, vol. II, p. 342 (2nd ed. 1875).

Troubles
of the
Ancient
Indian
Church.

As a matter of history, the life of the Nestorian Church in India has been a troubled one. A letter from the Patriarch Jesajabus to Simeon, Metropolitan of Persia, shows that before 660 A.D., the Christians along the Indian coast were destitute of a regular ministry.¹ In the 8th century, the Armenian friar Thomas found the Malabar Christians driven back into the recesses of the mountains. In the 14th century, Friar Jordanus declared them to be Christians only in name, without baptism. They even confounded St. Thomas with Christ.² A mixed worship, Christian, Muhammadan, and Hindu, went on at the old high place or joint hill shrine near Madras. In some centuries, the Church in Southern India developed, like the Sikhs in the Punjab, into a military sovereignty. In others, it dwindled away; its remnants lingering in the mountains and woods, or adopting heathen rites. The family names of a forest tribe³ in Kánara, now Hindus, bear witness to a time when they were Christians; and there were probably many similar reversions to paganism.

The St.
Thomas
Christians
a military
caste ;

The downfall of the Nestorian Church in India was due, however, neither to such reversions to paganism nor to any persecutions of native princes; but to the pressure of the Portuguese Inquisition, and the proselytizing energy of Rome. Before the arrival of Vasco da Gama in 1498, the St. Thomas Christians had established their position as a powerful military caste in Malabar. The Portuguese found them firmly organized under their spiritual leaders, bishops, archdeacons, and priests, who acted as their representatives in dealing with the Indian princes. For long they had Christian kings, and at a later period chiefs, of their own.⁴ In virtue of an ancient charter ascribed to Cherumal Perumal, Suzerain of Southern India in the ninth century A.D., the Malabar Christians enjoyed all the rights of nobility.⁵ They even claimed precedence of the Nairs, who formed the heathen aristocracy. The St. Thomas Christians

¹ *Assemani Bibliotheca*, quoted by Bishop Caldwell, *Comparative Grammar of the Dravidian Languages*, p. 27, footnote (ed. 1875). Jesajabus died 660 A.D.

² Jordanus, quoted in Mr. J. M. Campbell's *Bombay Gazetteer*, vol. xiii. part i. p. 200 (ed. 1882).

³ The Maráthi Sidis. For an interesting account of them, see Mr. J. M. Campbell's *Bombay Gazetteer*, Kánara District, vol. xv. part i. p. 397 (ed. 1883).

⁴ *Histoire du Christianisme des Indes*, par M. V. La Croze, vol. i. p. 72, ii. p. 133, etc. (2 vols. 12mo, The Hague, 1758).

⁵ *Idem*, i. p. 67. For details, see *The Syrian Church of Malabar*, by Edavalikel Philippos, p. 23, and footnote (Oxford, 1869). Local legend vainly places Cherumal Perumal and his grant as far back as 345 A.D.

and the Nairs were, in fact, the most important military castes on the south west coast.¹ They supplied the bodyguard of the local kings, and the Christian caste was the first to learn the use of gunpowder and fire arms. They thus became the matchlockmen of the Indian troops of Southern India, usually placed in the van, or around the person of the prince.

The Portuguese, by a happy chance, landed on the very Province of India in which Christianity was most firmly established, and in which Christians had for long formed a recognised and respected caste. The proselytizing energy of the new comers could not, however, rest satisfied with their good fortune. That energy was vigorously directed both against the natives and the ancient Christian communities. Indeed the Nestorian heresy of the St Thomas Christians seemed to the fervour of the friars to be a direct call from heaven for interference by the orthodox Church. The Portuguese established the Inquisition, as we shall presently see, at Goa in 1560. After various Portuguese attempts, strongly resisted by the St Thomas Christians, the latter were incorporated into the Catholic Church, by the labours of Alexis de Menezes, Archbishop of Goa, in 1599. The Synod held by him at Udayampura (or Diamper), near Cochín, in that year denounced Nestorius and his heresies, and put an end to the existence of the Indian Nestorian Church.

No document could be more exhaustively complete than the Acts and Decrees of the Synod of Diamper, in its provisions for bringing the Malabar Christians within the Roman fold.² The sacred books of the St Thomas congregations, their missals, their consecrated oil and church ornaments, were publicly burned, and their religious nationality as a separate caste was abolished. But when the firm hand of Archbishop Menezes was withdrawn, his parchment conversions began to lose their force. Notwithstanding the watchfulness of the Goa Inquisition over the new converts, the Decrees of the Synod of Diamper fell into neglect,³ and the Malabar Christians chafed under a line of Jesuit prelates from 1601 to 1653.

In 1653 they renounced their allegiance to their Jesuit

¹ For the military aspects of the Christian caste of St Thomas, see La Caze (*op cit*) ii 1, 128 129 130 140 155 etc. The *History of the Church of Malabar and Synod of Diamper* by the learned Michael Goides, Chancellor of the Cathedral Church of Sarum (London, 1694) an earlier and independent work, bears out this view.

² The Acts and Decrees of the Synod of Diamper (i.e. Udayampura) occupy 346 pages of the Chancellor of Sarum's *History of the Church of Malabar* pp. 67-443 (c.L. 1694).

³ La Caze, ii p. 193.

Reversions and Conversions, 1653-1663. bishop. A Carmelite mission was despatched from Rome in 1656 to restore order. The vigorous measures of its head, Joseph of St. Mary, brought back a section of the old Christian communities; and Joseph, having reported his success at Rome, returned to India as their bishop in 1661. He found the Protestant Dutch pressing the Portuguese hard on the Malabar coast, 1661-1663. But the old military caste of Malabar Christians rendered no assistance to their Catholic superiors, and remained tranquil spectators of the struggle, till the capture of Cochin by the Dutch brought about the ruin of the Portuguese power in 1663.

Malabar Christians freed by the Dutch, 1663;

The Malabar Christians, thus delivered from the temporal power of the Portuguese, re-asserted their spiritual independence. *The Portuguese had compelled the native princes to persecute the old Christian communities; and by confiscations, imprisonments, and various forms of pressure, to drive the Indian Nestorians into reconciliation with Rome.*¹ Such a persecution of a long recognised caste, especially of a valued military caste, was as foreign to the tolerant spirit of Hinduism, as it was repugnant to the policy of the Indian princes, and it has left a deep impression on the traditions of the south-western coast. The native Jacobite historian of the Church of Malabar rises to the righteous wrath of an old Scottish covenanter in recounting the bribing of the poorer chiefs by the Portuguese, and the killings, persecutions, and separations of the married clergy from their wives. The new Dutch masters of the southern coast, after a short antagonism to the Carmelite prelate and the native bishop whom he left behind, lapsed into indifference. They allowed the Roman missionaries free scope, but put an end to the exercise of the temporal power in support of the Catholic bishop.²

receive a Jacobite bishop, 1665.

The chief spiritual weapon of conversion, a weapon dexterously used by the Portuguese Viceroy, had been the interruption of the supply of Nestorian bishops from Persia. This they effected by watching the ports along the west coast of India, and preventing the entrance of any Nestorian prelate. The Syrian Church in India had therefore to struggle on under its archdeacon, with grave doubts disturbing the mind of its clergy and laity as to whether the archidiaconal consecration was sufficient for the ordination of its priests. The overthrow of the Portuguese on the seaboard put an end to this long episcopal blockade. In 1665, the Patriarch of

¹ La Croze, vol. ii. pp. 169, 176, 183, 189, 192, 198, 203, etc.

² La Croze, vol. ii. pp. 204, 205.

Antioch sent a bishop, Mar Gregory, to the orphaned Syrian Church of India. But the new bishop belonged to the Jacobite instead of the Nestorian branch of the Asiatic Church. Indian Nestorianism may therefore be said to have received its death blow from the Synod of Diamper in 1599.

Since the arrival of Mar Gregory in 1665, the old Syrian Church of India has remained divided into two sects. The *Pazhaya kuttakir*, or Old Church, owed its foundation to Archbishop Menezes and the Synod of Diamper in 1599, and its reconciliation, after revolt, to the Carmelite bishop, Joseph of St. Mary, in 1656. It retains in its services the Syrian language and in part the Syrian ritual. But it acknowledges the supremacy of the Pope, and his vicars apostolic. Its members are now known as Catholics of the Syrian Rite to distinguish them from the converts made direct from heathenism to the Latin Church by the Roman missionaries. The other section of the Syrian Christians of Malabar is called the *Putten kuttakir*, or New Church. It adheres to the Jacobite tenets introduced by its first Jacobite bishop, Mar Gregory, in 1665.

The present Jacobites of Malabar condemn equally the errors of Arius, Nestorius and the bishops of Rome. They hold that the Bread and Wine in the Eucharist become the Real Body and Blood of Christ and give communion in both kinds mixed together. They pray for the dead, practise confession, make the sign of the cross, and observe fasts. But they reject the use of images, honour the Mother of Jesus and the Saints only as holy persons and friends of God, allow the consecration of a married layman or deacon to the office of priest, and deny the existence of purgatory. In their Creed they follow the Council of Nicea (325 A.D.). They believe in the Trinity, assert the One Nature and the One Person of Christ and declare the procession of the Holy Ghost to be from the Father, instead of from the Father and the Son.¹

The Syrian Catholics and Syrian Jacobites of Malabar maintain their differences with a high degree of religious vitality at the present day. Their congregations keep themselves distinct from the Catholics of the Latin Rite converted direct from heathenism, and from the Protestant sects. No Nestorian Church is now known to exist in Malabar.² The Syrian

¹ *The Syrian Christians of Malabar*, being a Catechism of the doctrine and ritual by Edavalakkal Thelappan Chozhicon and Caluthir (revised) of the Great Church of Cochin in Travancore, pp. 3, 4, 8 (Easter 1869).

² The above summary is condensed from the Catechism of Malabar 171704, etc. at pp. 9, 13, 17, 19.

³ *Id.*, p. 27.

Malabar Christians since 1665,

(1) Syrian Catholics 200,000

(2) Jacobites 100,000³

Tenets of the Malabar Jacobites

Nestorianism extinct in Malabar

Christians were returned in 1871 at about one-third of a million; but the Census officers omitted to distinguish between Catholic Syrian and Jacobites. The Catholic Archbishop and Vicar-Apostolic of Verapoli, to whose kind assistance this chapter is indebted in many ways, estimates the Syrian Catholics at 200,000, and the Jacobites at 100,000. The totals for all Southern India cannot, however, be ascertained until the next Census of 1891.

Portu-
guese mis-
sionaries,
1500 A.D.,

Roman friars had visited India since the 13th century. The first regularly equipped Catholic mission, composed of Franciscan brethren, arrived from Portugal in 1500. Their attacks on the native religions seemed part of the Portuguese policy of aggression on the Native States. The pious Portuguese monks were popularly identified with the brutal Portuguese soldiery, whose cruelties have left so deep a stain on early European enterprise in India. The military attempts of the Portuguese, and their ill-treatment of the native princes and the native population, provoked unmerited hatred against the disinterested, if sometimes ill-judged, zeal of the Portuguese missionaries.

identified
with Portu-
guese aggres-
sions.

Native re-
prisals or
'persecu-
tions.'

Native reprisals, which certain writers have dignified by the name of persecutions, occasionally took place in return for Portuguese atrocities. But the punishments suffered by the friars were usually inflicted for disobedience to the native civil power, or for public attacks on native objects of veneration; such attacks as are provided for by the clauses in the Anglo-Indian Penal Code, which deal with words or signs calculated to wound the religious feelings of others. Attacks of this kind lead to tumults among an excitable population, and to serious breaches of the peace, often attended with bloodshed. The native princes, alarmed at the combined Portuguese assault on their territory and their religion, could not be expected to decide in such cases with the cold neutrality of an Anglo-Indian magistrate. Father Pedro de Covilham was killed in 1500.

Slow
progress.

For some time, indeed, missionary work was almost confined to the Portuguese settlements, although King Emmanuel (1498-1521) and his son John III. (1521-57) had much at heart the conversion of the Indians. The first bishop in India was Duarte Nunez, a Dominican (1514-17); and John de Albuquerque, a Franciscan, was the first bishop of Goa (1539-53). With St. Francis Xavier, who arrived in 1542, began the labours of the Society of Jesus in the East, and the progress of Christianity became more rapid.

Xavier and
the Jesuits,
1542.

St. Francis' name is associated with the Malabar coast, and with the maritime tracts of Madura and Southern Madras.

He completed the conversion of the Paravars in Tinneveli ^{St Francis District}¹ His relics repose in a silver shrine at Goa ² ^{Nasir} Punnaikāyal, in Tinneveli, was the scene, in 1549, of the death of Father Antonio Criminale, the protomartyr of the Society of Jesus, and in the following year, several other lives were lost in preaching the gospel. Goa became an Archbishopric in 1577. In 1596 to 1599, the Archbishop of Goa, Alexis de Menezes, an Augustinian, succeeded in recon- ^{Alexis de Menezes} ciling the Indian Nestorians to Rome, and at the Synod of Diamper (Udyampura, near Cochin) in 1599, the affairs of the Indian Christians were settled. The use of the Syrian rite was ^{Syrian rite reformed but retained, 1599} retained after it had been purged of its Nestorianism. The later history of the Syrian Christians in Malabar has already been traced.

The Jesuit mission to the Madras coast dates from 1606, ^{The Madras Jesuits} and is associated with the names of Robert de Nobili (its founder, who died 1656), John de Britto (killed in Madura 1693), Beschi the great scholar (who died about 1746), and other illustrious Jesuits, chiefly Portuguese.³ They laboured in Madura, Trichinopoly, Tanjore, Tinneveli, Salem, etc. The mission of the Karnatic, also a Jesuit mission, was French in its origin, and due in some measure to Louis XIV. in 1700. Its centre was at Pondicherry.

The early Jesuit missions are particularly interesting. Their ^{Good work done by the Jesuits,} priests and monks became perfect Indians in all secular matters, dress, food, etc., and had equal success among all castes, high and low. In the south of the peninsula they brought, as we have seen, the old Christian settlements of the Syrian rite into temporary communion with Rome, and converted large sections of the native population throughout extensive districts. The Society of Jesus had also numerous although less important missions in the north of India. During the 17th and 18th centuries, religious troubles and difficulties arose in Western India through the action of the missionaries in regard to caste observances. Schisms troubled the Church. The Portuguese king claimed, as against the Pope, to appoint the Archbishop of Goa, and the Dutch adventurers for a time persecuted the Catholics along the coast.

But in the 16th century it seemed as if Christianity was destined to be established by Jesuit preachers throughout

¹ See article TINNEVELLI DISTRICT, *The Imperial Gazetteer of India*

² See article GOA, *The Imperial Gazetteer of India*

³ See articles MADURA and TINNEVELLI, *id. et*

flowing with milk and honey, and teeming with a population eager for sacramental rites

The swift downfall of the Portuguese power, based upon conquest and conversion, will be exhibited in a later chapter. But the Portuguese are the only European nation who have created, or left behind them, a Christian State polity in India. To this day, their East India settlements are territorially arranged in parishes, and the traveller finds himself surrounded by churches and other ecclesiastical features of a Christian country, among the rice fields and jungles of Goa and Daman. This parochial organization of Portuguese India was the direct result of the political system imposed on the viceroys from Europe. But, indirectly, it represents the method adopted by the Society of Jesus in its efforts at conversion. The Jesuits worked to a large extent by means of industrial settlements. Many of their stations consisted of regular agricultural communities, with lands and a local jurisdiction of their own. Indeed, both in the town and country, conversion went hand in hand with attempts at improved husbandry, or with a training in some mechanical art.

This combination of Christianity with organized labour may best be understood from a description of two individual settlements.¹ Thana, a military agricultural station, and Cochin, a collegiate city and naval port. Thana, says a Jesuit letter writer in the middle of the 16th century, is a fortified town where the Brethren have a number of converts. Once on a time a wrinkled and deformed old man came to them from distant parts, greatly desiring to be made a Christian. He was accordingly placed before a picture of the Blessed Virgin, and, having sought to kiss the Child, was forthwith baptized. He died in peace and joy next morning. Many boys and girls were likewise bought from the barbarians for a few pence a piece. These swelled the family of Christ, and were trained up in doctrine and handicrafts. During the day they plied their trades as shoemakers, tailors, weavers, and iron workers, on their return at evening to the College, they sang the catechism and litanies in alternate choirs. Others of them were employed in agriculture, and went forth to collect fruits or to work with the Christian cultivators in the fields.

There was also a Christian village, the Hamlet of the

¹ The following details were chiefly condensed from the *Relatus Societate Jesu in Oriente Gestarum Volumen*, already referred to. This book is no longer in the author's possession, and as no copy is procurable in India, the pages cannot be cited nor the exact words verified.

and culti-
vators.

Trinity, 3000 paces off, upon temple lands bought up and consecrated by the Order. The Society had, moreover, certain farms, yielding 300 pieces of gold a year. This money supported the widows and orphans, the sick, and catechumens while engaged in their studies. The poorer converts were encouraged in agriculture by a system of advances. Everything seemed to prosper in the hands of the Jesuit Brethren, and their very goats had kids by couplets and triplets every year. The husbandmen 'are all excellent cultivators and good men,' well skilled in the Mysteries, and constant in the practice of their faith, assembling daily together *ad signum angelicæ salutationis*. 'Even in the woods, boys and men are heard chanting the Ten Commandments in a loud voice from the tops of the palm-trees.'

Jesuit rural
organiza-
tion.

The management of the mission stations seems to have been admirable. Four or five Brothers of the Order regulated alike the secular and the spiritual affairs of each community. One of them was a surgeon, who cured ulcers, sores, and dangerous maladies. The Christian village of the Trinity had, moreover, certain gardens which the inhabitants held in common, well irrigated and rich in *vines*, figs, and medicinal fruits. The catechism was publicly rehearsed once on ordinary days, twice on holidays. They held frequent musical services; the youths chanting the psalms, robed in white. The Thána choristers, indeed, enjoyed such a reputation that they were invited to sing at the larger gatherings at Bassein; and were much employed at funerals, at which they chanted the 'Misericordia' to the admiration alike of Christians and heathens. Besides their civil and secular duties in the town of Thána, and at the Christian village and farms, the Brethren of the Order visited a circle of outposts within a distance of thirty thousand paces; 'to the great gain of their countrymen, whom they strengthen in their faith; and of the natives (*barbari*), whom they reclaim from their errors and superstitions to the religion of Christ.'

Cochin, a
collegiate
city.

The station of Thána discloses the regulated industry, spiritual and secular, which characterized the Jesuit settlements in India. Cochin may be taken to illustrate the educational labours of the Order and its general scheme of operations. The College of the Society, writes brother Hieronymus in 1570,¹ has two grammar schools, attended by 260 pupils, who have made excellent progress both in their studies and in the practice of the Christian sacraments. They are all skilled in

¹ Letter to the General of the Order, dated Cochin, February 1570.

the tenets of the faith, many of them have learned the catechism, arranged in questions and answers, and are now teaching it to the heathen. The rites of confession and communion are in constant use, and resorted to on saints' days by 300 or 400 persons. An equal concourse takes place when Indulgences are promulgated, and on a late occasion, when the jubilee granted by the Pope in 1568 was celebrated, 'such was the importunity of those seeking confession, that our priests could not find a breathing space for rest from morning to night.' At the College Church alone a thousand persons received the Eucharist, chiefly new communicants. A whole sale restitution of fraudulent gains took place, with a general reconciliation of enemies and a great quickening of the faith in all. 'So vast was the concourse at this single church, with out mentioning the other churches in the city, that we had from time to time to push out the throngs from the edifice in to the courtyard, not without tears and lamentation on their part.'

The College of the Order likewise ministered to the Portuguese fleet stationed off Cochin, and the writer relates, with perhaps pardonable exaggeration, the strict discipline which the Brethren maintained among both officers and men. During the winter they had also collected a fund, and with it redeemed five Portuguese who the year before, had fallen into captivity among 'the Moors.' These men, on coming to offer up public thanksgiving in church edified the worthy fathers by relating how the Christians still remaining in captivity continued firm in the Catholic faith although sorely tormented *incommodis et cruciatibus*. They told how one youth, in particular, 'who had attended our school on being tied to a tree and threatened by the Moors with bows and arrows, had bravely answered that he would give up his life rather than his faith.' Upon which the Moors seem to have laid aside their lethal weapons, and let the lad off with a few kicks and cuffs. Another boy had at first apostatized, but his fellow-captives, foremost among them a nobleman of high station, threw themselves at his feet, and begged him to stand firm. The boy burst into tears, and declared that he had been led astray by terror, but that he would now rather die than abandon his religion. He proved himself as good as his word, rushed in front of his persecutors, and openly proclaimed himself to be still a Christian. 'The Moors,' as usual, seem to have taken the affair with much good nature, and after another little comedy of tying him to a tree and threatening to shoot him and cut his throat, let their young apostate go.

Jesuit
College at
Cochin

Jesuit
itineraries.

'I come now,' continues Father Hieronymus, 'to the harvest of this year.' He goes on to describe the work of itinerating, from which we gather that the King of Cochin was friendly rather than otherwise to the members of the Order and their converts, protecting them by letters patent, and even giving rise to hopes of his own conversion. No fewer than 220 natives were baptized in one day; and the Father adduces, as a proof of their sincerity, the fact that they did not expect any material advantage from their conversion. 'For neither do they look for a present of new clothes at their baptism, nor for anything else from us, excepting spiritual food. They think themselves greatly honoured by the name of Christians, and labour to bring others to the truth.' Among the converts the Nairs figure a good deal; and an acolyte of this race, notwithstanding that he was harassed by the 'older Christians,' brought in other Nairs, by twos and threes, for baptism. The worthy Father uses 'Nair' as the name of 'a certain military class,' and so touches on the actual position held by this tribe three hundred years ago.

Conver-
sions.

Conversion was not, however, always without its troubles. The story of a young Moor, whose mother was a cruel woman, and buried him in the ground up to his mouth for turning a Christian, is told with honest pride. His unkind parent likewise placed a huge stone round his head, designing that he should die a slow and painful death. But the boy managed to peep through a cleft in the stone, and spied some travellers passing that way, whereupon, although he had formerly known nothing of Latin, he managed to shout out the two words, '*exopto Christum.*' On hearing this, the travellers dug up the lad and took him before the Governor, who, in an obliging manner, gave over the boy to the College to be baptized, and sent the mother to prison. The neophytes seem to have been spirited lads; and the Father narrates how about two thousand of them took part in the military games held when the fleet was lying off Cochin, and distinguished themselves so greatly with various sorts of darts and weapons, that 'they came next to the Portuguese soldiers.'

Efforts at
royal con-
versions.

The College took advantage of the illness of the king during the course of the year to try to convert him; but his majesty, although civil and friendly, declined their well-meaning efforts. They were more successful with two 'petty Rájás' (*reguli*) in the neighbourhood, who, 'being desirous of the Portuguese friendship,' professed an interest in spiritual matters on behalf of themselves and people. Three hundred, apparently of their

subjects, promised to get themselves baptized as soon as a church should be built. 'But,' concludes the candid chronicler, 'as this particular people have a grievously bad reputation as liars, it is much to be prayed for that they will keep their word.' From another instance of a royal conversion, it appears that the introduction of Christianity, with 'letters of privilege' to converts, was a favourite method among the weaker Râjas for securing a Portuguese alliance.

The story of the Catholic missions thus graphically told by the *Rerum Gestarum Volumen* of the 16th century, is continued for the 17th and 18th by the letters from the Jesuit Fathers in Malabar. These letters have been edited by Le Père Bertrand in four volumes, which throw an important light, not only upon the progress of Christianity in India, but also upon the social and political state of the native kingdoms in which that progress was made.¹ The keynote to the policy of the Society of Jesus, in its work of Indian evangelization, is given in the following words — 'The Christian religion cannot be regarded as naturalized in a country, until it is in a position to propagate its own priesthood.'²

This was the secret of the wide and permanent success of the Catholic missions, it was also the source of their chief troubles. For in founding Christianity on an indigenous basis, the Fathers had to accept the necessity of recognising indigenous customs and native prejudices in regard to caste. The disputes which arose divided the Jesuit missionaries for many years, and had to be referred, not only to the General of the Order, but to the Pope himself. The *Question des Rites Malabares* occupies many pages in Père Bertrand's volumes.³ In the end, a special class of native priests was assigned to the low castes, while an upper class ministered to the Indians of higher degree. The distinction was rigidly maintained in the churches. Père Bertrand gives the plan of a

The
Malabar
Mission
17th and
18th cen-
turies

Quest on
of caste

¹ *Mémoires Historiques sur les Missions des Jésuites en Asie* (1 vol. 2:1 et 1, Paris, 1852). *La Mission du Maduré d'après ses documents inédits* (3 vols., Paris, 1845, 1850, 1854). The first edition of the *Mémoires Historiques* (Paris, 1847) formed apparently an introduction to the three volumes of Letters which constitute Père Bertrand's *La Mission du Maduré*. The author takes this opportunity of acknowledging his obligations to the authorities of St Xavier's College, Calcutta, for the loan of Père Bertrand's works, and for much kindness and assistance in his inquiries.

² Condensed from Père Bertrand, *Mémoires* vol. I. p. 1.

³ For example, *Mémoires Historiques*, vol. I. pp. 353 et seq. In fact this volume is largely devoted to the polemics of the question. Also *La Mission du Maduré*, vol. I. pp. 140 et seq. vol. II. pp. 404 to 416, and in many other places of Père Bertrand's works.

Jesuit
itineraries.

'I come now,' continues Father Hieronymus, 'to the harvest of this year.' He goes on to describe the work of itinerating, from which we gather that the King of Cochin was friendly rather than otherwise to the members of the Order and their converts, protecting them by letters patent, and even giving rise to hopes of his own conversion. No fewer than 220 natives were baptized in one day; and the Father adduces, as a proof of their sincerity, the fact that they did not expect any material advantage from their conversion. 'For neither do they look for a present of new clothes at their baptism, nor for anything else from us, excepting spiritual food. They think themselves greatly honoured by the name of Christians, and labour to bring others to the truth.' Among the converts the Nairs figure a good deal; and an acolyte of this race, notwithstanding that he was harassed by the 'older Christians,' brought in other Nairs, by twos and threes, for baptism. The worthy Father uses 'Nair' as the name of 'a certain military class,' and so touches on the actual position held by this tribe three hundred years ago.

Conver-
sions.

Conversion was not, however, always without its troubles. The story of a young Moor, whose mother was a cruel woman, and buried him in the ground up to his mouth for turning a Christian, is told with honest pride. His unkind parent likewise placed a huge stone round his head, designing that he should die a slow and painful death. But the boy managed to peep through a cleft in the stone, and spied some travellers passing that way, whereupon, although he had formerly known nothing of Latin, he managed to shout out the two words, '*exopto Christum.*' On hearing this, the travellers dug up the lad and took him before the Governor, who, in an obliging manner, gave over the boy to the College to be baptized, and sent the mother to prison. The neophytes seem to have been spirited lads; and the Father narrates how about two thousand of them took part in the military games held when the fleet was lying off Cochin, and distinguished themselves so greatly with various sorts of darts and weapons, that 'they came next to the Portuguese soldiers.'

Efforts at
royal con-
versions.

The College took advantage of the illness of the king during the course of the year to try to convert him; but his majesty, although civil and friendly, declined their well-meaning efforts. They were more successful with two 'petty Rájás' (*reguli*) in the neighbourhood, who, 'being desirous of the Portuguese friendship,' professed an interest in spiritual matters on behalf of themselves and people. Three hundred, apparently of their

subjects, promised to get themselves baptised as soon as a church should be built. But concludes the same observation, 'as this particular people have a generally bad reputation of liars, it is much to be feared for that they will keep their word.' From another instance of a royal conversion it appears that the introduction of Christianity with 'honors of privilege' to converts, was a favorite method among the ruler Rajas for securing a Portuguese Alliance.

The story of the Catholic missions thus gradually told by the *Retour Gesteiro* of the 17th century, is continued for the 17th and 18th by the letters from the Jesuit Fathers in Malabar. These letters have been edited by Père Bertrand in four volumes, which serve as important data not only upon the progress of Christianity in India, but also upon the social and political state of the native kingdoms in which that progress was made. The key-note to the policy of the Society of Jesus, in its work of Indian evangelization is given in the following words:—'The Christian religion cannot be regarded as naturalized in a country, until it is in a position to propagate its own priesthood.'¹

This was the secret of the wide and permanent success of the Catholic missions; it was also the source of their chief troubles. For in founding Christianity on an indigenous basis, the Fathers had to accept the necessity of recognizing indigenous customs and native prejudices in regard to caste. The disputes which arose divided the Jesuit missionaries for many years, and had to be referred, not only to the General of the Order, but to the Pope himself. The *Question des Rites Malabares* occupies many pages in Père Bertrand's volumes.² In the end, a special class of native priests was assigned to the low castes, while an upper class ministered to the Indians of higher degree. The distinction was rigidly maintained in the churches. Père Bertrand gives the plan of a

¹ *Mémoires Historiques sur les Missions des ordres religieux* (1 vol. 2nd ed., Paris, 1852): *La Mission du Maduré d'après des documents inédits* (3 vols., Paris, 1848, 1850, 1854). The first edition of the *Mémoires Historiques* (Paris, 1847) formed apparently an introduction to the three volumes of Letters which constitute Père Bertrand's *La Mission du Maduré*. The author takes this opportunity of acknowledging his obligations to the authorities of St. Xavier's College, Calcutta, for the loan of Père Bertrand's works, and for much kind assistance in his inquiries.

² Condensed from Père Bertrand, *Missions*, vol. i. p. 1.

³ For example, *Mémoires Historiques*, vol. i. pp. 353 *et seq.* Indeed, this volume is largely devoted to the polemics of the question. Also *La Mission du Maduré*, vol. ii. pp. 140 *et seq.*; vol. iv. pp. 404 to 496; and in many other places of Père Bertrand's work.

Number of *autos da fé*. punishments inflicted. But the records repeatedly speak of the necessity for additional cells, and in 1674 they numbered two hundred. Seventy-one *autos da fé*, or general jail deliveries, are mentioned between 1600 and 1773. The total number of persons condemned on these occasions is unknown. But at a few of the *autos* it is said that '4046 persons were sentenced to various kinds of punishment, of whom 3034 were males and 1012 females.'¹ These punishments included 105 men and 16 women condemned to the flames, of whom 57 were burned alive and 64 in effigy.

Christians
set ex-
ample of
religious
persecu-
tion.

It is not necessary to inquire how far such examples of religious punishment in Portuguese territory were responsible for the persecution of the Catholic missionaries in Cochin and Malabar. Nor, in passing judgment on the Hindu princes, should we forget the perpetual military aggressions and occasional cold-blooded massacres by the Portuguese on the southern and western coasts. Christian missions in Northern India had scarcely anything to fear from the native powers. Indeed, under Akbar, and almost throughout the entire period of the Mughal Emperors until the accession of Aurungzeb, Christianity seems to have been regarded with an enlightened interest, and certainly without disfavour, by the Delhi court. More than one of the Mughal queens and princes are said to have been Christians; and the faith was represented both by Imperial grants and in the Imperial seraglio. Many of the great Hindu Feudatories also displayed a courteous indifference to the Christian missionaries, and a liberal recognition of their scientific and secular attainments.

Inquisition
abolished
1812.

The Inquisition at Goa was temporarily suspended in 1774, but re-established in 1779. It was abolished in 1812, and the ancient palace in which it had been held was pulled down in 1820. The *débris* were finally removed in 1859 on the occasion of the exposition of the body of St. Francis Xavier.²

The
Jesuits
suppressed,
1759-73.

In 1759, Portugal broke up the Society of Jesus, seized its property, and imprisoned its members. France did the same in 1764; and to prevent greater evils, Clement XIV. in 1773 was forced to suppress the Society altogether. The French Revolution followed. These events deprived the Indian

¹ Da Fonseca's *Goa*, p. 220. The original authorities quoted are *O Chronista de Tissuary, Historia dos Principaes actos e Procedimentos da Inquisição em Portugal*, Lisboa, 1845, p. 38; and F. N. Xavier in the *Gabinete Litterario*, vol. iii. pp. 89 and 280; *Narração da Inquisição de Goa*, pp. 143 *et seq.* (Nova Goa, 1866).

² A popular account of its history will be found in Mr. E. Rehatsek's 'Holy Inquisition at Goa,' *Calcutta Review*, No. 145, April 1881.

Jesuit missions alike of priests and of funds, ~~and~~ for a long time they languished, served in the south only by a few priests from Goa and Pondicherry. That dismal period, however, presents some illustrious names, among them two well known writers, the Abbe Dubois of Mysore, and the Carmelite Fr. Paolino de San Bartholomeo (in India 1774-90). In the absence of priests to sustain the courage of the Christians, every occasional or local persecution told. Tipu, about 1784, forcibly circumcised 30,000 Catholics of Kanara, and deported them to the country above the Ghats. Many native Christians lived and died without ever seeing a priest, they baptized their own children, taught them the prayers, and kept up duly worship in their churches.

Better days, however, dawned. In 1814, the Society of the Jesus was re-established, under Gregory XVI, its missions ^{Jesuits re established 1814} began a new life, and have since made great progress. Their prosperity is, however, hampered by the action taken in Europe against the religious orders. The claims of Portugal to appoint the Archbishop of Goa and through him to regulate clerical patronage, as opposed to the right of the Pope, have occasioned schisms in the past, and still give rise to discord.

The Roman Catholics throughout all India, British, Feudal, and Foreign, number altogether 1,356,037 souls, as returned in the table to be presently given from the *Madras Catholic Directory* for 1885. The Census Report of 1881, adding the latest figures for Portuguese and French India, gives a total of 1,248,801. ^{Number of Roman Catholics in India}

The Roman Catholic missions are maintained by many of the European nations, and are nearly equally divided between the secular and regular clergy. Almost every mission contains a mixture of races among its priests, even Holland, Scotland, and Germany being ably represented. Although all are directed by Europeans, seven eighths of the priests are natives. It is also worthy of remark that, in the list of bishops during the last 300 years, the names of several natives are found, some of them Brahmans. The Roman Catholic missions are presided over by sixteen bishops (vicars and prefects apostolic), the delegates of the Pope, who governs the missions himself, without the intervention of the Camera. Side by side with these papal vicars apostolic, who are also bishops, the Archbishop of Goa (appointed by the King of Portugal) has an independent jurisdiction over a certain number of Catholics outside his diocese, who are scattered over India but chiefly in the south. ^{Archbishop of Goa} The prefect apostolic of Pondicherry

presides over the Catholics in several British Districts and throughout the southern French possessions. In Pondicherry he has technically jurisdiction only over 'those who wear hats.'

His separate jurisdiction.

Jus patronatus 1600.

The independent jurisdiction of the Archbishop of Goa, and the dissensions to which it gave rise, have been referred to.

It had its origin in the *Jus patronatus* granted by Pope Clement VIII. to King Philip. By the Pontifical Bull, the Portuguese king was charged with the support of the Catholic churches in India, and in return was invested with the patronage of their clergy. On the ruin of the Portuguese power in India by the Dutch, it was held that the sovereign was no longer in a position to fulfil his part of the agreement. The Indian clergy became a growing charge upon Rome.

Curtailed, 1673.

In 1673, therefore, Clement X. abrogated the jurisdiction of the Portuguese Archbishop of Goa beyond the limits of the Portuguese settlements. In 1674, two Briefs declared that the Portuguese bishops had no authority over the vicars and missionaries-apostolic sent from Rome to India. These orders only produced a long ecclesiastical dispute. Accordingly, in 1837, Gregory XVI. published his Bull, *Multa præclare*, dividing the whole of India into vicariates-apostolic, and forbade the Goanese prelates to interfere in their management.

Concordat of 1857.

The Portuguese Archbishop of Goa disregarded this decree, and the *Indo-Lusitanum schisma* continued until 1861. In 1857, a concordat was agreed to by the Pope and the King of Portugal, by which such churches as were then under the apostolic vicars should remain under the same, while those which then acknowledged the Goanese jurisdiction should

Settlement of 1861.

continue under the Archbishop of Goa. In 1861, joint commissioners were sent out from Rome and Portugal to put this arrangement into execution. In the end, the Pope granted for some time, '*ad tempus*,' to the Archbishop of Goa an extraordinary jurisdiction over certain churches, served by Goanese priests, but beyond the Portuguese dominions. Such churches are still to be found in Malabar, Madura, Ceylon, Madras, Bombay, and apparently in the lower delta of Bengal. It is intended that this independent jurisdiction of the Portuguese Archbishop of Goa shall in time lapse to the vicars-apostolic appointed from Rome. But meanwhile it continues to this day, and still gives rise to occasional disputes.¹

¹ The foregoing two paragraphs on the extraordinary jurisdiction of the Archbishop of Goa are condensed from MS. materials supplied to the author by the papal Vicar-Apostolic of Verapoli.

As the ecclesiastical and civil divisions of India do not correspond, it is difficult to compare missionary with official statistics. The Catholics in French territory numbered, according to the *Madras Catholic Directory* for 1885, 33,226, and in Portuguese territory in 1881, 252,477. This leaves 1,070,334 Catholics for British India and the Native States, according to the *Madras Directory* for 1885, or 963,058 according to the Census Report of 1881. Catholics are most numerous in the Native States of Travancore and Cochin (comprised in the vicariates of Verapoli and Quilon). The archdiocese of Goa, with 660 priests nearly all natives, for a very small territory containing over 250,000 Catholics, is a witness to the sternly proselytizing system of the Portuguese.

Verapoli, the smallest in area of the Roman vicariates, contains the largest number of priests and Catholics. These are chiefly the descendants of the Nestorians converted to Rome in the 16th century and were divided by the Census of 1881 into two classes—of the Syrian rite, 141,386, and of the Latin rite, 80,600. They were directed by 14 European Carmelite priests, and by 375 native priests, 39 of the Latin rite, and 336 of the Syrian rite.

The Census of 1881 returned the Syrian Christians altogether apart from the Roman Catholics but did not distinguish between Jacobites and Catholics of the Syrian rite. Out of a total of 304,410 Syrians in all India, 301,442 are returned by the Census Report as within the Native States of Travancore and Cochin (the vicariates of Verapoli and Quilon). The Census Report returned the total number of Roman Catholics in Travancore and Cochin at 274,734, while the returns officially accepted by the heads of the Catholic Church give the number in the *Madras Catholic Directory* at 378,096. From private inquiries since made, it appears that the discrepancy arises from the fact that the number of Catholics was underrated at the time of the Census. About 100,000 Roman Catholics of the Syrian rite, belonging to the jurisdiction of the vicars apostolic of Verapoli and Quilon, seem to have been included among the Syrian Jacobites.

The Pondicherry and Madura vicariates represent parts of the famous Jesuit missions of Madurai and of the Karnatic. In Bombay city, and along the fertile maritime strip or Konkan between the Western Ghats and the sea, the Roman Catholics form an important section of the native population.

The following table shows the Roman Catholic population for all India, as returned by the authorities of the Church.

ROMAN CATHOLIC POPULATION OF BRITISH INDIA AND NATIVE STATES.

(According to the 'Madras Catholic Directory' for 1885.)

	Number.
Vicariate-Apostolic of Madras,	56,548
" " Haiderabad (Nizam's Dominions),	9,100
" " Vizagapatam,	13,287
" " Mysore,	27,429
" " Coimbatore,	24,027
" " Madura,	176,169
" " Quilon (South Travancore),	97,496
" " Verapoli (North Travancore and Cochin),	280,600
" " Mangalore,	76,000
" " Pondicherri (within British Territory),	174,441
" " Bombay,	51,025
" " Agra,	8,400
" " Patna,	10,000
" " Punjab,	5,900
" " Western Bengal,	18,000
Prefecture-Apostolic of Central Bengal,	1,678
Vicariate-Apostolic of Eastern Bengal,	16,000
" " Southern Burma,	17,580
" " Eastern Burma,	6,654
Total in British India and Native States,	1,070,334

<p>ROMAN CATHOLIC POPULATION OF PORTUGUESE SETTLEMENTS IN INDIA.</p> <p>(According to the Census of February 17th, 1881.)</p>	
Goa,	250,645
Daman,	1,497
Diu,	335
Total in Portuguese Settlements in India,	252,477

<p>ROMAN CATHOLIC POPULATION OF FRENCH SETTLEMENTS IN INDIA.</p> <p>(According to the 'Madras Catholic Directory' for 1885.)</p>	
Pondicherri,	18,889
Karikal,	12,787
Chandarnagar,	300
Yanaon,	450
Mahé,	800
Total in French Settlements in India,	33,226
Grand Total in British, Native, and Foreign India,	1,356,037

The Roman Catholics in India steadily increase; and as in former times, the increase is chiefly in the south, especially in the missions of Pondicherry and Madura. The number of Catholics in British and French India and the Native States, but exclusive of the Portuguese Possessions, rose from 732,887 in 1851, to 934,400 in 1871, and to 1,103,560 in 1881. The Pondicherry mission lately performed over 50,000 adult baptisms in three years. In the Madura vicariate the increase is principally in Tinnevely and Ramanad. The converts are chiefly agriculturists, but are by no means confined to the low castes.

The principal Catholic colleges in India are those of the Society of Jesus, at Calcutta, Bombay, and Negapatam. Another Jesuit college has lately been opened at Mangalore in South Kanara, a District in which there are over 3000 Catholic Brahmins. England, being a Protestant country, supplies few priests, and hence Catholic missions have much difficulty in maintaining colleges where English is the vehicle of higher education. The statistics of the Catholic schools are incomplete, owing to want of information about certain parts of the Goa jurisdiction. But the number of Catholic schools actually returned in 1880 including Goa, was 1514, with 51,610 pupils. In British India and the Native States, the children in Catholic schools increased from 28,249 in 1871, to 44,699 in 1881.

The Roman Catholics work in India with slender pecuniary resources. They derive their main support from two great Catholic organizations, the Association for the Propagation of the Faith, and the Society of the Holy Childhood. The former contributes £24,464 yearly to Indian missions, and the latter £12,300, making a total of £36,764. This is exclusive of the expenditure within the Archbishopric of Goa, but it represents the European contributions to the whole Vicariates under the Pope. In 1880 they maintained a staff of 16 bishops and 1118 priests, teaching 1236 schools, with 40,907 pupils, and giving religious instruction to 1,002,379 native Christians. The Roman Catholic priests deny themselves the comforts considered necessities for Europeans in India. In many Districts they live the frugal and abstemious life of the natives, and their influence reaches deep into the social life of the communities among whom they dwell.

The first Protestant missionaries in India were Lutherans, Ziegenbalg and Plutschau, who in 1705 began work under the patronage of the King of Denmark at the Danish settlement

First Protestant mission, 1705.

Transla-
tion of the
Bible,
1725.

of Tranquebar. Ziegenbalg and many of the early Lutheran missionaries were men of great ability; and, besides their translations of the Scriptures, some of their writings still hold a high place in missionary literature. Ziegenbalg began the translation of the Bible into Tamil, and his successor Schultze completed it in 1725. This was the first Protestant translation of the Scriptures in India. Schultze also translated the whole Bible into Hindustani. Ziegenbalg died in 1719, leaving 355 converts. In spite of the patronage of the Kings of Denmark and England, and the liberal assistance of friends in Europe, the Lutheran mission made at first but slow progress, and was much hindered and opposed by the local Danish authorities. Gradually it extended itself into Madras, Cuddalore, and Tanjore; schools were set up, and conversion and education went hand in hand.

Schwartz
in Tan-
jore,
1750-98.
Serampur
mission-
aries.

In 1750, arrived the pious Schwartz, whose name is bound up with the history of Tanjore and adjacent Districts until his death in 1798. He was the founder of the famous Tinneveli missions.¹ Next to the Lutherans come the Baptists of Serampur, with the honoured names of Carey, Marshman, and Ward. In the 18th century, the English East India Company did not discourage the labours of Protestant missionaries. It had allowed Kiernander, originally sent out by the Danes, to establish himself at Calcutta in 1758. But subsequently, it put every obstacle in the way of missionaries, and deported them back to England on their landing. Carey arrived in 1793. In 1799, to avoid the opposition of the English East India Company, he established himself with four other missionaries at Serampur (15 miles from Calcutta), at that time, like Tranquebar, a Danish possession. Then began that wonderful literary activity which has rendered illustrious the group of 'Serampur missionaries.' In ten years, the Bible was translated, and printed, in whole or part, in 31 languages; and by 1816, the missionaries had about 700 converts. The London Missionary Society (established 1795) entered the field in 1798, and its missions have gradually grown into importance.

Kiern-
ander in
Calcutta,
1758.

Carey,
1793.

31 transla-
tions of the
Bible.

Official
opposi-
tion with-
drawn,
1813.

The opposition of the East India Company continued till 1813, when it was removed by the new Charter. The same document provided for the establishment of the bishopric of Calcutta, and three archdeaconries, one for each Presidency. Up to this period the Established Church of England had attempted no direct missionary work, although some of the East India Company's chaplains had been men of zeal, like the

¹ See article TINNEVELLI, *The Imperial Gazetteer of India*.

ardent Henry Martyn (1806-11) The first Bishop of Calcutta ^{Bishopric of Calcutta,} (Middleton) arrived in 1814 From this time the Church of England has constantly kept up a missionary connection with India, chiefly by means of its two great societies—the Church Missionary Society, which sent out its first representative in 1814, and the Society for the Propagation of the Gospel, which did so in 1826 Their most successful stations are in Southern India, where they have gathered in the seed sown by the Lutheran missions The second Bishop of Calcutta was the well known Heber (1823-26) In 1835 under a new Charter of the Last ^{Indian} India Company, the see of Madras was established, and in ^{Sees} 1837, that of Bombay In 1877, owing to the extension of mission work in Innervelli two missionaries were appointed bishops, as assistants to the Bishop of Madras, the dioceses of Lahore and Rangoon also were separated from Calcutta, and bishops appointed The missionary bishopric of Travancore and Cochin was established in 1879 It has no connection with Government, nor have the assistant bishops in Madras

The first missionary of the Church of Scotland was Dr Alexander Duff (1830-63), to whom the use of English as ^{Presby} the vehicle of higher education in India is largely due ^{terian mi} ^{sions,} ¹⁸³⁰⁻⁶³ ^{Other} ^{missions.} Missionaries of numerous other Protestant societies (European and American) have since entered India, and established numbers of churches and schools They have furnished memorable names to the roll of Indian educators, such as Judson (Baptist) in Burma, 1813-50, and John Wilson (Presbyterian) of Bombay, 1843-75

The progress of the several Protestant missions in India may be thus stated — In 1830 there were 9 societies at ^{Statistics of Pro} work, and about 27,000 native Protestants in all India, ^{testant} ^{missions} Ceylon, and Burma By 1870 there were no less than 35 societies at work, and in 1871 there were 318,363 converts (including Ceylon, etc., as above) In 1852 there were 459 Protestant missionaries, and in 1872 there were 606 Between 1856 and 1878, the converts made by the Baptist ^{Progress} ^{1856 to} ¹⁸⁷⁸ Societies of England and America, in India, Ceylon, and Burma, increased from about 30,000 to between 80,000 and 90,000 Those of the Basle missions of Germany multiplied from 1060 to upwards of 6000, those of the Wesleyan Methodist missions of England and America, from 7500 to 12,000, those of the American Board, from 3302 to

of peculiar care among the missionary bodies. The number of girls' day schools belonging to Protestant missions in India alone has risen from 285 in 1851 to 1120 in 1881. This is exclusive of girls' boarding schools and *zandua* work. The total number of female pupils, under Protestant mission teaching in India alone, exclusive of Burma, has multiplied from 11,193 in 1851 to 57,893 in 1881.

The great success of the missionaries of late years in their school work, as in their preaching, is due to the extended use of native agency. Complete statistics are available on this point only for 1871 and 1881. The number of 'Foreign' and Eurasian male teachers belonging to Protestant missions in India and Burma, has decreased from 146 in 1871 to 101 in 1881, while the native Christian teachers have been doubled, from 1978 in 1851 to 3675 in 1881. In 1881, there were also 2468 non Christian native teachers employed, making a total of 6143 native teachers in missionary employ in 1881, against 101 'Foreign' and Eurasian teachers. The native female teachers, Christian and non Christian, have increased from 863 in India and Burma in 1871, to 1996 in 1881. The following table may now be left to speak for itself —

SUMMARY OF PROTESTANT MISSIONS IN INDIA
AND BURMA

	Number in 1851	Number in 1861	Number in 1871	Number in 1881
Stations,	222	337	445	601
Foreign and Eurasian ordained agents, . . .	339	501	517	622
Native ordained agents,	21	143	302	575
Foreign and Eurasian lay preachers,				77
Native lay preachers,	493	1,677	2,344	2,856
Churches or congregations,	267	643	2,631	4,180
Native Christians,	91,092	198,097	256,057	492,882
Communicants,	14,661	43,415	73,330	135,254
Male pupils in schools,	52,550 ^a	64,525	100,750	135,477
Female pupils in schools,	11,193 ^b	17,035	27,627	57,893
Total male and female pupils,	64,043 ^c	81,563	128,377	196,360

^a Including British, European, American, and all others, not natives of India.

^b The pupils for 1851 were in India only; no returns being available for Burma for that year.

^c The return of total pupils is exclusive of 65,725 boys and girls attending San lay schools. The returns for 1851 and 1861 are as a whole less complete than those for 1871 and 1881.

^d Including British, European, American, and all non Indian teachers.

General
Statistics
of Chris-
tian popu-
lation in
India.

European
and
Native.

The foregoing pages have briefly traced the history of Christianity in India, and disclose the recent progress made by its main branches, Catholic and Protestant, among the natives. It remains to exhibit the Christian population as a whole, including both Europeans and Indians. In comparing the results, it must be borne in mind that the figures have been derived from various sources, and that the areas of enumeration in some cases overlap each other. Thus, the jurisdictions of the Catholic vicars-apostolic supply a basis for calculation which differs from the territorial areas adopted by the Census of British India. Every effort has been made to allow for such causes of error, and to render the following tables a true presentment of the Christian population of India, British, Feudatory, and Foreign. It will be observed that the total number of Christians has increased during the nine years from 1872 to 1881 by 365,251. In British India alone the increase has been 270,807, or 30·2 per cent. The total number of Christians was 2,148,228 in 1881, as against 1,782,977 in 1872.

TOTAL CHRISTIAN POPULATION IN INDIA IN 1872 AND
IN 1881.

	1872.	1881.	Increase	Percentage of Increase.	
In British India, .	897,682	1,168,489	270,807	30·2	Figures for 1872 less complete than for 1881.
In Native States, .	620,295	694,036	73,741	11·9	
In Portuguese India, .	235,000	252,477	17,477	7·4	
In French India, .	30,000	33,226	3,226	10·7	
Total, .	1,782,977	2,148,228	365,251	20·4	

Denomi-
national
Statistics,
1881.

The Census of 1881 returned the Christian population in British and Native India, according to sect. This return is useful as affording a test of the figures given in the foregoing pages from the Roman Catholic and Protestant missions. It will be observed that the two sets of figures practically agree, allowing for differences in the areas of the enumeration. In the total for all India these sources of discrepancy disappear; but it must be remembered that that total includes both Europeans and natives.

CHRISTIAN POPULATION OF INDIA ACCORDING TO SECT
(As returned by the Census of 1881)

	Church of England.	Church of Scotland.	Lutherans	Other Protestant Sects.	Roman Catholics	Syrians	Greeks and Armenians.	Others and Unspecified	Total
INDIAN DISTRICTS									
Madrass.	172,218	1,137	4,667	90,67	473,352	2,895	314	25,903	711,037
Bombay.	1,107	5,762	2,286	2,286	109,456	4	56	79,84	138,317
Bengal.	32,692	3,127	23,512	18,722	26,722	67	1,331	20,741	128,100
United Provinces and O. P.	90,838	2,692	4	1,663	8,021	10	31	1,871	33,420
Central Provinces.	27,024	3,411	483	3,232	9,184	2	85	3,766	47,449
Central Provinces.	4,823	715	12	222	5,833		11	625	11,949
Assam.	1,676	272	221	3,320	351		5	1,227	7,90
Orissa.	631	77	5	41	40			595	1,335
Allore.	392	69	522	31	478		15	93	2,225
British Burma.	9,90	655	346	56,112	17,281			3,152	84,215
Total in British India.	252,284	18,825	27,513	105,418	652,977	2,918	2,132	74,295	1,168,489
NATIVE STATES									
Bombay.	45	95	1	22	6,059			615	6,837
Central Provinces.	7	92			12			17	24
United Provinces.	3,1	22		44	401			82	279
Central India.	1,823	3,3	6	195	1,02		2	3,69	7,71
Chhota Nagpur.	4,99	450	1	184	120,47	14,031		3,69	7,065
Madagascar.	5,56	242		2,012	6,46		1	1,233	13,614
Hyderabad.	103	7		11	20,10		7	892	27,249
Travancore.	57,315				313,815	287,409		1,244	1,294
Total in Native States.	71,429	1,207	9	2,463	310,059	301,443	10	7,410	694,036
Total in British India and Native States.	323,713	20,034	27,522	107,886	963,038	304,410	9,142	81,705	1,862,525
Portuguese India, general return (practically all Catholics).									
Portuguese India.				Do					25,477
Grand Total for all India and Burma.									2,126,228

Notes.—No. 1. It is to be observed that the different sects of Christians in Portuguese India and French India, to the above figures, 252,477 Catholics, 1,168,489 Protestants (1881), and 33,723 Christians (1881), are to be added to the 1,168,489 Christians in British India, and 33,723 Christians in French India, to give the total Christian population of India in 1881, 2,350,691. No. 2. The figures for the Native States of British India, and for the Native States of French India, are to be added to the figures for the Native States of British India, and for the Native States of French India, to give the total Christian population of India in 1881, 2,350,691. No. 3. A considerable discrepancy exists between the number of Roman Catholics in Travancore and in Cochin States as returned by the Census of 1881, and that returned by the Roman Catholic Bishops of those States, as shown on a previous page. The difference is to be explained by the fact that the Roman Catholic Bishops for the entire of the States as returned by the Census of 1881, and that returned by the Roman Catholic Bishops of those States, as shown on a previous page, are to be added to the figures for the Native States of British India, and for the Native States of French India, to give the total Christian population of India in 1881, 2,350,691. No. 4. It is to be observed that the figures for the Native States of British India, and for the Native States of French India, are to be added to the figures for the Native States of British India, and for the Native States of French India, to give the total Christian population of India in 1881, 2,350,691.

Eccle-
siastical
establish-
ment.

The Government of India maintains an ecclesiastical establishment for its European soldiers and officials. It devotes on an average £660,000 a year to their medical requirements, and £160,000 to their spiritual wants.¹ The two following tables show the ecclesiastical staff, and the number of soldiers and Government servants who attend their ministrations. In making up the second table, it has not been found practicable to bring the statistics of attendance beyond the date of the last Parliamentary return of 1880. During the year 1879, to which the attendance columns in the second table refer, a large European force was absent in the field, and the church attendance of European troops was decreased by about 13,000 officers and men.

INDIAN ECCLESIASTICAL STAFF, 1884.

	BISHOPS.		ARCH- DEACONS.		CHAPLAINS.			REGISTRARS.	
	No.	Pay.	No.	Pay.	No.	Pay (sen.).	Pay (jun.).	No.	Pay.
		£		£		£	£		£
Church of England—									
Calcutta, . . .	1	4508	1	1280	92	960	600	1a	480
Lahore, . . .	1	900	1	900			
Rangoon, . . .	1	660	1	900				1	60
Madras, . . .	1	2500	1	1280	39	960	600	1	256
Bombay, . . .	1	2500	1	1280	26	960	600	1	180
Church of Scotland									
Bengal,	1b	1351	4	960	600
Madras,	1b	1140	3	960	600
Bombay,	1b	1140	3	960	600
Roman Catholic									
Priests—									
Bengal, . . .	2	600c	42	360d	240
Madras, . . .	1	600c	15	360d	240
Bombay, . . .	1	600c	18	360d	240
Total, . . .	9	...	8	...	242	4	...

a The registrar of the Calcutta Diocese is also registrar of the Lahore Diocese.

b These are the senior Presbyterian Chaplains in the three Presidencies.

c This is an allowance for furnishing ecclesiastical returns for transmission to England, paid to certain Roman Catholic Bishops in official communication with the British Government. The number of Catholic Bishops is sixteen for all India.

d There is also an intermediate class on £300 per annum. In addition to their rates of pay, Roman Catholic priests receive horse allowance at £36 per annum.

In the following table, it should be borne in mind that the salaries and number of chaplains refer to 1884, while the attendance is that of 1879, when a large force was in the field. The attendance in ordinary years is estimated

¹ The average of the ecclesiastical establishment during the ten years ending 188:

at over 50,000. This would raise the total Church attendance of British troops and Government servants (exclusive of women and children) to about 55,000.

INDIAN ECCLESIASTICAL MINISTRATIONS

	Salaries and Allowances (1884)	No of Priests, Archdeacons, Chaplains or Ministers (1884)	Number of European Troops and Officers ordinarily at tending Church (1879)	Number of other Government Servants (excluding Wives and Children) ordinarily at tending Church (1879)	Total of Government Servants attending Church (1879)
Church of England,	£124,175	167	23,842	3191	27,033
Church of Scotland, .	10,445	13	2,782	479	3,261
Church of Rome .	31,251	79	10,586	621	11,207
Total, . . .	£165,871	259	37,210	4291	41,501

CHAPTER X.

EARLY MUHAMMADAN RULERS (711 TO 1526 A.D.).

WHILE Buddhism was giving place to Hinduism throughout India, and Christianity under Nestorian bishops was spreading along the coast of Malabar, a new faith had arisen in Arabia. Muhammad, born in 570 A.D., created a conquering religion, and died in 632. Within a hundred years after his death, his followers had invaded the countries of Asia as far as the Hindu Kush. Here their progress was stayed, and Islám had to consolidate itself, during three more centuries, before it grew strong enough to grasp the rich prize of India. But, almost from the first, the Arabs had fixed eager eyes upon that wealthy country. Fifteen years after the death of the prophet, Usmán sent a sea-expedition to Thána and Broach on the Bombay coast (647? A.D.). Other raids towards Sind took place in 662 and 664, with no results.

Early Arab
expedi-
tions to
Bombay
coast, 636-
711 A.D.

Muham-
madan
settlement
in Sind,
711-828?

In 711, however, the youthful Kásim advanced into Sind, to claim damages for an Arab ship which had been seized at an Indian port. After a brilliant campaign, he settled himself in the Indus valley; but the advance of the Musalmáns depended on the personal daring of their leader, and was arrested by his death in 714 A.D. The despairing valour of the Hindus struck the invaders with wonder. One Rájput garrison preferred extermination to submission. They raised a huge funeral pile, upon which the women and children first threw themselves. The men then bathed, took a solemn farewell of each other, and, throwing open the gates, rushed upon the besiegers and perished to a man. In 750, the Rájputs are said to have expelled the Muhammadan governor, but it was not till 828 A.D. that the Hindus regained Sind.

Their ex-
pulsion,
828 A.D.

India on
the eve
of the
Muham-
madan
conquest,
1000 A.D.

The armies of Islám had carried the crescent from the Hindu Kush westwards, through Asia, Africa, and Southern Europe, to distant Spain and Gaul, before they obtained a foothold in the Punjab. This long delay was due, not only to the daring of individual tribes, such as the Sind Rájputs just

Their
success-
short-
lived.

Empire in India. That Empire, even in the north of India, had only been consolidated by Akbar's policy of incorporating Hindu chiefs and statesmen into his government (1556-1605). Up to Akbar's time, and even during the earlier years of his reign, a series of Rājput wars had challenged the Muhammadan supremacy. In less than two centuries after his death, the successor of Akbar was a puppet in the hands of the Hindu Maráthás at Delhi.

Muham-
madan
conquests
only partial,

The popular notion that India fell an easy prey to the Musalmáns is opposed to the historical facts. Muhammadan rule in India consists of a series of invasions and partial conquests, during eleven centuries, from Usmán's raid, *circa* 647, to Ahmad Sháh's tempest of invasion in 1761 A.D. They represent in Indian history the overflow of the nomad tribes of Central Asia, towards the south-east; as the Huns, Turks, and various Tartar tribes disclose in early European annals the westward movements from the same great breeding-ground of nations. At no time was Islám triumphant throughout the whole of India. Hindu dynasties always ruled over large areas. At the height of the Muhammadan power, the Hindu princes paid tribute, and sent agents to the Imperial Court. But even this modified supremacy of Delhi lasted for little over a century (1578-1707). Before the end of that brief period, the Hindus had begun the work of reconquest. The native chivalry of Rājputána was closing in upon Delhi from the south; the religious confederation of the Sikhs was growing into a military power on the north-west. The Maráthás had combined the fighting powers of the low-castes with the statesmanship of the Bráhmans, and were subjecting the Muhammadan kingdoms throughout all India to tribute. So far as can now be estimated, the advance of the English power at the beginning of the present century alone saved the Mughal Empire from passing to the Hindus.

and tem-
porary.

Hindus
reconquer
India from
the Musal-
máns,
1707-61.

This chapter will necessarily confine its survey to the essential stages in the spread of the Musalmán conquest, and will pass lightly over the intermediate princes or minor dynasties who flit across the scene.¹ The annexed summary presents a view of the whole :—

¹ The Hon. Mountstuart Elphinstone's *History of India* is still the standard popular work on the Muhammadan period. Professor Cowell's edition (Murray, 1866) incorporated some of the new materials accumulated since Mr. Elphinstone wrote. But much of the original work is a reproduction of *Firishta*, and requires to be re-written from Sir Henry Elliot's *Persian Historians* and the results of the Archaeological and

SUMMARY OF MUHAMMADAN CONQUERORS AND DYNASTIES
OF INDIA (1001-1857)

- I HOUSE OF GHAZNI (Turki)
1001-1186 Mahmud of Ghazni
to Sultan Khusru. Pp 272 75
- II HOUSE OF GHOR (Afghan?)
1186-1206. Muhammad Ghor
(Shahab ud din) Pp 275 78
- III SLAVE KINGS (chiefly Turki)
1206-1290 Kutub ud din Iqbal
Lodhi and Karkut ud din Pp 285 80.
- IV HOUSE OF KHILJI (Turki)
1290-1320 Fakhruddin Muhammad
bin Tughluq Pp 280 83
- V HOUSE OF TUGHLAK (Turki)
1320-1414 Iqbal 285 80
1320. Ghiyas ud din Tughluq
P 283
1324 Muhammad Tughluq I
283 85
1351 Firuz Tughluq I 285
1414 End of the dynasty I 286
[Invasion of the Mughals under
Timur (Tamerlane) in 1398
99, leaving behind him fifteen
years' anarchy under the last
of the line of Tughluqs until
the accession of the Sayyids
in 1414 P 285]
- VI THE SAYYIDS
1414-1450 Curtailed power of
Delhi P 286 *passim*
- VII THE LODHIS (Afghans)
1450-1526 Feeble reigns in independent States I 286
- VIII HOUSE OF TIMUR (Mughal)
1526-1857
1526-1530 Babur I 290
1530-1556 Humayun Pp 290 91
- [Sher Shah, the Afghan governor of Bengal, drives Humayun out of India in 1540, and his Afghan dynasty rules till 1555 P 291]
- 1556-1605 Akbar the Great
I 291-300
1605-1627 Jahangir Pp 300-302
1628-1658 Shah Jahan, deposed
Pp 302-305
1658-1707 Aurangzeb or Alam
giri I 306 312
1707-1719 Bahadur Shah or
Shah Alam I 312
1712 Bahadur Shah I 312
1713-1718 Farrukhsiyar I 312
1719-1748 Muhammad Shah
(after two boy Emperors) Pp
312 313
[Invasion of Nadir Shah the
Persian 1738-1739 I p
313-15]
- 1748-1754 Death of Muhammad
Shah and accession of Ahmad
Shah, deposed 1754 I 313
1754-1759 Alamgir II I 313
[Six invasions of India by
Ahmad Shah Durrani, the
Afghan 1748-1761 I
313 15]
- 1759-1806 Shah Alam II titular
Emperor I 313
1806-1834 Akbar II titular Emperor I 313
1834-1857 Muhammad Bahadur
Shah titular Emperor, the
seventeenth and last Mughal
Emperor died a State prisoner
at Rangoon in 1857. P 313

Statistical Surveys. The present chapter has chiefly used, besides Ephraïm, the following works for the Muhammadan period—(1) Sir Henry Elliot's *History of India as told by its own Historians*, i.e. the Arab and Persian travellers and writers, edited by Professor Dowson, 8 vols. 1867-77 (Trübner), (2) Mr Edward Thomas' *Chronicle of the Muslim Kings of Delhi*, especially for reigns from 1193 to 1554. In which period he gives the annual dates of the Hijra years (Trübner, 1871), (3) Mr Edward Thomas' *Chronicle of the Muslim Emperors*, with his manuscript marginal notes, (4) Lieut. Colonel James Translation of Muhammad Kasim Firishta's *History of the Fate of the Muhammadan*

First
Türkí
invasions.

The first collision between Hinduism and Islám on the Punjáb frontier was the act of the Hindus. In 977, Jaipál, the Hindu chief of Lahore, annoyed by Afghán raids, led his troops up the passes against the Muhammadan kingdom of Ghazní, in Afghánistán. Subuktigín, the Ghaznvide prince, after severe fighting, took advantage of a hurricane to cut off the Hindu retreat through the pass. He allowed them, however, to return to India on the surrender of fifty elephants, and the promise of one million *dirhams* (about £25,000).¹ Tradition relates how Jaipál, having regained his capital, was counselled by the Bráhmaṇ, standing at his right hand, not to disgrace himself by paying ransom to a barbarian; while his nobles and warrior chiefs, standing at his left, implored him to keep faith. In the end, Subuktigín swept down the passes to enforce his ransom, defeated Jaipál, and left an Afghán officer with 10,000 horse to garrison Pesháwar. Subuktigín was soon afterwards called away to fight in Central Asia, and his Indian raid left behind it only this outpost.² But henceforth, the Afgháns held both ends of the passes.

Subukti-
gín, 977
A.D.

Mahmúd
of Ghazní,
1001-1030.

In 997, Subuktigín died, and was succeeded by his son, Mahmúd of Ghazní, aged sixteen. This valiant monarch reigned for thirty-three years,³ and extended the limits of his father's little Afghán kingdom from Persia on the west, to deep into the Punjab on the east. Having spent four years in consolidating his power to the west of the Khaibar Pass, he led forth in 1001 A.D. the first of his seventeen⁴ invasions of India.

His seven-
teen inva-
sions,
1001-1026.

Power in India; (5) Reports of the Archæological Survey of Western India, and materials supplied by the Statistical Survey of the various Provinces of India; (6) Professor Blochmann's *Ain-i-Akbari* (Calcutta, 1873), together with Gladwin's older translation (2 vols. 1800). When the dates or figures in this chapter differ from Elphinstone's, they are derived from the original Persian authorities, as adopted by Sir Henry Elliot and Mr. Thomas.

¹ The *Táríkh Yamíní*, written *circa* 1020, by Al 'Utbi, a secretary of Sultán Mahmúd, is the contemporary authority for this invasion. It is translated in Sir Henry Elliot's *Persian Historians*, vol. ii. pp. 18-24. The materials for the invasions of Subuktigín are *Firishṭa*, i. pp. 11-25 (ed. 1829); and Sir Henry Elliot's *Persian Historians*, vols. ii. iii. iv. and vi.

² His chronicler, Al 'Utbi, never once mentions Delhi or Lahore.

³ The *Tabakát-i-Násirí* (Sir Henry Elliot's *Persian Historians*, vol. ii. p. 270) speaks of the '36th year of his reign.' But the dates 997 to 1030 seem authoritative. The original materials for the invasions of Mahmúd are *Firishṭa*, i. pp. 37-82; and Sir Henry Elliot's *Persian Historians*, vols. i. ii. iii. and iv.

⁴ This number, and subsequent details, are taken from the authorities translated in Sir Henry Elliot's *Persian Historians*, vols. ii. iii. iv.; and critically examined in the Appendix to his second volume, pp. 434-478 (1869).

Of these, thirteen were directed to the subjugation of the Punjab; one was an unsuccessful incursion into Kashmir; the remaining three were short but furious raids against more distant cities—Kanauj, Gwalior, and Somnāth.

Jaipāl, the Hindu frontier chief of Lahore, was again defeated. According to Hindu custom, a twice-conquered prince was deemed unworthy to reign, and Jaipāl, mounting a funeral pile, solemnly made over his kingdom to his son, and burned himself in his regal robes. Another local chief, rather than yield himself to the victor, fell upon his own sword. In the sixth expedition (1008 A.D.), the Hindu ladies melted their ornaments, while the poorer women spun cotton, to support their husbands in the war. In one great battle, the fate of the invaders hung in the balance. Mahmud, alarmed by a coalition of the Indian kings as far as Oudh and Mālwa, entrenched himself near Peshawar. A sortie which he made was driven back, and the wild Ghakkar tribe¹ burst into the camp and slaughtered nearly 4000 Musalmāns.

But each expedition ended by further strengthening the Muhammadan foothold in India. Mahmud carried away enormous booty from the Hindu temples, such as Thaneshwar and Nagarkot, and his sixteenth and most famous expedition was directed against the temple of Somnāth in Gujarat (1024 A.D.). After bloody repulses, he stormed the town, and the Hindu garrison, leaving 5000 dead, put out in boats to sea. The famous idol of Somnāth was merely one of the twelve *lingas* or phallic emblems erected in various parts of India. But Mahmūd having taken the name of the 'Idol Smasher,' the modern Persian historians gradually converted the plunder of Somnāth into a legend of his pious zeal. Forgetting the contemporary accounts of the idol as a rude stump of stone, Firishṭa tells how Mahmūd, on entering the temple, was offered

¹ Firishṭa says, '30,000 Ghakkars with their heads and feet bare.' Colonel Briggs's *Firishṭa*, vol. i. p. 47 (ed. 1829). Elphinstone gives the number of Mahmud's expeditions somewhat differently from the number and order adopted in the above text from the Persian authorities, translated by Sir Henry Elliot. Thus Elphinstone gives the expedition of 1008 A.D. as the fourth (p. 325), while Sir Henry Elliot gives it as the sixth (*Persian Historians*, vol. i. p. 444). In the same way, Elphinstone gives the Somnāth expedition as the twelfth (p. 334, ed. 1866), while Sir Henry Elliot gives it as the sixteenth (vol. ii. p. 465). These instances must suffice to indicate the differences between Elphinstone and the later materials derived from Sir Henry Elliot and Mr. Edward Thomas. In subsequent pages, the more accurate materials will be used without pausing to point out such differences.

Fiction of the jewel-bellied god. an enormous ransom by the priests if he would spare the image.¹ But Mahmúd cried out that he would rather be remembered as the breaker than the seller of idols, and clove the god open with his mace. Forthwith a vast treasure of jewels poured forth from its vitals, which explained the liberal offers of the priests, and rewarded the disinterested piety of the monarch. The growth of this myth can be clearly traced,² but it is still repeated by uncritical historians. The *linga* or solid stone fetish of Somnáth, had no stomach, and could contain no jewels.

The sandal-wood gates. Mahmúd carried off the temple gates, with fragments of the phallic emblem, to Ghazni,³ and on the way nearly perished with his army in the Indus desert. But the famous 'Sandal-wood gates of Somnáth,' brought back as a trophy from Ghazni by our troops in 1842, and paraded through Northern India, were as clumsy a forgery as the story of the jewel-bellied idol itself. Mahmúd died at Ghazni in 1030 A.D.

Results of Mahmúd's invasions, 1030 A.D. As the result of seventeen invasions of India, and twenty-five years' fighting, Mahmúd had reduced the western districts of the Punjab to the control of Ghazni, and left the remembrance of his raids as far as Kanauj on the east, and Gujarát in the south. He never set up as a resident sovereign in India. His expeditions beyond the Punjab were the adventures of a religious knight-errant, with the plunder of a temple-city, or the demolition of an idol, as their object, rather than serious efforts at conquest. But as his father had left Pesháwar as an outpost garrison, so Mahmúd left the Punjab as an outlying Province of Ghazni.

The Punjab conquered. Mahmúd's justice and thrift. The Muhammadan chroniclers tell many stories, not only of Mahmúd's valour and piety, but also of his thrift. One day a poor woman complained that her son had been killed by robbers in a distant desert of Irak. Mahmúd said he was very sorry, but that it was difficult to prevent such accidents so far from the capital. The old woman rebuked him with these words,

¹ Colonel Brigg's *Firishta*, vol. i. pp. 72, 73 (ed. 1829).

² Sir H. Elliot's *History of India from the Persian Historians*, vol. ii. p. 270, from the *Tabakát-i-Násiri*; also Appendix, vol. ii. p. 476; vol. iv. pp. 182, 183, from the *Habibu-s-Siyar* of Khondamir. But see, even in 1832, H. H. Wilson in the *Asiatic Researches*, vol. xvii. pp. 194 *et seq.* A foundation for *Firishta*'s invention is, however, to be found in the contemporary account of Al Biruni (970-1029 A.D.), who says that the top of the *linga* was garnished with gems of gold.

³ Of the four fragments, he deposited one in the Jamá Masjid at Ghazni, another at the entrance of his palace, and the third he sent to Mecca, and the fourth to Medina. *Tabakát-i-Násiri*.

'Keep therefore no more territory than you can rightly govern' The Sultan forthwith rewarded her, and sent troops to guard all caravans passing that way. Mahmud was an enlightened patron of poets, and his liberality drew the great Ferdousi to his court. The Sultan listened with delight to his *Shih námah*, or Book of Kings, and promised him a *dirham*, meaning a golden one, for each verse on its completion. After thirty years of labour, the poet claimed his reward. But the Sultan finding that the poem had run to 60 000 verses, offered him 60 000 silver *dirhams* instead of *dirhams* of gold. Ferdousi retired in disgust from the court, and wrote a bitter satire which records to this day the base birth of the monarch. Mahmud forgave the satire, but remembered the great epic, and, repenting of his meanness, sent 100 000 golden *dirhams* to the poet. The bounty came too late. For as the royal messengers bearing the bags of gold entered one gate of Ferdousi's city, the poet's corpse was being borne out by another.

During 1 century and 1 half, the Punjab remained under Mahmud's successors, as a Province of Gházni. But in 1152, the Afgháns of Ghor¹ overthrew the Ghaznívide dynasty, and Khusru, the last of Mahmud's line, fled to Lahore, the capital of his outlying Indian territory. In 1186, this also was wrested from him,² and the Ghorian prince Shaháb ud-dín better known as Muhammad of Ghor, began the conquest of India on his own account. But each of the Hindu principalities fought hard, and some of them still survive seven centuries after the torrent of Afghán invasion swept over their heads.

On his first expedition towards Delhi, in 1191, Muhammad of Ghor was utterly defeated by the Hindus at Thaneshwar, badly wounded, and barely escaped with his life. His scattered hosts were chased for 40 miles. But he gathered together the wreck at Lahore and aided by new hordes from Central Asia, again marched into Hindustán in 1193. Family quarrels among the Kaypúts prevented a united effort against him.

¹ Clor, one of the oldest seats of the Afghán race, is now a ruined town of Western Afghánistán 120 miles south-east of Herat. The feud between Ghor and Ghazni was of long standing and great bitterness. Mahmud of Ghazni had subdued Clor in 1010 A.D. But about 1031 the Ghorian chief seized Ghazni and dragged its chief inhabitants to Ghor, where he cut their throats and used their blood for making mortar for the fortifications. After various reprisals, Clor finally triumphed over Ghazni in 1152.

² *Tarikh-i-Alai*, vol. II, pt. II, p. 251.

Dissensions among the Hindu princes.

The cities of Delhi and Kanauj stand forth as the centres of rival Hindu monarchies, each of which claimed the first place in Northern India. A Chauhán prince, ruling over Delhi and Ajmere, bore the proud name of Prithwí Rájá or Suzerain. The Ráhtor king of Kanauj, whose capital can still be traced across eight square miles of broken bricks and rubbish,¹ celebrated a feast, in the spirit of the ancient Horse-sacrifice,² to proclaim himself the Over-lord.

Court pageant at Kanauj, 12th century A.D.

A *swayamvara*, or maiden's choice.

At such a feast, all menial offices had to be filled by royal vassals: and the Delhi monarch was summoned as a gate-keeper, along with the other princes of Hindustán. During the ceremony, the daughter of the King of Kanauj was nominally to make her *swayamvara*, or 'own choice' of a husband, a pageant survival of the reality in the Sanskrit epics. The Delhi Rájá loved the maiden, but he could not brook to stand at another man's gate. As he did not arrive, the Kanauj king set up a mocking image of him at the door. When the princess entered the hall to make her choice, she looked calmly round the circle of kings, then stepping proudly past them to the door, threw her bridal garland over the neck of the ill-shapen image. Forthwith, says the story, the Delhi monarch rushed in, sprang with the princess on his horse, and galloped off towards his northern capital. The outraged father led out his army against the runaways, and, having called in the Afgháns to attack Delhi on the other side, brought about the ruin of both the Hindu kingdoms.

Distribution of Rájputs, *circa* 1184.

The tale serves to record the dissensions among the Rájput princes, which prevented a united resistance to Muhammad of Ghor. He found Delhi occupied by the Tomára clan, Ajmere by the Chauháns, and Kanauj by the Ráhtors. These Rájput States formed the natural breakwaters against invaders from the north-west. But their feuds are said to have left the King of Delhi and Ajmere, then united under one Chauhán Over-lord, only 64 out of his 108 warrior chiefs. In 1193, the Afgháns again swept down on the Punjab. Prithwí Rájá of Delhi and Ajmere³ was defeated and slain. His heroic princess burned herself on his funeral pile. Muhammad of Ghor, having occupied Delhi, pressed on to Ajmere; and in

¹ See article KANAUJ, *The Imperial Gazetteer of India*.

² *Aswa-medha*, described in a previous chapter.

³ Descended from the eponymous Rájá Aja of Ajmere, *circa* 145 A.D.; and on the mother's side, from Anang Pál Tuar, Rájá of Delhi, who adopted him; thus uniting Delhi to Ajmere. See article AJMERE-MERWARA, in *The Imperial Gazetteer of India*.

1194, overthrew the rival Hindu monarch of Kanauj, whose body was identified on the field of battle by his false teeth. The brave Rahtor Rājputs of Kanauj, with other of the Rājput clans in Northern India, quitted their homes in large bodies rather than submit to the stranger. They migrated to the regions bordering on the eastern desert of the Indus, and there founded the military kingdoms which bear their name, Rājputānā, to this day.

Rājput
migrated
into Raj-
putana

History takes her narrative of these events from the matter of fact statements of the Persian annalists.¹ But the Hindu court bard of Prithwī Raja left behind a patriotic version of the fall of his race. His ballad chronicle, known as the *Prithvirāj Rāsau* of Chānd, is one of the earliest poems in Hindi. It depicts the Musalman invaders as beaten in all the battles except the last fatal one. Their leader is taken prisoner by the Hindus, and released for a heavy ransom. But the quarrels of the chiefs ruined the Hindu cause.

Setting aside these patriotic songs, Benares and Gwalior mark the south western limits of Muhammad of Ghor's own advance. But his general, Bakhtiyār Khilji, conquered Bihar in 1199,² and Lower Bengal down to the delta in 1203. On the approach of the Musalmāns, the Brāhman advised Lakshman Sen, the King of Bengal, to remove his residence from Nadiyā to some more distant city. But the prince, an old man of eighty, could not make up his mind until the Afghān general had seized his capital, and burst into the palace one day while his majesty was at dinner. The monarch slipped out by a back door without having time to put on his shoes, and fled to Puri in Orissa, where he spent his remaining days in the service of Jagannāth.³

Muham-
madan
conquest of
Bengal,
1203

Meanwhile the Sultān, Muhammad Ghori, divided his time between campaigns in Afghānistān and Indian invasions, and he had little time to consolidate his Indian conquests. Even in the Punjab, the tribes were defeated rather than subdued. In 1203, the Ghakkars issued from their mountains,

¹ *Tarikh-i Alā'ud-dīn* of Mubārak Shāh and others translated in Sir Henry Elliot's *History of the Sikhs*, vol. ii, p. 111.

² *History of Bengal from the first Muhammadan Invasion to 1757* by Major Charles Stewart, p. 25 (Calcutta, 1847). The nearly contemporary authority is the *Tarikh-i Alā'ud-dīn* (1227-41), Sir Henry Elliot's *History of the Sikhs*, vol. ii, pp. 307-309.

³ Stewart, p. 27. The *Tarikh-i Alā'ud-dīn* merely says "he went towards Sankhū (ii) (Jagannāth)". Sir Henry Elliot's *History of the Sikhs*, vol. ii, p. 309.

took Lahore,¹ and devastated the whole Province.² In 1206, a party of the same clan swam the Indus, on the bank of which the Afghán camp was pitched, and stabbed the Sultán to death while asleep in his tent.³

Muhammad of Ghor's work in India, 1191-1206.

Muhammad of Ghor was no religious knight-errant like Mahmúd of Ghazní, but a practical conqueror. The objects of his distant expeditions were not temples, but Provinces. Subuktigín had left Pesháwar as an outpost of Ghazní (977 A.D.); and Mahmúd had reduced the western Punjab to an outlying Province of the same kingdom (1030 A.D.). That was the net result of the Túrki invasions of India. But Muhammad of Ghor left the whole north of India, from the delta of the Indus to the delta of the Ganges, under Muhammadan generals, who on his death set up for themselves.

Northern India subdued.

Kutab-ud-dín, 1206-10;

first 'Slave King.'

His Indian Viceroy, Kutab-ud-dín, proclaimed himself sovereign of India at Delhi, and founded a line which lasted from 1206 to 1290. Kutab claimed the control over all the Muhammadan leaders and soldiers of fortune in India from Sind to Lower Bengal. His name is preserved at his capital by the Kutab Mosque, with its graceful colonnade of richly-sculptured Hindu pillars, and by the Kutab *Minár*,⁴ which raises its tapering shaft, encrusted with chapters from the Kurán, high above the ruins of old Delhi. Kutab-ud-dín had started life as a Túrki slave, and several of his successors rose by valour or intrigue from the same low condition to the throne. His dynasty is accordingly known as that of the Slave Kings. Under them India became for the first time the seat of resident Muhammadan sovereigns. Kutab-ud-dín died in 1210.⁵

The Slave Dynasty, 1206-90.

The Slave Dynasty found itself face to face with the three perils which have beset the Muhammadan rule in India from the outset, and beneath which that rule eventually succumbed. First, rebellions by its own servants, Musalmán generals, or viceroys of Provinces; second, revolts of the Hindus;

¹ *Firishta*, vol. i. pp. 182-184.

² As far south as the country near Múltán, *Táju-l-Ma-ásir*; Sir II. Elliot's *Persian Historians*, vol. ii. pp. 233-235; *Tárikh-i-Alfi*, v. 163. The Muhammadan historians naturally minimize this episode.

³ Sir H. Elliot's *Persian Historians*, vol. ii. pp. 235, 297, 393. Briggs's *Firishta*, vol. i. pp. 185, 186.

⁴ *The Imperial Gazetteer of India*, article DELHI CITY.

⁵ The original materials for Kutab-ud-dín Aibak's reign are to be found in *Firishta*, vol. i. pp. 189-202 (ed. 1829); and the *Persian Historians*, translated by Sir Henry Elliot, vols. ii. iii. iv. and v.

third, fresh invasions, chiefly by Mughals, from Central Asia

Altamsh, the third and greatest Sultán of the Slave line (1211-36 A D), had to reduce the Muhammadan Governors of Lower Bengal and Sind, both of whom had set up as independent rulers, and he narrowly escaped destruction by a Mughal invasion. The Mughals under Chingiz Khan swept through the Indian passes in pursuit of an Afghan prince, but their progress was stayed by the Indus, and Delhi remained untouched. Before the death of Altamsh (1236 A D), the Hindus had ceased for a time to struggle openly, and the Muhammadan Viceroys of Delhi ruled all India on the north of the Vindhya range, including the Punjab, the North Western Provinces, Oudh, Behar, Lower Bengal, Ajmere, Gwalior, Malwa, and Sind. The Khalif of Baghdad acknowledged India as a separate Muhammadan kingdom during the reign of Altamsh, and struck coins in recognition of the new Empire of Delhi (1229 A D).¹ Altamsh died in 1236.

His daughter Raziya was the only lady who ever occupied the Muhammadan throne of Delhi (1236-39 A D). Learned in the Kurán, industrious in public business, firm and energetic in every crisis, she bears in history the masculine name of the *Sultán* Raziya. But the favour which she showed to the master of the horse, an Abyssinian slave, offended her Afghan generals, and after a troubled reign of three and a half years, she was deposed and put to death.²

Mughal irruptions and Hindu revolts soon began to undermine the Slave dynasty. The Mughals are said to have burst through Tibet into North Eastern Bengal in 1245,³ and during the next forty four years, repeatedly swept down the Afghan passes into the Punjab (1244-88). The wild Indian tribes, such as the Ghakkars⁴ and the hillmen of Mewat, ravaged the Muhammadan lowlands almost up to the capital.

¹ *Chronicles of the Pathán Kings of Delhi* by Edward Thomas, p. 46 (Milne, 1871). Original materials for Shams ud-din Altamsh. *Firishta*, vol. i p. 205 212 (1829), Sir Henry Elliot's *Persian Histories* vol. ii p. 113.

² Thomas *Chronicles of the Pathán Kings*, pp. 104 108. *Firishta*, vol. i p. 217 222. Sir Henry Elliot's *Persian Histories* vol. ii and iii.

³ This invasion of Bengal is discredited by the latest and most critical historian Mr. Edward Thomas, in his *Pathán Kings of Delhi*, p. 121, note (ed. 1871). On the other side see *Firishta* vol. i p. 231, but cf. Col. Briggs's footnote, and the *Tahkik-i-Salasil* in Sir H. Elliot's *Persian Histories*, vol. ii p. 264 344. 'In March 1245, the infidels of Chaghatay came to the gates of Delhi' (Gauz).

⁴ For an account of the Ghakkars, see p. 186 of this volume.

with his cavalry, and plundered the Buddhist temple city of
Lihlsa, 300 miles off. After trying his powers against the
rebellious Hindu princes of Bundelkhand and Mithi he
conceived the idea of a grand raid into the Deccan. With
a band of 8000 horse, he rode into the heart of Southern
India. On the way he gave himself out as flying from his
uncle's court, to seek service with the Hindu King of Rājama-
hendri. The generous Rajput princes abstained from attacking
a refugee in his flight and Alauddin surprised the great city of
Deogarh, the modern Daulatabad at that time the capital of the
Hindu kingdom of Mahārashtra. Having suddenly galloped
into its streets, he announced himself as only the advance
guard of the whole imperial army, levied an immense booty,
and carried it back 700 miles to the seat of his Governorship
on the banks of the Ganges. He then lured the Sultan
Jalal ud din, his uncle, to Karra in order to divide the spoil,
and murdered the old man in the act of clasping his hand
(1205 A.D.)¹

Alauddin scattered his spoils in gifts or charity, and proclaimed himself Sultan (1295-1315 A.D.). The twenty years of his reign founded the Muhammadan sway in Southern India. He reconquered Gujarat from the Hindus in 1297, captured Rintimbur, after a difficult siege, from the Jajpur Rajputs in 1300, took the fort of Chittor and partially subjugated the Sesodia Rajputs (1303) and having thus reduced the Hindus on the north of the Vindhya prepared for the conquest of the Deccan. But before starting on this great expedition he had to meet five Mughal invasions from the north. In 1295 he defeated a Mughal invasion under the walls of his capital, Delhi, in 1304-5 he encountered four others sending all prisoners to Delhi, where the chiefs were trampled by elephants, and the common soldiery slaughtered in cold blood. He crushed with equal severity several rebellions which took place among his own family during the same period, first putting out the eyes of his insurgent nephews, and then beheading them (1299-1300).

Having thus arranged his affairs in Northern India he under H. 1301 took the conquest of the South. In 1303 he had sent his ^{Q. extd} eunuch slave, Malik Kafur, with an army through Bengal to ^{to the} attack Warangal the capital of the Hindu kingdom of Telugu. 1303 15

¹ Thomas' *First Latin*, 2, 144.

² Materials for the reign of Māuiddin Khilji. See Henry II. 1. 1. *Journal of the Asiatic Society of India* (1871). *Journal of the Asiatic Society of India* (1872).

³ See also J. KANTOR, *The Defenses of the State* (1964).

ána. In 1306, Káfur marched victoriously through Málwá and Khándesh into the Maráthá country, where he captured Deogiri, and persuaded the Hindu king Rám Deo to return with him to do homage at Delhi. While the Sultán Alá-ud-dín was conquering the Rájputs in Márwár, his slave general, Káfur, made expeditions through the Karnátic and Maháráshtra, as far south as Adam's Bridge, at the extremity of India, where he built a mosque.

His general, Malik Káfur.

Extent of the Muhammadan power in India, 1306.

Muhammadan population in India, 1286-1311.

Mughal mercenaries, 1286-1311.

Hindu revolts.

A renegade Hindu Emperor, 1316-20;

The Muhammadan Sultán of India was no longer merely an Afghán king of Delhi. Three great waves of invasion from Central Asia had created a large Muhammadan population in Northern India. First came the Túrki's, represented by the house of Ghazni; then the Afgháns (commonly so called), represented by the house of Ghor; finally the Mughals, having failed in their repeated attempts to conquer the Punjab, took service in great numbers with the Sultáns of Delhi. Under the Slave Kings the Mughal mercenaries had become so powerful as to require to be massacred (1286). About 1292, three thousand Mughals, having been converted from their old Tartar rites to Muhammadanism, received a suburb of Delhi, still called Mughalpur, for their residence. Other immigrations of Mughal mercenaries followed. After various plots, Alá-ud-dín slaughtered 15,000 of the settlers, and sold their families as slaves (1311 A.D.).

The unlimited supply of soldiers which Alá-ud-dín could thus draw upon from the Túrki, Afghán, and Mughal races in Northern India and the countries beyond, enabled him to send armies farther south than any of his predecessors. But in his later years, the Hindus revolted in Gujarát; the Rájputs reconquered Chittor; and many of the Muhammadan garrisons were driven out of the Deccan. On the capture of Chittor in 1303, the garrison had preferred death to submission. The peasantry still chant an early Hindí ballad, telling how the queen and thirteen thousand women threw themselves on a funeral pile, while the men rushed upon the swords of the besiegers. A remnant cut their way to the Aravalli Hills; and the Rájput independence, although in abeyance during Alá-ud-dín's reign, was never crushed. Having imprisoned his sons, and given himself up to paroxysms of rage and intemperance, Alá-ud-dín died in 1315, helped to the grave, it is said, by poison given by his favourite general, Káfur.

During the four remaining years of the house of Khiljí, the actual power passed to Khusrú Khán, a low-caste renegade

Hindu, who imitated the military successes and vices of his patron, Malik Kafur, and then personally superintended his murder¹ Khusru now became all in all to the debauched Emperor Mubarak, slew him, and seized the throne While outwardly professing Islam, Khusru desecrated the Kuran by using it as a seat, and degraded the pulpits of the mosques into pedestals for Hindu idols In 1320 he was slain, and the Khilji dynasty disappeared "

The leader of the rebellion was Ghiyas ud din Tughlak, who had started life as a Turki slave, and risen to the frontier Governorship of the Punjab He founded the Tughlak dynasty, which lingered on for ninety four years (1320-1414), although submerged for a time by the invasion of Timur (Tamerlane) in 1398 Ghiyas ud din Tughlak (1320-24 A D) removed the capital from Delhi to a spot about four miles further east, and called it Tughlakabad

His son and successor, Muhammad Tughlak (1324-51), was an accomplished scholar, a skilful captain, and a severely abstinent man² But his ferocity of temper, perhaps inherited from the tribes of the steppes, rendered him merciless as a judge and careless of human suffering The least opposition drove him into outbursts of insane fury He wasted the treasures accumulated by Ala ud din in buying off the Mughal hordes, who again and again swept down on the Punjab On the other hand, in fits of ambition, he raised an army for the invasion of Persia, and sent out an expedition of 100,000 men against China The first force broke up for want of pay, and plundered his own dominions, the second perished almost to a man in the Himálayan passes He planned great conquests into Southern India, and dragged the whole inhabitants of Delhi, 800 miles off, to Deogiri, to which he gave the name of Daulatabad Twice he allowed the miserable suppliants to return to Delhi, twice he compelled them on pain of death to quit it One of these forced migrations took place amid the horrors of a famine, the citizens perished by thousands, and in the end the king had to give up the attempt Having drained his treasury, he issued a forced currency of copper coins, by which he tried to make the king's brass equal to other men's

¹ Thomas *Path in Kings*, pp 178 179

² *Ibid*, pp 184 185

³ Materials for his reign Sir Henry Elliot's *Persian Historians*, vols 1 iii v vi vii, *Firishta*, vol 1 pp 408-443 (ed 1829), Elphinstone's narrative of this reign is an admirable specimen of his spirited style of work, pp 403 410 (ed 1866)

silver.¹ During the same century, the Mughal conqueror of China, Kublai Khán, had expanded the use of paper notes, early devised by the Chinese; and Kai Khátú had introduced a bad imitation of it into Persia. Tughlak's forced currency quickly brought its own ruin. Foreign merchants refused the worthless brass tokens, trade came to a stand, and the king had to take payment of his taxes in his own depreciated coinage.

Revolt of
the Pro-
vinces,
1338-51.

He slays
his
nephew.

His reign
one long
revolt.

Muham-
mad
Tughlak's
revenue
exactions,
1325-51.

His 'man-
hunt.'

Meanwhile the Provinces began to throw off the Delhi yoke. Muhammad Tughlak had succeeded in 1324 to the greatest Empire which had, up to that time, acknowledged a Muhammadan Sultán in India. But his bigoted zeal for Islám forbade him to trust either Hindu princes or Hindu officers; and he thus found himself compelled to fill every high post with foreign Muhammadan adventurers, who had no interest in the stability of his rule. The annals of the period present a long series of outbreaks, one part of the Empire renouncing its allegiance as soon as another had been brought back to subjection. His own nephew rebelled in Málwá, and being caught, was flayed alive (1338). The Punjab governor revolted (1339), was crushed, and put to death. The Musalmán Viceroy's of Lower Bengal and of the Coromandel coast set up for themselves (about 1340), and could not be subdued. The Hindu kingdoms of Karnáta and Telingána recovered their independence (1344), and expelled the Musalmán garrisons. The Muhammadan governors in the Deccan also revolted, while the troops in Gujarát rose in mutiny. Muhammad Tughlak rushed with an army to the south to take vengeance on the traitors, but hardly had he put down their rising than he was called away by insurrections in Gujarát, Málwá, and Sind. He died in 1351, while chasing rebels in the lower valley of the Indus.

Muhammad Tughlak was the first Musalmán ruler of India who can be said to have had a revenue system. He increased the land-tax between the Ganges and the Jumna; in some Districts ten-fold, in others twenty-fold. The husbandmen fled before his tax-gatherers, leaving their villages to lapse into jungle, and formed themselves into robber clans. He cruelly punished all who trespassed on his game preserves; and he invented a kind of man-hunt without precedent in the annals of human wickedness. He surrounded a large tract with his army, 'and then gave orders that the circle should close

¹ Thomas' *Pathán Kings*, p. 243. See his valuable monograph entitled 'Muhammad Bin Tughlak's Forced Currency,' *op. cit.* pp. 239-261.

towards the centre, and that all within it (mostly inoffensive peasants) should be slaughtered like wild beasts. This sort of hunt was more than once repeated; and on a subsequent occasion, there was a general massacre of the inhabitants of the great city of Kanauj. These horrors led in due time to famine, and the miseries of the country exceeded all powers of description.¹

His son, Firuz Tughlak (1351-88), ruled mercifully, but had to recognise the independence of the Muhammadan kingdoms of Bengal and the Deccan, and suffered much from bodily infirmities and court intrigues.² He undertook many public works, such as dams across rivers for irrigation, tanks, caravan strais, mosques, colleges, hospitals, and bridges. But his greatest achievement was the old Jumna Canal. This work drew its waters from the Jumna, near a point where it leaves the mountains and connected that river with the Ghaggar and the Sutlej by irrigation channels.³ Part of it has been reconstructed by the British Government, and spreads a margin of fertility on either side to this day. But the dynasty of Tughlak soon sunk amid Muhammadan mutinies and Hindu revolts, and under Mahmud, its last real king, Northern India fell an easy prey to the great Mughal invasion of 1398.

In that year, Timur (Tamerlane) swept through the Afghan passes at the head of the united hordes of Tartary. He defeated the Tughlak King, Mahmud, under the walls of Delhi, and entered the capital. During five days, a massacre raged, 'some streets were rendered impassable by heaps of dead,'⁴ while Timur calmly looked on and held a feast in honour of his victory. On the last day of 1398 he resumed his march, with a 'sincere and humble tribute of grateful praise' to God, in Firuz's marble mosque on the banks of the Jumna. He crossed the Ganges, and proceeded as far as Hardwar, after another great massacre at Meerut. Then, skirting the foot of the Himalayas, he retired through their north western passes into Central Asia (1399).

Timur left no traces of his power in India, save ruined cities. On his departure, Mahmud Tughlak crept back from

¹ Elphinstone's *History of India*, pp. 405-406 (ed. 1866).

² Materials for his reign. Sir Henry Elliot's *Indian Historians*, vols. i. iv. vi. viii., *Firushda*, vol. i. pp. 444-465 (ed. 1829).

³ Thomas' *Path in Kings*, p. 294. See article JUMNA CANAL, WESTERN, *The Imperial Gazetteer of India*.

⁴ *Firushda*, vol. i. p. 493. His whole account of Timur's invasion is very vivid, vol. i. pp. 485-497 (ed. 1829).

Firuz Shah
Tughlak
1351-88

Hiscanal,

Mahmud
Tughlak

Timur's
(Tamerlane's)
invasion
1398

Ruin of
the Tugh
laks, 1399

his retreat in Gujarát, and nominally ruled till 1412. The Tughlak line ended in 1414.

The
Sayyids,
1414-50.

It was succeeded by the Sayyid dynasty, who ruled from 1414 till 1450. The Afghán house of Lodi followed, from 1450 to 1526. But some of these Sultáns reigned over only a few miles round Delhi; and during the whole period, the Hindu princes and the local Muhammadan kings were practically independent throughout the greater part of India. The house of Lodi was crushed beneath the Mughal invasion of Bábar in 1526.

The Lodís,
1450-1526.

Hindu
kingdoms
of the
Deccan.

Chera,
Chola, and
Pándya.

Bábar founded the Mughal Empire of India, whose last representative died a British State prisoner at Rangoon in 1862. Before entering on the story of that great Empire, we must survey for a moment the kingdoms, Hindu and Muhammadan, on the south of the Vindhya range. The three ancient kingdoms, Chera, Chola, and Pándya occupied, as we have seen,¹ the Dravidian country peopled by Tamil-speaking races. Pándya, the largest of them, had its capital at Madura, and traces its foundation to the 4th century B.C. The Chola kingdom had its head-quarters successively at Combaconum and Tanjore. Talkad, in Mysore, now buried by the sands of the Káveri, was the capital of the Chera kingdom. The 116th king of the Pándya dynasty was overthrown by the Muhammadan general Malik Káfur, *circa* 1304. But the Musalmáns failed to establish their power in the extreme south, and a series of Hindu dynasties ruled from Madura over the old Pándya kingdom until the 18th century. No European kingdom can boast a continuous succession such as that of Madura, traced back by the piety of genealogists to the 4th century B.C. The Chera kingdom enumerates fifty kings, and the Chola sixty-six, besides minor dynasties.

Kingdom
of Vijaya-
nagar,
1118-1565.

But authentic history in Southern India begins with the Hindu kingdom of Vijayanagar or Narsinha, which flourished from 1118 to 1565 A.D. The capital can still be traced within the Madras District of Bellary, on the right bank of the Tungabhadra river,—vast ruins of temples, fortifications, tanks, and bridges, now inhabited by hyænas and snakes. For at least three centuries, Vijayanagar dominated the southern part of the Indian peninsula. Its Rájás waged war and made peace on equal terms with the Muhammadan Sultáns of the Deccan.

Those Sultáns derived their origin from the conquest of

¹ At the beginning of this chapter; and articles CHERA, CHOLA, PANDYA, in *The Imperial Gazetteer of India*.

Alá ud din (*post* 1303 A D) After a period of confused fighting, the Bahmaní kingdom of the Deccan emerged as the representative of Muhammadan rule in Southern India. Its founder, Zafar Khan, an Afghan general during the reign of Muhammad Tughlak (1325-51), defeated the Delhi troops, and set up as Musalmán sovereign of the Deccan. Having in early youth been the slave of a Brahman who had treated him kindly and foretold his future greatness, he took the title of Bahmaní,¹ and transmitted it to his successors

The rise of the Bahmaní dynasty is usually assigned to the year 1347, and it lasted for 178 years, until 1525.² Its successive capitals were Gulbargah Warangal, and Bidar, all in the Haidarábád territory and it loosely corresponded with the Nizám's Dominions of the present day. At the height of their power, the Bahmaní kings claimed sovereignty over half the Deccan, from the Tungabhadra river in the south to Orissa in the north and from Masulipatam on the east to Goa on the west. Their direct government was, however, much more confined. In their early struggle against the Delhi throne, they derived support from the Hindu southern kingdoms of Vijayanagar and Warangal. But during the greater part of its career, the Bahmaní dynasty represented the cause of Islám against Hinduism on the south of the Vindhya. Its alliances and its wars alike led to a mingling of the Musalman and Hindu populations.

For example, the King of Málwá invaded the Bahmaní dominions with a mixed force of 12,000 Afgháns and Rajputs. The Hindu Rajá of Vijayanagar recruited his armies from Afghan mercenaries, whom he paid by assignments of land, and for whom he built a mosque. The Muhammadan Bahmaní troops, on the other hand, were often led by converted Hindus. The Bahmaní army was itself made up of two hostile sects of Musalmáns. One sect consisted of Shiás, chiefly Persians, Turks or Tartars from Central Asia, the other, of native born Musalmáns of Southern India, together with Abyssinian mercenaries, both of whom professed the Sunni faith. The rivalry between these Musalman sects frequently imperilled the Bahmaní throne. The dynasty reached its highest power under the Bahmaní Alá ud-dín II about 1437, and was broken up by its discordant elements between 1489 and 1525.

¹ His royal name in full was Sultan (or Shah) Ala ud dín Gango Bahmaní.

² These extreme dates are taken from Thomas' *Pathán Kings*, pp 340, 341. Materials for the Bahmaní dynasty. Sir Henry Elliot's *Persian Historians*, vols IV V VI VIII, *Firishá*, vol II pp 283-558 (ed 1879).

Five Muhammadan States of the Deccan, 1489-1688.

Out of its fragments, five independent Muhammadan kingdoms in the Deccan were formed. These were—(1) The Adil Sháhí dynasty, with its capital at Bijápur, founded in 1489 by a son of Amurath II., Sultán of the Ottomans; annexed by the Mughal Emperor Aurangzeb in 1686-88. (2) The Kutab Sháhí dynasty, with its capital at Golconda, founded in 1512 by a Túrkomán adventurer; also annexed by Aurangzeb in 1687-88. (3) The Nizám Sháhí dynasty, with its capital at Ahmadnagar, founded in 1490 by a Bráhman renegade from the Vijayanagar Court; subverted by the Mughal Emperor Sháh Jahán in 1636. (4) The Imad Sháhí dynasty of Berar, with its capital at Ellichpur, founded in 1484 also by a Hindu from Vijayanagar; annexed to the Ahmadnagar kingdom (No. 3) in 1572. (5) The Baríd Sháhí dynasty, with its capital at Bídár, founded 1492-1498 by a Túrki or Georgian slave. The Baríd Sháhí territories were small and undefined; independent till after 1609. Bídár fort was finally taken by Aurangzeb in 1657.

Fall of Hindu kingdom of Vijayanagar.

Space precludes any attempt to trace the history of these local Muhammadan dynasties of Southern India. They preserved their independence until the firm establishment of the Mughal Empire in the north, under Akbar's successors. For a time they had to struggle against the great Hindu kingdom of Vijayanagar. In 1565 they combined against that power, and, aided by a rebellion within Vijayanagar itself, they overthrew it at Tálíkot in 1565.

Battle of Tálíkot, 1565.

Independent Náyaks and Pálegárs of Southern India.

The battle of Tálíkot marks the final downfall of Vijayanagar as a centralized Hindu kingdom. But its local Hindu chiefs or Náyaks seized upon their respective fiefs, and the Muhammadan kings of the south were only able to annex a part of its dominions. From the Náyaks are descended the well-known Pálegárs of the Madras Presidency, and the present Mahárájá of Mysore. One of the blood-royal of Vijayanagar fled to Chandragiri, and founded a line which exercised a prerogative of its former sovereignty by granting the site of Madras to the English in 1639. Another scion, claiming the same high descent, lingers to the present day near the ruins of Vijayanagar, and is known as the Rájá of Anagundi, a feudatory of the Nizám of Haidarábád. The independence of the local Hindu chiefs in Southern India, throughout the Muhammadan period, is illustrated by the Manjarábád family, which maintained its authority from 1397 to 1799.¹

Lower Bengal threw off the authority of Delhi in 1340. Its

¹ See article MANJARABAD, *The Imperial Gazetteer of India*.

Muhammadan governor, Fakir ud din, set up as sovereign, with his capital at Gaur, and stamped coin in his own name. A succession of twenty independent kings ruled Bengal until 1538, when it was temporarily annexed to the Mughal Empire by Humayun. It was finally incorporated with that Empire by Akbar in 1576. The great province of Gujarat in Western India had in like manner grown into an independent Muhammadan kingdom, which lasted for two centuries, from 1391 till conquered by Akbar in 1573. Malwa, which had also set up as an independent State under its Muhammadan governors, was annexed by the King of Gujarat in 1531. Even Jaunpur, including the territory of Benares, in the very centre of the Gangetic valley, maintained its independence as a separate Musalman State for nearly a hundred years from 1394 to 1478, under the disturbed rule of the Sayyids and of the first Lodi at Delhi.

Independence of Bengal, 1340-1576.

Of Gujarat, 1391-1573.

Of Jaunpur, 1394-1478.

CHAPTER XI.

THE MUGHAL EMPIRE (1526 TO 1761 A.D.).

State of India in 1526. WHEN, therefore, BABAR invaded India in 1526, he found it divided among a number of local Muhammadan kings and Hindu princes. An Afghán Sultán of the house of Lodí, with his capital at Agra, ruled over what little was left of the historical kingdom of Delhi. Bábar, literally the Lion, born in 1482, was the sixth in descent from Timúr the Tartar. At the early age of twelve, he succeeded his father in the petty kingdom of Ferghána on the Jaxartes (1494); and after romantic adventures, conquered Samarkand, the capital of Tamerlane's line in 1497. Overpowered by rebellion, and driven out of the Valley of the Oxus, he seized the kingdom of Kábul in 1504. During twenty-two years he grew in strength on the Afghán side of the Indian passes, till in 1526 he burst through them into the Punjab, and defeated the Delhi sovereign Ibráhim Lodí at Pánípat. This was the first of the three great battles which decided the fate of India on that same plain, viz. in 1526, 1556, and 1761. Having entered Delhi, he received the allegiance of the Muhammadans, but was speedily attacked by the Rájputs of Chittor. In 1527, Bábar defeated them at Fatehpur Síkri near Agra, after a battle memorable for its perils and for Bábar's vow, in his extremity, never again to touch wine. He rapidly extended his power as far as Múltán and Behar. He died at Agra in 1530, leaving an Empire which stretched from the river Amu in Central Asia to the borders of the Gangetic delta in Lower Bengal.

Early life of Bábar, 1482-1526.

Invades India, 1526.

Battles of Pánípat.

Conquers Northern India, 1526-30.

Humáyún, Emperor, 1530-56. His son, HUMAYUN, succeeded him in India, but had to make over Kábul and the Western Punjab to his rival brother Kámrán.¹ Humáyún was thus left to govern a new conquest,

A.D. ¹ REIGN OF HUMAYUN :—

1530. Accession to the throne. Capture of Lahore and occupation of the Punjab by his rival brother Kámrán. Final defeat of the Lodís under Mahmúd Lodí, and acquisition of Jaunpur by Humáyún.

1532. Humáyún's campaigns in Málwá and Gujarát.

[Footnote continued on next page.]

and at the same time was deprived of the base from which his father had drawn his supplies. The Mughal hordes who had accompanied Bábar were more hateful to the long settled Indian Afgháns than the Hindus themselves. After ten years of fighting, Humáyún was driven out of India by the Bengali Afgháns under Sher Sháh, the Governor of Bengal. While flying through the desert of Sind, as an exile to Persia, his famous son Akbar was born to him in the petty fort of Umarkot (1542). Sher Shah set up as Emperor, but was killed while storming the rock fortress at Káhnjar (1545). His son succeeded to his power. But under his grandson, the third of the Afghán house, the Provinces revolted, including Malwá, the Punjab, and Bengal. Humáyún returned to India, and with Akbar, then only in his thirteenth year, defeated the Indo Afghán army after a desperate battle at Pánipat (1556). India now passed finally from the Afghans to the Mughals. Sher Sháh's line disappears, and Humayun, having recovered his Kabul dominions, reigned again for a few months at Delhi, but died in 1556.

Humayun expelled by Sher Shah

Afghan dynasty of Delhi, 1540-56

Humayun regains his throne

AKBAR THE GREAT, the real founder of the Mughal Empire as it existed for two centuries, succeeded his father at the age of fourteen¹. Born in 1542, his reign lasted for almost fifty years, from 1556 to 1605, and was therefore contemporary with that of our own Queen Elizabeth (1558-1603). His father, Humáyún, left but a small kingdom in India, scarcely extending beyond the districts around Agra and Delhi. At the time of Humayun's death, Akbar was absent in the Punjab under the guardianship of Bairam Khan, fighting the revolted Afgháns. Bairam, a Turkoman by birth, had been the support of the exiled Humayun, and held the real command of the army which restored him to his throne at Pánipat in 1556. He now

Akbar the Great, 1556-1605

1539 Humayun defeated by Sher Sháh, the Afghan ruler of Bengal, at Chapar Ghat, near Baxar, the Mughal army being utterly routed. Retreats to Agra.

1540 Humayun finally defeated by Sher Shah near Kanauj, and escapes to Persia as an exile. Sher Shah ascends the Delhi throne.

1556 Humayun's return to India, and defeat of the Afghans at Pánipat by his young son Akbar. Remounts the throne, but dies in a few months, and is succeeded by Akbar.

For dates see Thomas' *Pathán Kings*, pp. 379-380. Materials for Humayun's reign. Sir Henry Elliot's *Persian Historians*, vols. iv & v, *Firishita*, vol. ii pp. 154-180 (1829), Elphinstone, pp. 441-472 (1866).

¹ Materials for reign of Akbar the *Ain-i-Akbari*, of Abul Fazl (old translation by Francis Gladwin, 2 vols., 1800, best edition by Professor Blochmann (Calcutta, 1873), left unfinished at his death), Sir Henry Elliot's *Persian Historians*, vols. i & v and vi, *Firishita*, vol. ii pp. 1812-82, Elphinstone, 495-547 (1866).

Bairám
Regent,
1556-60.

Akbar
reigns for
himself,
1560.

Akbar's
work in
India.

became the Regent for the youthful Akbar, under the honoured title of Khán Bába, equivalent to 'the King's Father.' Brave and skilful as a general, but harsh and overbearing, he raised many enemies; and Akbar, having endured four years of thralldom, took advantage of a hunting-party to throw off his minister's yoke (1560). The fallen Regent, after a struggle between his loyalty and his resentment, revolted, was defeated, but pardoned. Akbar granted him a liberal pension; and Bairám was in the act of starting on a pilgrimage to Mecca, when he fell beneath the knife of an Afghán assassin, whose father he had slain in battle.

The chief events in the reign of Akbar are summarized below.¹ India was seething with discordant elements. The earlier invasions by Túrks, Afgháns, and Mughals had left a powerful Muhammadan population in India under their own chiefs. Akbar reduced these Musalmán States to Provinces of the Delhi Empire. Many of the Hindu kings and Rájput nations had also regained their independence; Akbar brought them into political dependence to his authority. This double task he effected partly by force of arms, but in part also by

¹ REIGN of AKBAR, 1556-1605:—

1542. Born at Umarkot in Sind.

1555-56. Regains the Delhi throne for his father by the great victory over the Afgháns at Pánípat (Bairám Khán in actual command). Succeeds his father after a few months in 1556, under regency of Bairám Khán.

1560. Akbar assumes the direct management of the kingdom. Revolt of Bairám, who is defeated and pardoned.

1566. Invasion of the Punjab by Akbar's rival brother Hákim, who is defeated.

1561-68. Akbar subjugates the Rájput kingdoms to the Mughal Empire.

1572-73. Akbar's campaign in Gujarát, and its re-annexation to the Empire.

1576. Akbar's re-conquest of Bengal; its final annexation to the Mughal Empire.

1581-93. Insurrection in Gujarát. The Province finally subjugated in 1593 to the Mughal Empire.

1586. Akbar's conquest of Kashmír; its final revolt quelled in 1592.

1592. Akbar's conquest and annexation of Sind to the Mughal Empire.

1594. His subjugation of Kandahár, and consolidation of the Mughal Empire over all India north of the Vindhya as far as Kábul and Kandahár.

1595. Unsuccessful expedition of Akbar's army to the Deccan against Ahmadnagar under his son Prince Murád.

1599. Second expedition against Ahmadnagar by Akbar in person. Captures the town, but fails to establish Mughal rule.

1601. Annexation of Khándesh, and return of Akbar to Northern India.

1605. Akbar's death at Agra.

N.B. — Such phrases as 'Akbar's conquest' or 'Akbar's campaign' mean the conquest or campaign by Akbar's armies, and do not necessarily imply his personal presence.

alliances He enlisted the Rájput princes by marriage and by a sympathetic policy in the support of his throne He then employed them in high posts, and played off his Hindu generals and Hindu ministers against the Mughal party in Upper India, and against the Afghan faction in Bengal

Concilia-
tion of
Hindus

On his accession in 1556, he found the Indian Empire confined to the Punjab, and the districts around Agra and Delhi He quickly extended it at the expense of his nearest neighbours, namely, the Rajputs Jampur was reduced to a fief of the Empire, and Akbar cemented his conquest by marrying the daughter of its Hindu prince Jodhpur was in like manner overcome, and Akbar married his heir, Salim, who afterwards reigned under the title of Jahangir, to the grand-daughter of the Rájá. The Rájputs of Chittor were overpowered after a long struggle, but disinclined to mingle their high-caste Kshattriyan blood even with that of an Emperor They found shelter among the mountains and in the deserts of the Indus, whence they afterwards emerged to recover most of their old dominions, and to found their capital of Udaipur, which they retain to this day They still boast that alone, among the great Rájput clans, they never gave a daughter in marriage to a Mughal Emperor

Albani
extends
the
Empire

Pe-
luction
of Raj-
puts,
1561-68

Akbar pursued his policy of conciliation towards all the Hindu States He also took care to provide a career for the lesser Hindu nobility He appointed his Hindu brother in law, the son of the Jaipur Rájá, to be Governor of the Punjab Rájá Mán Singh, also a Hindu relative, did good war service for Akbar from Kábul to Orissa. He ruled as Akbar's Governor of Bengal from 1589 to 1604, and again for a short time under Jahángir in 1605-06 Akbar's great finance minister, Raja Todar Mall, was likewise a Hindu, and carried out the first land settlement and survey of India. Out of 415 *mansabdars*, or commanders of horse, 51 were Hindus Akbar abolished the *jazia*, or tax on non Musalmans, and placed all his subjects upon a political equality He had the Sanskrit sacred books and epic poems translated into Persian, and showed a keen interest in the literature and religion of his Hindu subjects

Employ-
ment of
Hindus

Mán
Singh

Todar
Mall

He respected their laws, but he put down their inhuman rites He forbade trial by ordeal, animal sacrifices, and child marriages before the age of puberty He legalized the re-marriage of Hindu widows, but he failed to abolish widow burning on the husband's funeral pile, although he took steps to ensure that the act should be a voluntary one

Reform of
Hindu
customs

Akbar thus incorporated his Hindu subjects into the

Indian
Muham-
madan
States
reduced by
Akbar.

effective machinery of his Empire. With their aid he reduced the independent Muhammadan kings of Northern India. He subjugated the Musalman potentates from the Punjab to Behar. After a struggle, he wrested Bengal from its Afghan princes of the house of Sher Sháh, who had ruled it from 1539 to 1576. From the latter date, Bengal remained during two centuries a Province of the Mughal Empire, under governors appointed from Delhi (1576-1765). In 1765 it passed by an imperial grant to the British. Orissa, on the Bengal seaboard, submitted to Akbar's armies under his Hindu general, Todar Mall, in 1574.

On the opposite coast of India, Gujarát was reconquered from its Muhammadan king in 1572-73, although not finally subjugated until 1593. Málwá had been reduced in 1570-72. Kashmir was conquered in 1586, and its last revolt quelled in 1592. Sind was also annexed in 1591-92; and by the recovery of Kandahár in 1594, Akbar had extended the Mughal Empire from the heart of Afghanistan across all India north of the Vindhya to Orissa and Sind. The magnificent circumference of Mughal conquest in Northern India and Afghanistan was thus complete.

Capital
changed
from Delhi
to Agra.

Akbar also removed the seat of the Mughal government from Delhi to Agra, and founded Fatehpur Sikri to be the future capital of the Empire. From this latter project he was, however, dissuaded, by the superior position of Agra on the great water-way of the Jumna. In 1566 he built the Agra fort, whose red sandstone battlements majestically overhang the river to this day.

Akbar's
efforts in
Southern
India.

His efforts to establish the Mughal Empire in Southern India were less successful. Those efforts began in 1586, but during the first twelve years were frustrated by the valour and statesmanship of Chánd Bibí, the queen-regent of Ahmadnagar. This celebrated lady skilfully united the Abyssinian and the Persian factions¹ in the Deccan, and strengthened herself by an alliance with Bijápur and other Muhammadan States of the south. In 1599, Akbar led his armies in person against the princess; but, notwithstanding her assassination by her mutinous troops, Ahmadnagar was not reduced till the reign of Sháh Jahán, in 1637. Akbar subjugated Khándesh; and with this somewhat precarious annexation, his conquests in the Deccan ceased. He returned to Northern India, perhaps feeling that the conquest of the south was beyond the strength of his young Empire. His last years were rendered miserable by the intrigues of his family, and by the misconduct of his

Only
annexed
Khándesh.

¹ Professing the hostile Sunni and Shiah creeds.

beloved son, Prince Salim, afterwards Jahangir. In 1605 he died, and was buried in the noble mausoleum at Sikandra, whose mingled architecture of Buddhist design and Arabesque tracery bear witness to the composite faith of the founder of the Mughal Empire. In 1873, the British Viceroy, Lord Northbrook, presented a cloth of honour to cover the plain marble slab beneath which Akbar lies.

Akbar's conciliation of the Hindus, and his interest in their literature and religion, made him many enemies among the pious Musalmáns. His favourite wife was a Rájput princess, another of his wives is said to have been a Christian, and he ordered his son Prince Murad, when a child, to take lessons in Christianity. On Fridays (the Sabbath of Islám) he loved to collect professors of many religions around him. He listened impartially to the arguments of the Brahman and the Musalmán, the Parsi, the ancient fire-worshipper, the Jew, the Jesuit, and the sceptic philosopher. The history of his life, the *Akbar namah*, records such a conference, in which the Christian priest Redif disputed with a body of Muhammadan *mullas* before an assembly of the doctors of all religions, and is given the best of the argument. Starting from the broad ground of general toleration, Akbar was gradually led on by the stimulant of cosmopolitan discussion to question the truth of his inherited beliefs.

The counsels of his friend Abul Fazl,¹ coinciding with that sense of superhuman omnipotence which is bred of despotic power, led him at last to promulgate a new State religion,—‘the Divine Faith,’ based upon natural theology, and comprising the best practices of all known creeds. Of this eclectic creed Akbar himself was the prophet, or rather the head of the Church. Every morning he worshipped in public the sun, as the representative of the divine soul which animates the universe, while he was himself worshipped by the ignorant multitude. It is doubtful how far he encouraged this popular adoration, but he certainly allowed his disciples to prostrate themselves before him in private. The stricter Muhammadans accused him, therefore, of accepting a homage permitted only to God.²

¹ Abul Fazl is accused, by the unanimous voice of the Muhammadan historians, of leading away Akbar's religious sympathies from Islam. See the valuable biography of *Shaikh Abul Fa'iz 'Allami*, prefixed to Blochmann's *Ain-i-Akbari*, p. xxix, etc.

² Akbar's perversion from Islam has formed the subject of much learned censure by Mulla 'Abdul Kadir Badauni and other Musalman writers. The question is exhaustively dealt with by Blochmann in a 'Note' of 46 pages *Ain-i-Akbari*, pp. 167-213. See also Sir Henry Elliot's *Persian Historians*, vol. v. pp. 477 et seq.

Indian
Muham-
madan
States
reduced by
Akbar.

effective machinery of his Empire. With their aid he reduced the independent Muhammadan kings of Northern India. He subjugated the Musalmán potentates from the Punjab to Behar. After a struggle, he wrested Bengal from its Afghán princes of the house of Sher Sháh, who had ruled it from 1539 to 1576. From the latter date, Bengal remained during two centuries a Province of the Mughal Empire, under governors appointed from Delhi (1576-1765). In 1765 it passed by an imperial grant to the British. Orissa, on the Bengal seaboard, submitted to Akbar's armies under his Hindu general, Todar Mall, in 1574.

On the opposite coast of India, Gujarát was reconquered from its Muhammadan king in 1572-73, although not finally subjugated until 1593. Málwá had been reduced in 1570-72. Kashmir was conquered in 1586, and its last revolt quelled in 1592. Sind was also annexed in 1591-92; and by the recovery of Kandahár in 1594, Akbar had extended the Mughal Empire from the heart of Afghánistán across all India north of the Vindhya to Orissa and Sind. The magnificent circumference of Mughal conquest in Northern India and Afghánistán was thus complete.

Capital
changed
from Delhi
to Agra.

Akbar also removed the seat of the Mughal government from Delhi to Agra, and founded Fatehpur Sikrí to be the future capital of the Empire. From this latter project he was, however, dissuaded, by the superior position of Agra on the great water-way of the Jumna. In 1566 he built the Agra fort, whose red sandstone battlements majestically overhang the river to this day.

Akbar's
efforts in
Southern
India.

His efforts to establish the Mughal Empire in Southern India were less successful. Those efforts began in 1586, but during the first twelve years were frustrated by the valour and statesmanship of Chánd Bibí, the queen-regent of Ahmadnagar. This celebrated lady skilfully united the Abyssinian and the Persian factions¹ in the Deccan, and strengthened herself by an alliance with Bijápur and other Muhammadan States of the south. In 1599, Akbar led his armies in person against the princess; but, notwithstanding her assassination by her mutinous troops, Ahmadnagar was not reduced till the reign of Sháh Jahán, in 1637. Akbar subjugated Khándesh; and with this somewhat precarious annexation, his conquests in the Deccan ceased. He returned to Northern India, perhaps feeling that the conquest of the south was beyond the strength of his young Empire. His last years were rendered miserable by the intrigues of his family, and by the misconduct of his

Only
annexed
Khándesh.

¹ Professing the hostile Sunni and Shiah creeds.

beloved son, Prince Salim, afterwards Jahangir. In 1605 he died, and was buried in the noble mausoleum at Sikandra, whose mingled architecture of Buddhist design and Arabesque tracery bear witness to the composite faith of the founder of the Mughal Empire. In 1873, the British Viceroy, Lord Northbrook, presented a cloth of honour to cover the plain marble slab beneath which Akbar lies.

Akbar's conciliation of the Hindus, and his interest in their literature and religion, made him many enemies among the pious Musalmáns. His favourite wife was a Rájput princess, another of his wives is said to have been a Christian, and he ordered his son Prince Murad, when a child, to take lessons in Christianity. On Fridays (the Sabbath of Islám) he loved to collect professors of many religions around him. He listened impartially to the arguments of the Brahman and the Musalman, the Parsi, the ancient fire-worshipper, the Jew, the Jesuit, and the sceptic philosopher. The history of his life, the *Akbar námah*, records such a conference, in which the Christian priest Redif disputed with a body of Muhammadan *mullas* before an assembly of the doctors of all religions, and is given the best of the argument. Starting from the broad ground of general toleration, Akbar was gradually led on by the stimulant of cosmopolitan discussion to question the truth of his inherited beliefs.

The counsels of his friend Abul Fazl,¹ coinciding with that sense of superhuman omnipotence which is bred of despotic power, led him at last to promulgate a new State religion,—‘the Divine Faith,’ based upon natural theology, and comprising the best practices of all known creeds. Of this eclectic creed Akbar himself was the prophet, or rather the head of the Church. Every morning he worshipped in public the sun, as the representative of the divine soul which animates the universe, while he was himself worshipped by the ignorant multitude. It is doubtful how far he encouraged this popular adoration, but he certainly allowed his disciples to prostrate themselves before him in private. The stricter Muhammadans accused him, therefore, of accepting a homage permitted only to God.

¹ Abul Fazl is accused, by the unanimous voice of the Muhammadan historians of leading away Akbar's religious sympathies from Islam. See the valuable biography of *Shaiikh Abul Fazl: 'Allami*, prefixed to I. A. Marn's *Ain-i-Akbari*, p. xxix, etc.

² Akbar's perversion from Islam has formed the subject of much learned censure by Mulla 'Abdul Kadir Badauni and other Musalman writers. The question is exhaustively dealt with by Blochmann in a 'Note' of 4 pages *Ain-i-Akbari*, pp. 167-213. See also Sir Henry Ellis's *Persian History*, vol. v. pp. 477 et seq.

Akbar's
organiza-
tion of the
Empire.

Akbar not only subdued all India to the north of the Vindhya Mountains, he also organized it into an Empire. He partitioned it into Provinces, over each of which he placed a Governor, or Viceroy, with full civil and military control. This control was divided into three departments—the military, the judicial, including the police, and the revenue. With a view to preventing mutinies of the troops, or assertions of independence by their leaders, he reorganized the army on a new basis. He substituted, as far as possible, money payments to the soldiers, for the old system of grants of land (*jāgīrs*) to the generals. Where this change could not be carried out, he brought the holders of the old military fiefs under the control of the central authority at Delhi. He further checked the independence of his provincial generals by a sort of feudal organization, in which the Hindu tributary princes took their place side by side with the Mughal nobles.

Army
reforms.

Akbar's
system of
justice,

The judicial administration was presided over by a lord justice (*Mir-i-adl*) at the capital, aided by *Kāzīs* or law-officers in the principal towns. The police in the cities were under a superintendent or *kotwāl*, who was also a magistrate. In country districts where police existed at all, they were left to the management of the landholders or revenue officers. But throughout rural India, no regular police force can be said to have existed for the protection of person and property until after the establishment of British rule. The Hindu village had its hereditary watchman, who in many parts of the country was taken from the predatory castes, and as often leagued with the robbers as opposed them. The landholders and revenue-officers had each their own set of myrmidons who plundered the peasantry in their names.

and police.

Akbar's
revenue
system.

Akbar's revenue system was based on the ancient Hindu customs, and survives to this day. He first executed a survey to measure the land. His officers then found out the produce of each acre of land, and settled the Government share, amounting to one-third of the gross produce. Finally, they fixed the rates at which this share of the crop might be commuted into a money payment. These processes, known as the land settlement, were at first repeated every year. But to save the peasant from the extortions and vexations incident to an annual inquiry, Akbar's land settlement was afterwards made for ten years. His officers strictly enforced the payment of a third of the whole produce, and Akbar's land revenue from Northern India exceeded what the British take at the present day.

From his fifteen Provinces, including Kábul beyond the Afghan frontier, and Khandesh in Southern India, Akbar demanded 14 millions sterling per annum, or excluding Kabul, Khandesh, and Sind, 12½ millions. The British land tax from a much larger area of Northern India was only 11¼ millions in 1883.¹ Allowing for the difference in area and in the purchasing power of silver, Akbar's tax was about three times the amount which the British take. Two later returns show the land revenue of Akbar at 16½ and 17½ millions sterling. The Provinces had also to support a local militia (*buni* = *bhuni*) in contradistinction to the regular royal army, at a cost of at least 10 millions sterling. Excluding both Kábul and Khandesh, Akbar's demand from the soil of Northern India exceeded 22 millions sterling per annum, under the two items of land revenue and militia cess. There were also a number of miscellaneous taxes. Akbar's total revenue is estimated at 42 millions.²

¹ Namely, Bengal, £3 816 796, Assam, £385 504, North Western Provinces and Oudh, £5,700 816, and Punjab, £1,889,807 total, £11,792 923 — *Administration Reports* (1882-83)

² PROVINCES OF THE DELHI EMPIRE UNDER AKBAR, CIRC 1580

Land tax in Rupees

1 Allahábad,	5 310 677
2 Agra,	13 656 257
3 Oulh,	5 043 954
4 Ajmere	7,153,449
5 Gujarát,	10 924,122
6 Behar,	5 547 985
7 Bengal,	14 961,482
8 Delhi,	15 040 388
9 Lahore	13 986 460
10 Multan,	9,600 764
11 Malwa,	6 017,376
12 Berar	17 376,117
13 Khandesh,	7 563 237
14 Ahmadnagar (only nominally a Province, yielded no revenue),	
15 Tatta (Sind),	1 656,284
Total,	133 838 552
16 Kabul (omitting payments in kind),	8 071,024
Grand Total,	141,909,576

The land revenue was returned at 16½ millions sterling in 1594, and £17 450 000 at Akbar's death in 1605. The aggregate taxation of Akbar was 32 millions sterling with 10 millions for militia cess (*biml*), total, 42 millions sterling. See Thomas' *Revenue Resources of the Mughal Empire*, pp 521 and p 54 (Tubner, 1871). These and the following conversions

The large
totals of
Mughal
taxation.

Are they to
be relied
on?

General
Cunning-
ham's
view.

Since the first edition of this work was written, the author has carefully reconsidered the evidence for the large revenue totals under the Mughal Emperors. The principal authority on the subject is Mr. Edward Thomas, F.R.S., who has summed up the results of a lifetime devoted to Indian numismatics, in his *Revenue Resources of the Mughal Empire from A.D. 1593 to A.D. 1707*.¹ No one can study that work without acknowledging the laborious and accurate research which Mr. Thomas has devoted to the points involved. His results were accepted without reserve in the first edition of *The Imperial Gazetteer of India*. Since the publication of this work, however, the author has received several communications from Mr. H. G. Keene, questioning the soundness of Mr. Thomas' conclusions. Those conclusions point to a comparatively heavier taxation under the Mughal Emperors than under British rule; and have been made the basis of contrasts flattering to the British administration. The author felt it, therefore, incumbent on him to submit Mr. Keene's views to the scrutiny of the two most eminent numismatists now living, namely General Cunningham and Mr. Edward Thomas himself.

Mr. Thomas, after examining the counter-statements, adheres to his former conclusions. General Cunningham is inclined to think that the great totals of revenue recorded by Muhammadan writers, could not have been actually enforced from India at the different periods to which they refer. He thinks that individual items may be reduced by a technical scrutiny.² But that scrutiny only affects certain of the entries. He rests his general conclusion on wider grounds, and believes that the revenues recorded by the Muhammadan writers represent rather the official demand than the amounts actually realized. The following pages will reproduce Mr. Edward Thomas' conclusions, as revised by himself for the first edition of this work. But they are reproduced subject to the considerations stated in the present paragraph.

are made at the nominal rate of 10 rupees to the pound sterling. But the actual rate was then about 8 or 9 rupees to the £. The real revenues of the Mughal Emperors represented, therefore, a considerably larger sum in sterling than the amounts stated in the text and footnotes. The purchasing power of silver, expressed in the staple food-grains of India, was two or three times greater than now.

¹ This monograph was written as a supplement to Mr. Thomas' *Chronicles of the Pathán Kings of Delhi*. (Trübner & Co., 1871.)

² See General Cunningham's Letter, dated 5th July 1883, printed in the paper 'On some Copper Coins of Akbar,' in the *Journal of the Asiatic Society of Bengal*, vol. liv. Part I., 1885.

GROWTH OF MUGHAL REVENUES

299

It may be here convenient to exhibit the revenues of the Mughal Empire in India, as compiled by Mr Edward Thomas from Muhammadan authorities and European travellers, during the century from its practical foundation by Akbar to its final expansion under Aurangzeb in 1697, and thence to its fall in 1761 —

REVENUES OF THE MUGHAL EMPERORS AT THIRTEEN VARIOUS PERIODS FROM 1593 TO 1761, FROM A SUMMARY OF POPULATION THAN THAT OF BRITISH INDIA

Mughal Emperors	Authority	Land Revenue	Revenue from all Sources
1 Akbar, A.D. 1593,	Nizamuddin Ahmad not for all India Allowance for Provincial Troops (<i>Udmi</i>),		
2 " " 1594,	Alul Fazl MSS not for all India,		
3 " " 1605,	Official Documents, not for all India,		
4 Jahangir, 1605-11,	Indian Authorities quoted by De la Motte		
5 " " 1628,	Captain Hawkins		
6 Shah Jahan, 1628-49,	Abdul Hamid I's report		
7 Aurangzeb, 1655,	" "		
8 " " 1670?	Official Documents,		
9 " " 1695,	Later Official Documents,		
10 " " 1697,	Gemelli Careri,		
11 " " 1707,	Manucci (Caton),		
12 Shah Alam, 1761,	Official Statement presented to Ahmad Shah Abdali on his entering Delhi,		
13			
		net £16 574 388 net 16 582 440 net 17 450 000 net 17 500 000 net 22 000 000 net 26 743 970 net 24 056 114 net 35 641 431 net 34 505 590 net 38 719 400 net 30 179 632 net 34 506 640	£32 000 000 10 000 000 net £42 000 000 net 50 000 000 net 50,000 000 net 77,438,800

The above Table is reproduced from Mr. F. H. and Thomas' *Revenue Resources of the Mughal Empire*, published in 1871. The words 'net' in 1871 are inserted by the editor.

Mr Thomas

Rájá Todar Mall. Akbar's Hindu minister, Rájá Todar Mall, conducted the

revenue settlement, and his name is still a household word among the husbandmen of Bengal. Abul Fazl, the man of letters and Finance Minister of Akbar, compiled a Statistical Survey of the Empire, together with many vivid pictures of his master's court and daily life, in the *Ain-i-Akbari*—a work of perennial interest, and one which has proved of great value in carrying out the Statistical Survey of India at the present day.¹ Abul Fazl was killed in 1602, at the instigation of Prince Salim, the heir to the throne.

Salim, the favourite son of Akbar, succeeded his father in 1605, and ruled until 1627 under the title of JAHANGIR, or Conqueror of the World. The chief events of his reign are summarized below.² His reign of twenty-two years was spent in reducing the rebellions of his sons, in exalting the influence

Jahángir,
Emperor,
1605-27.

¹ The old translation is by Gladwin (1800); the best is by the late Mr. Blochmann, Principal of the Calcutta *Madrasah*, or Muhammadan college, whose early death was one of the greatest losses which Persian scholarship has sustained in this century.

² REIGN OF JAHANGIR, 1605-27:—

- 1605. Accession of Jahángir.
- 1606. Flight, rebellion, and imprisonment of his eldest son, Khusrú.
- 1610. Malik Ambar recovers Ahmadnagar from the Mughals, and re-asserts independence of the Deccan dynasty, with its new capital at Aurang-ábád.
- 1611. Jahángir's marriage with Núr Jahán.
- 1612. Jahángir again defeated by Malik Ambar in an attempt to recover Ahmadnagar.
- 1613-14. Defeat of the Udaipur Rájá by Jahángir's son Sháh Jahán. Unsuccessful revolt in Kábul against Jahángir.
- 1615. Embassy of Sir T. Roe to the Court of Jahángir.
- 1616-17. Temporary re-conquest of Ahmadnagar by Jahángir's son Sháh Jahán.
- 1621. Renewed disturbances in the Deccan; ending in treaty with Sháh Jahán. Capture of Kandahár from Jahangir's troops by the Persians.
- 1623-25. Rebellion against Jahángir by his son Sháh Jahán, who, after defeating the Governor of Bengal at Rájmahál, seized that Province and Behar, but was himself overthrown by Mahábat Khán, his father's general, and sought refuge in the Deccan, where he unites with his old opponent Malik Ambar.
- 1626. The successful general Mahábat Khán seizes the person of Jahángir. Intrigues of the Empress Núr Jahán.
- 1627. Jahángir recovers his liberty, and sends Mahábat Khán against Sháh Jahán in the Deccan. Mahábat joins the rebel prince against the Emperor Jahángir.
- 1627. Death of Jahángir.

Materials for Jahángir's reign: Sir Henry Elliot's *Persian Historians*, vols. v. vi. and vii.; Elphinstone, pp. 550-603.

of his wife, and in drunken self-indulgence. In spite of long wars in the Deccan, he added little to his father's territories India south of the Vindhya still continued apart from the northern Empire of Delhi. Malik Ambar, the Abyssinian minister of Ahmadnagar maintained, in spite of reverses, the independence of that kingdom. At the end of Jahangir's Rebellion of his son reign, his rebel son, Prince Shah Jahán, was a refugee in the Deccan, in alliance with Malik Ambar against the Mughal troops. The Rajputs also began to reassert their independence. In 1614, Prince Sháh Jahan on behalf of the Emperor defeated the Udaipur Rája. But the conquest was only partial and for a time. Meanwhile, the Rajputs formed an important contingent of the imperial armies and 5000 of their cavalry aided Sháh Jahan to put down a revolt in Kabul. The Afghán Province of Kandahar was wrested from Jahangir by the Persians in 1621. The land tax of the Mughal Empire remained at 17½ millions under Jahangir but his total revenues were estimated at 50 millions sterling.¹

The principal figure in Jahangir's reign is his Empress, Nur The Light of the World. Born in great poverty but of a noble Persian family, her beauty won the love of Jahangir while they were both in their first youth, during the reign of Akbar. The old Emperor tried to put her out of his sons' way, by marrying her to a brave soldier who obtained high employment in Bengal. Jahangir on his accession to the throne commanded her divorce. Her husband refused, and was killed. His wife, being brought into the imperial palace, lived for some time in chaste seclusion as his widow, but in the end emerged as Nur Jahan, the Light of the World. She surrounded herself with her relatives and at first influenced Jahangir for his good. But the jealousy of the imperial princes and of the Mughal generals against her party led to intrigue and rebellion. In 1626, her successful general, Mahabat Khán, found himself compelled, in self-defence, to turn against her. He seized the Emperor, whom he kept, together with Nur Jahan, in captivity for six months. Jahangir died in the following year, 1627, in the midst of a rebellion against him by his son Sháh Jahán and his greatest general, Mahabat Khán.

Jahangir's personal character is vividly portrayed by Sir Thomas Roe, the first British Ambassador to India (1615) personal character otherwise known as Nur Mahal, the Light of the Palace.

¹ Mr. Edward Thomas' *Accrued Resources of the Mughal Empire*, 1-26 and p. 54.

His
drunken
feasts.

Agra continued to be the central seat of the government, but the imperial army on the march formed in itself a splendid capital. Jahángír thought that Akbar had too openly severed himself from the Muhammadan faith. The new Emperor conformed more strictly to outward observances, but lacked the inward religious feeling of his father. While he forbade the use of wine to his subjects, he spent his own nights in drunken revelry. He talked religion over his cups until he reached a certain stage of intoxication, when he 'fell to weeping, and to various passions, which kept them to midnight.' In public he maintained a strict appearance of virtue, and never allowed any person whose breath smelled of wine to enter his presence. A courtier who had shared his midnight revels, and indiscreetly referred to them next morning, was gravely examined as to who were the companions of his debauch, and one of them was bastinadoed so that he died.

Jahángír's
justice.

During the day-time, when sober, Jahangír tried to work wisely for his Empire. A chain hung down from the citadel to the ground, and communicated with a cluster of golden bells in his own chamber, so that every suitor might apprise the Emperor of his demand for justice without the intervention of the courtiers. Many European adventurers repaired to his court, and Jahángír patronized alike their arts and their religion. In his earlier years he had accepted the eclectic faith of his father. It is said that on his accession he had even permitted the divine honours paid to Akbar to be continued to himself. His first wife was a Hindu princess; figures of Christ and the Virgin Mary adorned his rosary; and two of his nephews embraced Christianity with his full approval.¹

His
religion.

Sháh
Jahán,
Emperor,
1628-58.

SHAH JAHAN hurried north from the Deccan in 1627, and proclaimed himself Emperor at Agra in January 1628.² He

¹ Elphinstone's *Hist.*, p. 560 (ed. 1866), on the authority of Roe, Hawkins, Terry, Coryat.

² Materials for Sháh Jahán's reign: Sir Henry Elliot's *Persian Historians*, vols. vi. vii. and viii.; Elphinstone, pp. 574-603.

REIGN OF SHAH JAHAN, 1628-58:—

1627. Imprisonment of Núr Jahán on the death of Jahángír, by Asaf Khán on behalf of Sháh Jahán.

1628. Sháh Jahán returns from the Deccan and ascends the throne (January). He murders his brother and kinsmen.

1628-30. Afghán uprisings against Sháh Jahán in Northern India and in the Deccan.

[Footnote continued on next page.]

put down for ever the court fiction of the Empress Núr Jahán, by confining her to private life upon a liberal allowance, and by murdering his brother Shahryár, with all members of the house of Akbar who might prove rivals to the throne. He was, however, just to his people, blameless in his private habits, a good financier and as economical as a magnificent court, splendid public works, and distant military expeditions could permit.

Under Shah Jahan the Mughal Empire was finally shorn of its Afghan Province of Kandahar but it extended its conquests in the Deccan and raised the magnificent buildings in Northern India which now form its most splendid memorials. After a temporary occupation of Balkh and the actual reconquest of Kandahar by the Delhi troops in 1657 Shah Jahan lost much of his Afghan territories and the Province of Kandahar was severed from the Mughal Empire by the Persians in 1653. On the other hand, in the Deccan, the kingdom of Ahmadnagar (to which Ellichpur had been united in 1572) was at last annexed to the Mughal Empire in 1636. Bidar fort was taken in 1657, while the remaining two of the five Muhammadan kingdoms of Southern India, namely Bijápur and Golconda were forced to pay tribute although not finally reduced until the succeeding reign of Aurangzeb. But the Marathas now appear on the scene, and commenced,

- 1639 33 Shah Jahan's wars in the Deccan with Ahmadnagar and Bijapur
 an unsuccessful siege of Bijapur
 1634 Shahjís Bhonsla grandfather of Shiváí the Maráthá
 power, attempts to restore the independent Kingdom of Ahmadnagar but
 fails and in 1636 makes peace with the Emperor Shah Jahan
 1636 Bijapur and Golconda agree to pay tribute to Shah Jahan. Final
 submission of Ahmadnagar to the Mughal Empire
 1637 Re-conquest of Kandahar by Shah Jahan
 1645 Invasion and temporary conquest of Balkh by Shah Jahan. Balkh
 was abandoned two years later
 1647 53 Kandahar again taken by the Persians, and three unsuccessful
 attempts made by the Emperor's son Aurangzeb and Dara to recapture it
 1655 56 Kandahar finally lost to the Mughal Empire 1653
 His attack on Haidarabad and temporary submission of the Golconda
 king to the Mughal Empire
 1656 Renewed campaign of Shah Jahan's armies against Bijapur
 1657 58 Dispute as to the succession between the Emperor's sons
 Aurangzeb defeats Dara imprisons Murad, his other brother, deposes
 his father by confining him in his palace, and openly assumes the
 government. Shah Jahán dies, practically a State prisoner in the
 fort of Agra, in 1666
 ante, end of chapter x

unsuccessfully at Ahmadnagar in 1637, that series of persistent Hindu attacks which were destined in the next century to break down the Mughal Empire.

Sháh Jahán's
buildings.
Táj Mahál.

Delhi
Mosque.

Sháh
Jahán's
palace at
Delhi.

Aurangzeb and his brothers carried on the wars in Southern India and in Afghánistán for their father, Sháh Jahán. Save for one or two expeditions, the Emperor lived a magnificent life in the north of India. At Agra he raised the exquisite mausoleum of the Táj Mahál, a dream in marble, designed by Titans and finished by jewellers.¹ His Pearl Mosque, the *Molí Masjid*, within the Agra fort is perhaps the purest and loveliest house of prayer in the world. Not content with enriching his grandfather Akbar's capital, Agra, with these and other architectural glories, he planned the re-transfer of the seat of Government to Delhi, and adorned that city with buildings of unrivalled magnificence. Its Great Mosque, or *Jamí Masjid*, was commenced in the fourth year of his reign and completed in the tenth. The palace at Delhi, now the fort, covered a vast parallelogram, 1600 feet by 3200, with exquisite and sumptuous buildings in marble and fine stone. A deeply-recessed portal leads into a vaulted hall, rising two storeys like the nave of a gigantic Gothic cathedral, 375 feet in length; 'the noblest entrance,' says the historian of architecture, 'to any existing palace.'² The *Diwán-i-Khás*, or Court of Private Audience, overlooks the river, a masterpiece of delicate inlaid work and poetic design. Sháh Jahán spent many years of his reign at Delhi, and prepared the city for its destiny as the most magnificent capital in the world under his successor Aurangzeb. But exquisite as are its public buildings, the manly vigour of Akbar's red-stone fort at Agra, with its bold sculptures and square Hindu construction, has given place to a certain effeminate beauty in the marble structures of Sháh Jahán.³

¹ Sháh Jahán's architectural works are admirably described in Dr. James Fergusson's *Hist. Architecture*, vol. iii. pp. 589-602 (ed. 1876). See also article AGRA CITY, *The Imperial Gazetteer of India*.

² Fergusson's *Hist. Architecture*, vol. iii. p. 592. See also article DELHI CITY, *The Imperial Gazetteer of India*.

³ PROVINCES OF THE DELHI EMPIRE UNDER SHAH JAHAN, 1648-49:—

In India—	Land-tax in Rupees.
1. Delhi,	25,000,000
2. Agra,	22,500,000
3. Lahore,	22,500,000
4. Ajmere,	15,000,000
Carry forward,	85,000,000

Akbar's dynasty lay under the curse of rebellious sons. As Jahāngir had risen against his most loving father, Akbar, and as Shah Jahān had mutinied against Jahāngir, so Shāh Jahan in his turn suffered from the intrigues and rebellions of his family. In 1658, Shah Jahān, old and worn out, fell ill, and in the following year his son Aurangzeb, after a treacherous conflict with his brethren, deposed his father, and proclaimed himself Emperor in his stead. The unhappy Shāh Jahān was kept in confinement for seven years, and died a State prisoner in the fort of Agra in 1666.

Rebellion of Prince Aurangzeb, 1657
Shah Jahan's deposition, 1658

Under Shāh Jahān, the Mughal Empire attained its highest union of strength with magnificence. His son Aurangzeb added to its extent, but at the same time sowed the seeds of its decay. Akbar's land revenue of 17½ millions had been raised, chiefly by new conquests, to 22 millions sterling under Shāh Jahan. But this sum included Kashmir, and five Provinces in Afghanistan, some of which were lost during Shāh Jahān's reign. The land revenue of the Mughal Empire within India, under Shah Jahān, was 20½ millions. The magnificence of Shah Jahān's court was the wonder of European travellers. His Peacock Throne, with its tail blazing in the shifting natural colours of rubies, sapphires, and emeralds, was valued by the jeweller Tavernier at 6½ millions sterling.

Shah Jahan's revenues

Brought forward,	Rs 85 000 000
5 Daulatābad,	13 750 000
6 Berar,	13 750 000
7 Ahmadabad,	13 250 000
8 Bengal,	12 500 000
9 Allahabad,	10 000 000
10 Behar,	10,000 000
11 Malwā,	10 000 000
12 Khāndesh,	10,000 000
13 Oudh,	7 500,000
14 Telingana,	7,500 000
15 Multan,	7,000 000
16 Orissa,	5 000 000
17 Tatta (Sind),	2,000,000
18 Baglanah	500,000
<hr/>	
Land Revenue of India,	207,750,000
19 Kashmir,	3 750 000
20 Kabul, .	4 000,000
21 Balkh, .	2,000,000
22 Kandahar,	1,500,000
23 Ladakhshan,	1,000 000
<hr/>	

Total Rs 220,000,000

Aurang-
zeb's
usurpa-
tion, 1658.

His reign,
1658-1707.

AURANGZEB proclaimed himself Emperor in 1658, in the room of his imprisoned father, with the title of Alamgír, the Conqueror of the Universe, and reigned until 1707. Under Aurangzeb, the Mughal Empire reached its widest limits.¹ But his long rule of forty-nine years merely presents on a more magnificent stage the old unhappy type of a Mughal reign. In its personal character, it commenced with his rebellion against his father; consolidated itself by the murder of his brethren; and darkened to a close amid the mutinies, intrigues, and gloomy jealousies of his own sons. Its public aspects consisted of a magnificent court in Northern India; conquests of the independent Muhammadan kings in the south; and wars against the Hindu powers, which, alike in Rájputána and the Deccan, were gathering strength for the overthrow of the Mughal Empire.

The chief events of the reign of Aurangzeb are summarized below.² The year after his accession, he defeated and put to death his eldest brother, the noble but impetuous Dárá

¹ Materials for Aurangzeb's reign : Sir Henry Elliot's *Persian Historians*, vols. vii. and viii. ; Elphinstone, pp. 598-673.

² REIGN OF AURANGZEB, 1658-1707 :—

- 1658. Deposition of Sháh Jahán, and usurpation of Aurangzeb.
- 1659. Aurangzeb defeats his brothers Shujá and Dárá. Dárá, his flight being betrayed by a chief with whom he sought refuge, is put to death by order of Aurangzeb.
- 1660. Continued struggle of Aurangzeb with his brother Shujá, who ultimately fled to Arakan, and there perished miserably.
- 1661. Aurangzeb executes his youngest brother, Murád, in prison.
- 1662. Unsuccessful invasion of Assam by Aurangzeb's general Mir Jumlá. Disturbances in the Deccan. War between Bijápur and the Maráthás under Sivají. After various changes of fortune, Sivají, the founder of the Maráthá power, retains a considerable territory.
- 1662-1665. Sivají in rebellion against the Mughal Empire. In 1664 he assumed the title of Rájá, and asserted his independence; but in 1665, on a large army being sent against him, he made submission, and proceeded to Delhi, where he was placed under restraint, but soon afterwards escaped.
- 1666. Death of the deposed Emperor, Sháh Jahán. War in the Deccan, and defeat of the Mughals by the King of Bijápur.
- 1667. Sivají makes peace on favourable terms with Aurangzeb, and obtains an extension of territory. Sivají levies tribute from Bijápur and Golconda.
- 1670. Sivají ravages Khándesh and the Deccan, and there levies for the first time *chauth*, or a contribution of one-fourth of the revenue.
- 1672. Defeat of the Mughals by the Maráthá Sivají.
- 1677. Aurangzeb revives the *jáziah* or poll-tax on non-Muhammadans.

[Footnote continued on next page.]

(1659) After another twelve months' struggle, he drove out of India his second brother, the self-indulgent Shujá, who perished miserably among the insolent savages of Arakan (1660-61)¹ His remaining brother, the brave young Murad, was executed in prison the following year (1661) Aurangzeb, having thus killed off his brethren, set up as an orthodox sovereign of the strictest sect of Islám, while his invalid father, Sháh Jahan, lingered on in prison, mourning over his murdered sons, until 1666, when he died

Aurangzeb continued, as Emperor, that persistent policy of the subjugation of Southern India which he had so brilliantly commenced as the lieutenant of his father, Sháh Jahan the five Muhammadan kingdoms of the Deccan, three, namely Bidar, and Ahmadnagar with Ellichpur, had fallen to Aurangzeb's arms before his accession to the Delhi throne² The two others, Bijápur and Golconda, struggled longer, but Aurangzeb was determined at any cost to annex them to the Mughal Empire During the first half of his reign, or exactly twenty five years, he waged war in the south by means of his generals (1658-83) A new Hindu power had arisen in the Deccan, the Marathás³ The task before Aurangzeb's armies was not only the old one of subduing the Muhammadan kingdoms of Bijapur and Golconda,

He murders his brothers

Subjugation of Southern India

Rise of the Maratha power

1679 Aurangzeb at war with the Rajputs Rebellion of Prince Akbar, Aurangzeb's youngest son, who joins the Rajputs, but whose army deserts him Prince Akbar is forced to fly to the Marathas

1681 Aurangzeb has to continue the war with the Rajputs

[1672-1680 Maratha progress in the Deccan Sivaji crowns himself an independent sovereign at Raigarh in 1674 His wars with Bijapur and the Mughals Sivaji dies in 1680, and is succeeded by his son Sambhaji]

1683 Aurangzeb invades the Deccan in person, at the head of his Grand Army

1686-88 Aurangzeb conquers Bijapur and Golconda, and annexes them to the Empire (1688)

1689 Aurangzeb captures Sambhaji, and barbarously puts him to death

1692 Guerilla war with the Marathas under independent leaders

1698 Aurangzeb captures Jinji from the Marathas.

1699-1701 The Maratha war Capture of Satara and Maratha forts by the Mughals under Aurangzeb Apparent ruin of Marathas

1702-05 Successes of the Marathas

1706 Aurangzeb retreats to Ahmadnagar, and

1707 Miserably dies there (February)

¹ See article AKBAR, *The Imperial Gazetteer of India*

² The five kingdoms have been described in chapter x

³ For the rise and history of the Marathás, see next chapter, xii

but also of crushing the quick growth of the Maráthá confederacy.

Sivaji
crowns
himself.

Aurang-
zeb's
southern
campaign,
1683-1707.

His 20
years'
Maráthá
war,
1688-1707.

His
'Grand
Army'
worn out,
1705.

Aurangzeb
hemmed
in.

During a quarter of a century his efforts failed. Bijápur and Golconda were not conquered. In 1670, the Maráthá leader, Sivají, levied *chauth*, or one-fourth of the revenues, as tribute from the Mughal Provinces in Southern India; and in 1674, enthroned himself an independent sovereign at Raigarh. In 1680-81, Aurangzeb's rebel son, Prince Akbar, gave the prestige of his presence to the Maráthá army. Aurangzeb felt that he must either give up his magnificent life in the north for a soldier's lot in the Deccan, or he must relinquish his most cherished scheme of conquering Southern India. He accordingly prepared an expedition on an unrivalled scale of numbers and splendour, to be led by himself. In 1683 he arrived at the head of his Grand Army in the Deccan, and spent the next half of his reign, or twenty-four years, in the field. Golconda and Bijápur fell after another long struggle, and were finally annexed to the Mughal Empire in 1688.

But the conquests of these two last of the five Muhammadan kingdoms of the Deccan only left the arena bare for the Maráthás. Indeed, the attacks of the Maráthás on the two Muhammadan States had prepared the way for the annexation of those States by Aurangzeb. The Emperor waged war during the remaining twenty years of his life (1688-1707) against the rising Hindu power of the Maráthás. Their first great leader, Sivají, had proclaimed himself king in 1674, and died in 1680. Aurangzeb captured his son and successor Sambhají in 1689, and cruelly put him to death; seized the Maráthá capital, with many of their forts, and seemed in the first year of the new century to have almost stamped out their existence (1701). But after a guerilla warfare, the Maráthás again sprang up into a vast fighting nation. In 1705 they recovered their forts; while Aurangzeb had exhausted his health, his treasures, and his troops, in the long and fruitless struggle. His soldiery murmured for arrears; and the Emperor, now old and peevish, told the malcontents that if they did not like his service they might quit it, while he disbanded some of his cavalry to ease his finances.

Meanwhile the Maráthás were pressing hungrily on the imperial camp. The Grand Army of Aurangzeb had grown during a quarter of a century into an unwieldy capital. Its movements were slow, and incapable of concealment. If Aurangzeb sent out a rapid small expedition against the Maráthás who plundered and insulted the outskirts of his camp,

they cut it to pieces. If he moved out against them in force, they vanished. His own soldiery feasted with the enemy, who prayed with mock ejaculations for the health of the Emperor as their best friend. In 1706, the Grand Army was so disorganized that Aurangzeb opened negotiations with the Maráthás. He even thought of submitting the Mughal Provinces to their tribute or *chauth*. But their insolent exultation broke off the treaty, and the despairing Aurangzeb, in 1706, sought shelter in Ahmadnagar, where he died the next year. Dark suspicion of his sons' loyalty, and just fears lest they should subject him to the fate which he had inflicted on his own father, left him alone in his last days. On the approach of death, he gave utterance in broken sentences to his worldly counsels and adieus, mingled with terror and remorse, and closing in an agony of desperate resignation. 'Come what may, I have launched my vessel on the waves. Farewell! Farewell! Farewell!'¹

His
despair,
1706

Aurang
zeb's
death,
1707

The conquest of Southern India was the one inflexible purpose of Aurangzeb's life, and has therefore been dealt with here in a continuous narrative. In the north of India, great events had also transpired. Mir Jumla led the imperial troops as far as Assam, the extreme eastern Province of India (1662). But amid the pestilential swamps of the rainy season, the army melted away, its supplies were cut off, and its march was harassed by swarms of natives who knew the country and defied the climate. Mir Jumla succeeded in extricating the main body of his troops, but died of exhaustion and a broken heart before he reached Dacca.

Mir
Jumla's
expedition
to Assam,
1662

In the west of India, Aurangzeb was not more fortunate. During his time the Sikhs were growing into a power, but it was not till the succeeding reigns that they commenced the series of operations which in the end wrested the Punjab from the Mughal Empire. Aurangzeb's bigotry arrayed against him the Hindu princes and peoples of Northern India. He revived the *jazia* or insulting poll tax on non Musalmáns (1677), drove the Hindus out of the administration, and oppressed the widow and children of his father's faithful Hindu general Jaswant Singh. A local sect of Hindus was forced into rebellion in 1676, and in 1677, the Rajput States combined against him. The Emperor waged a protracted war

Aurang
zeb's
bigoted
policy
Oppresses
the
Hindus

The Raj
puts revolt,

¹ Aurangzeb's *Letters* form a popular Persian book in India to this day. His counsels to his sons are edifying and most pathetic, and the whole work is written in a deeply religious tone, which could scarcely have been assumed.

against them; at one time devastating Rájputána, at another time saving himself and his army from extermination only by a stroke of genius and rare presence of mind. In 1679, his son, Prince Akbar, rebelled and joined the Rájputs with his division of the Mughal army. From that year, the permanent alienation of the Rájputs from the Mughal Empire dates; and the Hindu chivalry, which had been a source of strength to Akbar the Great, became an element of ruin to Aurangzeb and his successors. The Emperor sacked and slaughtered throughout the Rájput States of Jaipur, Jodhpur, and Udaipur. The Rájputs retaliated by ravaging the Muhamniadan Provinces of Málwá, defacing the mosques, insulting the ministers of Islám, and burning the Kurán. In 1681, the Emperor patched up a peace in order to allow him to lead the Grand Army into the Deccan, from which he was destined never to return.

and can-
not be
subdued.

Aurang-
zeb's
revenues.

The land
revenue,
30 to 38
millions.

All Northern India except Assam, and the greater part of Southern India, paid revenue to Aurangzeb. His Indian Provinces covered nearly as large an area as the British Empire at the present day, although their dependence on the central Government was less direct. From these Provinces his net land-revenue demand is returned at 30 to 38 millions sterling; a sum which represented at least three times the purchasing power of the land revenue of British India at the present day. But it is doubtful whether the enormous demand of 38 millions was fully realized during any series of years, even at the height of Aurangzeb's power before he left Delhi for his long southern wars. It was estimated at only 30 millions in the last year of his reign, after his absence of a quarter of a century in the Deccan. Fiscal oppressions led to evasions and revolts, while some or other of the Provinces were always in open war against the Emperor.

Maximum
Mughal
land-tax.

The following statements exhibit the Mughal Empire in its final development, just before it began to break up. The standard return of Aurangzeb's land revenue was *net* £34,505,890; and this remained the nominal demand in the accounts of the central exchequer during the next half-century, notwithstanding that the Empire had fallen to pieces. When the Afghán invader, Ahmad Sháh Durání, entered Delhi in 1761, the treasury officers presented him with a statement showing the land revenue of the Empire at £34,506,640. The highest land revenue of Aurangzeb, after his annexations in Southern India, and before his final reverses, was 38½ millions sterling;

of which close on 38 millions were from Indian Provinces¹ The total revenue of Aurangzeb was estimated in 1695 at 80 millions, and in 1697 at 77¹ millions sterling² The gross taxation levied from British India, deducting the opium excise, which is paid by the Chinese consumer, averaged 35¹/₂ millions sterling during the ten years ending 1879, and 40³/₄ millions from 1879 to 1883 The table on a previous page, showing the growth of the revenues of the Mughal Empire from Akbar to Aurangzeb, may be contrasted with the taxation of British India, as given in chapter xv

¹ PROVINCES OF THE DELHI EMPIRE UNDER AURANGZEB

LAND REVENUE OF AURANGZEB
IN 1697 (according to Manucci)

	Rupees
1 Delhi,	12,550,000
2 Agra,	22,203,550
3 Lahore	23,305,000
4 Ajmere	21,900,002
5 Gujarat,	23,395,000
6 Malwa,	9,906,250
7 Behar,	12,150,000
8 Multan	5,025,000
9 Tatta (Sind)	6,002,000
10 Bakar,	2,400,000
11 Orissa,	5,707,500
12 Allahabad	7,733,000
13 Deccan,	16,204,750
14 Berar,	15,807,500
15 Khandesh,	11,105,000
16 Laghana,	6,885,000
17 Nande (Nandair),	7,200,000
18 Bengal	40,000,000
19 Ujjain,	20,000,000
20 Kajmahal,	10,050,000
21 Bijapur,	50,000,000
22 Golconda,	50,000,000
Total,	379,534,552
23 Kashmir,	3,505,000
24 Kabul,	3,207,250

Grand Total, 386,246,802
or £38,624,680

LAND REVENUE OF AURANGZEB
IN 1707 (according to Ramusio)

	Rupees
1 Delhi,	30,548,753
2 Agra,	28,669,003
3 Ajmere	16,308,634
4 Allahabad	11,413,581
5 Punjab,	20,653,302
6 Oudh	8,058,195
7 Multan,	5,361,073
8 Gujarat,	15,196,228
9 Behar,	10,179,025
10 Sind,	2,295,420
11 Daulatabad	25,873,627
12 Malwa,	10,097,541
13 Berar,	15,350,625
14 Khandesh	11,215,750
15 Bidar,	9,324,359
16 Bengal	13,115,506
17 Orissa,	3,570,500
18 Haidarabad	27,834,000
19 Bijapur,	26,957,625
Total,	292,023,147
20 Kashmir,	5,747,734
21 Kabul,	4,025,983

Grand Total, 301,796,864
or £30,179,686

The above lists are taken from Mr Edward Thomas' *Revenue Resources of the Mughal Empire*, pp 46 and 50 The whole subject is admirably discussed in his chapter entitled 'Aurangzeb's Revenues,' pp 33 *et seq* The four returns of the land revenue for his reign are, *net*, 24 millions in 1655, 34¹/₂ millions in later official documents, 38¹/₂ millions in 1697, 30 millions in 1707

² Mr Edward Thomas' *Revenue Resources of the Mughal Empire*, i 54, etc (1871)

Character
of Aurang-
zeb.

Aurangzeb tried to live the life of a model Muhammadan Emperor. Magnificent in his public appearances, simple in his private habits, diligent in business, exact in his religious observances, an elegant letter-writer, and ever ready with choice passages alike from the poets and the Kurán, his life would have been a blameless one, if he had had no father to depose, no brethren to murder, and no Hindu subjects to oppress. But his bigotry made an enemy of every one who did not share his own faith; and the slaughter of his kindred compelled him to entrust his government to strangers. The Hindus never forgave him; and the Sikhs, the Rájputs, and the Maráthás, immediately after his reign, began to close in upon the Empire. His Muhammadan generals and viceroys, as a rule, served him well during his vigorous life. But at his death they usurped his children's inheritance. The succeeding Emperors were puppets in the hands of the too powerful soldiers or statesmen who raised them to the throne, controlled them while on it, and killed them when it suited their purposes to do so. The subsequent history of the Empire is a mere record of ruin. The chief events in its decline and fall are summarized below.¹

Decline
of the
Mughal
Empire.

¹ THE DECLINE AND FALL OF THE MUGHAL EMPIRE,

From death of Aurangzeb to that of Muhammad Bahádur Sháh, 1707-1862.

- 1707. Succession contest between Muázim and Alam, two sons of Aurangzeb; victory of the former, and his accession under the title of Bahádur Sháh; controlled by the General Zul-fikar Khán. Revolt of Prince Kambaksh; his defeat and death.
- 1710. Expedition against the Sikhs.
- 1712. Death of Bahádur Sháh, and accession of his eldest son, Jahándar Sháh, after a struggle for the succession; an incapable monarch, who only ruled through his *wazír*, Zul-fikar Khán. Revolt of his nephew, Farukhsiyyar; defeat of the Imperial army, and execution of the Emperor and his prime minister.
- 1713. Accession of Farukhsiyyar, under the auspices and control of Husáin Alí, Governor of Behar, and Abdullá, Governor of Allahábád.
- 1716. Invasion by the Sikhs; their defeat, and cruel persecution.
- 1719. Deposition and murder of Farukhsiyyar by the Sayyid chiefs Husáin Alí and Abdullá. They nominate in succession three boy Emperors, the first two of whom died within a few months after their accession. The third, Muhammad Sháh, commenced his reign in September 1719.
- 1720. Murder of Husáin Alí, and overthrow of the Sayyid 'king-makers.'
- 1720-48. The Governor of the Deccan, or Nízám-ul-Mulkh, establishes his independence, and severs the Haidarábád Provinces from the Mughal Empire.
- 1732-43. The Governor of Oudh, who was also *Wazír* of the Empire, becomes practically independent of Delhi.

[Footnote continued on next page.]

For a time, Mughal Emperors still ruled India from Delhi. But of the six immediate successors of Aurangzeb, two were under the control of an unscrupulous general, Zulfiqar Khan,¹ while the four others were the creatures of a couple of Sydd adventurers who well earned their title of the 'king makers'. From the year 1720, the breaking up of the Empire took a more open form. The Nizam ul Mulkh, or Governor of the

The six
'duplet'
kings

1735-51 General decline of the Empire: revolts within and invasion of Nadir Shah from Persia (1739). The Marathas obtain Malwa (1743), followed by the cession of Southern Orissa and tribute from Bengal (1751). First invasion of India by Ahmad Shah Durani, who had obtained the throne of Kandahar (1747), his defeat in Surbund (1748).

1748 Death of Muhammad Shah

1748-50 Accession of Ahmad Shah, his son, disturbances by the Rohilla Afghans in Oudh, and defeat of the Imperial troops

1751 The Rohilla insurrection crushed with the aid of the Marathas

1751-52 Second invasion of India by Ahmad Shah Durani, and cession of the Punjab to him

1754 Deposition of the Emperor, and accession of Alamgir II

1756 Third invasion of India by Ahmad Shah Durani, and sack of Delhi

1759-61 Fourth invasion of India by Ahmad Shah Durani, and murder of the Emperor Alamgir II by his *reza*, Ghazi ud din. The Maratha conquests in Northern India. The Marathas complete their organization for the conquest of Hindustan, capture of Delhi.

1761-1805 The third battle of Panipat, between the Afghans under Ahmad Shah and the Marathas; defeat of the latter. From this time the Mughal Empire ceased to exist, except in name. The victory of Baxar, gained by Major Munro, breaks the Mughal power in Bengal. The Diwani, or administration, of Bengal, Behar, and Orissa is granted by the Emperor to the British in 1765. The nominal Emperor on the death of Alamgir II was Shah Alam II, an exile, who resided till 1771 in Allahabad, a pensioner of the British. In 1771 he threw in his fortunes with the Marathas, who restored him to a fragment of his hereditary dominions. The Emperor was blinded and imprisoned by rebels. He was afterwards rescued by the Marathas, but was virtually a prisoner in their hands till 1803, when the Maratha power was overthrown by Lord Lake. Shah Alam died in 1806, and was succeeded by his son,

1806-1837 Akbar II, who succeeded only to the nominal dignity, and lived till 1837, when he was followed by

1837-62 Muhammad Bahadur Shah, the seveneenth Mughal Emperor, and last of the race of Timur. For his complicity in the Mutiny of 1857 he was deposed and banished for life to Rangoon, where he died, a British State prisoner, in 1862. Two of his sons and grandsons were shot by Hodson in 1857, to prevent a rescue, and for their part in the murder of English women and children at Delhi.

¹ Sir Henry Elliot's *Persian History*, vol. vi, pp. 348-556 (Trübner, 1877).

Independence
of the
Deccan,
1720-48 :
of Oudh,
1732-43.

Deccan,¹ established his independence, and severed the largest part of Southern India from the Delhi rule (1720-48). The Governor of Oudh,² originally a Persian merchant, who had risen to the post of Wazir or Prime Minister of the Empire, established his own dynasty in the Provinces which had been committed to his care (1732-43).

Hindu
risings.

The Hindu subjects of the Empire were at the same time establishing their independence. The Sikh sect in the Punjab, driven by oppression into revolt, had been mercilessly crushed in 1710-16. The indelible memory of the cruelties then inflicted by the Mughal troops nerved the Sikh nation with that hatred to Delhi which served the British cause so well in 1857. In 1716, the Sikh leader, Banda, was carried about by the insulting Mughals in an iron cage, tricked out in the mockery of imperial robes, with scarlet turban and cloth of gold. His son's heart was torn out before his eyes, and thrown in his face. He himself was then pulled to pieces with red-hot pincers, and the Sikhs were exterminated like mad dogs (1716). The Hindu princes of Rájputána were more fortunate. Ajít Singh of Jodhpur asserted his independence, and Rájputána practically severed its connection with the Mughal Empire in 1715. The Maráthás having enforced their claim to black-mail (*chauth*) throughout Southern India, burst through the Vindhya upon the north, obtained the cession of Málwá (1743) and Orissa (1751), with an Imperial grant for tribute from Bengal (1751). But the great Hindu military revival represented by the Maráthá power demands a separate section for itself, and will be narrated in the next chapter.

Oppres-
sion of
the Sikhs,
1710-16.

Rájput
independ-
ence.
1715.

The
Maráthá
chauth,
1751.

Invasions
from the
north-
west,
1739-61.
Nádir
Sháh,
1739.

While the Muhammadan governors and Hindu subjects of the Empire were thus asserting their independence, two new sets of external enemies appeared. The first of these consisted of invasions from the north-west. In 1739, Nádir Sháh, the Persian, swept down with his destroying host, and, after a massacre in the streets of Delhi and a fifty-eight days' sack, went off with a booty estimated at 32 millions sterling.³ Six times the Afgháns burst through the passes under Ahmad Sháh Durání, plundering, slaughtering, and then scornfully retiring to their homes with the plunder of the Empire. In 1738, Kábul, the last Afghán Province of the Mughals, had been severed from Delhi; and in 1752, Ahmad Sháh the Afghán obtained the

¹ Chin Khilich Khán or Azaf Sháh, a Túrkomán Sunní.

² Saádat Ali Khán, a Persian Shiah.

³ Mill's *History of British India*, vol. ii. p. 456 (Wilson's edition, 1840).

cession of the Punjab The cruelties inflicted upon Delhi and Northern India during these six invasions form an appalling tale of bloodshed and wanton cruelty The miserable capital opened her gates, and was fain to receive the Afghans as guests Yet on one occasion it suffered for six weeks every enormity which a barbarian army can inflict upon a prostrate foe Meanwhile the Afghán cavalry were scouring the country, slaying, burning, and mutilating in the meanest hamlet as in the greatest town They took especial delight in sacking the holy places of the Hindus and murdering the defenceless votaries at the shrines

Ahmad
Shah
1748-61
Afghan
invasions,
1747-61

A horde of 25,000 Afghan horsemen swooped down upon the sacred city of Muttra during a festival, while it was thronged with peaceful Hindu pilgrims engaged in their devotions 'They burned the houses,' says the Tyrolese Jesuit Ieffenthaler, who was in India at that time, 'together with their inmates, slaughtering others with the sword and the lance, hauling off into captivity maidens and youths, men and women In the temples they slaughtered cows,' the sacred animal of the Hindus, 'and smeared the images and pavement with the blood' The border land between Afghánistan and India lay silent and waste, indeed, districts far within the frontier, which had once been densely inhabited, and which are now again thickly peopled, were swept bare of inhabitants

Misery
of the
Province
1747-61

Afghan
atrocities

Another set of invaders came from the sea In the wars between the French and English in Southern India, the last vestiges of the Delhi authority in the Madras Presidency disappeared (1748-61) The victory of Baxar, gained by Major Munro in 1764, broke the Mughal power in Northern India, and drove the Emperor himself to seek shelter in our camp Bengal, Behar, and Orissa were handed over to the English by an imperial grant in 1765 We technically obtained these fertile Provinces as the nominee of the Emperor, but the third battle of Panípat had four years previously reduced the throne of Delhi to a shadow The third battle of Panípat was fought in 1761, between the Afghán invader Ahmad Sháh and the Maratha powers, on the memorable plain on which Babar in 1526, and Akbar in 1556, had twice won the sovereignty of India

Invaders
from the
sea

Fall of the
Empire

Battle of
Panípat
1761

That sovereignty was now, after little more than two centuries of Mughal rule, lost for ever by their degenerate descendants. The Afgháns defeated the Maráthás at Panípat in 1761, and during the anarchy which followed, the British patiently built up a new power out of the wreck of the Mughal Empire.

Mughal pensioners and imperial puppets reigned still at Delhi over a numerous seraglio under such lofty titles as Akbar II. or Alamgir (Aurangzeb) II. But their power was confined to the palace, while Maráthás, Sikhs, and Englishmen struggled for the sovereignty of India. The last nominal Emperor emerged for a moment as a rebel during the Mutiny of 1857, and died a State prisoner in Rangoon in 1862.

Last of the
Mughals,
1862.

CHAPTER XII

THE MARATHA POWER (1634 TO 1818 A.D.)

THE British won India, not from the Mughals, but from the ^{British} Hindus. Before we appeared as conquerors, the Mughal ^{India won,} Empire had broken up. Our conclusive wars were neither with ^{not from} the Delhi King, nor with his revolted governors, but with the ^{the} two Hindu confederacies, the Marathas and the Sikhs. Our ^{Mughal} last Maráthá war dates as late as 1818, and the Sikh Confedera ^{but from} tion was not finally overcome until 1849 ^{Hindu}

About the year 1634, a Maratha soldier of fortune, SHAHJI ^{Rise of the} BHONSLA by name, began to play a conspicuous part in ^{Maratha} Southern India.¹ He fought on the side of the two independent ^{Sháhji} Muhammadan States, Ahmadnagar and Bijapur against the ^{Bhonsla,} Mughals, and left a band of followers, together with a military ¹⁶³⁴ fief, to his son Sivaji, born in 1627.² Sivaji formed a national ^{Sivaji} party out of the Hindu tribes of Southern India, as opposed alike to the imperial armies from the north, and to the independent Muhammadan kingdoms of the Deccan. There were thus, from 1650 onwards, three powers in the Deccan.

¹ The original authorities for the Maratha history are—(1) James Grant Duff's *History of the Marathas*, 3 vols (Bombay reprint 1863), (2) Edward Scott Waring's *History of the Maráthas* (quarto, 1810), (3) Major William Thorne's *Memoir of the War in India conducted by General Lord Lake* (quarto, 1818), (4) Sidney J. Owen's *Selections from the Despatches of the Marquis of Wellesley* (1877), (5) his *Selections from the Indian Despatches of the Duke of Wellington* (1880), and (6) Henry T. Prinsep's *Narrative of Political and Military Transactions of British India under the Marquis of Hastings* (quarto, 1820). The very brief notice of the Marathas which the scope of the present work allows, precludes an exhaustive use of these storehouses. But it should be mentioned that the later history of the Marathas (since 1819) has yet to be written. The leading incidents of that history are described in separate articles in *The Imperial Gazetteer of India*. To save space, this chapter confines itself, as far as practicable, to referring in footnotes to those articles. Ample materials will be found in the *Gazetteers of the Bombay Districts and Central Provinces*.

² Grant Duff's *History of the Maráthas*, vol. 1 p. 90 (ed. 1863).

Three parties in the Deccan, 1650. first, the ever-invading troops of the Delhi Empire; second, the forces of the two remaining independent Muhammadan States of Southern India, namely, Ahmadnagar and Bijápur; third, the military organization of the local Hindu tribes, which ultimately grew into the Maráthá confederacy.

Strength of the Hindu or third party. During the eighty years' war of Sháh Jahán and Aurangzeb, with a view to the conquest of Southern India (1627-1707), the third or Hindu party fought from time to time on either side, and obtained a constantly-increasing importance. The Mughal armies from the north, and the independent Muhammadan kingdoms of the south, gradually exterminated each other. Being foreigners, they had to recruit their exhausted forces chiefly from outside. The Hindu confederacy drew its inexhaustible native levies from the wide tract known as Maháráshtra, stretching from the Berars in Central India to

Courted by the other two. near the south of the Bombay Presidency. The Maráthás were therefore courted alike by the Imperial generals and by the independent Muhammadan sovereigns of the Deccan. With true Hindu statecraft, their leader, Sivají, from time to time aided the independent Musalmán kingdoms of the Deccan against the Mughal avalanche from the north. Those kingdoms, with the help of the Maráthás, long proved a match for the imperial troops. But no sooner were the Delhi armies driven back, than the Maráthás proceeded to despoil the independent Musalmán kingdoms. On the other hand, the Delhi generals, when allied with the Maráthás, could completely overpower the independent Muhammadan States.

Sivají, born 1627, died 1680. SIVAJI saw the strength of his position, and, by a course of treachery, assassination, and hard fighting, won for the Maráthás the practical supremacy in Southern India.¹ As a

His hill forts. His army of horse-men. of impregnable hill forts in the Bombay Presidency. His troops consisted of Hindu spearmen, mounted on hardy ponies. They were the peasant proprietors of Southern India, and could be dispersed or called together on a moment's notice, at the proper seasons of the agricultural year. Sivají had therefore the command of an unlimited body of troops, without the expense of a standing army. With these he swooped down upon his enemies, exacted tribute, or forced them to come to terms. He then paid off his soldiery by a part of the plunder; and while they returned to the sowing or

Histactics.

¹ The career of Sivají is traced in Grant Duff's *History of the Maráthás*, vol. i. pp. 90-220. The Bombay reprint of Grant Duff's *History*, in three volumes, 1863, is invariably referred to in this chapter.

reaping of their fields, he retreated with the lion's share to his hill forts. In 1659 he lured the Bijápur general into an ambush, stabbed him at a friendly conference, and exterminated his army. In 1662-64, Sivaji raided as far as the extreme north of the Bombay Presidency, and sacked the Imperial city of Surat. In 1664 he assumed the title of king (Rajá), with the royal prerogative of coining money in his own name ¹ Coins money

The year 1665 found Sivaji helping the Mughal armies against the independent Musalman State of Bijapur. In 1666 he was induced to visit Delhi. Being coldly received Visit Delhi, 1666 by the Emperor Aurangzeb, and placed under restraint, he escaped to the south, and raised the standard of revolt ². In 1674, Sivaji enthroned himself with great pomp at Raigarh, weighing himself in a balance against gold, and distributing the precious counterpoise among his Brahmans ³. After sending forth his hosts as far as the Karnatik in 1676, he died in 1680 Enthroned himself 1674

The Emperor Aurangzeb would have done wisely to have left the independent Musalman Kings of the Deccan alone, until he had crushed the rising Maratha power. Indeed, a great statesman would have buried the old quarrel between the Muhammadans of the north and south, and united the whole forces of Islám against the Hindu confederacy which was rapidly organizing itself in the Deccan. But the fixed resolve of Aurangzeb's life was to annex to Delhi the Muhammadan kingdoms of Southern India. By the time he had carried out this scheme, he had wasted his armies, and left the Mughal Empire ready to break into pieces at the first touch of the Maráthas Died, 1680
Aurangzeb's mistaken policy, 1688-1707

SAMBHAJI succeeded his father, Sivaji, in 1680, and reigned till 1689 ⁴. His life was entirely spent in wars with the Portuguese and Mughals. In 1689, Aurangzeb captured him. The Emperor burnt out his eyes with a red hot iron, cut out the tongue which had blasphemed the Prophet, and struck off his head Sambhaji, 1680-89

His son, SAHU, then six years of age, was also captured and kept a prisoner till the death of Aurangzeb. In 1707 he was restored, on acknowledging allegiance to Delhi. But his long captivity among the Mughals left him only half a Marathá ⁵ Sahu, 1707

¹ Grant Duff's *History of the Maráthas*, vol. 1 p. 146

² *Ibid* vol. 1 chap. v. at *finem*

³ *Ibid*, vol. 1 pp. 191-193

⁴ For the career of Sambhaji see Grant Duff's *History of the Maráthas*, vol. 1 pp. 220-261

⁵ The career of Sahu is traced in Grant Duff's *History of the Maráthas*, vol. 1 pp. 297-306

He wasted his life in his seraglio, and resigned the rule of his territories to his Bráhmaṇ minister Bálají Vishwanáth, with the title of Peshwá.¹ This office became hereditary, and the power of the Peshwá superseded that of the Maráthá kings. The family of Sivají only retained the little principalities of Sátára and Kolhápur. Sátára lapsed, for want of a direct heir, to the British in 1848. Kolhápur has survived through their clemency, and was ruled, under their control, by the last adopted representative of Sivají's line² until 1883. On his death, in December 1883, another Maráthá youth of high family was placed by the British Government, in virtue of the adoption *sanaad*, on the State cushion of Kolhápur.

Meanwhile the PESHWAS were building up at Poona the great Maráthá confederacy. In 1718, Bálají, the first Peshwá, marched an army to Delhi in support of the Sayyid 'king-makers.'³ In 1720⁴ he extorted an Imperial grant of the *chauth* or 'one-fourth' of the revenues of the Deccan. The Maráthás were also confirmed in the sovereignty of the countries round Poona and Sátára. The second Peshwá, Bájí Ráo (1721-40), converted the tribute of the Deccan granted to his father into a practical sovereignty. In fifteen years he wrested the Province of Málwá from the Empire (1736), together with the country on the north-west of the Vindhya, from the Narbada to the Chambal.⁵ In 1739⁶ he captured Bassein from the Portuguese.

The third Peshwá, Bálají Bájí Ráo, succeeded in 1740, and carried the Maráthá terror into the heart of the Mughal Empire.⁷ The Deccan became merely a starting-point for a vast series of their expeditions to the north and the east. Within the Deccan itself he augmented his sovereignty, at the expense of the Nizám, after two wars. The great centres of the Maráthá power were now fixed at Poona in Bombay and Nágpur in the Berars. In 1741-42, a general of the Berar branch of the Maráthás known as the Bhonslas, swept down upon Bengal; but, after plundering to the suburbs of the Muhammadan capital Murshidábád, he was driven back through Orissa by the Viceroy Alí Vardí Khán. The 'Maráthá Ditch,' or

¹ For Bálají's career, see Grant Duff's *Hist. of the Maráthás*, vol. i. pp. 307-339.

² See articles KOLHAPUR and SATARA, *Imperial Gazetteer of India*.

³ *Vide ante*, p. 313.

⁴ Grant Duff's *History of the Maráthás*, vol. i. pp. 324, 325.

⁵ Grant Duff's *History of the Maráthás*, vol. i. pp. 393-395.

⁶ For Bájí Ráo's career, see *op. cit.* vol. i. pp. 344-410.

⁷ His career is sketched in *op. cit.* vol. ii. pp. 1-115.

semicircular moat around part of Calcutta, records to this day the panic which then spread throughout Bengal. Next year, 1743 the head of the Berar Maráthás, Raghuji Bhonsla, himself invaded Bengal in force. From this date, in spite of quarrels between the Poona and Berar Maráthas over the spoil, the fertile Provinces of the Lower Ganges became a plundering ground of the Bhonslas. In 1751 they obtained a formal grant from the Viceroy Ali Vardí of the *chaauth* or 'quarter revenue' of Bengal, together with the cession of Orissa. In Northern India, the Poona Maráthás raided as far as the Punjab, and drew down upon them the wrath of Ahmad Sháh, the Afghan, who had wrested that Province from Delhi. At the third battle of Panípat, the Maráthás were overthrown, by the combined Muhammadan forces of the Afghans and of the Provinces still nominally remaining to the Mughal Empire (1761).

To the
Punjab,
1760

Panípat,
1761

The fourth Peshwá, Madhu Ráo, succeeded to the Maratha sovereignty in this moment of ruin.¹ The Hindu confederacy seemed doomed to destruction, alike by internal treachery and by the superior force of the Afghán arms. As early as 1742, the Poona and Berar branches had taken the field against each other, in their quarrels over the plunder of Bengal. Before 1761, two other branches, under Holkar and Sindhia, had set up for themselves in the old Mughal Province of Malwá and the neighbouring tracts, now divided between the States of Indore and Gwalior. At Panípat, Holkar, the head of the Indore branch, deserted the Hindu line of battle when he saw the tide turn, and his treachery rendered the Maratha rout complete. The fourth Peshwá was little more than the nominal centre of the five great Maratha branches with their respective head quarters at Poona, the seat of the Peshwas, at Nágpur, the capital of the Bhonslas, in Berar, at Gwalior, the residence of Sindhia, at Indore, the capital of Holkar, and at Baroda, the seat of the rising power of the Gíekwárs. Madhu Ráo, the fourth Peshwa, just managed to hold his own against the Muhammadan princes of Haidarábád and Mysore, and against the Bhonsla branch of the Maráthás in Berar. His younger brother, Náráyan Ráo, succeeded him as fifth Peshwá in 1772, but was quickly assassinated.²

Fourth
Peshwa,
1761-72

The five
Marathá
branches

Fifth
Peshwa,
1772

From this time the Peshwa's power at Poona begins to recede, as that of his nominal masters, the lineal descendants

Decline
of the
Peshwas,
1772-1818

¹ For his career, see Grant Duff's *Hist. of the Maráthás*, vol. II pp. 115-172.

² Grant Duff's *History of the Maráthas*, vol. II pp. 174-178.

of Sivají, had faded out of sight at Sâtára and Kolhápur. The Peshwás came of a high Bráhmaṇ lineage, while the actual fighting force of the Maráthás consisted of low-caste Hindus. It thus happened that each Maráthá general who rose to independent territorial sway, was inferior in caste, although possessed of more real power than the Peshwá, the titular head of the confederacy. Of the two great northern houses, Holkar was descended from a shepherd,¹ and Sindhia from a slipper-bearer.² These potentates lay quiet for a time after their crushing disaster at Pánipat. But within ten years of that fatal field, they had finally established themselves throughout Málwá, and invaded the Rájput, Ját, and Rohillá Provinces, from the Punjab on the west to Oudh on the east (1761-71). In 1765, the titular Emperor, Sháh Alam, had sunk into a British pensioner after his defeat at Baxar. In 1771 he made overtures to the Maráthás. Holkar and Sindhia nominally restored him to his throne at Delhi, but held him a virtual prisoner till 1803-04, when they were overthrown by our second Maráthá war.

Progress
of the
northern
Maráthás.

Sindhia
and
Holkar,
1761-1803.

The
Bhonslas
of Berar,
1751-1853.

The third of the northern Maráthá houses, namely, the Bhonslas of Berar and the Central Provinces, occupied themselves with raids to the east. Operating from their basis at Nágpur,³ they had extorted, by 1751, the *chauth* or 'quarter-revenue' of Bengal, together with the sovereignty of Orissa. The accession of the British in Bengal (1756-65) put a stop to their raids in that Province. In 1803, a division of our army drove them out of Orissa. In 1817, their power was finally broken by our last Maráthá war. Their head-quarter territories, now forming the Central Provinces,⁴ were administered under the guidance of British Residents from 1817 to 1853. On the death of the last Raghuji Bhonsla, without issue, in 1853, Nágpur lapsed to the British.

The
Gáekwárs
of Baroda.

The fourth of the northern Maráthá houses, namely, Baroda,⁵ extended its power throughout Gujarát, on the north-western coast of Bombay, and the adjacent peninsula of Káthiáwár. The scattered but wealthy dominions known as the Territories of the Gáekwár were thus formed. Since our last Maráthá war, in 1817, Baroda has been ruled by the Gáekwár, with the help of a British Resident and a

¹ See article INDORE, *The Imperial Gazetteer of India.*

² See article GWALIOR, *The Imperial Gazetteer of India.*

³ See article NAGPUR, *The Imperial Gazetteer of India.*

⁴ See article CENTRAL PROVINCES, *The Imperial Gazetteer of India.*

⁵ See article BARODA, *The Imperial Gazetteer of India.*

subsidiary force In 1874 the reigning Gáekwar, having attempted to poison the Resident, was tried by a High Commission consisting of three European and three native members, found guilty, and deposed But the British Government refrained from annexing the State, and raised a descendant of the founder of the family from poverty to the State cushion

While these four northern houses of the Marathás were pursuing their separate careers, the Peshwa's power was being broken to pieces by family intrigues The sixth Peshwa, Madhu Rao Náráyan, was born after his father's death, and during his short life of twenty one years the power remained in the hands of his minister, Náná Farnavis Raghoba, the uncle of the late Peshwá disputed the birth of the posthumous child, and claimed for himself the office of Peshwa The infant's guardian, Náná Farnavis having invoked the aid of the French, the British sided with Raghoba These alliances brought on the first Marathá war (1779-81) ending with the treaty of Salbai (1782) That treaty ceded the islands of Salsette and Elephanta with two others to the British secured to Raghobá a handsome pension and confirmed the child Peshwá in his sovereignty The latter however, only reached manhood to commit suicide at the age of twenty one

His cousin Báji Rao II, succeeded him in 1795 as the seventh and last Peshwá The northern Maratha house of Holkar now took the lead among the Marathás and forced the Peshwa into the arms of the English By the treaty of Bassein in 1802, the Peshwá agreed to receive and pay for a British force to maintain him in his dominions The northern Marathá houses combined to break down this treaty The second Marathá war followed (1803-04) General Wellesley crushed the forces of the Sindhí and Nágpur houses on the great fields of Assaye and Argaum in the south while Lord Lake disposed of the Marathá armies at Laswári and Delhi in the north In 1804, Holkar was completely defeated at Digr. These campaigns led to large cessions of territory to the British, the overthrow of the French influence in India, and the replacement of the titular Delhi Emperor under the protection of the English In 1817-18, the Peshwá Holkar, and the Bhonslá Marathás at Nágpur took up arms, each on his own account, against the British, and were defeated in detail That war finally broke the Marathá power The Peshwá, Báji Rao, surrendered to the British, and his territories

Baola
1874

Sixth
Peshwa
1774-95

First Mar
atha war
1779-81

Seventh
and last
Peshwa
1795-1818

Second
Marathá
war
1803-04

Last Mar
atha war
1817-18

were annexed to our Bombay Presidency.¹ The Peshwá remained a British pensioner at Bithúr, near Cawnpore, on a magnificent allowance, till his death. His adopted son grew up into the infamous Náná Sáhib of the Mutiny of 1857, when the last relic of the Peshwás disappeared from the eyes of men.

End of the
Peshwás,
1849.

¹ For a summary of the events of this last Maráthá war, *vide post*, pp. 401, 402. Also Grant Duff's *History of the Maráthás*, vol. iii. *passim*.

CHAPTER XIII

THE INDIAN VERNACULARS AND THEIR LITERATURE

THE foregoing chapters have summarized the successive settlements of Asiatic peoples in India. The remainder of this volume will deal with altogether different aspects of Indian history. For the three essential stages in that history are— (1) first the long struggle for India by the races of Asia, second, a shorter struggle for India by European nations, third, the consolidation of India under British rule. From the great contest of five thousand years, England emerged the victor. We have seen how the tidal waves of Asiatic populations—pre Aryan, Aryan, Scythic, Afghan, and Mughal—swept across India from the north. The next chapter (xiv) will exhibit the briefer, but not less eventful, efforts of the European maritime powers to enter India from the sea. The conquest of India by the British, and an account of the administration which they have established throughout its widely separated Provinces, will conclude this volume.

The inroads under Alexander the Great and his successors had proved momentary episodes—episodes, moreover, of an Asiatic rather than of a European type. The Greek and Greco-Bactrian hosts entered India from the north, they effected no settlements beyond the frontier Province, and the permanent element in their forces consisted of Asiatic rather than of European troops. The civilisation and organization of India, from a prehistoric period many thousand years before Christ down to the 15th century A.D., had been essentially the work of Asiatic races. Since the end of that century, when the Portuguese landed on the Malabar coast, the course of Indian history has been profoundly influenced by European nations.

Before entering on this new period, therefore, it is desirable to obtain a clear idea of India, as moulded by the survival of the fittest among the Asiatic peoples who had struggled for the Indian supremacy during so many thousand years. The social constitution of the Indian

The three stages in Indian history
(1) Struggle for India by the Asiatic races,
(2) by the European nations,
(3) Consolidation of India under British rule

Greek inroads, temporary and semi-Asiatic in type

Asiatic civilisation of India

As found
by the
European
Powers.

twofold basis of religion and caste, has been fully explained. Their later political organization under the Afgháns, Mughals, and Maráthás, has been more briefly summarized. It remains, however, to exhibit the geographical distribution of the Indian races, and the local landmarks, literatures, and languages, which the Europeans found on their arrival in India.

India in
the 1st
century
A. D.

Before the beginning of the Christian era, Northern India was partitioned out among civilised communities in which the Aryan element prevailed, while the southern peninsula was covered with forests, and dotted with the settlements of non-Aryan peoples. The Northern Aryans had a highly developed literary language, Sanskrit. They spoke less artificial cognate dialects, called Prákrits, which (equally with the Sanskrit) had grown out of the primitive Indo-Germanic tongue. The non-Aryans of Southern India at that period knew nothing of the philosophy or sciences which flourished in the north. They had not even a grammatical settlement of the principles of their own language; and they used vernaculars so uncouth as to earn for them, from the civilised Aryans, the name of Mlechchhas, meaning the people of imperfect utterance or broken speech.¹

India in
the 16th
century
A. D.

When the European nations arrived in India during the 16th and 17th centuries, all this had changed. The stately Sanskrit of the Northern Aryans had sunk into a dead language, still used as a literary vehicle by the learned, but already pressed hard by a popular literature in the speech of the people. The Prákrits, or ancient-spoken dialects, had given place to the modern vernaculars of Northern India. In Southern India a still greater change had taken place. The obscure non-Aryan races had there developed a political organization and a copious literature, written in vernaculars of their own,—vernaculars which, while richly endowed for literary uses, remained non-Aryan in all essentials of structure and type.

The Dra-
vidians.

Leaving aside, for the moment, the changes among the Aryans in the north, let us briefly examine this survival of prehistoric non-Aryan life in the southern peninsula. The non-Aryan races of the south were spoken of by Sanskrit authors under the general name of Dravidas, and their

¹ For the ideas connoted by this word, and its later application to the Huns and Musalmáns, see the Honourable K. T. Telang's *Essay on the Mudrárákhasa*, pp. 4-7, 12, etc., and footnotes. Bombay.

languages under the vague term *Paishchi*. The latter term covered, however, a wider linguistic area, from the speech of the Bhotas of Tibet to that of the Pándyas or Tamil speaking tribes of Southern India.

Modern philology, rejecting any generic term, proves that the scattered non Aryan languages of India belong to separate stocks. Some of the isolated tribes, who still survive in their hill and forest retreats around Bengal entered from the north east, and brought with them dialects akin to the Chinese. The great body of Dravidian speech in the south seems, however, to have had its origin, equally with the Aryan languages, to the north west of the Himálayas. It would appear that long before the Aryan invasions, a people speaking a very primitive Central Asian language, had entered by the Sind passes. These were the Dravidas or Dravidians of later times. Other non Aryan races from the north pushed them onwards to the present Dravidian country in the south of the peninsula. But the Dravidians had left more than one colony on their line of march. The Brahuís of the Sind frontier, the Gonds and Kus of the Central Provinces, the Uraons of Chutrá Nágpur, with a tribal offshoot in the Ráymahál hills overlooking the Gangetic valley,¹ remain to this day as landmarks along the Dravidian route through India.

The Dravidian language contains words apparently belonging to a phase of human speech, anterior to the separation of the Indo Germanic from the Scythian stocks.² It presents affinities to the present Ugrian of Siberia, and to the present Finnish of Northern Europe, while its analogies to the ancient Behistun tablets of Media have been worked out by the great Dravidian scholar of our times.³ Those tablets recorded the life of Darius Hystaspes in the old Persian, together with a rendering in the speech of the Scythians of the Medo-Persian Empire. They date from the 5th century B.C., and they indicate a common starting place of the Turanian family of languages whose fragments have been scattered to the shores of

¹ *Introduction to the Vaito Language* p. iv (Agra, 1884) by the Rev. Ernest Droege, to whom the author is indebted for valuable local details which he hopes to incorporate hereafter in a larger work.

² *Comparative Grammar of the Dravidian Languages*, by Bishop Caldwell, p. 46, ed. 1875. Unfortunately, the paging of that edition repeats itself, running as far as p. 154 in the introduction, and commencing again (in a slightly different type) at p. 1 of the Grammar itself. Except when otherwise mentioned, the pages cited in this book refer to the first or introductory series, of Bishop Caldwell's numerals.

³ *Ibid.*, pp. 72, and 106.

the Baltic, the Steppes of Northern Siberia, and the Malabar coast. This family belongs to the primæval agglutinative phase of human speech, as opposed to the inflectional stage which the later Aryan migrations into India represent. The Dravidians found refuge, after their long wanderings, in the sea-girt extremity of the Indian peninsula. In its isolation this Turanian speech has there preserved its primitive type, and forms one of the most ancient relics of the prehistoric world.

The
Dravidians
in Sanskrit
literature.

The extrusion of the Dravidians from Northern India had taken place before the arrival of the Aryan-speaking races. The Dravidians are to be distinguished from the later non-Aryan immigrants, whom the Vedic tribes found in possession of the valleys of the Indus and Ganges. These later non-Aryans were in their turn subjugated or pushed out by the Aryan newcomers; and they accordingly appear in the Vedic hymns as the 'enemies' (Dasyus) and 'serfs' (Súdras) of the Indo-Aryan settlers. The Dravidian non-Aryans of the south, on the other hand, appear from the first in the Sanskrit as friendly forest folk, the monkey armies who helped the Aryan hero Ráma on his march through Southern India against the demon king of Ceylon.

Pre-Aryan
Dravidian
civilisa-
tion.

The Tamil language still preserves evidence of a Dravidian civilisation before the southern advance of the Aryans which the Rámáyana represents. 'They had "kings,"' writes Bishop Caldwell,¹ 'who dwelt in "strong houses," and ruled over small "districts of country." They had "minstrels" who recited "songs" at "festivals," and they seem to have had alphabetical "characters" written with a stylus on palmyra leaves. A bundle of those leaves was called a "book." They acknowledged the existence of God, whom they styled Kô or King. They erected to his honour a "temple," which they called Kô-il, God's house. Marriage existed among them. They were acquainted with the ordinary metals, with the exception of tin, lead, and zinc; with all the planets ordinarily known to the ancients, excepting Mercury and Saturn. They had numerals up to a hundred, some of them up to a thousand. They had "medicines;" "hamlets" and "towns," but no cities; "canoes," "boats" and even "ships" (small decked coasting vessels).

Dravidian
arts.

'They were well versed in "agriculture," and delighted in "war." They were armed with "bows" and "arrows," with "spears" and "swords." All the ordinary or necessary arts of life, including "spinning," "weaving," and "dyeing," existed

¹ *Comparative Grammar of the Dravidian Languages*, condensed from pp. 117, 118.

among them. They excelled in "pottery," as their places of sepulture show. They were ignorant, not only of every branch of "philosophy," but even of "grammar." Their undeveloped intellectual condition is especially apparent in words relating to the operations of the mind. To express "the will" they would have been obliged to describe it as "that which in the inner part says, I am going to do so and so."

While the Dravidians appear in Sanskrit literature as friends or allies, the Aryans were not their conquerors, but their 'instructors' or 'fathers'. The first Bráhmán settlers in the south came as hermits or sages, who diffused around them a halo of higher civilisation. The earliest of such Bráhmán colonies among the Dravidians, led by the holy Agastya, has long faded into the realms of mythology. 'The Vindhya Mountains,' it is said, 'prostrated themselves before Agastya, still fondly remembered as the Tamir muni, pre eminently the Sage to the Tamil race. He introduced philosophy at the court of the first Pándyan king, wrote many treatises for his royal disciple, and now lives for ever in the heavens as Canopus, the brightest star in the Southern Indian hemisphere. He is worshipped as Agastes wara, the Lord Agastya, near Cape Comorin. But the orthodox still believe him to be alive, although invisible to sinful mortals, hidden away in the conical mountain called Agastya's Hill, from which the sacred river of Tinneveli springs.

This legend serves to indicate the influence of Sanskrit civilisation and learning among the Dravidian race. That influence was essentially a friendly one. The Bráhmáns became the 'fathers' of the less advanced race, and although they classified the non Aryan multitude as Sudras, yet this term did not connote in Southern India the ideas of debasement and servitude which it affixed to the non Aryan races in the north. The Buddhist missionaries were probably the first Aryan instructors of the Dravidian kings and peoples, and their labours must have begun before the commencement of the Christian era.

Bishop Caldwell takes the Aryan emigration under Vijaya, from Magadha in Bengal to Ceylon, *circa* B.C. 550, as the starting point of Aryan civilisation in Southern India. Dr Burnell, however, believes that Aryan civilisation had not penetrated deeply among the Dravidians until the advent of Kumárika, the Brahman reformer from Behar in the 8th century A.D.

¹ Dr Burnell's article in the *Indian Antiquary* for October 1872

Bráhmaṇ hermits had doubtless taught the Dravidian peoples, and Bráhmaṇ sages had adorned Dravidian courts long before this latter date. But it was from the great religious revival of the 8th century, that the continuous and widespread influence of Bráhmaṇ civilisation in Southern India took its rise.

Dravidian
speech
developed

The Bráhmaṇ apostles of the Sivaite and Vishnuite faith, from the 8th to the 12th century A.D.,¹ composed their religious treatises in Sanskrit. The intellectual awakening, produced by their teaching, also gave the first impulse to the use of the vernacular languages of India for literary purposes. The Dravidians gratefully acknowledge that they owe the settlement of the grammatical principles of their speech to Sanskrit sages, among whom the legendary Agastya holds the highest rank. But the development of that speech into a vernacular literature was chiefly the work of the Dravidians themselves. Indeed, the first outburst of their vernacular literature sprang from the resistance of their previous Buddhistic faith to the Bráhmaṇical religious revival.

into ver-
nacular
literatures.

The Dra-
vidian
dialects.

Before the arrival of the European nations in the 16th and 17th centuries, four Dravidian dialects had developed literatures. The Tamil, the Telugu, the Kánaresé, and the Malayálam are now literary languages of established reputation. But space compels us to concentrate our attention on the oldest and most influential of the vernacular literatures of Southern India,—the Tamil. This language, in its structure and its vocabulary, forms the best representative of cultivated Dravidian speech. It has not feared to incorporate such philosophical, religious, and abstract terms as it required from the Sanskrit. But its borrowings in this respect are the mere luxuries or delicacies of the language, and they have left unaffected its robust native fabric. ‘Tamil,’ writes Bishop Caldwell, ‘can readily dispense with the greater part or the whole of its Sanskrit, and by dispensing with it, rises to a purer and more refined style.’² He maintains that the Ten Commandments can be translated into classical Tamil with the addition of a single Sanskrit word. That word is ‘image.’

The
Tamil.

First cul-
tivation of
Tamil.

According to native tradition, Tamil was first cultivated by the sage Agastya. Many works, besides a grammar and treatises on philosophy and science, are ascribed to him. His name served indeed as a centre around which Tamil compositions of widely separated periods, including some of recent date, gather. The oldest Tamil grammar now extant,

¹ *Vide ante*, pp. 209 and 217. ² *Comparative Grammar*, pp. 50, 51.

the *Tol Káppiyam*, is assigned to one of his disciples. But the rise of a continuous Tamil literature belongs to a later period. The Sivaite and Vishnuite revival of the Bráhmaṇ apostles in Southern India, from the 8th century onwards, stirred up a counter movement on the part of the Jains. Before that period, the Buddhism of the Dravidian kingdoms had modelled itself on the Jain type. We shall see hereafter that early Buddhism in Northern India adopted the Prákrit or vernacular speech for its religious treatises. On the same analogy, Buddhism in Southern India, as the religion of the people, defended itself against the Brahmanical revival of the 8th century by works in the popular dialects. The Dravidian Buddhists or Jains created a cycle of Tamil literature, into Bráhmaṇical in tone, stretching from the 9th to the 13th century. Jain cycle of Tamil literature
9th to 13th century
A D

Its first great composition, the *Kural* of Tiruvalluvar, not later than the 10th century A D, is said to have been the work of a poet sprung from the Pariah or lowest caste. It enforces the old Sankya philosophy in 1330 distichs or poetical aphorisms, dealing with the three chief desires of the human heart, wealth, pleasure, and virtue. To the sister of its author, a Pariah poetess, are ascribed many compositions of the highest moral excellence, and of undying popularity in Southern India. The Jain period of Tamil literature includes works on ethics and language, among them the *Divakaram*, literally the 'Day making' Dictionary. The period culminated in the *Chintámaṇi*, a romantic epic of 15,000 lines by an unknown Jain author. Its great Pariah poet 900 A D (?)
The Jain epic Indeed, it is worthy of remark that several of the best Indian authors, whether Sanskrit or vernacular, have left no indication of their names. As it was the chief desire of an Indian sage to merge his individual existence in the Universal Existence, so it appears to have been the wish of many Indian men of letters of the highest type to lose their literary individuality in the school or cycle of literature to which they belonged.

Contemporaneous with the Jain cycle of Tamil literature, the great adaptation of the *Rámáyana* was composed by Kaṇva for the Dravidian races. This work is a Tamil paraphrase or imitation, rather than a translation of the ancient Sanskrit epic. A stanza prefixed to the work states that it was finished in the year corresponding to 886 A.D. But this stanza may itself be a later addition, and Bishop Caldwell, after a careful examination of the whole evidence, places the work after 1100. The Tamil Kama Jana

Bráhmaṇ hermits had doubtless taught the Dravidian peoples, and Bráhmaṇ sages had adorned Dravidian courts long before this latter date. But it was from the great religious revival of the 8th century, that the continuous and widespread influence of Bráhmaṇ civilisation in Southern India took its rise.

Dravidian
speech
developed

into ver-
nacular
literatures.

The Bráhmaṇ apostles of the Sivaite and Vishnuite faith, from the 8th to the 12th century A.D.,¹ composed their religious treatises in Sanskrit. The intellectual awakening, produced by their teaching, also gave the first impulse to the use of the vernacular languages of India for literary purposes. The Dravidians gratefully acknowledge that they owe the settlement of the grammatical principles of their speech to Sanskrit sages, among whom the legendary Agastya holds the highest rank. But the development of that speech into a vernacular literature was chiefly the work of the Dravidians themselves. Indeed, the first outburst of their vernacular literature sprang from the resistance of their previous Buddhistic faith to the Bráhmaṇical religious revival.

The Dra-
vidian
dialects.

The
Tamil.

Before the arrival of the European nations in the 16th and 17th centuries, four Dravidian dialects had developed literatures. The Tamil, the Telugu, the Kánarese, and the Malayálam are now literary languages of established reputation. But space compels us to concentrate our attention on the oldest and most influential of the vernacular literatures of Southern India,—the Tamil. This language, in its structure and its vocabulary, forms the best representative of cultivated Dravidian speech. It has not feared to incorporate such philosophical, religious, and abstract terms as it required from the Sanskrit. But its borrowings in this respect are the mere luxuries or delicacies of the language, and they have left unaffected its robust native fabric. ‘Tamil,’ writes Bishop Caldwell, ‘can readily dispense with the greater part or the whole of its Sanskrit, and by dispensing with it, rises to a purer and more refined style.’² He maintains that the Ten Commandments can be translated into classical Tamil with the addition of a single Sanskrit word. That word is ‘image.’

First culti-
vation of
Tamil.

According to native tradition, Tamil was first cultivated by the sage Agastya. Many works, besides a grammar and treatises on philosophy and science, are ascribed to him. His name served indeed as a centre around which Tamil compositions of widely separated periods, including some of recent date, gather. The oldest Tamil grammar now extant,

¹ *Vide ante*, pp. 209 and 217. ² *Comparative Grammar*, pp. 50, 51.

the Tol Kappivam, is assigned to one of his disciples. But the rise of a continuous Tamil literature belongs to a later period. The Shaivite and Vishnuvite revival of the Brāhman apostles in Southern India, from the 8th century onwards, stirred up a counter movement on the part of the Jains. Before that period, the Buddhism of the Dravidian kingdoms had modelled itself on the Jain type. We shall see hereafter that early Buddhism in Northern India adopted the Prakrit or vernacular speech for its religious treatises. On the same analogy, Buddhism in Southern India, as the religion of the people, defended itself against the Brahmanical revival of the 8th century by works in the popular dialects. The Dravidian Buddhists or Jains created a cycle of Tamil literature, anti Brāhmanical in tone, stretching from the 9th to the 13th century.

Jain cycle
of Tamil
literature

9th to 13th
century
A D

Its first great composition, the Kural of Tiruvalluvar, not later than the 10th century A D, is said to have been the work of a poet sprung from the Pariah or lowest caste. It enforces the old Sankya philosophy in 1330 distichs or poetical aphorisms, dealing with the three chief desires of the human heart, wealth, pleasure, and virtue. To the sister of its author, a Pariah poetess, are ascribed many compositions of the highest moral excellence, and of undying popularity in Southern India. The Jain period of Tamil literature includes works on ethics and language, among them the Divakaram, literally the 'Day making' Dictionary. The period culminated in the Chintāmani, a romantic epic of 15,000 lines by an unknown Jain author. Indeed, it is worthy of remark that several of the best Indian authors, whether Sanskrit or vernacular, have left no indication of their names. As it was the chief desire of an Indian sage to merge his individual existence in the Universal Existence, so it appears to have been the wish of many Indian men of letters of the highest type to lose their individuality in the school or cycle of literature to which they belonged.

Its great
Pariah
poet 900
A D (?)

The

Contemporaneous with the Jain cycle of Tamil literature is the great adaptation of the Rāmāyana by Kāribār for the Dravidian races. This work is a phrase or imitation, rather than a translation of the Sanskrit epic. A stanza prefixed to it was finished in the year corresponding to the stanza may itself be a later addition after a careful examination of the work after 1100.

Tamil
Sivaite
hymno-
logies.

Between that period and the 16th century, two encyclopædic collections of Tamil hymns in praise of Siva were gradually formed. They breathe a deeply religious spirit, and the earlier collection (*post* 1200 A.D.) still holds its place in the affections of the Tamil-speaking people. The later collection was the work of a Sivaite devotee and his disciples, who devoted themselves to uprooting Jainism (*circa* 1500 A.D.). During the same centuries, the Vishnuite apostles were equally prolific in Tamil religious song. Their Great Book of the Four Thousand Psalms constitutes a huge hymnology dating from the 12th century onwards. After a period of literary inactivity, the Tamil genius again blossomed forth in the 16th and 17th centuries with a poet-king as the leader of the literary revival.

Tamil
Vishnuite
hymno-
logy.

The Sittar
Tamil
poets.

Their pure
theism.

In the 17th century arose an anti-Bráhmancial Tamil literature known as the Sittar school. The Sittars or sages were a Tamil sect who, while retaining Siva as the name of the One God, rejected everything in Siva-worship inconsistent with pure theism. They were quietists in religion, and alchemists in science. They professed to base their creed upon the true original teaching of the Rishís, and indeed assumed to themselves the names of these ancient inspired teachers of mankind. They thus obtained for their poems, although written in a modern colloquial style, the sanction of a venerable antiquity. Some scholars believe that they detect Christian influences in works of the Sittar school. But it must be remembered that the doctrines and even the phraseology of ancient Indian theism and of Indian Buddhism approach closely to the subsequent teaching and, in some instances, to the very language of Christ.¹

¹ The following specimens of the Sittar school of Tamil poetry are taken from Bishop Caldwell's *Comparative Grammar*, p. 148. The first is a version of a poem of Siva-vákya, given by Mr. R. C. Caldwell, the Bishop's son, in the *Indian Antiquary* for 1872. He unconsciously approximates the verses to Christian ideas, for example, by the title, 'The Shepherd of the Worlds,' which Bishop Caldwell states may have meant to the poet only 'King of the Gods.'

THE SHEPHERD OF THE WORLDS.

How many various flowers
Did I, in bygone hours,
Cull for the gods, and in their honour strew;
In vain how many a prayer
I breathed into the air,
And made, with many forms, obeisance due.

The Tamil writers of the 18th and 19th centuries are classified as modern. The honours of this period are divided between a pious Sivaite and the Italian Jesuit, Beschi. This missionary of genius and learning not only wrote Tamil prose of the highest excellence, but he composed a great religious epic in classical Tamil, which has won for him a conspicuous rank among Dravidian poets. His work, the *Tembávam*, gives a Tamil adaptation of the narrative and even of the geography of the Bible, suited to the Hindu taste of the 18th century.

Modern
Tamil
writers.
Beschi

Since the introduction of printing, the Tamil press has been prolific. A catalogue of Tamil printed books, issued in Madras up to 1865, enumerated 1409 works. In the single year 1882, no fewer than 558 works were printed in the vernaculars in Madras, the great proportion of them being in Tamil.

Recent
Statistics.

While the non Aryans of Southern India had thus evolved

Beating my breast, aloud
How oft I called the crowd
To drag the village car; how oft I stray'd,
In manhood's prime, to lave
Sunwards the flowing wave,
And, circling Saiva fanes, my homage paid
Ere they, the truly wise,
Who know and realize
Where dwells the Shepherd of the Worlds, will ne'er
To any visible shrine,
As if it were divine,
Deign to raise hands of worship or of prayer

THE UNITY OF GOD AND OF TRUTH

God is one, and the Veda is one;
The disinterested, true Guru is one, and his initiatory rite one;
When this is obtained his heaven is one,
There is but one birth of men upon the earth,
And only one way for all men to walk in.
But as for those who hold four Vedas and six shastras,
And different customs for different people,
And believe in a plurality of gods,
Down they will go to the fire of hell!

GOD IS LOVE.

The ignorant think that God and love are different.
None knows that God and love are the same.
Did all men know that God and love are the same,
They would dwell together in peace, considering love is God.

Aryan languages of North-India ;
Sanskrit. a copious literature and cultivated spoken dialects out of their isolated fragments of prehistoric speech, a more stately linguistic development was going on in the Aryan north. The achievements of Sanskrit as a literary vehicle in the various departments of poetry, philosophy, and science, have been described in chapter iv. at such length as the scope of this work permits. But Sanskrit was only the most famous of several Aryan dialects in the north. One of its eminent modern teachers defines it as 'that dialect which, regulated and established by the labours of the native grammarians, has led for the last 2000 years or more an artificial life, like that of the Latin during most of the same period in Europe.'¹ The Aryan vernaculars of modern India are the descendants not of Sanskrit, but of the spoken languages of the Aryan immigrants into the north. The Bráhmancial theory is that these ancient spoken dialects, or Prákrits, were corruptions of the purer Sanskrit. European philology has disproved this view, and the question has arisen whether Sanskrit was ever a spoken language at all.

Was Sanskrit ever a vernacular?

Dr. John Muir's affirmative answer. 'This question has a deep significance in the history of the Indian vernaculars, and it is necessary to present, with the utmost brevity, the views of the leading authorities on the subject. Dr. John Muir, that *clarum et venerabile nomen* in Anglo-Indian scholarship, devotes many pages to 'reasons for supposing that the Sanskrit was originally a spoken language.'² He traces the Sanskrit of the philosophical period to the earlier forms in the Vedic hymns, and concludes 'that the old spoken language of India and the Sanskrit of the Vedas were at one time identical.'³

Professor Benfey's view ;
affirmative. Professor Benfey gives the results of his long study of the question in even greater detail. He believes that Sanskrit-speaking migrations from beyond the Himálayas continued to follow one another into India down to perhaps the 9th century B.C. That Sanskrit became the prevailing Indian vernacular dialect throughout Hindustán, and as far as the southern borders of the Maráthá country. That it began to die out as a spoken language from the 9th century B.C., and had become extinct as a vernacular in the 6th century B.C. ; its place being taken by derivative dialects or Prákrits. But that it still lingered in the schools of the Bráhmans ; and that, about the 3rd century

¹ Professor Whitney's *Sanskrit Grammar*, p. ix. Leipzig, 1879.

² Muir's *Sanskrit Texts*, vol. ii. pp. 144-160, ed. 1874.

³ *Idem*, p. 160, and Dr. Muir's long footnote, No. 181.

and it was brought back into public life as a sacred language with a view to refuting the Buddhistic teachers who wrote in the vernacular or Prakrit dialects. Professor Benfey also holds that about the 5th century A.D. Sanskrit had diffused itself over the whole of India as a literary language. We know that a subsequent revival of Sanskrit for the Purānic or orthodox treatises of the Brāhmins, as opposed to the new doctrines of the reformers who used the vernacular, actually took place about the 10th century A.D.

Lassen inclines to the same general view. He thinks that, in the time of Asoka, the main body of Aryans of Northern India spoke local dialects, while Sanskrit still remained the speech of Brahmins, and of dignitaries of State.

Sanskrit scholars of not less eminence have come to the conclusion that Sanskrit was not at any time a vernacular tongue. Professor Weber assigns it to the learned alone. He thinks that the Prakrits, or Aryan vernaculars of Northern India, were derived directly from the more ancient Vedic dialects, while Sanskrit was 'the sum of the Vedic dialects constructed by the labour and zeal of grammarians, and polished by the skill of learned men.' Professor Aufrecht agrees 'in believing that Sanskrit proper (*i.e.* the language of the epic poems, the law books, nay, even that of the Brāhmanas) was never actually spoken, except in schools or by the learned.'

The question has been finally decided, however, not by Sanskrit scholars in Europe, but by students of the modern Aryan vernaculars in India. During the past fourteen years, a bright light has been brought to bear upon the language and literature of ancient India, by an examination of the actual speech of the people at the present day.

Two learned Indian civilians, Mr. Salmon Growse and Mr. John Beames, led the way from not always concurrent points of view. In 1872, Mr. Beames' *Comparative Grammar of the Modern Aryan Languages of India*¹ opened up a new field of human knowledge, and began to effect for the Aryan dialects of the North, what Bishop Caldwell's great work accomplished for non-Aryan speech in Southern India. Dr. Ernest Trümpf's *Grammar of the Sindhi Language* followed, and would probably have modified some of Mr. Beames' views. Another learned German officer of the Indian Government, Professor Rudolf

¹ Three volumes, Trübner & Co. The first volume was published in 1872; the last in 1879.

Hoernle, further specialized the research by his *Comparative Grammar of the Gaudian Languages* (1880), with particular reference to the Hindí. The same scholar and Mr. George Grierson, of the Civil Service, have, during the present year (1885), jointly brought out the first part of a *Comparative Dictionary of the Bihari Language*, which will enable every European inquirer to study the structure and framework of a modern Aryan vernacular for himself. These and other cognate works have accumulated a mass of new evidence, which settles the relationship of the present Aryan vernaculars to the languages of ancient India.

Results disclosed by the vernaculars.

Divergence of Sanskrit and Prákrit.

Pánini and Vararuchi.

The Prákrits spread south.

They prove that those vernaculars do not descend directly from Sanskrit. They indicate the existence of an Aryan speech older than Sanskrit, older, perhaps, than the Vedic hymns; from which the Sanskrit, the Prákrits or ancient spoken dialects of India, and the modern vernaculars were alike derived. Passing beyond the Vedic period, they show that ancient Aryan speech diverged into two channels. The one channel poured its stream into the ocean of Sanskrit, a language 'at once archaic and artificial,' elaborated by the Bráhmañical schools.¹ The other channel branched out into the Prákrits or ancient spoken vernaculars. The artificial Sanskrit (*Samskrita*, i.e. the perfected language) attained its complete development in the grammar of Pánini (circ. 350 B.C.).² The Prákrits (i.e. naturally evolved dialects) found their earliest extant exposition in the grammar of Vararuchi, about the 1st century B.C.³ But the 4000 algebraic aphorisms of Pánini mark the climax of the labours of probably a long antecedent series of Sanskrit elaborators, while Vararuchi stands at the head of a long series of subsequent Prákrit grammarians.

The spread of the Aryans from Northern India is best marked by the southern advance of their languages. The three great routes of Prákrit speech to the southward were—down the Indus valley on the west; along the Ganges valley to the east; and through certain historical passes of the

¹ Hoernle and Grierson's *Comparative Dictionary of the Bihari Language*, pp. 33 and 34. Secretariat Press, Calcutta, 1885. It should be remembered that Indian grammarians, when speaking of the Vedic language technically, do not call it Sanskrit, but *Chhandas*. They restrict the technical application of Sanskrit to the scholastic language of the Bráhmañas, elaborated on the lines of the earlier Vedic.

² *Vide ante*, pp. 100 et seq.

³ Hoernle's *Comparative Grammar of the Gaudian Languages*, p. xviii. et seq., ed. 1880.

Vindhya in the centre Between 500 B C and 500 A D, the western or Apabhramsa dialects of Prakrit had spread across the Indus basin, and down the Bombay coast During the same period dialects of Eastern or Magadhī Prakrit had occupied the valleys of the Jumna and the Ganges Aryan tribes, speaking the Maharashtra and Sauraseni Prakrits, had poured through the Vindhyan passes, one of their great lines of march being that followed by the Jabalpur Railway at the present day The Mahārāshtrī dialect reached as far south as Goa on the western coast The peninsula, to the south and east of the Maharashtra linguistic frontier, was inhabited by the Dravidian or Paisāchi speaking races

Their three lines of march

By degrees the main Prakrits or spoken Aryan dialects, differentiated themselves into local vernaculars, each occupying a more contracted area. A series of maps has been compiled showing the stages of this process between 500 B C and 1800 A D¹ Various classifications have been framed, both of the modern vernaculars and of the ancient Prakrits Vararuchi, the earliest Prakrit grammarian extant, enumerates four classes in the 1st century P C,—Mahārāshtrī, now Marathī,² Sauraseni, now the Brj of the North Western Provinces, Magadhī, now Bihārī, and Paisāchi, loosely applied to outlying non Aryan dialects from Nepal to Cape Comorin

Classification of Prakrits

Vararuchi's four classes

Apart from the last named Paisāchi, the literary Prakrits really divide themselves between two great linguistic areas Sauraseni, with the so called Mahārāshtrī, occupied the upper part of the North Western Provinces, and sent forth offshoots through the Vindhya passes as far south as Goa Magadhī spread itself across the middle valley of the Ganges, with its brightest literary centre in Behar These were the two parents of the most highly developed of the Aryan vernaculars of modern India The Apabhramsa, or 'broken' dialects of the Indus region, may for the moment be left out of sight

The two main Prakrits

The Prakrits, or spoken Aryan dialects of ancient India, received their first literary impulse from Buddhism As the Brahmins elaborated Sanskrit into the written vehicle for their

Prakrits developed by Buddhism

¹ Prefixed to Hearnle and Grierson's *Comparative Dictionary of the Bihārī Language* See also the Language Map appended to Hearnle's *Comparative Grammar of the Gaudian Languages*

² Mr Beames thinks that there is as much of the Magadhī and Sauraseni type in the modern Marathī as there is of the Maharashtra Prakrit, *Comparative Grammar of the Modern Aryan Languages*, vol 1 p 34, c 1 1872 He holds that Marathī reduces the name rather than the substance of Mahārāshtrī

orthodox religion, so the teachers of the new faith appealed to the people by works in the popular tongues. The Buddhist missionaries to Ceylon, *circa* 307 B.C., carried with them the spoken Prākṛit of the Gangetic kingdom of Magadha. This dialect of Northern Indian became Pāli, literally the series or *catena* of holy scripture in Ceylon. While the early Buddhists thus raised the Eastern or Magadhī Prākṛit of Behar to a sacred language, the Jains made use of the Mahārāshtrī Prākṛit of Western India for their religious treatises. In this way, the two most characteristic of the spoken Aryan dialects of ancient India obtained a literary fixity, during the centuries shortly before and after the commencement of our era.

for their
scriptures ;

and by the
Jains.

The
Prākṛits
also
remained
spoken
languages.

The Prākṛits also remained the speech of the people, and underwent those processes of development, decay, and regeneration to which all spoken languages are subject. On the one hand, therefore, we have the literary Magadhī and Mahārāshtrī Prākṛits of the beginning of the Christian era, the former embalmed in the Buddhist scriptures of Ceylon, the latter in the Jain sacred books of Western India. On the other hand, we have the spoken representatives of these two ancient Prākṛits in the modern vernaculars of Behar and of the Marāthā country.¹

Evolution
of modern
vernacu-
lars from
Prākṛits.

Obscure
interval,
400-1000
A.D.

The evolution of the modern vernaculars from the ancient Prākṛits is involved in deep obscurity. The curtain falls on the era of Prākṛit speech within a few hundred years after the birth of Christ, and does not again draw up until the 10th century. When it rises, Prākṛit dialects have receded from the stage, and their place has been taken by the modern vernaculars. During the dark interval, linguistic changes had taken place in the old Prākṛits not less important than those which transformed Latin into Italian and Anglo-Saxon into English. Those changes are now being elucidated by the series of comparative grammars and dictionaries mentioned on pp. 335-36. It is only practicable here to state the most important of the results.

The old Prākṛits were synthetical in structure. The

¹ This statement leaves untouched the question how far Marāthī is the direct representative of Mahārāshtrī, or how far it is derived from the Saurasenī Prākṛit. As already mentioned, both the Saurasenī and Mahārāshtrī poured through the Vindhya passes into South-Western India, and combined to form the second of the two main Prākṛits referred to in the classification on a previous page.

modern Aryan vernaculars of India are essentially analytical. During the eight centuries while the curtain hangs down before the stage, the synthetic inflections of the Prakrits had worn out. The terminals of their nouns and verbs had given place to post positions, and to the disjointed modern particles to indicate time, place, or relation. The function performed in the European languages by prepositions for the nouns are discharged, as a rule, by post positions in the modern Indian vernaculars. The process was spontaneous, and it represents the natural course of the human mind. 'The flower of synthesis,' to use the words at once eloquent and accurate of Mr Beames, 'budded and opened, and when full blown began, like all other flowers, to fade. Its petals, that is its inflections dropped off one by one, and in due course the fruit of analytical structure sprang up beneath it, and grew and ripened in its stead.'¹

As regards their vocabularies, the Aryan vernaculars of modern India are made up of three elements. One class of their words is named Tatsama, 'the same as' the corresponding words in Sanskrit. A second class is termed Tadbhava, 'similar in nature or origin' to the corresponding words in Sanskrit. The third class is called Desaja, or 'country born'. This classification is an ancient one of the Indian grammarians, and it is so far artificial that it refers the modern vernaculars to Sanskrit standards, while we know that the modern vernaculars were derived not from the Sanskrit, but from the Prakrits. It suffices, however, for practical purposes.

The great body of modern Indian speech belongs to the second or Tadbhava class of words, and may be taken loosely to represent its inheritance from the old spoken dialects or Prakrits. But the vernaculars have enriched themselves for literary purposes by many terms imported directly from the Sanskrit, to represent religious, philosophical, or abstract ideas. These are the Tatsamas, 'the same as' in Sanskrit. The different vernaculars borrow such 'identical' words from Sanskrit in widely varying proportions. The strongest of the vernaculars, such as Hindi and Maráthi, trust most to their own tadbhava or Prakrit element, while the more artificial of them, like the Bengali and Uriya, are most largely indebted to direct importations of Sanskrit words.

The third element in modern vernacular speech is the Desaja, or 'country born'. This represents the non Aryan and

¹ Mr Beames' *Comparative Grammar of the Modern Aryan Languages of India*, vol. 1, p. 45 (ed. 1872).

Non-Aryan element in the vernaculars ; other words not derived either from the Sanskrit or the Prākritis. At one time it was supposed, indeed, that the modern vernaculars of India were simply made up of the Sanskrit of the Aryan settlers, modified by, and amalgamated with, the speech of the ruder non-Aryan races whom they subdued. Modern philology renders this theory no longer tenable. It has proved that Sanskrit played a comparatively unimportant function in the formation of those vernaculars. It also tends to show that the non-Aryan element is less influential than was supposed. Both in structure and in vocabulary the modern vernaculars of India are the descendants neither of the written Sanskrit, nor of the aboriginal tongues, but of the Prākritis or spoken dialects of the ancient Aryans.

less important than formerly supposed. In regard to grammatical structure, this position is now firmly established. But the proportion of aboriginal or non-Aryan words in the modern Indian vernaculars still remains undetermined. The non-Aryan scholars, with Brian Hodgson and Bishop Caldwell at their head, assign a considerable influence to the non-Aryan element in the modern vernaculars.¹ Dr. Ernest Trumpp believes that nearly three-fourths of the

in Sindhī, Sindhī words commencing with a cerebral are taken from some non-Aryan or Scythic language, which he would prefer to call *Tátár*. He thinks, indeed, that there is very strong proof to show that the cerebral letters themselves were borrowed, by the Prākritis and modern Indian vernaculars, from some idiom

in Gangetic vernaculars, anterior to the introduction of the Aryan languages into India. Bishop Caldwell states that the non-Aryan element, even in the Northern Indian languages, has been estimated at one-tenth of the whole, and in the Maráthí at one-fifth.²

in Maráthí. Such generalizations are not accepted by the most eminent students of the Indo-Aryan vernaculars. Mr. Beames strongly expresses his view that the speech of the conquering Aryans completely overmastered that of the aboriginal tribes. The early grammarians were wont to regard as Desaja, or non-Aryan, all words for which they could not discover a Tatsama

The real proportion still unknown.

¹ See Mr. Brian Houghton Hodgson's *Aborigines of India*, Calcutta, 1849; and pp. 1-152 of vol. ii. of his *Miscellaneous Essays* (Trübner, 1880). Also the Rev. Dr. Stevenson's paper in the *Journal of the Asiatic Society of Bombay*.

² Bishop Caldwell's *Comparative Grammar of the Dravidian Languages*, introd. p. 57 (ed. 1875). Lassen held that the aboriginal tribes not only introduced 'peculiar varieties into the Prākrit dialects,' but also 'occasioned very great corruptions of sound and form in the Indo-Aryan languages' (*Indische Alterthumskunde*, ii. 1149). But the more recent investigations of Beames, Hoernle, and Grierson render these *dicta* doubtful.

or Tadbhava origin. But the more delicate processes of modern philology have reduced the number of this class, and tend still further to diminish it. The truth is, that until a complete examination is made with the new lights, both of the vocabulary and of the structure of the Indian vernaculars, no final conclusion can be arrived at.

Dr Hoernle thus sums up the existing knowledge in regard to the group of Indian vernaculars on which he is the highest authority. 'That there are non Aryan elements in the Bihari, I have no doubt. Considering that the Aryans immigrated into India, and absorbed large masses of the indigenous population into their ranks, it would be a wonder if no portion of the aboriginal languages had become incorporated into the Aryan speech. But what the several constituents of that aboriginal portion are, and what proportion they bear to the Aryan element in the vernacular language, it is impossible at present to form any scientific opinion. And what is more,—it is impossible to say whether the assumed aboriginal portion of the Aryan speech was Dravidian, or some other language, such as Kolarian or Tibeto Burman.'¹

¹ Letter from Dr. Rudolf Hoernle to the author, dated 28th May 1885. Dr. Hoernle continues—'Attempts have been made now and then (e.g. in *The Indian Antiquary*) to show that some particular selected words of the North Indian languages are really Dravidian. But these, even supposing they had been successful, would not enable any one to pronounce an opinion on the general question of the proportion of non Aryan words in the Gaudian languages. As a matter of fact some of these attempts, notably those referring to the genitive and dative post positions (*ka ke ki*, etc.), have been conspicuous failures. It is now, I think, generally admitted that these post positions are thoroughly Aryan. The truth is that the way in which the question of the non Aryan element in the vernaculars should be approached has been hitherto almost entirely misconceived. A little consideration must convince any one that whatever aboriginal elements there may be in the vernaculars, they must have been incorporated into them before the present vernacular times, that is, in the period when Sanskrit and Prakrit flourished. The question therefore properly stands thus—What are the aboriginal elements in Sanskrit and Prakrit? The vernaculars arose from Prakrit (and in a certain sense from Sanskrit) according to certain phonetic laws peculiar to the Aryan languages. Hence it is next to useless to try to refer Bihari (or any Aryan) vernacular words direct to the Dravidian. They must in the first place be referred back (by the well known Aryan phonetic laws) to their earlier forms in Prakrit and Sanskrit. Only when this is done, the question can properly be asked whether they are Aryan or non Aryan. And in order to decide this question, it will, among other points, have to be considered whether they possess correlates in the other Aryan languages (e.g. of Europe). But there is every probability that there is a considerable number of words in Sanskrit and Prakrit which are not Aryan, but only

Fourfold composition of the vernaculars :

(1) Prākṛit element.

(2) Aboriginal element.

(3) Sanskrit borrowings.

(4) Persian terms.

At present, therefore, we cannot advance further than the four following conclusions :—First, that in grammatical structure and in their vocabularies, the modern analytical vernaculars of India represent the old synthetic Prākṛits ; after a process of development, decay, and regeneration, which has been going on, as the result of definite linguistic laws, during the past fifteen hundred years. Second, that the modern vernaculars contain a non-Aryan element, derived from the so-called aborigines of India ; but that this element has very slightly affected their grammatical structure, and that the proportion which it holds in their vocabularies is yet undetermined. Third, that the modern vernaculars have enriched themselves, for literary and philosophical purposes, by direct and conscious borrowings from the Sanskrit. Fourth, that they have also imported many terms connected with the administration, the land revenue, judicial business, and official life, from the Persian court language of the Afghān and Mughal dynasties.

The seven Aryan vernaculars.

(1) Sindhī.

(2) Punjabi.

(3) Gujarāthī.

(4) Hindī.

(5) Marāthī.

The Aryan vernaculars of modern India may be distributed according to their geographical areas into seven main languages.

Towards the north-western frontier, Sindhī is spoken by the descendants of the shepherd tribes and the settlements who were left behind by the main stream of the prehistoric Aryan immigrants. The Sindhī language abounds in words of non-Aryan origin ; it contains very few Tatsamas, *i.e.* Sanskrit words in their original shape ; and it is almost destitute of an original literature. The Punjabi language is spoken in the valleys of the Indus and its tributaries. Like the Sindhī, it contains few Tatsamas, *i.e.* words borrowed directly from the Sanskrit.

Gujarāthī occupies the area immediately to the south of Punjabi ; while Hindī is conterminous with the Punjabi on the east. These two languages rank next to Punjabi in respect to the paucity of words borrowed directly from the Sanskrit. They are chiefly composed of Tadbhava, *i.e.* words representing the Prākṛits or old spoken dialects. Marāthī is spoken in the Districts to the south and east of the Guja-

Aryanized. The question, however, has never been systematically or satisfactorily investigated. Some attempts have latterly been made in this direction by showing that not a few Sanskrit words are, in reality, Prākṛit words Sanskritized. The next step will be to show that some Prākṛit words are non-Aryan words Prākṛitized (*i.e.* Aryanized).⁷

rāthi frontier, Bengali succeeds to Hindi in the east of Bengal (6) Bengali and the Gangetic delta, while Uriya occupies the Mahānadi (7) Uriya delta and the coast of the Bay of Bengal from near the mouth of the Hughli to the northern Districts of Madras. These three last named vernaculars, Marāthī, Bengali, and Uriya, are most largely indebted to modern and artificial importations direct from the Sanskrit.

With the exception of Sindhi, the modern vernaculars of India have each a literature of their own. Some of them, indeed, possess a very rich and copious literature. This subject still awaits careful study. The lamented Garcin de Tassy has shown how interesting, and how rich in results, that study may be rendered. His history of Hindi literature,¹ and his yearly review of works published in the Indian vernaculars, form a unique monument to the memory of a scholar who worked under the disadvantage of never having resided in India. But the unexhausted literary stores of the Indian vernaculars can only be appreciated by personal inquiry among the natives themselves. The barest summary of the written and unwritten works in the modern Indian vernaculars is altogether beyond the scope of the present work. It can merely indicate the wealth of unprinted, and in many cases unwritten, works handed down from generation to generation, arranged in geographical areas. The chapter will then conclude by selecting for description a few authors from three of the most advanced of the vernaculars — namely Hindi, Marāthī, and Bengali. It will not touch on the Persian or Musalman literature of the Delhi Empire.

As regards the isolated vernacular of Orissa, the present writer has elsewhere given an analytical catalogue of 107 Uriyá authors, with a brief description of 47 Uriyá manuscripts of undetermined authorship. Several of the Uriya poets and theologians were prolific authors, and have left behind them a number of distinct compositions. Thus, Dina Krishna Dās (circa 1550 A.D.) was so popular a writer as to earn for himself the title of 'The Son of God Jagannath'. His separate works number fifteen, and embrace a wide range of subjects, from 'the Waves of Sentiment,' an account of the youthful sports of Krishna, to severe medical treatises. Another Orissa poet of the 16th century composed 23 works,

¹ *Histoire de la Littérature Hindoue et Hindoustanie*, par M. Garcin de Tassy, 3 vols. large octavo 2nd ed., Paris 1870 71

² *Hunters Orissa*, vol. II App. ix. ed. 1872

on religious and metaphysical subjects, such as 'A Walk round the Sacred Enclosures of the Purí Temple,' and 'The Sea of the Nectar of Faith.' The greatest of the Uriyá poets, Upendra Bhanj, a Rájá of Gumsar, belongs to nearly the same period. He left behind him 42 collections of poems and treatises, some of them of great length.

Messrs. Hoernle and Grierson have lately exhibited the local literature of Behar, and its sub-divisions, with admirable learning and distinctness.¹ It must suffice here to refer the student to their lists of works in Bihárí and the modern dialects of the Gaudian group.

Rájputána
literature.

An idea of the wealth of poetry current in Rájputána may be gathered from the following statement. The figures are taken from a manuscript note forwarded to the author by the Rev. John Traill, Presbyterian missionary at Jaipur. Besides the ordinary Hindí works, such as translations from the Sanskrit, the Rájputs have a vast store of religious poetry and traditional song, still living in the mouths of the people. The works of only a single sect can be specified in detail.

Dadu.

Dadu, a religious reformer, born at Ahmadábád in 1544, left behind him a Báni, or body of sacred poetry, extending to twenty thousand lines. His life, by Jai Gopál, runs to three thousand lines. Fifty-two disciples spread his doctrine throughout Rájputána and Ajmere, each of them leaving a large collection of religious verse. The literary fertility of the sect may be inferred from the works of nine of the disciples. The poems and hymnology of Gharib Dás are said to amount to 32,000 lines; Jaisá is stated to have composed 124,000 lines; Prayág Dás, 48,000 lines; Rajab-jí, 72,000 lines; Bakhna-jí, 20,000 lines; Bábabá Banwári Dás, 12,000 lines; Shankar Dás, 4400 lines; Sándar Dás, 120,000 lines; and Mádhv Dás, 68,000 lines.

Sacred
poetry of a
single sect.

Dadu
hymno-
logies.

These figures are stated on the authority of Mr. Traill, and they are subject to the qualification that no European scholar has yet collected the writings of the sect. They are given as reported by the natives among whom the poems are still current. It is to be regretted that so little has yet been done to edit the stores of vernacular literature in the Feudatory States of India. A noble task lies before the more enlightened of the native princes; and in this task they would receive the willing assistance of English scholars now in India.

¹ *Comparative Dictionary of the Bihárí Language*, pp. 38-42 (quarto; Calcutta, 1885).

A very brief notice of the most distinguished authors in Hindi, Maráthi, and Bengali must conclude this chapter. For practical purposes, those three vernaculars represent the highest modern development of the modern Indian mind. This is, of course, exclusive of the Dravidian literature in the south of India, which has already been dealt with at the beginning of the chapter. The monastic literature of Burma is almost entirely a reproduction of the ancient Buddhist writings, and does not come within the scope of this work.

Hindi ranks, perhaps, highest among the Indian vernaculars in strength and dignity. At the head of Hindi authors is Chand Bardai. Chand was a native of Lahore, but lived at the court of Prithwí Rájá, the last Hindu sovereign of Delhi, at the close of the twelfth century.¹ His poems are a collection of ballads in which he recites, in his old age, the gallant deeds of the royal master whom he had served, and whose sad fate he had survived. They disclose the ancient Prákrit in the very act of passing into the modern vernacular. In grammatical structure they still retain many relics of the synthetic or inflectional type, although the analytical forms of the modern vernaculars are beginning to crowd out these remnants of the earlier phase of the Indian speech. Chand's ballads have been printed, but they also survive in the mouths of the people. They are still sung by wandering bards throughout North Western India and Rájputána, to near the mouths of the Indus, and to the frontier of Baluchistan.

The vernacular literatures derived their chief impulse, however, not from court minstrelsy, but from religious movements. Each new sect seems to have been irresistibly prompted to embody its doctrines in verse. Kabír, the Indian Luther of the fifteenth century, may be said to have created the sacred literature of Hindi.² His Ramainis and Sabdas form an immense body of religious poetry and doctrine. In the following century, Sur Dás of Mathura, Nabhají and Keshava Dás of Bijapur, wrote respectively the Surságar, the Bhaktamálá, and the Ramchandriká. A brief notice of the Bhaktamálá has already been given at page 208. In the seventeenth century, Bihari Lál, of the ancient city of Amber near Júpúr, composed his famous Satsai, and Bundelkhand produced its prince of poets, Lal Kavi, the author of the Chháttra Prakas. All these were natives of western

¹ For Prithwí Rájá *vide ante*, chap. x p. 276.

² For Kabír's work as a religious reformer, *vide ante*, pp. 208, 218.

Hindustán, except Kabír, who belonged to the Benares district.

18th century. The last troubled years of the Mughal dynasty in the eighteenth century brought about a silence in Hindí literature. That silence was effectually broken by the introduction of the printing press in the nineteenth century. It has been succeeded by a great outburst of Hindí activity in prose and verse. Every decade now produces hundreds of Hindí publications, to some extent reproductions or translations of ancient authors, but also to a large extent original work.

Maráthí literature. The Maráthás are scarcely more celebrated as a military than as a literary race. Their language is highly developed, and possesses structural complications attractive to the Indian student. The first Maráthí poet of fame was Nám Deva, 13th century A.D. about the end of the thirteenth century. Like his contemporary, Dnyánoba the author of the celebrated Dnyáneshwarí, he was deeply impressed with the spiritual aspects of life. Indeed, almost all the Maráthí writers are religious poets. About the year 1571, Sridhar compiled his huge Maráthí adaptation or paraphrase of the Sanskrit Puránas.

Tukarám, 17th century A.D. Maráthí poetry reached its highest flight in the Abhangas or spiritual poems of Tukarám or Tukoba (*circa.* 1609). This famous ascetic started life as a petty shopkeeper; but failing in retail trade, he devoted himself to religion and literature. The object of his adoration was Vithoba, a corruption of Bishtu or Vishnu. Tukarám was the popular poet in Western India of the reformed Vishnuite faith which Chaitanyá had taught in Bengal. He inveighed with peculiar unctiousness and beauty against the riches of the world, which in his earlier years he had himself failed to secure.

Mayúr Pandit, 18th century A.D. About 1720, Mayúr Pandit or Moropanth poured forth his copious song in strains which some regard as even more elevated than the poems of Tukarám.

Besides its accumulations of religious verse, Maráthí possesses a prose literature, among which the chief compositions are the Bakhars or Annals of the Kings. It is also rich in love songs, and farcical poetry of a broad style of wit.

Bengalí literature; Bengalí is, in some respects, the most modern of the Indian vernaculars. As a spoken language, it begins on the north, where Hindí ends on the south; that is to say, in the Gangetic valley below Behar. From Rájmahal on the north to the Bay of Bengal, and from Assám on the east to Orissa on the

west, Bengali forms the speech of about 50 millions of people in the valleys and deltas of the Brahmaputra and the Ganges. The language exhibits clearly marked dialectical modifications in the north the east, and the west, of this great area. But for literary purposes Bengali may be regarded as a linguistic entity. Indeed literary Bengali of the modern type is, to some extent, an artificial creation. Much more than the Hindi, it has enriched itself by means of words directly imported from the Sanskrit. Such words not only supply the philosophical, religious, and abstract terms of Bengali literature, but they enter largely into the every day language of the people. This is to some extent due to the circumstance that the Bengalis have very rapidly adopted western ideas. With the introduction of such ideas arose the necessity for new terms, and for these terms, Bengali writers naturally turned towards the Sanskrit.

The process has not been confined, however, to philosophic works. Even in poetry the best Bengali writers of the present day affect a more classical style than that of their predecessors from the fourteenth to the eighteenth century. In 17 lines of Bengali verse taken from a contemporary periodical, the *Banga darshana*, there are only six or seven words which are not Sanskrit importations. 'If we progress in this direction a century longer,' writes a native author, 'the Bengali language will be distinguishable from the Sanskrit only by the case terminations and mood and tense terminations.'¹ The framework of the colloquial language still continues to be derived from the Prakrit, although Sanskrit terms are diffusing themselves even among the spoken language of the educated classes.

Bengali literature commences with the vernacular poets of the fourteenth century. During its first two hundred years, Bengali song was devoted to the praises of Krishna, and the loves of the young god. In the sixteenth century two great revolutions, religious and political, took place in Bengal. In the political world, the independent Afghan dynasty of Bengal succumbed to the advancing Mughal power, and

¹ *The Literature of Bengal*, by Argy Dae p. 43 Calcutta, 1877. This interesting volume is based on the more elaborate Bengali work of Pandit Jagat Narayana. A complete treatment of the subject is still a desideratum which it is hoped that Bengali research will before long supply. Mr. Dae whose volume has been freely used in the following pages, would confer a benefit both on his countrymen and on European students of the Indian vernaculars by undertaking the task.

Bengal was finally incorporated as a Province of the Delhi Empire.

(2) 16th to
18th cen-
tury.

In religion, a reformation of the Sivaite religion was effected under Bráhmán impulses, and Krishna-worship receded from its literary pre-eminence. During the next two hundred and fifty years Bengálí poetry found its chief theme in the praises of Kálí or Chandí, the queen of Siva, who is alike the god of Destruction and of Reproduction. Early in the nineteenth century, European influences began to impress themselves on Bengálí thought. Bengálí literature accordingly entered upon a third period, the period through which it is still passing, and which corresponds to the imported Western civilisation of India in the nineteenth century.

Bidyápati
Thákur,
14th cen-
tury.

Putting aside Jayadeva of Bír bhúm, the Sanskrit singer in the twelfth century, Bengálí poetry commences with Bidyápati Thákur, a Bráhmán of Tirhút. Bidyápati adorned the court of King Sivasinha of Tirhút in the fourteenth century; and a deed of gift, still existing, proves that he had made his fame before 1400 A.D. Although popularly claimed as the Chaucer of Bengal, he wrote in what must now be regarded as a Bihárí rather than a Bengálí dialect; and recited in learned verse the loves of Rádhá and Krishna. About the same period Chandí Dás, a Bír bhúm Bráhmán, took up the sacred strain in the Bengálí tongue. Originally a devotee of the goddess Chandí, queen of Siva, he was miraculously converted to the worship of Krishna, whose praises he celebrated in a less learned, but more forcible colloquial style. To these two poets and their followers, Krishna was a lover rather than a deity; and his mistress Rádhá, more of a pastoral beauty than a goddess. But their poetry constantly realizes that beneath the human amours of the divine pair, lies a deep spiritual significance. This didactic side of their poetry may be illustrated by three verses of Bidyápati to Krishna under his title of Mádhava, 'The Honeyed One.'

Chandí
Dás, 15th
century.

Verses by
Bidyápati.

A HYMN TO KRISHNA.

'O ! Mádhava ! our final stay,
The Saviour of the world Thou art,
In mercy look upon the weak,
To Thee I turn with trustful heart.

Half of my life in sleep has past ;
In illness—boyhood—years have gone,
In pleasure's vortex long I roamed,
Alas ! forgetting Thee, the One.

Unnumbered beings live and die,
They rise from Thee and sink in Thee,
(Thou uncreate and without end)
Like ripples melting in the sea. ¹

At the beginning of the sixteenth century, the great religious reformer Chaitanyá² gave a more serious turn to the poetry of Bengal. He preached the worship of Vishnu, and the doctrine of saving faith in that deity. Krishna was the pastoral incarnation of the god, but the Vishnuism taught by Chaitanyá spiritualized the human element in the amours which the earlier poets had somewhat warmly sung. Chaitanyá declared the spiritual equality of mankind, and combated the cruel distinctions of caste. His doctrine amounted to a protest against the Hinduism of his day, although it has been skilfully incorporated by the later Hinduism of our own. The opposition, excited by Chaitanya's Vishnuite reformation, took the form of a revival of the worship of Siva and his queen.

There were thus in the sixteenth century, two great religious movements going on in Bengal, the one in favour of Vishnu, the second person of the Hindu triad, and the other in favour of Siva, the third person of that trinity. The more serious aspect which Chaitanya gave to Vishnuism did not lend itself to popular song so easily as the human loves of Krishna, celebrated by the earlier Vishnuite poets. On the other hand, the counter revival of Sivaism accepted as its objects of adoration, some form or other of the Goddess of Destruction and Reproduction under her various names³ of Uma, Párvatí, Durgá, Kali or Chandí. These names suggested alike the terrors and the mercies of the Queen of Siva, and appealed in a special manner to a people dwelling amid the stupendous catastrophes of nature in a deltaic Province like Bengal.

The result was an outburst of Bengali song, which took as its theme the praises of Chandí, the wife of Siva. Kirtibás Ojá, a Bráhmaṇ of Nadiya District in the sixteenth century, marks the transition stage. Kirtibás drew his inspiration from the Sanskrit epics, and his great work is the Bengali version of the *Rámajana*. His translation is still recited by Ghattaks or bards at a thousand religious and festive gatherings every year throughout Bengal. Its modern versions have received much

¹ Slightly altered from the rendering of Mr Dae's *Literature of Bengal*, 60 (Bose & Co., Calcutta, 1877)
² *Ide ante*, pp 219-21

³ For the different names of the wife of Siva, and the aspects of the goddess which these names connote, *vide ante*, pp 211, 212

His Bengali *Rámáyana*.

re-touching from later poets of the classical or Sanskritizing school; but an old copy of 1693 proves that Kirtibás wrote in a strong colloquial style, with a ring and rhythm of peculiar beauty. The *Rámáyana* recites the achievements of the heroic incarnation of Vishnu, and Kirtibás Ojhá may therefore be claimed as a Vishnuite poet. But in reality his work marks the Sanskrit revival which gave the impulse to the Sivaite or Chandí poets of the next two and a half centuries.

Sivaite and Chandí poets, 16th to 18th century.

Makunda Rám.

These Sivaite poets kept possession of Bengali literature during the 250 years which elapsed before the commencement of the third or present period. First among them was Makunda Rám Chakravarti, a Bráhmaṇ of Bardwán District, and a contemporary of Kirtibás Ojhá in the 16th century. He was driven from his home by the oppressions of Muhammadan officers, and his verses give a lifelike picture of the Muhammadan land settlement of Lower Bengal. All classes, he says, were crushed with an equal tyranny; fallow lands were entered as arable, and by a false measurement, three-fourths of a *bighá* were taxed as a full *bighá*. In the collection of the revenue, the oppressions were not less than in the assessment. The treasury officers deducted more than one rupee in seven for short weight and exchange. The husbandmen fled from their lands, and threw their cattle and goods into the markets, 'so that a rupee worth of things sold for ten annas.' Makunda Rám's family shared the common ruin; but the young poet, after a wandering life, found shelter as tutor in the family of Bánkurá Deb, a powerful landholder of Bírghúm and Midnapur Districts. He was honoured with the title of Kabi Kankan, or the Jewel of Bards, and wrote two great poems besides minor songs.

The story of Kálketu, by Makunda Rám.

His most popular work is the story of Kálketu, the hunter. Kálketu, a son of Indra, King of Heaven, is born upon earth as a poor hunter. In his celestial existence he had a devoted wife, and she, too, is born in this world, and becomes his faithful companion throughout their allotted earthly career. Their mortal births had been brought about by the goddess Chandí, queen of Siva, in order that she might have a city founded and dedicated to herself. The poor hunter and his wife, Fullorá, after years of hardship, are guided to a buried treasure by their kind patroness, Chandí. With this, the hunter builds a city, and dedicates it to the goddess. But misled by a wicked adviser, he goes to war with the King of Kalinga on the south, is defeated, and cast into prison. In due time Chandí rescues her foolish but faithful servant. At

lost the hunter and his true wife die and ascend to heaven
He lives again as the son of Indra, while Fullora again becomes
his celestial spouse

The other poem of Makunda Rám narrates the adventures of a spice merchant, Dhanapati, and his son, Srimanta Sada-
gar. A celestial nymph, Khulloná is sent down to live on earth as penance for a venial offence. She grows into a beautiful girl, and is wedded by the rich merchant Dhanapati, who has, however, already a first wife. Before the marriage can be consummated the king of the country sends off the merchant to Eastern Bengal to procure a golden cage for a favourite bird. The bride is left with his elder wife in the family home upon the banks of the Adjú, a river which separates Birbhum and Bardwan Districts in South Western Bengal. A wicked handmaid excites the jealousy of the elder wife, and the girl bride is condemned to menial offices and sent forth as a goat herd to the fields. The kind goddess Chandi however converts the elder lady to a better frame of mind, the girl bride is received back and on the return of her husband becomes his favourite wife. In due time she bears him a son, Srimanta Sadagar, the hero of the subsequent story.

The king next sends the merchant for spices to Ceylon, and his voyage down the great rivers of Bengal and across the sea is vividly described. From the towns mentioned on his route it appears that in those days the water way from Bardwán District and the neighbouring country to the Bay of Bengal, lay by the Huglí as far down as Calcutta and then struck south eastward by what is now the dead river of the Adí Gangá. The poor merchant is imprisoned by the King of Ceylon, and there languishes until he is sought out by his brave son, Srimanta Sadagar, from whom the poem takes its name. Srimanta is also seized, and led out to execution by the cruel king. But the kind goddess Chandi delivers both father and son, and the beautiful Khulloná receives back with her lost treasures from the sea.

In the 17th century, the second of the two great Sanskrit poems, the *Mahábhārata*, was translated by Kasi Rám Das, 17th century poet also belonged to Bardwán District. His version holds its place in the affections of the people, and is hunted by professional birds throughout all Bengal. The Bengali tender episodes are rendered with feeling and grace, and

See article HUGLI RIVER in *The Imperial Gazetteer of India*

but the fiery quarrels and heroic spirit of the Sanskrit original lose much in the Bengali translation.

Bengali
poets of
the 18th
century.

Rám
Prasád
Sen.

The 18th century produced two great Bengali poets. In 1720, Rám Prasád Sen, of the Vaidya caste, was born in Nadiyá District. Sent at an early age as clerk to a Calcutta office, he scribbled verses when he should have been casting up accounts, and was reported for punishment by the chief clerk. The head of the business read the rhymes, dismissed the poet, but assigned to him a pension of Rs. 30 a month. With this he retired to his native village, and wrote poetry for the rest of his life. Rám Prasád was a devout Tantrik or worshipper of the wife of Siva, and his poems consist chiefly of appeals to the goddess under her various names of Káli, Sakti, etc. His songs, however, are more often complaints of her cruelty than thanksgivings for her mercies.¹

The Court
of Nadiyá,
18th cen-
tury.

The little Hindu court of Nadiyá then formed the centre of learning and literature in Bengal, and the Rájá endowed Rám Prasád with 33 acres of rent-free land. The grateful poet in return dedicated to the prince his *Kabiranján*, or version of the tale of *Bidyá Sundar*. The fame of this version has, however, been eclipsed by the rendering of the same story by a rival poet Bhárat Chandra. Two other well-known works, the *Káli Kirtan* and the *Krishna Kirtan*, in honour respectively of Káli and Krishna, with many minor poems, have also come down from the pen of Rám Prasád.

Bhárat
Chandra
Rái.

The other great Bengal poet of the 18th century was Bhárat Chandra Rái, who died 1760. The son of a petty Rájá, he was driven from his home by the oppressions of the Rájá of Bardwán, and after many adventures and imprisonment, obtained the protection of the chief native officer of the French Settlement at Chandarnagar. The generosity of the Rájá of Nadiyá² afterwards raised him to comfort, and he devoted his life to three principal poems. His version of the *Bidyá Sundar* is a passionate love poem, and remains the accepted rendering of that tale to the present day. The goddess Káli interposes at the end to save the life of the frail heroine. His other two principal poems, the *Annadá Mangal* and the *Mánsinha*, form continuations of the same work; and, like it, are devoted to the glorification of the queen of Siva under her various names.

With the printing press, and the Anglo-Indian School, arose

¹ Dae's *Literature of Bengal*, p. 147. (Calcutta, 1877.)

² Mr. Dae says, inadvertently, the Rájá of Bardwán.

a generation of Bengalis whose chief ambition is to live by the pen. The majority find their career in official, mercantile, or professional employment. But a large residue become writers of books, and Bengal is at present passing through a grand literary climacteric. Nearly 1300 works per annum are published in the vernacular languages of Lower Bengal alone. It is an invidious task to attempt to single out the most distinguished authors of our own day. Amid such a climax of literary activity, much inferior work is produced. But it is not too much to say that in poetry, philosophy, science, the novel and the drama, Bengali literature has, in this century, produced masterpieces without rivals in its previous history. In two departments it has struck out entirely new lines. Bengali prose practically dates from Rám Mohan Rai, and Bengali journalism is essentially the creation of the third quarter of the present century.¹

Recent
Bengali
literature,
19th cen-
tury

As Bengali poetry owed its rise in the 14th century, and its fresh impulse in the 16th, to outbursts of religious song, so Bengali prose is the offspring of the religious movement headed by the Rájá Rám Mohan Rai in the 19th. This great theistic reformer felt that his doctrines and arguments required a more serious vehicle than verse. When he died in 1833, he at once received the position of the father of Bengali prose,—a position which he still enjoys in the grateful memories of his countrymen.² Of scarcely less importance, however, in the creation of a good prose style, were two rival authors born in 1820. Akkhai Kumár Datta enforced the theistic doctrines of the Brahmi Samaj with indefatigable ability in his religious journal, the *Tatvalodhini Patrika*. Reprints of his articles still rank as text books of standard Bengali prose. Iswar Chandra Vidyasagar, also born in 1820, devoted himself to social reform upon orthodox Hindu lines. The enforced celibacy of widows, and the abuses of polygamy, have formed the subject of his life long attacks.

Bengali
prose, 19th
century

An older worker, Iswar Chandra Gupta, born 1809, took the lead in the modern popular poetry of Bengal. His fame has

¹ From no list of 19th century Bengali authors should the following names be omitted —Rám Mohan Rai, Akkhai Kumár Datta, Iswar Chandra Vidyasagar, Iswar Chandra Gupta, Madhu Sudan Datta, Hem Chandra Banarji, Bankim Chandra Chattarji, Dinó Bandhu Mitra, and Nabín Chandra Sen.

² Rájá Rám Mohan Rai (Kámmohun Roy) is also well known for his English works, of which it is pleasant to record that a collected reprint is now appearing under the editorship of Ítábu Gogendra Chandra Ghose, M.A. (Calcutta, 1885).

Modern
Bengali
poets,
19th cen-
tury.

been eclipsed, however, by Madhu Sudan Datta, born 1828, who now ranks higher in the estimation of his countrymen than any Bengali poet of this or any previous age. Madhu Sudan's epic, the *Meghnád Badh Kábya*, is reckoned by Bengali critics as second only to the masterpieces of Válmiki, Kálidása, Homer, Dante, and Shakspeare. This generous appreciation is characteristic of the catholic spirit of Hinduism. For Madhu Sudan Datta became a Christian, lectured as professor in a Christian college, went to England, and returned to Bengal only to die, after a too brief career, in 1875. His epic relates the death of Meghnad or Indrajít, greatest of the sons of Ravana, and takes its materials from the well-known episode in the *Rámáyana*. Among Bengali poets still living, Hem Chandra Banarji occupies perhaps the highest place of honour.

Madhu
Sudan
Datta,
1828-1875.

The
Bengali
Drama.

In the Bengali drama, Dina Bandhu Mitra, born 1829, died 1873, led the way. His first and greatest work, the *Níl Darpan* or Mirror of Indigo, startled the community by its picture of the abuses of indigo planting a quarter of a century ago. It was translated into English by the well-known missionary and philanthropist, the Rev. James Long; and formed the ground of an action for libel, ending in the fine and imprisonment of the latter gentleman. In prose fiction, Bunkim Chandra Chattarjí, born 1838, ranks first. The Bengali novel is essentially a creation of the last half century, and the *Durgesh Nandini* of this author has never been surpassed. But many new novelists, dramatists, and poets are now establishing their reputation in Bengal; and the force of the literary impulse given by the State School and the printing press seems still unabated. It is much to be regretted that so little of that intellectual activity has flowed into the channels of biography and critical history.

The mean-
ing of this
chapter.

This chapter has dealt at some length with the vernacular literature of India, because a right understanding of that literature is necessary for the comprehension of the chapters which follow. It concludes the part of the present book which treats of the struggle for India by the Asiatic races. In the next chapter the European nations come upon the scene. How they strove among themselves for the mastery will be briefly narrated. The conquest of India by any one of them formed a problem whose magnitude not one of them appreciated. The Portuguese spent the military resources of their country, and the religious enthusiasm of their Church, in the vain

attempt to establish an Indian dominion by the Inquisition and the Sword This chapter has shown the strength and the extent of the indigenous civilisation which they thus ignorantly and unsuccessfully strove to overthrow

Assaults
on the
indigenous
civilisation
of India

The Indian races had themselves confronted the problems for which the Portuguese attempted to supply solutions from without One religious movement after another had swept across India, one philosophical school after another had presented its explanation of human existence and its hypothesis of a future life A popular literature had sprung up in every Province The Portuguese attempt to uproot these native growths, and to forcibly plant in their place an exotic civilisation and an exotic creed, was foredoomed to failure From any such attempt the Dutch and the French wisely abstained One secret of the success of the British power has been its non interference with the customs and the religions of the people

English
non inter
ference

CHAPTER XIV.

EARLY EUROPEAN SETTLEMENTS (1498 TO 18TH CENTURY A.D.).

The Portuguese in India. Vasco da Gama, 1498. THE Muhammadan invaders of India had entered from the north-west. Her Christian conquerors approached by sea from the south. From the time of Alexander to that of Vasco da Gama, Europe held little direct intercourse with the East. An occasional traveller brought back stories of powerful kingdoms and of untold wealth; but the passage by sea was scarcely dreamed of, and by land, wide deserts and warlike tribes lay between. Commerce, indeed, struggled overland and *viâ* the Red Sea; being carried on chiefly by the Italian cities on the Mediterranean, which traded to the ports of the Levant.¹ But to the Europeans of the 15th century, India was an unknown land, which powerfully attracted the imagination of spirits stimulated

¹ The following is a list of the most noteworthy early travellers to the East, from the 9th century to the establishment of the Portuguese as a conquering power in India in the 16th. The Arab geographers will be found in Sir Henry Elliot's first volumes of the *Indian Historians*. The standard European authority is *The Book of Ser Marco Polo the Venetian*, edited by Colonel Henry Yule, C.B., 2 vols., second edition, 1875. The author's best thanks are due to Colonel Yule for the assistance he has kindly afforded both here and in those articles of *The Imperial Gazetteer of India*, which came within the scope of Colonel Yule's researches. The authorities for the more ancient travellers and Indian geographers are, as already stated, M'Crindle's *Megasthenes and Arrian*, his *Ktesias*, and his *Navigation of the Erythrean Sea*, which originally appeared in the *Indian Antiquary*, and were republished by Messrs. Trübner. *The Commerce and Navigation of the Ancients in the Indian Ocean*, by Dr. William Vincent, Dean of Westminster (2 vols. quarto, 1807), may still be perused with interest, although Dr. Vincent's materials have been supplemented by fuller and more accurate knowledge. 883 A.D. King Alfred sends Sigheilm of Sherburn to the shrine of Saint Thomas in 'India.' The site of the shrine is doubtful, see chap. ix. 851-916. Suláimán and Abu Zaid, whose travels furnished the *Relations* of Reinaud.

912-30. The geographer Mas'udi.

1159-73. Rabbi Benjamin of Tudela; visited Persian Gulf, reported on India.

1260-71. The brothers Nicolo and Maffeo Polo, father and uncle of Marco Polo; make their first trading venture through Central Asia.

by the renaissance, and ardent for discovery. The materials for this period have been collected by Sir George Birdwood in his admirable official *Report on the Old Records of the India Office* (1879), to which the following paragraphs are largely indebted. The history of the various European settlements will be found in greater detail, under their respective articles, in *The Imperial Gazetteer of India*.

In 1492, Christopher Columbus sailed westwards under the Spanish flag to seek India beyond the Atlantic, bearing with him a letter to the great Khan of Tartary. He found America instead. An expedition under Vasco da Gama started from Lisbon five years later, in the opposite, or south eastern, direction. It doubled the Cape of Good Hope, and cast anchor off the city of Calicut on the 20th May 1498, after a protracted voyage of nearly eleven months. An earlier Portuguese emissary, Covilham, had reached Calicut overland about 1487.

1271 They started on their second journey accompanied by Marco Polo, and about 1275 arrived at the Court of Kublai Khan in Shangtu, whence Marco Polo was entrusted with several missions to Cochinchina, Khanbulug (Pekin), and the Indian Seas.

1292 Friar John of Monte Corvino, afterwards Archbishop of Pekin, spent thirteen months in India on his way to China.

1304-78 Ibn Batuta, an Arab of Tangiers, after many years in the East, attached himself to the Court of Muhammad Tughlak at Delhi, 1334-42, whence he was despatched on an Embassy to China.

1316-30 Odorico di Pordenone, a Minorite friar, travelled in the East and through India by way of Persia, Bombay, and Surat (where he collected the bones of four missionaries martyred in 1321), to Malabar, the Coromandel coast, and thence to China and Tibet.

1328 Friar Jordanus of Severac, Bishop of Quilon.

1338-49 John de Marignolli, a Franciscan friar, on his return from a mission to China, visited Quilon in 1347, and made a pilgrimage to the shrine of St. Thomas in India in 1349.

1327-72 Sir John Mandeville, wrote his travels in India (supposed to be the first printed English book, London 1499), but beyond the Levant his travels are invented or borrowed.

1419-40 Nicolo Conti, a noble Venetian, travelled throughout Southern India and along the Bombay coast.

1442-44 Abd ur Razzak, during an embassy to India, visited Calicut, Mangalore, and Vijayanagar, where he was entertained in state by the Hindu sovereign of that kingdom.

1468-74 Athanasius Nikitin, a Russian, travelled from the Volga, through Central Asia and Persia, to Gujarat, Cambay, and Chaul, whence he proceeded inland to Bidar and Golconda.

1494-99 Hieronimo di Santo Stefano, a Genoese, visited the port of Malabar and the Coromandel coast as a merchant adventurer, and after proceeding to Ceylon and Pegu sailed for Cambay.

1503-08 Travels of Ludovico di Varthema. In the *Hakluyt Series*.

State of
India on
arrival of
Portu-
guese.

From the first, Da Gama encountered hostility from the Moors, or rather Arabs, who monopolized the sea-borne trade; but he seems to have found favour with the Zamorin or Hindu Rájá of Malabar. An Afghán of the Lodí dynasty was then on the throne of Delhi, and another Afghán king was ruling over Bengal. Ahmadábád formed the seat of a Muhammadan dynasty in Gujarát. The five independent Muhammadan kingdoms of Ahmednagar, Bijápur, Elichpur, Golconda, and Bídár had partitioned out the Deccan. But the Hindu Rájá of Vijayanagar still ruled as paramount in the south, and was perhaps the most powerful monarch to be found at that time in India, not excepting the Lodí dynasty at Delhi.

Rájá of
Calicut's
letter,
1498.

After staying nearly six months on the Malabar coast, Da Gama returned to Europe, bearing with him the following letter from the Zamorin to the King of Portugal:—'Vasco da Gama, a nobleman of your household, has visited my kingdom and has given me great pleasure. In my kingdom there is abundance of cinnamon, cloves, ginger, pepper, and precious stones. What I seek from thy country is gold, silver, coral, and scarlet.' The safe arrival of Da Gama at Lisbon was celebrated with national rejoicings as enthusiastic as those which had greeted the return of Columbus. If the West Indies belonged to Spain by priority of discovery, Portugal might claim the East Indies by the same right. The Portuguese mind became intoxicated by dreams of a mighty oriental empire.

Portuguese
expedi-
tion, 1500.

The early Portuguese navigators were not traders or private adventurers, but admirals with a royal commission to conquer territory and to promote the spread of Christianity. A second expedition, consisting of thirteen ships and twelve hundred soldiers, under the command of Cabral, was despatched in 1500. 'The sum of his instructions was to begin with preaching, and if that failed, to proceed to the sharp determination of the sword.' On his outward voyage, Cabral was driven by stress of weather to the coast of Brazil. Ultimately he reached Calicut, and established factories both there and at Cochin, in spite of active hostilities from the natives.

Portuguese
supremacy
in eastern
seas, 1500-
1600.

In 1502, the King of Portugal obtained from Pope Alexander VI. a bull constituting him 'Lord of the Navigation, Conquests, and Trade of Ethiopia, Arabia, Persia, and India.' In that year Vasco da Gama sailed again to the East, with a fleet numbering twenty vessels. He formed an alliance with the Rájás of Cochin and Cananore against the Zamorin of Calicut, and bombarded the latter in his palace. In 1503, the great Alfonso d'Albuquerque sailed to the East in command of

one of three expeditions from Portugal. In 1505, a large fleet of twenty two sail and fifteen thousand men was sent under Francisco de Almeida, the first Portuguese Governor and Viceroy of India.

In 1509, Albuquerque succeeded as Governor, and widely extended the area of Portuguese influence. Having failed in an attack upon Calicut, he in 1510 seized Goa, which has since remained the capital of Portuguese India. Then, sailing round Ceylon, he captured Malacca, the key to the navigation of the Indian archipelago, and opened a trade with Siam and the Spice Islands. Lastly, he sailed back westwards, and after penetrating into the Persian Gulf and the Red Sea, returned to Goa only to die in 1515. In 1524, Vasco da Gama came out to the East for the third time, and he too died at Cochin, in 1527. For exactly a century, from 1500 to 1600, the Portuguese enjoyed a monopoly of Oriental trade.¹ 'From Japan and the Spice Islands to the Red Sea and the Cape of Good Hope, they were the sole masters and dispensers of the treasures of the East, while their possessions along the Atlantic coast of Africa and in Brazil completed their maritime empire.'²

But the Portuguese had neither the political strength nor the personal character necessary to maintain such an Empire. Their national temper had been formed in their contest with the Moors at home. They were not traders, but knights errant and crusaders, who looked on every pagan as an enemy of Portugal and of Christ. Only those who have read the contemporary narratives of their conquests, can realize the superstition and the cruelty with which their history in the Indies is stained.

Albuquerque alone endeavoured to conciliate the goodwill of the natives, and to live in friendship with the Hindu princes, who were naturally better pleased to have the Portuguese, as governed by him, for their neighbours and allies, than the Muhammadans whom he had expelled or subdued. The justice and magnanimity of his rule did as much to extend and confirm the power of the Portuguese in the East, as his courage and the success of his military achievements.

¹ For a full account of the Portuguese in India and the curious phases of society which they developed, see article GOA *The Imperial Gazetteer of India*. Also for local notices, see articles DAMAN, DIU, BASSEIN, CALICUT.

² This and the following paragraphs are condensed from Sir George Grieco's official *Report on the Miscellaneous Old Records in the India Office*, dated 1st November 1878 (folio, 1879).

In such veneration was his memory held, that the Hindus of Goa, and even the Muhammadans, were wont to repair to his tomb, and there utter their complaints, as if in the presence of his shade, and call upon God to deliver them from the tyranny of his successors.

Later
Viceroys ;

their
bravery.

‘The cruelties of Soarez, Sequeyra, Menezes, Da Gama, and succeeding viceroys, drove the natives to desperation, and encouraged the princes of Western India in 1567 to form a league against the Portuguese, in which they were joined by the King of Achin.’ But the undisciplined Indian troops were unable to stand against the veteran soldiers of Portugal; 200 of whom, at Malacca, routed 15,000 natives with artillery. When, in 1578, Malacca was again besieged by the King of Achin, the small Portuguese garrison destroyed 10,000 of his men, and all his cannon and junks. Twice again, in 1615 and for the last time in 1628, Malacca was besieged, and on each occasion the Achinese were repulsed with equal bravery. But the increased military forces sent out to resist these attacks proved an insupportable drain on the revenues and population of Portugal.

Spanish
influences,
1580.

In 1580, the Portuguese crown was united with that of Spain, under Philip II. This proved the ruin of the maritime and commercial supremacy of Portugal in the East. The interests of Portugal in Asia were henceforth subordinated to the European interests of Spain. In 1640, Portugal again became a separate kingdom. But in the meanwhile the Dutch and English had appeared in the Eastern Seas; and before their indomitable competition, the Portuguese empire of the Indies withered away as rapidly as it had sprung up. The period of the highest development of Portuguese commerce was probably from 1590 to 1610 on the eve of the subversion of their commercial power by the Dutch, and when their political administration in India was at its lowest depth of degradation. At this period a single fleet of Portuguese merchantmen sailing from Goa to Cambay or Surat would number as many as 150 or 250 *carracks*. Now, only one Portuguese ship sails from Lisbon to Goa in the year.¹

Downfall
of Portu-
guese in
India,
1639-1739.

The Dutch besieged Goa in 1603, and again in 1639. Both attacks were unsuccessful on land; but the Portuguese were gradually driven off the sea. In 1683, the Maráthás plundered to the gates of Goa. The further history of the Portuguese in India is a miserable chronicle of pride, poverty, and sounding

¹ Reproduced, without verification, from Sir George Birdwood's Report, p. 70.

titles The native princes pressed upon them from the land On the sea they gave way to more vigorous European nations

The only remaining Portuguese possessions in India are Goa, Portuguese c
Damán, and Diu, all on the west coast, with a total area of 2365 square miles, and a total population of 475,172 in 1881 ¹ The Possessions in 1881
The general Census of 1871 also returned 426 Portuguese in British India, not including those of mixed descent About 30,000 of the latter are found in Bombay ('Portuguese' half castes), and 20,000 in Bengal, chiefly in the neighbourhood of Dacca and Chittagong The latter are known as Feringhis, and, excepting Mixed de
that they retain the Roman Catholic faith and European sur scendant
names, they are scarcely to be distinguished either by colour, language, or habits of life from the natives among whom they live

The Dutch were the first European nation who broke through the Portuguese monopoly During the 16th century, Bruges, The Dutch
Antwerp, and Amsterdam became successively the great em in 1611
poriums whence Indian produce, imported by the Portuguese, 1602 1624
was distributed to Germany, and even to England At first the Dutch, following in the track of the English, attempted to find their way to India by sailing round the northern coast of Europe and Asia William Barents is honourably known as the leader of three of these arctic expeditions, in the last of which he perished.

The first Dutchman to double the Cape of Good Hope Dutch
was Cornelius Houtman, who reached Sumatra and Bantam India
in 1596 Forthwith private companies for trade with the Com
East were formed in many parts of the United Provinces, panies
but in 1602 they were all amalgamated by the States General into 'The Dutch East India Company' Within fifty years the Dutch had established factories on the continent of

¹ This number, 475 172, is the 'actual' population of all the Portuguese Settlements in India as shown in the General Statement No 1 of the Census of Portuguese India taken on the 17th February 1881 The same table shows the 'nominal' population at 481,467 Both these returns differ somewhat from the totals obtained from the detailed tables showing the males and females, age, and civil condition of the people Thus, the total obtained for Goa is 444 449 from the detailed statements, while the General Statement No 1 of the Portuguese Settlements shows an 'actual' population for Goa of 413 698 and a 'nominal' population of 420 868 Similar differences on a smaller scale may be detected in the general and detailed statements of the Settlement of Damán In both cases, the separate articles in *The Imperial Gazetteer of India* follow the detailed tables of male and female, age, and civil condition, while in general statements of population for Portuguese India, the general totals issued under the authority of the Portuguese Government are accepted

Their
progress,
1619.

India, in Ceylon, in Sumatra, in the Persian Gulf, and in the Red Sea, besides having obtained exclusive possession of the Moluccas. In 1619 they laid the foundation of the city of Batavia in Java, as the seat of the supreme government of the Dutch possessions in the East Indies, which had previously been at Amboyna. At about the same time the Dutch discovered the coast of Australia; while in North America they founded the city of New Amsterdam or Manhattan, now New York.

Dutch
supremacy
in eastern
seas, 1600-
1700.

During the 17th century the Dutch were the foremost maritime power in the world. Their memorable massacre of the English at Amboyna, in 1623, forced the British Company to retire from the Eastern Archipelago to the continent of India, and thus led to the foundation of our Indian Empire. The long naval wars and bloody battles between the English and the Dutch within the narrow seas were not terminated until William of Orange united the two countries in 1689. In the Eastern Archipelago the Dutch ruled without a rival, and expelled the Portuguese from almost all their territorial possessions. In 1635 they occupied Formosa; in 1640 they took Malacca, a blow from which the Portuguese never recovered; in 1647 they were trading at Sadras, on the Pálár river; in 1651 they founded a colony at the Cape of Good Hope, as a half-way station to the East; in 1652 they built their first Indian factory at Pálakollu, on the Madras coast; in 1658 they captured Jaffnapatam, the last stronghold of the Portuguese in Ceylon. Between 1661 and 1664 the Dutch wrested from the Portuguese all their earlier settlements on the pepper-bearing coast of Malabar; and in 1669 they expelled the Portuguese from St. Thomé and Macassar.

Their
brilliant
progress,
1635-69.

Their
short-
sighted
policy.

Stripped
of their
Indian
posses-
sions,
1759-1811.

The fall of the Dutch colonial empire resulted from its short-sighted commercial policy. It was deliberately based upon a monopoly of the trade in spices, and remained from first to last destitute of sound economical principles. Like the Phœnicians of old, the Dutch stopped short of no acts of cruelty towards their rivals in commerce; but, unlike the Phœnicians, they failed to introduce their civilisation among the natives with whom they came in contact. The knell of Dutch supremacy was sounded by Clive, when in 1759 he attacked the Dutch at Chinsurah both by land and water, and forced them to an ignominious capitulation. In the great French wars from 1793 to 1811, England wrested from Holland every one of her colonies; although Java was restored in 1816, and Sumatra exchanged for Malacca in 1824.

At present, the Dutch flag flies nowhere on the mainland of India. But quaint houses, Dutch tiles and carvings, at Chinsurah, Negapatam, Jaffnapatam, and at petty ports on the Coromandel and Malabar coast, with the formal canals in some of these old Settlements remind the traveller of scenes in the Netherlands. The passage between Ceylon and the mainland still bears the name of the Dutch governor, Palk. In the Census of 1872, only 70 Dutchmen were enumerated throughout all British India, and 79 in 1881.¹

The earliest English attempts to reach India were made by the North west passage. In 1496 Henry VII granted letters patent to John Cabot and his three sons (one of whom was the famous Sebastian) to fit out two ships for the exploration of this route. They failed, but discovered the island of Newfoundland and sailed along the coast of America from Labrador to Virginia. In 1553 the ill-fated Sir Hugh Willoughby attempted to force a passage along the north of Europe and Asia, the successful accomplishment of which has been reserved for a Swedish savant of our own day. Sir Hugh perished miserably but his second in command, Chancellor, reached a harbour on the White Sea now Archangel. Thence he penetrated by land to the court of the Grand Duke of Moscow, and laid the foundation of the Russia Company for carrying on the overland trade between India, Persia, Bokhara and Moscow.

Many English attempts were made to find a North west passage to the East Indies, from 1576 to 1616. They have left on our modern maps the imperishable names of Frobisher, Davis, Hudson, and Baffin. Meanwhile in 1577 Sir Francis Drake had circumnavigated the globe and on his way home had touched at Ternate, one of the Moluccas the king of which island agreed to supply the English nation with all the cloves which it produced.

The first modern Englishman known to have visited the Indian Peninsula was Thomas Stephens, in 1579. William of Malmesbury states, indeed, that in 883 St.helmus of Sherborne, sent by King Alfred to Rome with presents to the Pope, proceeded thence to 'India,' to the tomb of St. Thomas and brought back jewels and spices. But, as already pointed out, it by no means follows that the 'India' of William of

¹ For local notices of the Dutch in India see articles SADRAS, PALAKOLLU, CHINSURAH, NEGAPATAM, PALK, PASSIC, &c., in their respective volumes of *The Imperial Gazetteer of India*.

Malmesbury meant the Indian peninsula. Stephens (1579) was educated at New College, Oxford, and became rector of the Jesuit College in Salsette. His letters to his father are said to have roused great enthusiasm in England to trade directly with India.

Fitch,
Newberry,
Leedes,
1583.

In 1583, three English merchants, Ralph Fitch, James Newberry, and Leedes, went out to India overland as mercantile adventurers. The jealous Portuguese threw them into prison at Ormuz, and again at Goa. At length Newberry settled down as a shopkeeper at Goa; Leedes entered the service of the Great Mughal; and Fitch, after a lengthened peregrination in Ceylon, Bengal, Pegu, Siam, Malacca, and other parts of the East Indies, returned to England.¹

The defeat of the 'Invincible Armada' in 1588, at which time the crowns of Spain and Portugal were in union, gave a fresh stimulus to maritime enterprise in England; and the successful voyage of Cornelius Houtman in 1596 showed the way round the Cape of Good Hope, into waters hitherto monopolized by the Portuguese.

English
East India
Com-
panies.

The following paragraph on the early history of the English East India Companies is condensed, with little change, from Sir George Birdwood's official report.² In 1599, the Dutch, who had now firmly established their trade in the East, raised the price of pepper against us from 3s. per lb. to 6s. and 8s. The merchants of London held a meeting on the 22nd September at Founders' Hall, with the Lord Mayor in the chair, and agreed to form an association for the purposes of trading directly with India. Queen Elizabeth also sent Sir John Mildenhall by Constantinople to the Great Mughal to apply for privileges for an English Company. On the 31st December 1600,³ the English East India Company was incorporated by royal charter under the title of 'The Governor and Company of Merchants of London trading to the East Indies.' The original Company had only 125 shareholders, and a capital of £70,000, which was raised to £400,000 in 1612-13, when voyages were first undertaken on the joint-stock account.

First
charter,
31st De-
cember
1600.

Courten's Association, known as 'The Assada Merchants,' from a factory subsequently founded by it in Madagascar, was

¹ Condensed from *Report on Old Records in the India Office*, pp. 75-77.

² Condensed from *Report on Old Records in the India Office*, pp. 77 et seq.

³ Auber gives the date as the 30th December, *Analysis of the Constitution of the East India Company*, by Peter Auber, Assistant-Secretary to the Honourable Court of Directors, p. ix. (London, 1826).

established in 1635, but, after a period of internecine rivalry, was united with the London Company in 1650. In 1654-55, the 'Company of Merchant Adventurers' obtained a charter from Cromwell to trade with India, but united with the original Company two years later. A more formidable rival subsequently appeared in the English Company, or 'General Society trading to the East Indies,' which was incorporated under powerful patronage in 1698, with a capital of 2 millions sterling. According to Evelyn, in his *Diary* for March 5, 1698, 'the old East India Company lost their business against the new Company by 10 votes in Parliament, so many of their friends being absent, going to see a tiger baited by dogs.' However, a compromise was effected through the arbitration of Lord Godolphin¹ in 1708, by which the amalgamation of the 'London' and the 'English' Companies was finally carried out in 1709, under the style of 'The United Company of Merchants of England trading to the East Indies'. About the same time, the Company advanced loans to the English Government aggregating £3,200,000 at 5 per cent interest, in return for the exclusive privilege to trade to all places between the Cape of Good Hope and the Straits of Magellan.²

Later
com
panies,
1635,
1655,
1698,
1708
Amalga
mated
Company,
1709

The early voyages of the Company from 1600 to 1612 are distinguished as the 'separate voyages,' twelve in number. The subscribers individually bore the expenses of each voyage, and reaped the whole profits. With the exception of the fourth, all these separate voyages were highly prosperous, the profits hardly ever falling below 100 per cent. After 1612, the voyages were conducted on the joint stock account.

English
Voyages,
1600-12

The English were promptly opposed by the Portuguese. But James Lancaster, even in the first voyage (1601-2), established commercial relations with the King of Achin and at Priaman in the island of Sumatra, as well as with the Malaccas, and at Bantam in Java, where he settled a 'House of Trade' in 1603. In 1604 the Company undertook their second voyage, commanded by Sir Henry Middleton, who extended their trade to Banda and Amboyna. The success of these voyages attracted a number of private merchants to the business, and in 1606, James I granted a licence to Sir Edward Michelborne and others to trade 'to Cathay, China, Japan, Corea, and Cambaya.' But Michelborne, on arriving

First
English
voyage,
1601-06

¹ Under the award of Lord Godolphin, by the Act of the 6th of Queen Anne, in 1708, cap 17. Auber's *Analysis*, p. xi.

² Mill, *Hist Brit Int*, vol. i p. 151 (ed. 1840). Auber gives a detailed statement of these loans, from 1708 to 1793, *Analysis*, p. xi etc.

in the East, instead of exploring new sources of commerce like the East India Company, followed the pernicious example of the Portuguese, and plundered the native traders among the islands of the Indian Archipelago. He in this way secured a considerable booty, but brought disgrace on the British name, and seriously hindered the Company's business at Bantam.

Voyages,
1608-11.

In 1608, Captain D. Middleton, in command of the fifth voyage, was prevented by the Dutch from trading at Banda, but succeeded in obtaining a cargo at Pulo Way. In this year also, Captain Hawkins proceeded from Surat, as envoy from James I. and the East India Company, to the court of the Great Mughal. He was graciously received by the Emperor (Jahángír), and remained three years at Agra. In 1609, Captain Sharpay obtained the grant of free trade at Aden, and a cargo of pepper at Priaman in Sumatra. In 1609, also, the Company constructed the dockyard at Deptford, which was the beginning, observes Sir William Monson, 'of the increase of great ships in England.' In 1611, Sir Henry Middleton, in command of the sixth voyage, arrived before Cambay. He resolutely fought the Portuguese, who tried to beat him off, and obtained important concessions from the Native Powers. In 1610-11, also, Captain Hippon, commanding the seventh voyage, established agencies at Masulipatam, and in Siam, at Patania or Patany on the Malay Peninsula, and at Pettipollée. We obtained leave to trade at Surat in 1612.

Swally
fight,
1615.

In 1615, the Company's fleet, under Captain Best, was attacked off Swally, the port of Surat, at the mouth of the river Tápti, by an overwhelming force of Portuguese.¹ But the assailants were utterly defeated in four engagements, to the astonishment of the natives, who had hitherto considered them invincible. The first-fruit of this decisive victory was the pre-eminence of our factory at Surat, with subordinate agencies at Gogra, Ahmadábád, and Cambay. Trade was also opened with the Persian Gulf. In 1614, an agency was established at Ajmere by Mr. Edwards of the Surat factory. The chief seat of the Company's government in Western India remained at Surat until 1684-87, when it was transferred to Bombay.²

¹ For this date and account of the engagement, see *Bombay Gazetteer*, SURAT and BROACH, vol. ii. pp. 77, 78 (Bombay Government Press, 1877).

² Orders issued, 1684; transfer commenced, 1686; actually carried out, 1687. *Bombay Gazetteer*, vol. ii. p. 98.

In 1615, Sir Thomas Roe was sent by James I as ambassador to the court of Jahangir, and succeeded in placing the Company's trade in the Mughal dominions on a more favourable footing. In 1618, the English established a factory at Mocha, but the Dutch compelled them to resign all pretensions to the Spice Islands. In that year also, the Company failed in its attempt to open a trade with Dabhol, Baticola, and Calicut, through a want of sincerity on the part of the Zamorin or Calicut Raja. In 1619 we were permitted to establish a factory and build a fort at Jask, in the Persian Gulf.

In 1619, the 'Treaty of Defence' with the Dutch, to prevent disputes between the English and Dutch companies, was ratified. When it was proclaimed in the East, the Dutch and English fleets, dressed out in all their flags, and with yards manned, saluted each other. But the treaty ended in the smoke of that stately salutation, and the perpetual strife between the Dutch and English Companies went on as bitterly as ever. Up to this time, the English Company did not possess any territory in sovereign right in the 'Indies,' excepting in the island of Lantore or Great Banda. The island was governed by a commercial agent of the Company, who had under him thirty Europeans as clerks and warehousemen. This little band, with two hundred and fifty armed Malays, constituted the only force by which it was protected. In the islands of Banda and Pulo Roon and Rosengyn, the English Company had factories, at each of which were ten agents. At Macassar and Achin they possessed agencies, the whole being subordinate to a head factory at Bantam in Java.

In 1620, the Dutch, notwithstanding the Treaty of Defence, concluded the previous year, expelled the English from Pulo Roon and Lantore, and in 1621 from Bantam in Java. The fugitive factors tried to establish themselves, first at Pulicat, and afterwards at Masulipatam on the Coromandel coast, but were effectually opposed by the Dutch. In 1620, the Portuguese also attacked the English fleet under Captain Shillinge, but were defeated with great loss. From this time the estimation in which the Portuguese were held by the natives declined, while that of the English rose. In 1620, too, the English Company established agencies at Agra and Patna. In 1622 they joined with the Persians, attacked and took Ormuz from the Portuguese, and obtained from Shah Abbas a grant in perpetuity of the customs of Gombroon. This was the first time that the English took the offensive against the Portuguese.

Sir
Thomas
Roe, 1615

Treaty
with
Dutch,
1619

English
attacked
by Dutch,
1620.

Masulipatam factory, 1622. In the same year, 1622, our Company succeeded in re-establishing their factory at Masulipatam.

The massacre of Amboyna, 1623. The massacre of Amboyna, which made so deep an impression on the English mind, marked the climax of the Dutch hatred to us in the eastern seas. After long and bitter recriminations, the Dutch seized our Captain Towerson at Amboyna, with 9 Englishmen, 9 Japanese, and 1 Portuguese sailor, on the 17th February 1623. They tortured the prisoners at their trial, and found them guilty of a conspiracy to surprise the garrison. The victims were executed in the heat of passion, and their torture and judicial murder led to an outburst of indignation in England. Ultimately, commissioners were appointed to adjust the claims of the two nations; and the Dutch had to pay a sum of £3615 as satisfaction to the heirs of those who had suffered. But from that time the Dutch remained masters of Lantore and the neighbouring islands. They monopolized the whole trade of the Indian Archipelago, until the great naval wars which commenced in 1793. In 1624, the English, unable to oppose the Dutch, withdrew nearly all their factories from the Archipelago, the Malay Peninsula, Siam, and Java. Some of the factors and agents retired to the island of Lagundy, in the Strait of Sunda, but were forced by its unhealthiness to abandon it.

English driven out of Archipelago, 1624.

English retire to India, 1625.

Their early factories, 1625-53.

Trade to Bengal, 1634.

Driven out of the Eastern Archipelago by the Dutch, and thus almost cut off from the lucrative spice trade, the English betook themselves in earnest to founding settlements on the Indian seaboard. In 1625-26, the English established a factory at Armagáon on the Coromandel coast, subordinate to Masulipatam.¹ But in 1628, Masulipatam was, in consequence of the oppressions of the native governors, for a time abandoned in favour of Armagáon, which now mounted 12 guns, and had 23 factors and agents. In 1629, our factory at Bantam in Java was re-established as an agency subordinate to Surat; and in 1630, Armagáon, reinforced by 20 soldiers, was also placed under the presidency of Surat. In 1632, the English factory was re-established at Masulipatam, under a grant, the 'Golden Firman,' from the King of Golconda. In 1634, by a *farmán* dated February 2, the Company obtained from the Great Mughal liberty to trade in Bengal. But their ships were to resort only to Pippli

¹ These brief chronological abstracts follow, with a few omissions, additions and corrections of dates, Sir George Birdwood's official *Report on the Old Records in the India Office* (folio), p. 83. For notices of the Indian towns mentioned, see the articles in *The Imperial Gazetteer of India*.

in Orissa, now left far inland by the sea. The Portuguese were in the same year expelled for a time from Bengal

In 1634-35, the English factory at Bantam in Java was again raised to an independent presidency, and an agency was established at Tatta, or 'Scindy'. In 1637, Courten's Association (chartered 1635) settled agencies at Goa, Braticola, Karwar, Achin, and Rajapur. Its ships had the year before plundered some native vessels at Surat and Diu. This act disgraced the Company with the Mughal authorities (who could not comprehend the distinction between the Company and the Association) and depressed the English trade with Surat, while that of the Dutch proportionately increased.

In 1638 Armagon was abandoned as unsuited for commerce and in 1639 Fort St George or Madraspatnam (Chennapatnam)¹ was founded by Francis Day and the factory at Armagon were removed to it. It was made subordinate to Bantam in Java, until raised in 1653 to the rank of a Presidency. In 1640, the Company established an agency at Bussorah and a factory at Karwar. Trade having much extended, the Company's yard at Deptford was found too small for their ships, and they purchased some copyhold ground at Blackwall, which at that time was a waste marsh without an inhabitant. Here they opened another dockyard in which was built the *Royal George* of 1200 tons the largest ship up to that time constructed in England.

Our factory at Hugli in Bengal was established in 1640 and H¹ at Balasore in 1642. In 1645 in consequence of professional services rendered by Mr Gabriel Boughton surgeon of the *Hopewell*, to the Emperor Shah Jahan additional privileges were granted to the Company and in 1646 the Governor of Bengal, who had also been medically attended by Boughton made concessions which placed the factories at Palasore and Hugli on a more favourable footing. In 1647 Courten's Association established its colony at Assada in Madagascar. In 1652, Cromwell declared war against the Dutch on account of their accumulated injuries against the English Company. In 1653, the English factory at Lucknow was withdrawn. No record has been found of its establishment. In 1658, the Company established a factory at Kasimábar (pelt 'Castle Bazaar' in the records), and the English establishments in

¹ Bishop Caldwell derives Madras from the Telugu *maduru* the surrounding wall of a fort. Its native name is obtained from Chennappa a father in law of the Nayakkur or Chief of Chinglepat. *Comparative Grammar of the Dravidian Languages*, p. 10 (ed 1875).

Bengal were made subordinate to Fort St. George or Madras, instead of to Bantam.

Bombay
ceded,
1661.

Our fac-
tories,
1685.
Bantam.

Madras.
Bombay.

Persian
Gulf.

Bengal.

In 1661, Bombay was ceded to the British crown as part of the dower of Catharine of Braganza, but was not delivered up until 1665. King Charles II. transferred it to the East India Company, for an annual payment of £10, in 1668. The seat of the Western Presidency was removed to it from Surat in 1684-87. The Company's establishments in the East Indies then consisted in 1685 of the Presidency of Bantam in Java, with its dependencies of Jambí, Macassar, and minor agencies in the Indian Archipelago; Fort St. George and its dependent factories on the Coromandel coast and Bengal; Surat, with its affiliated dependency of Bombay; and factories at Broach, Ahmadábád, and other places in Western India; also at Gombroon (Bandar Abbas) and Bussorah in the Persian Gulf and Euphrates valley. In 1661, the factory at Biliapatam was founded. In 1663, the English factories established at Patná, Balasor, and Kásimbázár were ordered to be discontinued, and purchases to be made only at Húglí. In 1664, Surat was pillaged by the Maráthá Sivají, but Sir George Oxenden bravely defended the English factory; and the Mughal Emperor, in admiration of his conduct, granted the Company an exemption from customs for one year.

Bengal
separated
from
Madras,
1681.

In 1681, Bengal was separated from Madras, and Mr. Hodges appointed 'agent and governor' of the Company's affairs 'in the Bay of Bengal, and of the factories subordinate to it, at Kásimbázár, Patná, Balasor, Maldah, and Dacca. A corporal of approved fidelity, with 20 soldiers, to be a guard to the agent's person at the factory of Húglí, and to act against interlopers.' In 1684, Sir John Child was made 'Captain-General and Admiral of India;' and Sir John Wyborne, 'Vice-Admiral and Deputy Governor of Bombay.' In 1687, the seat of the Presidency was finally transferred from Surat to Bombay. In 1686, Kásimbázár, in common with the other English factories in Bengal, had been condemned to confiscation by the Nawáb Shaistá Khán. The Húglí factory was much oppressed, and the Company's business throughout India suffered from the wars of the Mughals and Maráthás.

'Governor-
General.'

Sir John Child was appointed 'Governor-General,'¹ with full power in India to make war or peace; and was ordered to

¹ Sir George Birdwood's *Report on the Old Records of the India Office*, p. 85, quotes this title from the MSS. It is therefore, nominally, a century older than is usually supposed; but Hastings was the first real Governor-General, 1774.

proceed to inspect the Company's possessions in Madras and Bengal and arrange for their safety. On the 20th of December 1686, the Company's Agent and Council were forced by the exactions of the Muhammadan Governor to quit their factory at Hugli. They retired down the river to Sutanati (Calcutta). Tegnapatam (Fort St David) was founded in this year (1686), and definitively established in 1691-92.

In 1687-88, the Company's servants broken in spirit by the oppressions of the native Viceroy, determined to abandon their factories in Bengal. In 1688, Captain Heath of the *Resolution*, in command of the Company's forces embarked all its servants and goods, sailed down the Hughli and anchored off Balasor on the Orissa coast. They were, however, soon invited to return by the Emperor, who granted them the site of the present city of Calcutta for a fortified factory. In 1689, our factories at Vizagapatam and Masulipatam on the Madras coast were seized by the Muhammadans, and the factors were massacred.

But in this same year, the Company determined to consolidate their position in India on the basis of territorial sovereignty, to enable them to resist the oppression of the Mughals and Marathas. With that view, they passed the resolution, which was destined to turn their clerks and factors throughout India into conquerors and proconsuls. 'The increase of our revenue is the subject of our care, as much as our trade, 'tis that must maintain our force when twenty accidents may interrupt our trade, 'tis that must make us a nation in India. Without that we are but a great number of interlopers, united by His Majesty's royal charter, fit only to trade where nobody of power thinks it their interest to prevent us. And upon this account it is that the wise Dutch, in all their general advices that we have seen write ten paragraphs concerning their government, their civil and military policy, warfare, and the increase of their revenue, for one paragraph they write concerning trade.' The subsequent history of the English East India Company and its settlements will be narrated in the next chapter.

The Portuguese at no time attempted to found a Company, but kept their eastern trade as a royal enterprise and monopoly. The first incorporated Company was the English, established in 1600, which was quickly followed by the Dutch in 1602. The Dutch conquests, however, were made in the name of the Dutch State, and ranked as national colonies, not as semi-commercial

French ; possessions. Next came the French, whose first East India Company was founded in 1604; the second, in 1611; the third, in 1615; the fourth (Richelieu's), in 1642; the fifth (Colbert's), in 1644. The sixth was formed by the union of the French East and West India, Senegal, and China Companies under the name of 'The Company of the Indies,' in 1719. The exclusive privileges of this Company were, by the French king's decree, suspended in 1769; and the Company was finally abolished by the National Assembly in 1796.

French
possession.

Dupleix, the governor of the French factories and possessions on the Madras coast, first conceived the idea of founding an Indian Empire upon the ruins of the Mughal dynasty; and for a time the French nation successfully contended with the English for the supremacy in the East. The French settlements in India are still five in number, with an area of 203 square miles, and a population of 273,611 souls. The brilliant history of our great national rivals is summarized under the article FRENCH POSSESSIONS in *The Imperial Gazetteer of India*, vol. iv. (2nd edition).

Danish ; The first Danish East India Company was formed in 1612, and the second in 1670. The settlements of Tranquebar and Serampur were both founded in 1616, and acquired by the English by purchase from Denmark in 1845. Other Danish settlements on the mainland of India were Porto Novo; with Eddova and Holcheri on the Malabar coast. The Company started by the Scotch in 1695 may be regarded as having been still-born. The 'Royal Company of the Philippine Islands,' incorporated by the King of Spain in 1733, had little to do with India proper.

Scotch ;

Spanish ;

German, or Ostend Company. Of more importance was 'The Ostend Company,' incorporated by the Emperor of Austria in 1722;¹ its factors and agents being chiefly persons who had served in the Dutch and English Companies. This enterprise forms the subject of Carlyle's 'Third Shadow Hunt' of the Emperor Karl vi.² 'The Kaiser's Imperial Ostend East India Company, which convulsed the diplomatic mind for seven years to come, and made Europe lurch from side to side in a terrific manner, proved a mere paper Company; never sent ships, only produced Diplomacies, and "had the honour to be."' Carlyle's

Described by Carlyle.

¹ The deed of institution is dated 17th December 1722.

² *History of Friedrich II. of Prussia, called Frederick the Great*, by Thomas Carlyle, vol. i. pp. 555-557 (3rd ed. 1859).

picturesque paragraphs do not disclose the facts. The Ostend Company formed the one great attempt of the German Empire, then with Austria at its head, to secure a share of the India trade. It not only sent ships, but it founded two settlements in India which threatened the commerce of the older European Companies. One of its settlements was at Coblom or Covelong, between the English Madras and the Dutch ^{Its Indian settlements} *Sadrás*, on the south eastern coast. The other was at Bankipur, or 'Banky bazar', on the Hugli River, between the English Calcutta and the Dutch Chinsura. Each of these German settlements was regarded with hatred by the English and Dutch, and with a more intense fear by the less successful French, whose adjacent settlements at Pondicherry on the Madras coast, and at Chandanagar on the Hugli, were also threatened by the Ostend Company. ^{Threatening attitude of the Ostend Company}

So far from the German association being 'a mere paper Company' never sending ships, as Carlyle supposes, its formation was the result of a series of successful experimental voyages. In 1717, Prince Eugene ordered two vessels to sail for India, under the protection of his own passports. The profits of the expedition led to others in succeeding years, and each voyage proved so fortunate, that the Austrian Emperor found it necessary to protect and consolidate the property of the adventurers by a charter in 1722. This deed granted to the Ostend Company more favourable terms than any of the other European Companies enjoyed. Its capital was one million sterling, and so great were the profits during its first years that its shares brought in 15 per cent. The French, Dutch, and English Companies loudly complained of its factories, built at their very doors, both on the Hugli River and on the Madras coast. These complaints were warmly taken up by their respective Governments in Europe. ^{Its experimental voyages 1717-22}

For the object which the Emperor Karl VI had in view was political not less than commercial. Prince Eugene had urged that an India Company might be made to form the nucleus of a German fleet, with a first-class naval station at Ostend on the North Sea, and another at Trieste on the Adriatic. Such a fleet would complete the greatness of Germany by sea as by land, and would render her independent of the Maritime Powers, especially of England and Holland. The Empire would at length put its ports on the Baltic and the Adriatic to a proper use, and would thenceforth exert a commanding maritime influence in Europe. ^{Their great success}

The existing Maritime Powers objected to this, and the

Ostend
Company
opposed
by the
Maritime
Powers ;

and sacri-
ficed to the
Pragmatic
Sanction,
1727.

Ostend
settle-
ment
destroyed,
1733 ;

and disap-
peared
from the
map.

Ostend
Company
bankrupt,
1784 ;
and extin-
guished,
1793.

Prussian
Com-
panies.

Ostend Company became the shuttlecock of European diplomacy for the next five years: The Dutch and English felt themselves particularly aggrieved. They pleaded the treaties of Westphalia and Utrecht. After long and loud altercations, the Emperor sacrificed the Ostend Company in 1727 to gain the acceptance of a project nearer his heart—the Pragmatic Sanction for the devolution of his Imperial heritage. To save his honour, the sacrifice at first took the form of a suspension of the Company's charter for seven years. But the Company was doomed by the Maritime Powers. Its shareholders did not, however, despair. They made attempts to transfer their European centre of trade to Hamburg, Trieste, Tuscany, and even Sweden.

Meanwhile the other European Companies in Bengal had taken the law into their own hands. They stirred up the Muhammadan Government against the new-comers. In 1733, the Muhammadan military governor of Húglí picked a quarrel, in the name of the Delhi Emperor, with the little German settlement at Bankipur, which lay about eight miles below Húglí town on the opposite side of the river. The Muhammadan troops besieged Bankipur ; and the garrison, reduced to fourteen persons, after a despairing resistance against overwhelming numbers, abandoned the place, and set sail for Europe. The Ostend agent lost his right arm by a cannon ball during the attack ; and the Ostend Company, together with the German interests which it represented, became thenceforward merely a name in Bengal. Its chief settlement, Bankipur or 'Banky-bazaar,' has long disappeared from the maps ; and the author could only trace its existence from a chart of the last century, aided by the records of that period, and by personal inquiry on the spot.¹ The Ostend Company, however, still prolonged its existence in Europe. After a miserable struggle, it became bankrupt in 1784 ; and was finally extinguished by the arrangements made at the renewal of the English East India Company's charter in 1793.

What the Emperor of Austria had failed to effect, Frederick the Great, King of Prussia, resolved to accomplish. Having got possession of East Friesland in 1744, he tried to convert

¹ There is an interesting series of MSS. labelled *The Ostenders* in the India Office. See also the Abbé Raynal's *History of the Settlements and Trade of the Europeans in the East and West Indies*, Book v. (pp. 176-182, vol. ii. of the 1776 edition) ; and the article BANKIPUR on the Húglí in *The Imperial Gazetteer of India*.

its capital, Embden, into a great northern port. Among other measures, he gave his royal patronage to the Asiatic Trading Company, started 1st September 1750, and founded the *Bengalische Handelsgesellschaft* on the 24th January 1753.¹ The first of these Companies had a capital of £170,625, but six ships sent successively to China only defrayed their own expenses, and yielded a profit of 10 per cent in seven years. The Bengal Company of Embden proved still more unfortunate, its existence was summed up in two expeditions which did not pay, and a long and costly lawsuit.²

The failure of Frederick the Great's efforts to secure for Prussia a share in the India trade, resulted to some extent from the jealousy of the rival European Companies in India. The Dutch, French, and English pilots refused to show the way up the dangerous Hughli river to the Embden ships, 'or any other not belonging to powers already established in India.'³ It is due to the European Companies to state that in thus refusing pilots to the new comers, they were carrying out the orders of the Native Government of Bengal to which they were then strictly subject. 'If the Germans come here,' the Nawab had written to the English merchants on a rumour of the first Embden expedition reaching India, 'it will be very bad for all the Europeans, but for you worst of all, and you will afterwards repent it, and I shall be obliged to stop all your trade and business. Therefore take care that these German ships do not come.'⁴ 'God forbid that they should come,' was the pious response of the President of the English Council, 'but should this be the case, I am in hopes they will be either sunk, broke, or destroyed.'

They came nevertheless, and some years later the English Court of Directors complain that their Bengal servants are anxious to trade privately with the Embden Company. 'If any of the Prussian ships,' wrote the Court, 'want the usual assistance of water, provisions, or real necessities, they are to be supplied according to the customs of nations in amity one with the other. But you are on no pretence whatsoever to

¹ These dates are taken from Carlyle's *Frederick the Great*, vol. iv. pp. 367, 368 (ed. 1864). Carlyle's account of the Embden Companies is unfortunately of slight historical value.

² The commercial details of these Companies are given by the *Asiatick Researches*, vol. ii. pp. 201, 207.

³ Despatch from the Calcutta Council to the Court of Directors, dated 6th September 1754, para. 11.

⁴ Letter from the Nawab of Mursliabad. Bengal Consultations of 19th August 1751.

Frederick
sacrifices
the Com-
pany.

have any dealings with them, or give the least assistance in their mercantile affairs.'¹ The truth is that the German Company had effected an entrance into Bengal, and found the French, English, and Dutch merchants quite willing to trade with it on their private account. But the German investments were made without experience, and the Embden Company was before long sacrificed by the Prussian king to the exigencies of his European diplomacy.

Swedish
Company,
1731.

The last nation of Europe to engage in maritime trade with India was Sweden. When the Ostend Company was suspended, a number of its servants were thrown out of employment. Mr. Henry Köning, of Stockholm, took advantage of their knowledge of the East, and obtained a charter for the 'Swedish Company,' dated 13th June 1731. This Company was reorganized in 1806, but did little; and after many troubles, disappeared from India.

Causes of
failure :
of the
Portu-
guese ;

of the
Dutch ;

of the
French.

Such is a summary of the efforts by European nations to obtain a share in the India trade. The Portuguese failed, because they attempted a task altogether beyond their strength; the conquest and the conversion of India. Their memorials are the epic of the *Lusiad*, the death-roll of the Inquisition, an indigent half-caste population, and three decayed patches of territory on the Bombay coast. The Dutch failed on the Indian continent, because their trade was based on a monopoly which it was impossible to maintain, except by great and costly armaments. Their monopoly, however, still flourishes in their isolated island dominion of Java. The French failed, in spite of the brilliancy of their arms and the genius of their generals, from want of steady support at home. Their ablest Indian servants fell victims to a corrupt Court and a careless people. Their surviving settlements disclose that talent for careful administration which, but for French monarchs and their ministers and their mistresses, might have been displayed throughout a wide Indian Empire.

Causes of
failure of
the Ger-
mans.

The German Companies, whether Austrian or Prussian, were sacrificed to the diplomatic necessities of their royal patrons in Europe; and to the dependence of the German States in the wars of the last century upon the Maritime Powers. But the German people has never abandoned the struggle. The share in the Indian trade which Prussian King

¹ Letter from the Court of Directors to the Calcutta Council, March 25, 1756, para. 71.

and Austrian Kaiser failed to grasp in the 18th century, has been gradually acquired by German merchants in our own day. An important part of the commerce of Calcutta and Bombay is now conducted by German firms, German mercantile agents are to be found in the rice districts, the jute districts, the cotton districts, and persons of German nationality have rapidly increased in the Indian Census returns.

Revival of
German
trade in
India

England emerged the prize winner from the long contest of the European nations for India. Her success was partly the good gift of fortune, but chiefly the result of four elements in the national character. There was—first a marvellous patience and self-restraint in refusing to enter on territorial conquests or projects of Indian aggrandizement until she had gathered strength enough to succeed. Second, an indomitable persistence in those projects once they were entered on and a total incapacity, on the part of her servants in India, of being stopped by defeat. Third, an admirable mutual confidence of the Company's servants in each other in times of trouble. Fourth, and chief of all, the resolute support of the English nation at home. England has never doubted that she must retrieve, at whatever strain to herself, every disaster which may befall Englishmen in India, and she has never sacrificed the work of her Indian servants to the exigencies of her diplomacy in Europe. She was the only European power which unconsciously but absolutely carried out these two principles of policy. The result of that policy, pursued during two and a half centuries, is the British India of to-day.

Fixed
policy of
England
in India

The extent to which the chief continental nations of Europe now resort to British India, may be inferred from the following figures. These figures are exclusive of Europeans in French and Portuguese territory, and in the Native States. Germans numbered 655 in 1872, and 1170 in 1881, French, 631 in 1872, and 1013 in 1881, Portuguese, 426 in 1872, and 147 in 1881, Italians 282 in 1872, and 788 in 1881, Greeks, 127 in 1872, and 195 in 1881, Swedes, 73 in 1872, and 337 in 1881, Russians, 45 in 1872, and 204 in 1881, Dutch, 70 in 1872, and 79 in 1881, Norwegians, 58 in 1872, and 358 in 1881, Danes, 45 in 1872, and 126 in 1881, Spaniards, 32 in 1872, and 87 in 1881, Belgians, 20 in 1872, and 180 in 1881, Swiss, 19 in 1872, and 87 in 1881, Turks, 18 in 1872, and 355 in 1881, Austrians, 53 in 1872, and 296 in 1881.

European
traders in
1872 and
1881

CHAPTER XV.

HISTORY OF BRITISH RULE (1757 TO 1885 A.D.).

Our first territorial possession. Madras, 1639.

THE political history of the British in India begins in the 18th century with the French wars in the Karnátik. Fort St. George, the nucleus of Madras, founded by Francis Day in 1639, was our earliest possession. The French settlement of Pondicherri, about 100 miles lower down the Coromandel coast, was established in 1674; and for many years the English and French traded side by side without rivalry or territorial ambition. The English paid a rent of 1200 pagodas (£500) to the deputies of the Mughal Empire when Aurangzeb annexed the south, and on two occasions bought off a besieging army by a heavy bribe.

Southern India after 1707.

After the death of Aurangzeb in 1707, the whole of Southern India became practically independent of Delhi. In the Deccan Proper, the Nizám-ul-Mulk founded a hereditary dynasty, with Haidarábád for its capital, which exercised a nominal authority over the entire south. The Karnátik, or the lowland tract between the central plateau and the eastern sea, was ruled by a deputy of the Nizám, known as the Nawáb of Arcot. Farther south, Trichinopoli was the capital of a Hindu Rájá; Tanjore formed another Hindu kingdom under a degenerate descendant of Sivají. Inland, Mysore was gradually growing into a third Hindu State; while everywhere local chieftains, called *pálegárs* or *naiks*, were in semi-independent possession of citadels or hill-forts. These represented the fief-holders of the ancient Hindu kingdom of Vijayanagar; and many of them had maintained a practical independence since its fall in 1565.

Local rulers.

French and English in the Karnátik.

Such was the condition of affairs in Southern India when war broke out between the English and the French in Europe in 1744. Dupleix was at that time Governor of Pondicherri, and Clive was a young writer at Madras. An English fleet first appeared on the Coromandel coast, but Dupleix, by a judicious present, induced the Nawáb of Arcot to interpose and prevent hostilities. In 1746, a French squadron arrived,

under the command of La Bourdonnais Madras surrendered almost without a blow, and the only settlement left to the English was Fort St David, a few miles south of Pondicherry, where Clive and a few other fugitives sought shelter. The Nawáb, faithful to his impartial policy, marched with 10,000 men to drive the French out of Madras, but was defeated. In 1748, an English fleet arrived under Admiral Boscawen, and attempted the siege of Pondicherry, while a land force co-operated under Major Lawrence, whose name afterwards became associated with that of Clive. The French repulsed all attacks, but the treaty of Aix la Chapelle, in the same year, restored Madras to the English.¹

The first war with the French was merely an incident in the greater contest in Europe. The second war had its origin in Indian politics, while England and France were at peace. The easy success of the French arms had inspired Dupleix with the ambition of founding a French empire in India, under the shadow of the Muhammadan powers. Disputed successions at Haidarabad and at Arcot supplied his opportunity. On both thrones Dupleix placed his nominees, and posed as the arbiter of the entire south. The English of Madras, under the instinct of self preservation had supported another candidate to the throne of Arcot, in opposition to the nominee of Dupleix. Our candidate was Muhammad Ali, afterwards known in history as Wálá jáh. The war which ensued between the French and English in Southern India has been exhaustively described by Orme. The one incident that stands out conspicuously is the capture and subsequent defence of Arcot by Clive in 1751. This heroic feat, even more than the battle of Plassey, spread the fame of English valour throughout India. Shortly afterwards, Clive returned to England in ill health, but the war continued fitfully for many years. On the whole, English influence predominated in the Karnátik or Madras coast, and their candidate Muhammad Ali, maintained his position at Arcot. But, inland, the French were supreme in the Deccan, and they were able to seize the maritime tract called 'the Northern Circars.'

The final struggle did not take place until 1760. In that year Colonel (afterwards Sir Eyre) Coote won the decisive

¹ The authorities for the French and English wars in Southern India are—(1) Orme's *Indostan*, 2 vol., Madras reprint, 1861, (2) Mills's *History of British India* (ed. 1840), and (3) for the French views of those transactions, Colonel Mallet's admirable *History of the French in India* (London, 1865), and *Final Struggle of the French in India* (London, 1875).

Gingi sur-
rendered,
5th April
1761.

victory of Wandewash over the French General, Lally, and proceeded to invest Pondicherri, which was starved into capitulation in January 1761. A few months later the hill-fortress of Ginjee (Gingi) also surrendered.¹ In the words of Orme: 'That day terminated the long hostilities between the two rival European powers in Coromandel, and left not a single ensign of the French nation avowed by the authority of its Government in any part of India.'²

The
English
in Bengal,
1634-96.

Meanwhile, the narrative of British conquest shifts with Clive to Bengal. The first English settlement near the Gangetic estuary was Pippli in Orissa, at which the East India Company was permitted to trade in 1634, five years before the foundation of Madras. The river on which Pippli stood has since silted up, and the very site of the English settlement is now a matter of conjecture. In 1640, a factory was opened at Húgli; in 1642, at Balasor; and in 1681, Bengal was erected into a separate presidency, though still subordinate to Madras. The name of Calcutta is not heard of in the Company's records till 1686, when Job Charnock, the English chief, was forced to quit Húgli by the deputy of Aurangzeb, and settled lower down the river on the opposite bank. There he acquired a grant of the three petty villages of Sutanati, Gobindpur, and Kálíghát (Calcutta), and founded the original Fort William in 1696.

Native
rulers of
Bengal,
1707-56.

At the time of Aurangzeb's death, in 1707, the Nawáb or Governor of Bengal was Murshid Kulí Khán, known also in European history as Jafar Khán. By birth a Bráhmaṇ, and brought up as a slave in Persia, he united the administrative ability of a Hindu with the fanaticism of a renegade. Hitherto the capital of Bengal had been at Dacca, on the eastern frontier of the empire, whence the piratical attacks of the Portuguese and of the Arakanese or Maghs could be most easily checked. Murshid Kulí Khán transferred his residence to Murshidábád, in the immediate neighbourhood of Kásimbázár, which was then the chief emporium of the Gangetic trade. The English, the French, and the Dutch had each factories at Kásimbázár, as well 'as at Dacca, Patná, and Maldah. But

¹ A full account of GINGI is given, *sub verbo*, in *The Imperial Gazetteer of India*. In like manner, the local history of each Presidency, Province, or town is treated in the separate article upon it, and can therefore only be very briefly summarized here. Thus, with regard to Calcutta, the reader is referred to article CALCUTTA in *The Imperial Gazetteer of India*.

² Orme's *History of Military Transactions in Indostan* (1803), Madras reprint, vol. ii. p. 733 (1861).

Calcutta was the head-quarters of the English, Chandarnagar of the French, and Chinsurah of the Dutch. These three settlements were situated not far from one another upon reaches of the Húgli, where the river was navigable for sea-going ships. Calcutta is about 80 miles from the sea, Chandarnagar, 24 miles by river above Calcutta, and Chinsurah, 2 miles above Chandarnagar. Húgli town, to which reference has so often been made, is almost conterminous with Chinsurah, but lies one mile above it.

Murshid Kuli Khan ruled over Bengal prosperously for twenty one years, and left his power to a son in law and a grandson. The hereditary succession was broken in 1740 by Ali Vardi Khan, a usurper, but the last of the great Nawabs of Bengal. In his days the Marátha horsemen began to ravage the country, and the inhabitants of Calcutta obtained permission in 1742 to erect an earthwork, known to the present day as the Marátha ditch. Ali Vardi Khan died in 1756, and was succeeded by his grandson, Siráj ud Daulá (Surajah Dowlah), a youth of only eighteen years, whose ungovernable temper led to a rupture with the English within two months after his accession.

In pursuit of one of his own family who had escaped from his vengeance, he marched upon Calcutta with a large army. Many of the English fled down the river in their ships. The remainder surrendered after a brave resistance, and were thrust for the night into the 'Black Hole' or military jail of Fort William, a room about 18 feet square, with only two small windows barred with iron. It was our ordinary garrison prison in those times of cruel military discipline. But although the Nawáb does not seem to have been aware of the consequences, it meant death to a crowd of 146 English men and women in the stifling heats of June. When the door of the prison was opened next morning, only 23 persons out of 146 remained alive.¹

The news of this disaster fortunately found Clive back again at Madras, where also was a squadron of the King's ships under Admiral Watson. Clive and Watson promptly sailed to

¹ The contemporary record of that terrible night is Holwell's Narrative. The original materials have been carefully examined, and much misrepresentation has been cleared away by Dr H. F. Basteel, in the *Calcutta Englishman*, several dates, 1880. The site of the 'Black Hole' has been lately identified, at the entrance to the lane behind the General Post-Office; and the spot has been paved with fine stone (1884).

Calcutta
recovered,
1757.

the mouth of the Ganges with all the troops they could get together. Calcutta was recovered with little fighting, and the Nawáb consented to a peace which restored to the Company all their privileges, and gave them ample compensation for their losses. It is possible that matters might have ended thus, if a fresh cause of hostilities had not suddenly arisen. War had just been declared between the English and French in Europe; and Clive, following the traditions of warfare in the Karnátik, captured the French settlement of Chandarnagar. The Nawáb Siráj-ud-Daulá, enraged by this breach of the peace within his dominions, took the side of the French. But Clive, acting upon the policy which he had learned from Dupleix, provided himself with a rival candidate (Mír Jafar) to the throne. Undaunted, he marched out to the grove of Plassey, about 70 miles north of Calcutta, at the head of 1000 Europeans and 2000 sepoys, with 8 pieces of artillery. The Bengal Viceroy's army numbered 35,000 foot and 15,000 horse, with 50 cannon.

Battle of
Plassey,
1757.

How the
victory
was
gained.

Clive is said to have fought in spite of his Council of War. The truth is, he could scarcely avoid a battle. The Nawáb attacked with his whole artillery, at 6 A.M.; but Clive kept his men well under shelter, 'lodged in a large grove, surrounded with good mud banks.' At noon the enemy drew off into their entrenched camp for dinner. Clive only hoped to make a 'successful attack at night.' Meanwhile, the enemy being probably undressed over their cooking-pots, he sprang upon one of their advanced posts, which had given him trouble, and stormed 'an angle of their camp.' Several of the Nawáb's chief officers fell. The Nawáb himself, dismayed by the unexpected confusion, fled on a camel; his troops dispersed in a panic, and Clive found he had won a great victory. Mír Jafar's cavalry, which had hovered undecided during the battle, and had been repeatedly fired on by Clive, 'to make them keep their distance,' now joined our camp; and the road to Murshidábád lay open.¹

Its small
results at
first.

The battle of Plassey was fought on June 23, 1757, an anniversary afterwards remembered when the Mutiny of 1857 was at its height. History has agreed to adopt this date as the beginning of the British Empire in the East. But the immediate results of the victory were comparatively small, and several years passed in hard fighting before even the Bengalis would admit the superiority of the British arms. For the

¹ These numbers and the account of the battle are taken by the author from Clive's MS. Despatch to the Secret Committee, dated 26th July 1757. The quotations are Clive's own words.

moment, however, all opposition was at an end Clive, again following in the steps of Dupleix, placed Mir Jafar upon the Viceregal throne at Murshidábád, being careful to obtain a patent of investiture from the Mughal court

Enormous sums were exacted from Mir Jafar as the price of his elevation The Company claimed 10 million rupees as compensation for its losses For the English, native, and Armenian inhabitants of Calcutta were demanded, respectively, 5 million, 2 million, and 1 million rupees, for the naval squadron and the army, 2½ million rupees apiece The members of the Council received the following amounts —Mr Drake, the Governor, and Colonel Clive, as second member of the Select Committee, 280,000 rupees each Colonel Clive also received 200,000 rupees as Commander in Chief, and 1,600,000 rupees 'as a private donation,' Mr Becker, Mr Watts, and Major Kilpatrick, 240,000 rupees each, besides 'private donations,' amounting in the case of Mr Watts to 800,000 rupees The gratifications of a personal character, including the donation to the troops and the fleet, aggregated £1,238,575 ¹ while the whole claim amounted to £2,697,750 The English still cherished extravagant ideas of Indian wealth But no funds existed to satisfy their inordinate demands, and they had to be contented with one half the stipulated sums Even of this reduced amount, one third had to be taken in jewels and plate, there being neither coin nor bullion left

At the same time, the Nawab made a grant to the Company of the *zamindári* or landholder's rights over an extensive tract of country round Calcutta, now known as the District of the Twenty four Parganás. The area of this tract was 882 square miles In 1757 the Company obtained only the *zamindári* rights—*i.e.*, the rights to collect the cultivators' rents, with the revenue jurisdiction over them The superior lordship, or right to receive the land tax, remained with the Nawab But in 1759 this also was granted by the Delhi Emperor, the nominal Suzerain of the Nawáb, in favour of Clive, who thus became the landlord of his own masters, the Company Clive was enrolled among the highest nobility of the Mughal Empire, with the rank of commander of 6000 foot and 5000 horse, and a large allotment of land near Calcutta, in 1759

This military fief, or Clive's *jagir*, as it was called, subsequently became a matter of inquiry in England Lord Clive's

¹ For a full statement of the personal donations, see *Mills History of British India*, vol. iii pp. 367, 368 (Wilson's ed. 1840)

claims to the property as feudal Suzerain over the Company were contested in 1764. On the 23rd June 1765, when he returned to Bengal, a new deed was issued, confirming the unconditional *jágír* to Lord Clive for ten years, with reversion afterwards to the Company in perpetuity. This deed, having received the Emperor's sanction on the 12th August 1765, gave absolute validity to the original *jágír* grant in favour of Lord Clive. It transferred, in reversion, to the Company the Twenty-four Parganá as a perpetual property based upon a *jágír* grant. The sum of Rs. 222,958, the amount at which the land was assessed when first made over to the Company in 1757, was paid to Lord Clive from 1765 until his death in 1774, when the whole proprietary right reverted to the Company.¹

Clive, first
Governor
of Bengal,
1758;

In 1758, Clive was appointed by the Court of Directors the first Governor of all the Company's settlements in Bengal.²

¹ For a full account of the different grants, and the powers granted by them, see Hunter's *Statistical Account of Bengal*, vol. i. (TWENTY-FOUR PARGANAS), pp. 19, 20.

² GOVERNORS AND GOVERNORS-GENERAL OF INDIA UNDER THE EAST INDIA COMPANY, 1758-1858.

1758. Lord Clive, Governor.	1805. Sir George Barlow (<i>pro tem.</i>).
1760. Mr. Z. Holwell (<i>pro tem.</i>).	1807. Earl of Minto.
1760. Mr. Vansittart.	1813. Earl of Moira, Marquis of Hastings.
1765. Lord Clive (second time).	1823. John Adam (<i>pro tem.</i>).
1767. Harry Verelst.	1823. Lord Amherst.
1769. John Cartier.	1828. Mr. Butterworth Bayley (<i>pro tem.</i>).
1772. Warren Hastings (first Governor-General, 1774).	1828. Lord William Cavendish Bentinck.
1785. Sir John Macpherson (<i>pro tem.</i>).	1835. Sir Chas. Metcalfe, afterwards Lord Metcalfe (<i>pro tem.</i>).
1786. Marquis of Cornwallis.	1836. Earl of Auckland.
1793. Sir John Shore (Lord Teignmouth).	1842. Earl of Ellenborough.
1798. Sir Alured Clarke (<i>pro tem.</i>).	1844. Viscount Hardinge.
1798. Lord Mornington (Marquis Wellesley).	1848. Earl (afterwards Marquis) of Dalhousie.
1805. Marquis of Cornwallis (second time).	1856. Earl Canning.

VICEROYS OF INDIA UNDER THE CROWN, 1858-85.

1858. Earl Canning.	1869. Earl of Mayo.
1862. Earl of Elgin.	1872. Sir John Strachey (<i>pro tem.</i>).
1863. Sir R. Napier, afterwards Lord Napier of Magdala (<i>pro tem.</i>).	1872. Lord Napier of Merchistoun (<i>pro tem.</i>).
1863. Sir William Denison (<i>pro tem.</i>).	1872. Earl of Northbrook.
1864. Sir John Lawrence (Lord Lawrence).	1876. Earl of Lytton.
	1880. Marquis of Ripon.
	1884. Lord Dufferin.

Two powers threatened hostilities On the west, the Sháhzáda or Imperial prince, known afterwards as the Emperor Shah Alam, with a mixed army of Afgháns and Marathás, and supported by the Nawáb Wazir of Oudh, was advancing his own claims to the Province of Bengal In the south, the influence of the French under Lally and Bussy was over shadowing the British at Madras

The vigour of Clive exercised a decisive effect in both directions Mir Jafar was anxious to buy off the Shahzáda, who had already invested Patná But Clive marched in person to the scatters rescue, with an army of only 450 Europeans and 2500 sepoy's, ^{Oudh army,} and the Mughal army dispersed without striking a blow Clive also despatched a force southwards from Bengal under Colonel ^{overcomes French in Madras,} Forde, in 1759, which recaptured Masulipatam from the French, and permanently established British influence throughout the Northern Circars, and at the court of Haidarábád He next attacked the Dutch, the only other European nation who might yet prove a rival to the English He defeated them ^{defeats Dutch} both by land and water and their settlement at Chinsurah existed thenceforth only on sufferance

From 1760 to 1765, Clive was in England He had left Mirman no system of government in Bengal, but merely the tradition ^{agreement, 1760-64} that unlimited sums of money might be extracted from the natives by the terror of the English name In 1761, it was found expedient and profitable to dethrone Mir Jafar, the English Nawáb of Murshidabad, and to substitute his son in law, Mir Kásim, in his place On this occasion, besides Mir Kásim private donations, the English received a grant of the three ^{set up 1761} Districts of Bardwán, Midnapur, and Chittagong, estimated to yield a net revenue of half a million sterling But Mir Kásim soon began to show a will of his own, and to cherish dreams of independence He retired from Murshidábád to Monghyr a strong position on the Ganges, commanding the only means of communication with the north west There he proceeded to organize an army, drilled and equipped after European models, and to carry on intrigues with the Nawab Wazir of Oudh He resolved to try his strength with the English, and found a good pretext The Company's servants claimed the privilege of carrying their private trade throughout Bengal, free from inland taxes and all imposts The assertion of this claim caused Mir Kásim to break with the English traders, who, whether truly or not, represented that English

they were acting on behalf of the servants of the Company. The Nawáb alleged that his civil authority was everywhere set at nought. The majority of the Council at Calcutta would not listen to his complaints. The Governor, Mr. Vansittart, and Warren Hastings, then a junior member of Council, attempted to effect some compromise. But the controversy had become too hot. The Nawáb's officers fired upon an English boat, and forthwith all Bengal rose in arms. Two thousand of our sepoy were cut to pieces at Patná; about 200 Englishmen, who there and in various other parts of the Province fell into the hands of the Muhammadans, were massacred.¹

Patná
Massacre,
1763.

But as soon as regular warfare commenced, Mír Kásim met with no more successes. His trained regiments were defeated in two pitched battles by Major Adams, at Gheriah and at Udhaná (Oodeynullah); and he himself took refuge with the Nawáb Wazír of Oudh, who refused to deliver him up. This led to a prolongation of the war. Sháh Alam, who had succeeded his father as Delhi Emperor, and Shujá-ud-Daulá the Nawáb Wazír of Oudh, united their forces, and threatened Patná, which the English had recovered. A more formidable danger appeared in the English camp, in the form of the first sepoy mutiny. This was quelled by Major (afterwards Sir Hector) Munro, who ordered 24 of the ringleaders to be blown from guns—an old Mughal punishment. In 1764, Major Munro won the decisive battle of Baxár, which laid Oudh at the feet of the conquerors, and brought the Mughal Emperor a suppliant to the English camp.

First
sepoy
mutiny,
1764.

Battle of
Baxár,
1764.

Clive's
second
governor-
ship,
1765-67.

Meanwhile, the Council at Calcutta had twice found the opportunity they loved of selling the government of Bengal to a new Nawáb. But in 1765, Clive (now Baron Clive of Plassey in the peerage of Ireland) arrived at Calcutta, as Governor of Bengal for the second time. Two landmarks stand out in his policy. First, he sought the substance, although not the name, of territorial power, under the fiction of a grant from the Mughal Emperor. Second, he desired to purify the Company's service, by prohibiting illicit gains, and by guaranteeing a reasonable pay from honest sources. In neither respect were his plans carried out by his immediate successors. But the beginning of our Indian rule dates from

¹ The massacre of Patná is described in sufficient detail under article PATNA DISTRICT in *The Imperial Gazetteer of India*, and in Hunter's *Statistical Account of Bengal*, vol. xi. pp. 71 *et seq.*

this second governorship of Clive, as our military supremacy had dated from his victory at Plassey

Clive landed, advanced rapidly up from Calcutta to Allah Clive's
partition of
Gangetic
valley,
1765
ābād, and there settled in person the fate of nearly half of India. Oudh was given back to the Nawāb Wazīr, on condition of his paying half a million sterling towards the expenses of the war. The Provinces of Allahābad and Kora,¹ forming the greater part of the Doab were handed over to Shāh Ālīm, the Delhi Emperor who in his turn granted to the Company the *diwānī* or fiscal administration of Bengal Behar, and Orissa, with the jurisdiction of the Northern Circars. A puppet Nawāb was still maintained at Murshidābād with an annual allowance from us of £600,000. Half that amount, or about £300,000 we paid to the Emperor as tribute from Bengal.² Thus was constituted the dual system of Government, by which the English received the revenues of Bengal and undertook to maintain the army while the criminal jurisdiction, or *mizmat* was vested in the Nawāb. In Indian phraseology, the Company was *darīn* and the Nawāb was *nizam*. The actual collection of the revenues still remained for some years in the hands of native officials.

Clive's other great task was the reorganization of the Company's service. All the officers civil and military alike were tainted with the common corruption. Their legal salaries were paltry and quite insufficient for a livelihood. But they had been permitted to augment them sometimes a hundred fold by means of private trade and gifts from the native powers. Despite the united resistance of the civil servants, and an actual mutiny of two hundred military officers Clive carried through his reforms. Private trade and the receipt of presents were prohibited for the future while a substantial increase of pay was provided out of the monopoly of salt.

Lord Clive quitted India for the third and last time in 1767. Dual sys-
tem of
admini-
stration
1767-72.
Between that date and the governorship of Warren Hastings in 1772, little of importance occurred in Bengal beyond the terrible famine of 1770, which is officially reported to have swept away one third of the inhabitants. The dual system of government, established in 1765 by Clive, had proved a

¹ The 'Corah' of the F. I. Company's records, the capital of an ancient Muhammadan governorship now a decayed town in Fatehpur District. See article KORA in *The Imperial Gazetteer of India*.

² The exact sums were Sikka Rs. 5,386,131 to the Nawāb and Rs. 2,600,000 to the Emperor.

Dual
system
abolished,
1772.

failure. Warren Hastings, a tried servant of the Company, distinguished alike for intelligence, for probity, and for knowledge of oriental manners, was nominated Governor by the Court of Directors, with express instructions to carry out a predetermined series of reforms. In their own words, the Court had resolved to 'stand forth as *dīwān*, and to take upon themselves, by the agency of their own servants, the entire care and administration of the revenues.' In the execution of this plan, Hastings removed the exchequer to Calcutta from Murshidábád, which had up to that time remained the revenue head-quarters of Bengal. He also appointed European officers, under the now familiar title of Collectors, to superintend the revenue collections and preside in the courts.

Warren
Hastings,
1772-85.

His admini-
strative
reforms.

Clive had laid the territorial foundations of the British Empire in Bengal. Hastings may be said to have created a British administration for that Empire. The wars forced on him by Native Powers in India, the clamours of his masters in England for money, and the virulence of Sir Philip Francis with a faction of his colleagues at the Council table in Calcutta, retarded the completion of his schemes. But the manuscript records disclose the patient statesmanship and indomitable industry which he brought to bear upon them. From 1765 to 1772, Clive's dual system of government, by corrupt native underlings and rapacious English chiefs, prevailed. Thirteen years were now spent by Warren Hastings in experimental efforts at rural administration by means of English officials (1772-85). The completion of the edifice was left to his successor. But Hastings was the administrative organizer, as Clive had been the territorial founder, of our Indian Empire.

Hastings'
policy
with
native
powers.

Hastings' true fame as an Indian ruler rests on his administrative work. He reorganized the Indian service, reformed every branch of the revenue collections, created courts of justice and some semblance of a police. History remembers his name, however, not for his improvements in the internal administration, but for his bold foreign policy, and for the crimes into which it led him. From 1772 to 1774, he was Governor of Bengal; from the latter date to 1785, he was the first Governor-General, presiding over a Council nominated, like himself, under a statute of Parliament known as the Regulating Act (1773). In his domestic policy he was greatly hampered by the opposition of his colleague in council, Sir Philip Francis. But in his external relations with Oudh, with the Maráthás, and with Haidar Ali, he was generally able to compel assent to his views.

Warren
Hastings
first
Governor-
General,
1774.

His relations with the native powers, like his domestic policy, formed a well considered scheme. Hastings had to find money for the Court of Directors in England, whose thirst for the wealth of India was not less keen, although more decorous, than that of their servants in Bengal. He had also to protect the Company's territory from the Native Powers, which, if he had not destroyed them, would have annihilated him. An honest man under such circumstances might be led into questionable measures. Hastings in his personal dealings, and as regards his personal gains, seems to have been a high minded English gentleman. But as an Anglo Indian statesman, he shared the laxity which he saw practised by the native potentates with whom he had to deal. Parts of his policy were vehemently assailed in Parliament, and cannot be upheld by right thinking men. It is the object of the present summary neither to attack nor to defend his measures, but to give a short account of them as a connected whole.

His two fold aim

Warren Hastings had in the first place to make Bengal pay. This he could not do under Clive's dual system of administration. When he abolished that double system, he cut down the Nawábs' allowance to one half, and so saved about £160,000 a year. In defence of this act, it may be stated that the titular Nawáb, being then a minor, had ceased to render even any nominal service for his enormous pension. Clive had himself reduced the original £600,000 to £450,000 on the accession of a new Nawáb in 1766, and the grant was again cut down to £350,000 on a fresh succession in 1769¹. The allowance had practically been of a fluctuating and personal character². Its further reduction in the case of the new child Nawáb had, moreover, been expressly ordered by the Court of Directors six months before Hastings took office.

Hastings makes Bengal pay

Hastings' next financial stroke was the sale of Allahábad and Kora Provinces to the Wazir of Oudh. These Provinces had been assigned by Clive, in his partition of the Gangetic valley, to the Emperor Sháh Alam, together with a tribute of about £300,000 (26 *laks* of rupees), in return for the grant of Bengal to the Company. But the Emperor had now been

Sells Allahabad and Kora, 1773

¹ The detailed history of these transactions, and a sketch of each of the 14 Nawabs of Bengal from 1704 to 1854 will be found under District Murshidabad, vol. ix pp. 172-195, of Hunter's *Statistical Account of Bengal*.

² See separate agreements with the successive Nawabs of 30th September 1765, 19th May 1766 and 21st March 1770 in each of which the grant is to the Nawab without mention of heirs or successors.—Vitchison's *Treaties and En. 1300 n. 1*, vol. 1 pp. 56-59 (ed. 1876).

cruel pressure on herself and the eunuchs of her household, over a million sterling was extorted for the English Company

On his return to England, Warren Hastings was impeached, ^{Charges against Hastings} in 1786, by the House of Commons for these and other alleged acts of oppression. He was solemnly tried by the House of Lords, and the proceedings dragged themselves out for seven years (1788-95). They form one of the most celebrated State trials in English history, and ended in a verdict of not guilty on all the charges. Meanwhile, the cost of the defence had ruined Warren Hastings, and left him dependent upon the charity of the Court of Directors—a charity which never failed.

The real excuse, such as it is, for some of Hastings' measures ^{Hastings' poor excuse} is that he had to struggle for his very existence, that native perfidy gave him his opportunity, and that he used his opportunity, on the whole, less mercilessly than a native Viceroy would have done. It is a poor excuse for the clearest English head, and the firmest administrative hand, that ever ruled India. In his dealings with Southern India Warren Hastings had not to regard solely the financial results. He there appears as the great man that he really was, calm in council, cautious of enterprise, but swift in execution, and of indomitable courage in all that he undertook.

The Bombay Government was naturally emulous to follow the example of Madras and Bengal, and to establish its supremacy at the Court of Poona by placing its own nominee upon the throne. This ambition found its scope in 1775 by the treaty of Surat, by which Raghunáth Ráo, one of the claimants to the throne of the Peshwá, agreed to cede Salsette and Bassein to the English, in consideration of being himself restored to Poona. The military operations that followed are ^{First Maráthá war 1778-81} known as the first Maráthá war. Warren Hastings, who in his capacity of Governor General claimed some degree of control over the decisions of the Bombay Government, strongly disapproved of the treaty of Surat. But when war actually broke out, he threw the whole force of the Bengal army into the scale. One of his favourite officers, General Goddard, marched across ^{God's first march 1778-79} the peninsula from sea to sea, and conquered the rich Province of Gujarat almost without a blow. Another, Captain Popham, snatched by storm the rock fortress of Gwalior, which was regarded as the key of Hindustán.

These brilliant successes of the Bengal troops atoned for the contemporaneous disgrace of the convention of Wargaum in 1779, when the Maráthás overpowered and dictated terms to our Bombay force. The war in Bombay lasted till 1781.

Treaty of
Salbai,
1782.

It was closed by the treaty of Salbai (1782), which practically restored the *status quo*. Raghunáth Ráo, the English claimant to the Peshwáship, was set aside on a pension; Gujarát was restored to the Maráthás; and only Salsette, with Elephanta and two other small islands, was retained by the English.

War with
Mysore,
1780-84.

Meanwhile, Warren Hastings had to deal with a more formidable enemy than the Maráthá confederacy. The reckless conduct of the Madras Government had roused the hostility both of Haidar Ali of Mysore and of the Nizám of the Deccan, the two strongest Musalmán powers in India. These princes began to draw the Maráthás into an alliance against the English. The diplomacy of Hastings won back the Nizám and the Maráthá Rájá of Nágpur; but the army of Haidar Ali fell like a thunderbolt upon the British possessions in the Karnátik. A strong detachment under Colonel Baillie was cut to pieces at Pollilore, and the Mysore cavalry ravaged the country up to the walls of Madras. For the second time the Bengal army, stimulated by the energy of Hastings, saved the honour of the English name. He despatched Sir Eyre Coote, the victor of Wandewash, to relieve Madras by sea, with all the men and money available, while Colonel Pearse marched south overland to overawe the Rájá of Berar and the Nizám. The war was hotly contested, for the aged Sir Eyre Coote had lost his energy, and the Mysore army was not only well disciplined and equipped, but skilfully handled by Haidar and his son Tipú. Haidar died in 1782; and peace was finally concluded with Tipú in 1784, on the basis of a mutual restitution of all conquests.

Death of
Haidar
Ali, 1782.

Lord
Corn-
wallis,
1786-93.

Two years later, Warren Hastings was succeeded by Lord Cornwallis, the first English nobleman of rank who undertook the office of Governor-General of India. Between these two great names an interval of twenty months took place under Sir John Macpherson, a civil servant of the Company (Feb. 1785 to Sept. 1786). Lord Cornwallis twice held the high post of Governor-General. His first rule lasted from 1786 to 1793, and is celebrated for two events—the introduction of the Permanent Settlement into Bengal, and the second Mysore war. If the foundations of the system of civil administration were laid by Hastings, the superstructure was raised by Cornwallis. It was he who first entrusted criminal jurisdiction to Europeans, and established the Nizámat Sadr Adálat, or Supreme Court of Criminal Judicature, at Calcutta.

It was he, also, who separated the functions of the District Collector and Judge.

The system thus organized in Bengal was afterwards extended to Madras and Bombay, when those Presidencies also acquired territorial sovereignty. But the achievement most familiarly associated with the name of Cornwallis is the Permanent Settlement of the land revenue of Bengal. During four years, 1786-90, he laboured, with the help of an able Bengal civilian, John Shore, to arrive at the facts of the case. Warren Hastings had introduced, unsuccessfully and only for a period of five years, settlement of the land revenue Lord Cornwallis after three years of inquiry and of provisional measures, introduced a ten years' or 'decennial' settlement. Up to this time, the revenue had been collected pretty much according to the old Mughal system. The *samindars*, or Government farmers, whose office always tended to become hereditary, were recognised as having a right to collect the revenue from the actual cultivators. But no principle of assessment existed, and the amount actually realized varied greatly from year to year. Hastings seems to have looked to experience, as acquired from a succession of quinquennial settlements, to furnish the standard rate of the future. Francis, on the other hand, Hastings' great rival, advocated the fixing of the State demand in perpetuity. The same view recommended itself to the authorities at home, founded partly because it would place their finances on a more stable basis, partly because it seemed to identify the landlord of the English system of property. Accordingly, Cornwallis took out with him in 1786 instructions to introduce a Permanent Settlement.

The process of assessment began in 1789, and terminated in 1791. No attempt was made to measure the fields or calculate the out-turn, as had been done by Akbar, and it is now done whenever settlements are made in the British Provinces. The amount to be paid in the future was fixed by reference to what had been paid in the past. At first the settlement was called decennial, but in 1793 it was declared permanent for ever. The total assessment amounted to Sikka Rs. 26,800,989, or about 3 millions sterling for Bengal. Lord Cornwallis carried the scheme into execution, but the praise or blame, so far as tails are concerned, belongs to Sir John Shore, afterwards Earl Teignmouth, a civil servant, whose knowledge of the country was unsurpassed in his time. Shore would have proceeded more cautiously than Cornwallis' preconceived English

His
revenue
reforms

The De
centennial
Settle-
ment,
1789-91

expect
ment

permanent
Settlement
of Bengal,
1793.

idea of a proprietary body, and the Court of Directors' haste after fixity, permitted.¹

Second
Mysore
war,
1790-92.

The second Mysore war of 1790-92 is noteworthy on two accounts. Lord Cornwallis, the Governor-General, led the British army in person, with a pomp and a magnificence of supply which recalled the campaigns of Aurangzeb. The two great southern powers, the Nizám of the Deccan and the Maráthá confederacy, co-operated as allies of the British. In the end, Tipú Sultán submitted when Lord Cornwallis had commenced to beleaguer his capital. He agreed to yield one-half of his dominions to be divided among the allies, and to pay 3 millions sterling towards the cost of the war. These conditions he fulfilled, but ever afterwards he burned to be revenged upon his English conquerors.

Sir John
Shore,
1793-98.

The period of Sir John Shore's rule as Governor-General, from 1793 to 1798, was uneventful. In 1798, Lord Mornington, better known as the Marquis of Wellesley, arrived in India, already inspired with imperial projects which were destined to change the map of the country. Mornington was the friend and favourite of Pitt, from whom he is thought to have derived his far-reaching political vision, and his

Marquis of
Wellesley,
1798-1805.

antipathy to the French name. From the first he laid down as his guiding principle, that the English must be the one paramount power in the peninsula, and that native princes could only retain the insignia of sovereignty by surrendering their political independence. The history of India since his time has been but the gradual development of this policy, which received its finishing touch when Queen Victoria was proclaimed Empress of India on the 1st of January 1877.²

French
influence
in India,
1798-1800.

To frustrate the possibility of a French invasion of India, led by Napoleon in person, was the governing idea of

¹ The Permanent Settlement will be referred to in greater detail, and its practical working exhibited, under the Administrative chapter.

² An admirable account of Lord Wellesley's policy will be found in the Despatch of the Governor-General in Council to the Secret Committee of the Court of Directors, dated Fort William, 12th April 1804. This Despatch extends to 791 paragraphs, and covers all the great Indian questions of that eventful period. It was printed by John Stockdale, Piccadilly, in 1805, as a quarto volume, entitled, *History of all the Events and Transactions which have taken place in India*, etc. It will continue to form the most authentic record of any Governor-Generalship of India, until the seal is taken off Lord Dalhousie's long closed diaries.

Wellesley's foreign policy. France at this time, and for many years later, filled the place afterwards occupied by Russia in the imagination of English statesmen. Nor was the danger so remote as might now be thought. French regiments guarded and overawed the Nizam of Hyderabad. The soldiers of Sindhia, the military head of the Maratha confederacy, were disciplined and led by French adventurers. Tipu Sultan of Mysore carried on a secret correspondence with the French Directorate, allowed a tree of liberty to be planted in his dominions, and enrolled himself in a republican club as 'Citizen Tippu.' The islands of Mauritius and Bourbon afforded a convenient half-way rendezvous for French intrigue, and for the assembling of a hostile expedition. Above all, Napoleon Buonaparte was then in Egypt dreaming of the conquests of Alexander, and no man knew in what direction he might turn his hitherto unconquered legion.

Wellesley conceived the scheme of crushing for ever the French hopes in Asia by placing himself at the head of a great Indian confederacy. In Lower Bengal the conquests of Clive and the policy of Warren Hastings had made the English paramount. Before Lord Wellesley's arrival our power was consolidated from the seaboard to Benares high up the Gangetic valley. Beyond our frontier there the Nawab Wazir of Oudh had agreed to pay a subsidy for the aid of British troops. This sum in 1797 amounted to £760,000 a year, and the Nawab being always in arrears entered into negotiations for a cession of territory in lieu of a cash payment. In 1801 the treaty of Lucknow made over to the British the *doab*, or fertile tract between the Ganges and the Jumna together with Rohilkhand. In Southern India our possessions were chiefly confined in 1798 before Lord Wellesley, to the coast Districts of Madras and Bombay.

Wellesley resolved to make the British supreme as far as Delhi in Northern India, and to compel the great powers of the south to enter into subordinate relations to the Company's government. The intrigues of the native princes gave him his opportunity for carrying out his plan without breach of faith. The time had arrived when the English must either become supreme in India, or be driven out of it. The Mughal Empire was completely broken up, and the sway had to pass either to the local Muhammadan governors of that Empire, or to the Hindu confederacy represented by the Marathas, or to the British. Lord Wellesley determined that it should pass to the British.

Lord Wellesley's work ;

in the north ;

His work in Northern India was at first easy. By the treaty of Lucknow in 1801, he made us territorial rulers as far as the heart of the present North-Western Provinces, and established our political influence in Oudh. Beyond those limits, the northern branches of the Maráthás practically held sway, with the puppet Emperor in their hands. Lord Wellesley left them untouched for a few years, until the second Maráthá war (1802-04) gave him an opportunity for dealing effectively with their nation as a whole.

in the south.

In Southern India, Lord Wellesley quickly perceived that the Muhammadan Nizám at Haidarábád stood in need of his protection, and he converted him into a useful follower throughout the succeeding struggle. The other Muhammadan power of the south, Tipú Sultán of Mysore, could not be so easily handled. Lord Wellesley resolved to crush him, and had ample provocation for so doing. The third power of Southern India—namely, the Hindu Maráthá confederacy—was so loosely organized that Lord Wellesley seems at first to have hoped to live on terms with it. When several years of fitful alliance had convinced him that he had to choose between the supremacy of the Maráthás or of the British in Southern India, he did not hesitate in his decision.

Treaty with the Nizám, 1798.

Lord Wellesley first addressed himself to the weakest of the three southern powers, the Nizám at Haidarábád. Here he won a diplomatic success, which turned a possible rival into a subservient ally. The French battalions at Haidarábád were disbanded, and the Nizám bound himself by treaty¹ not to take any European into his service without the consent of the English Government,—a clause since inserted in every leading engagement entered into with Native Powers.

Third Mysore war, 1799.

Wellesley next turned the whole weight of his resources against Tipú, whom Cornwallis had defeated, but had not subdued. Tipú's intrigues with the French were laid bare, and he was given an opportunity of adhering to the new subsidiary system. On his refusal, war was declared, and Wellesley came down in viceregal state to Madras to organize the expedition in person, and to watch over the course of events. One English army marched into Mysore from Madras, accompanied by a contingent from the Nizám. Another advanced from the western coast. Tipú, after a feeble resistance in the field, retired into Seringapatam, and, when his capital was stormed, died fighting bravely in the breach, 1799. Since the battle of Plassey

¹ Dated 1st September 1798.—Aitchison's *Treaties and Engagements*, vol. v. pp. 173-176 (ed. 1876).

o event had so greatly impressed the native imagination as the capture of Seringapatam, which won for General Harris a peerage, and for Wellesley an Irish Marquisate

Fall of
Seringapatam 1799

In dealing with the territories of Tipu, Wellesley acted with moderation. The central portion, forming the old State of Mysore, was restored to an infant representative of the Hindu Rájás, whom Haider Ali had dethroned. The rest of Tipu's dominions was partitioned between the Nizam, the Maráthás, and the English. At about the same time, the Karnatik, or the part of South eastern India ruled by the Nawab of Arcot, and also the principality of Tanjore were placed under direct British administration, thus constituting the Madras Presidency almost as it has existed to the present day. The sons of the late Tipu were treated by Lord Wellesley with paternal tenderness. They received a magnificent allowance with semi royal establishment, first at Vellore and afterwards in Calcutta. The last of them, Prince Ghulam Muhammad was long well known as a public spirited citizen of Calcutta and an active Justice of the Peace. He died only a few years ago (about 1877).

The Maráthás had been the nominal allies of the English in both their wars with Tipu. But they had not rendered active assistance, nor were they secured to the English side as the Nizam now was. The Maráthá powers at this time were five in number. The recognised head of the confederacy was the Peshwa of Poona, who ruled the hill country of the Western Ghats, the cradle of the Maráthá race. The fertile Province of Gujarát was annually harried by the horse men of the Gíekwár of Baroda. In Central India, two military leaders, Sindhia of Gwalior and Holkar of Indore, alternately held the pre eminency. Towards the east, the Bhonsla Rájá of Nágpur reigned from Berar to the coast of Orissa.

The Maráthas in 1800

Wellesley laboured to bring these several Maráthá powers within the net of his subsidiary system. In 1802, the necessities of the Peshwa, who had been defeated by Holkar, and driven as a fugitive into British territory, induced him to sign the treaty of Lassein. By this he pledged himself to the British to hold communications with no Power, European or Native, except ourselves. He also granted to us Districts for the maintenance of a subsidiary force. This greatly extended the English territorial influence in the Bombay Presidency. It led to the second Maráthá war, as neither Sindhia nor the Peshwa would tolerate the Peshwa's betrayal of Maráthá interests.

Wellesley's dealings with the Maráthas

Second
Maráthá
war,
1802-04.

British
victories,
1802-03.

Additions
to British
India,
1803.

Later dis-
asters,
1804-05.

India after
Lord
Wellesley,
1805 ;
in the
north ;

in the
south.

The campaigns which followed are perhaps the most glorious in the history of the British arms in India. The general plan, and the adequate provision of resources, were due to the Marquis of Wellesley, as also the indomitable spirit which refused to acknowledge defeat. The armies were led by Sir Arthur Wellesley (afterwards Duke of Wellington), and General (afterwards Lord) Lake. Wellesley operated in the Deccan, where, in a few short months, he won the decisive victories of Assaye and Argaum, and captured Ahmadnagar. Lake's campaign in Hindustán was no less brilliant, although it has received less notice from historians. He won pitched battles at Aligarh and Láswári, and took the cities of Delhi and Agra. He scattered the French troops of Sindhia, and at the same time stood forward as the champion of the Mughal Emperor in his hereditary capital. Before the end of 1803, both Sindhia and the Bhonsla Rájá of Nágpur sued for peace.

Sindhia ceded all claims to the territory north of the Jumna, and left the blind old Emperor Sháh Alam once more under British protection. The Bhonsla forfeited Orissa to the English, who had already occupied it with a flying column in 1803 ; and Berar to the Nizám, who gained a fresh addition by every act of complaisance to the British Government. The freebooter Jaswant Ráo Holkar alone remained in the field, supporting his troops by raids through Málwá and Rájputána. The concluding years of Wellesley's rule were occupied with a series of operations against Holkar, which brought little credit on the British name. The disastrous retreat of Colonel Monson through Central India (1804) recalled memories of the convention of Wargáum, and of the destruction of Colonel Baillie's force by Haidar Ali. The repulse of Lake in person at the siege of Bhartpur (Bhurt-pore) is memorable as an instance of a British army in India having to turn back with its object unaccomplished (1805). Bhartpur was not finally taken till 1827.

Lord Wellesley during his six years of office carried out almost every part of his territorial scheme. In Northern India, Lord Lake's campaigns, 1803-05, brought the North-Western Provinces (the ancient *Madhya-desha*) under British rule, together with the custody of the puppet Emperor. The new Districts were amalgamated with those previously acquired from the Nawáb Wazír of Oudh into the 'Ceded and Conquered Provinces.' This partition of Northern India remained till the Sikh wars of 1845 and 1848-49 gave us the Punjab. In South-eastern India, we have seen that Lord Wellesley's con-

quests constituted the Madras Presidency almost as it exists at this date. In South western India, the Peshwa was reduced to a vassal of the Company. But the territories now under the Governor of Bombay were not finally built up into their present form until the last Maratha war in 1818.

The financial strain caused by these great operations of Lord Wellesley had meanwhile exhausted the patience of the Court of Directors at home. In 1805 Lord Cornwallis was sent out as Governor General a second time with instructions to bring about peace at any price while Holkar was still subdued, and with Sindhia threatening a fresh war. But Cornwallis was now an old man, and broken down in health. Travelling up to the north west during the rainy season, he sank and died at Gházipur, before he had been ten weeks in the country.

Marquis Cornwallis again, 1805

His immediate successor was Sir George Barlow, a civil servant of the Company who as a *locum tenens* had no alternative but to carry out the commands of his employers. Under these orders, he curtailed the area of British territory, and, in violation of engagements, abandoned the Rájput chiefs to the cruel mercies of Holkar and Sindhia. During his administration, also, occurred the mutiny of the Madras sepoys at Vellore (1806) which although promptly suppressed, sent a shock of insecurity throughout the Empire. The feebly economical policy of this interregnum proved a most disastrous one. But, fortunately, the rule soon passed into other hands.

Sir George Barlow 1805

Lord Minto Governor General from 1807 to 1813 consolidated the conquests which Wellesley had acquired. His only military exploits were the occupation of the island of the Mauritius, and the conquest of Java by an expedition which he accompanied in person. The condition of Central India continued to be disturbed but Lord Minto succeeded in preventing any violent outbreaks without himself having recourse to the sword. The Company had ordered him to follow a policy of non intervention, and he managed to obey his orders without injuring the prestige of the British name. Under his auspices, the Indian Government opened relations with a new set of foreign powers, by sending embassies to the Punjab, to Afghanistan, and to Persia. The ambassadors had been trained in the school of Wellesley, and formed, perhaps, the most illustrious trio of 'politicals' whom the Indian services have produced. Metcalfe went as envoy to the Sikh Court of Ranjit Singh at Lahore, Elphinstone met the Sháh of Afghán

Earl of Minto 1807-13

istán at Pesháwar; and Malcolm was despatched to Persia. It cannot be said that these missions were fruitful of permanent results; but they introduced the English to a new set of diplomatic relations, and widened the sphere of their influence.

Lord Moira (Marquis of Hastings), 1814-23. The successor of Lord Minto was the Earl of Moira, better known by his later title as the Marquis of Hastings. The Marquis of Hastings completed Lord Wellesley's conquests in Central India, and left the Bombay Presidency almost as it stands at present. His long rule of nine years, from 1814 to 1823, was marked by two wars of the first magnitude—namely, the campaigns against the Gúrkhas of Nepál, and the last Maráthá struggle.

The Gúrkhas of Nepál. The Gúrkhas, the present ruling race in Nepál, trace their descent from Hindu immigrants and claim a Rájput origin. The indigenous inhabitants, called Newars, belong to the Indo-Tibetan stock, and profess Buddhism. The sovereignty of the Gúrkhas dates only from 1767-68, when they overran the valley of Khatmandu, and gradually extended their power over the hills and valleys of Nepál. Organized upon a military and feudal basis, they soon became a terror to their neighbours, marching east into Sikkim, west into Kumáun, and south into the Gangetic plains. In the last quarter their victims were British subjects (natives of Bengal), and it became necessary to check their advance. Sir George Barlow and Lord Minto had remonstrated in vain, and nothing was left to Lord Moira but to take up arms.

Nepál war, 1814-15. The first campaign of 1814 was unsuccessful. After overcoming the natural difficulties of a malarious climate and precipitous hills, our troops were on several occasions fairly worsted by the impetuous bravery of the little Gúrkhas, whose heavy knives or *kukris* dealt terrible execution. But in the cold weather of 1814, General Ochterlony, who advanced by way of the Sutlej, stormed one by one the hill forts which still stud the Himálayan States, now under the Punjab Government, and compelled the Nepál *darbár* to sue for peace. In the following year, 1815, the same general made his brilliant march from Patná into the lofty valley of Khatmandu, and finally dictated the terms which had before been rejected, within a few miles of the capital. By the treaty of Segauli, which defines the English relations with Nepál to the present day, the Gúrkhas withdrew on the south-east from Sikkim; and on the south-west, from their advanced posts in the outer

Treaty of Segauli; cedes Himálayan tracts, 1815.

ranges of the Himalayas which enabled us to obtain the health giving stations of Naini Tal, Massuri, and Simla.

Meanwhile, the condition of Central India was every year becoming more unsatisfactory. The great Maráthá chiefs had learned to live as princes rather than as predatory leaders. But their original habits of lawlessness were being followed by a new set of freebooters known as the Pindaris. As opposed to the Marathas, who were at least a Hindu nationality bound by the traditions of a united government, the Pindaris were merely plundering bands closely corresponding to the free companies of mediæval Europe. Of no common race and of no common religion, they welcomed to their ranks the outlaws and broken men of all India—Afgháns, Marathas or Jats. They represented the debris of the Mughal Empire which had not been incorporated by any of the local Muhammadan or Hindu powers that spring up out of its ruins. For a time, indeed, it seemed as if the inheritance of the Mughal might pass to these armies of banditti. In Bengal, similar hordes had formed themselves out of the disbanded Muhammadan troops and the Hindu predatory castes. But they had been dispersed under the vigorous rule of Warren Hastings. In Central India, the evil lasted longer, attained a greater scale, and was only stamped out by a regular war.

The Pindari head quarters were in Málwa, but their depredations were not confined to Central India. In bands, sometimes of a few hundreds, sometimes of many thousands, they rode out on their forays as far as the opposite coasts of Madras and of Bombay. The most powerful of the Pindari captains, Amír Khán, had an organized army of many regiments, and several batteries of cannon. Two other leaders, known as Chitu and Karím, at one time paid a ransom to Sindhiya of £100,000. To suppress the Pindari hordes, who were supported by the sympathy, more or less open, of all the Maráthá chiefs, Lord Hastings (1817) collected the strongest British army which had yet been seen in India, numbering 120,000 men. One half operated from the north, the other half from the south. Sindhiya was overawed, and remained quiet. Amír Khán disbanded his army, on condition of being guaranteed the possession of what is now the principality of Bhopál. The remaining bodies of Pindaris were attacked in their homes, surrounded, and cut to pieces. Karím threw himself upon the mercy of the conquerors. Chitu fled to the jungles, and was killed by a tiger.

In the same year (1817) and almost in the same month

(November) as that in which the Pindáris were crushed, the three great Maráthá powers at Poona, Nágpur, and Indore rose separately against the English. The Peshwá, Báji Ráo, had long been chafing under the terms imposed by the treaty of Bassein (1802). A new treaty of Poona, in June 1817, now freed the Gáekwár from his control, ceded further districts to the British for the pay of the subsidiary force, and submitted all future disputes to the decision of our Government.

New
Maráthá
treaty,
1817.

The
Maráthá
attack.

Elphinstone, then our Resident at his Court, foresaw a storm, and withdrew to Kírki, whither he had ordered up a European regiment. The next day the Residency was burnt down, and Kírki was attacked by the whole army of the Peshwá. The attack was bravely repulsed, and the Peshwá immediately fled from his capital, Poona. Almost the same plot was enacted at Nágpur, where the honour of the British name was saved by the sepoys, who defended the hill of Sítábalí against enormous odds.

Last Mar-
áthá war,
1817-18.

It had now become necessary to crush the Maráthás. Their forces under Holkar were defeated in the following month at the pitched battle of Mehidpur. All open resistance was now at an end. Nothing remained but to follow up the fugitives, and to impose conditions for a general pacification. In both these duties Sir John Malcolm played a prominent part. The dominions of the Peshwá were annexed to the Bombay Presidency, and the nucleus of the present Central Provinces was formed out of the territory rescued from the Pindáris. The Peshwá himself surrendered, and was permitted to reside at Bithúr, near Cawnpur, on a pension of £80,000 a year. His adopted son was the infamous Náná Sáhib of the Mutiny of 1857.

Bombay
territories
annexed,
1818.

Sátára ;

To fill the Peshwá's place, as the traditional head of the Maráthá confederacy, the lineal descendant of Sivají was brought forth from obscurity and placed upon the throne of Sátára. An infant was recognised as the heir of Holkar, and a second infant was proclaimed Rájá of Nágpur under British guardianship. At the same time, the States of Rájputána accepted the position of feudatories to the paramount British power.

Rájputána.

Map of
India,
1818-48.

The map of India, as thus drawn by Lord Hastings, remained substantially unchanged until the time of Lord Dalhousie. But the proudest boast of Lord Hastings and Sir John Malcolm was, not that they had advanced the *pomarium*, but that they had conferred the blessings of peace and good government upon millions who had groaned under the extortions of the Maráthás and Pindáris.

The Marquis of Hastings was succeeded by Lord Amherst, Mr Adam, after the interval of a few months, during which Mr Adam, 1823 a civil servant, acted as Governor General. The Maráthá war in the Peninsula of India was hardly completed when our armies had to face new enemies beyond the sea. Lord Amherst's administration lasted for five years, from 1823 to 1828. It is known in history by two prominent events, the first Burmese war and the capture of Bharrpur. Lord Amherst 1823 28

For some years past, our north eastern frontier had been disturbed by Burmese raids. Burma, or the country which fringes the western shore of the Bay of Bengal, and runs up the valley of the Irrawadi, has a people of Tibeto Chinese origin, and a history of its own. Tradition asserts that its civilisation was introduced from the coast of Coromandel, by a people who are supposed to preserve a trace of their origin in their name of Talang (*cf* Telingána). However this may be, the Buddhist religion, professed by the Burmese at the present day, certainly came from India at a very early date. Waves of invasion from Siam on the south, and from the wild mountains of China in the north, have passed over the land. These conquests were marked by the wanton and wholesale barbarity which seems to characterize the Tibeto Chinese race, but the civilisation of Buddhism survived every shock, and flourished around the ancient pagodas. European travellers in the 15th century visited Pegu and Tenasserim, which they describe as flourishing seats of maritime trade. During the Portuguese predominance in the East, Arakan in Northern Burma became an asylum for desperate European adventurers. With their help, the Arakanese conquered Chittagong on the Bengal seaboard, and (under the name of the Maghs) became the terror of the Gangetic delta. About 1750, a new Burmese dynasty arose, founded by Alaung payá or Alompra, with its capital at Ava. Alompra's successors ruled Independent Burma until its annexation to British India in 1886.¹ Ancient Burma. Burma 15th cc to A.D.

The dynasty of Alompra, after having subjugated all Burma, and overrun (1800) Assam, which was then an independent kingdom, began a series of encroachments upon the British Districts. As they rejected all peaceful proposals with scorn, Lord Amherst was at last compelled to declare war in 1824. Little military glory could be gained by beating the Burmese, who were formidable chiefly from the pestilential First Burmese war, 1824-28.

¹ For the history of Burma, see the articles BURMA, BRITISH, and BURMA, INDEPENDENT, in *The Imperial Gazetteer of India*.

character of their country. One expedition with gunboats proceeded up the Brahmaputra into Assam. Another marched by land through Chittagong into Arakan, as the Bengal sepoys refused to go by sea. A third, and the strongest, sailed from Madras direct to the mouth of the Irawadi. The war was protracted over two years. After a loss to us of about 20,000 lives, chiefly from disease, and an expenditure of £14,000,000, the King of Ava signed, in 1826, the treaty of Yandabu. By this he abandoned all claim to Assam, and ceded the Provinces of Arakan and Tenasserim, already in the military occupation of the British. He retained the whole valley of the Irawadi, down to the sea at Rangoon.

Assam,
etc., an-
nexed,
1826.

Bhartpur
taken,
1827.

The capture of Bhartpur in Central India by Lord Combermere, in January 1827, wiped out the repulse which Lake had received before that city in January 1805. A disputed succession led to the British intervention. Artillery could make little impression upon the massive walls of mud. But at last a breach was effected by mining, and the city was taken by storm, thus removing the popular notion throughout India that it was impregnable—a notion which had threatened to become a political danger.

Lord
William
Bentinck,
1828-35.

The next Governor-General was Lord William Bentinck, who had been Governor of Madras twenty years earlier, at the time of the mutiny of Vellore (1806). His seven years' rule (from 1828 to 1835) is not signalized by any of those victories or extensions of territory by which chroniclers measure the growth of an Empire. But it forms an epoch in administrative reform, and in the benign process by which a subject population is won over to venerate as well as to dread its alien rulers. The modern history of the British in India, as benevolent administrators, ruling the country with an eye to the good of the natives, may be said to begin with Lord William Bentinck. According to the inscription upon his statue at Calcutta, from the pen of Macaulay: 'He abolished cruel rites; he effaced humiliating distinctions; he gave liberty to the expression of public opinion; his constant study was to elevate the intellectual and moral character of the nations committed to his charge.'

His
financial
reforms.

Lord William Bentinck's first care on arrival in India was to restore equilibrium to the finances, which were tottering under the burden imposed upon them by the Burmese war. This he effected by three series of measures—first, by reductions in permanent expenditure, amounting to 1½ million

sterling a year, second, by augmenting the revenue from lands which had surreptitiously escaped assessment, third, by duties on the opium of Malwa. He also widened the gates by which educated natives could enter the service of the Company. Some of these reforms were distasteful to the covenanted service and to the officers of the army. But Lord William was staunchly supported by the Court of Directors and by the Whig Ministry at home.

His two most memorable acts are the abolition of *sati*, or widow burning, and the suppression of the *thags*. At this distance of time it is difficult to realize the degree to which these two barbarous practices had corrupted the social system of the Hindus. European research has clearly proved that the text in the Vedas adduced to authorize the immolation of widows, was a wilful mistranslation.¹ But the practice had been enshrined in Hindu opinion by the authority of centuries, and had acquired the sanctity of a religious rite. The Emperor Akbar prohibited it, but failed to put it down. The early English rulers did not dare to violate the religious traditions of the people. In the year 1817, no less than 700 widows are said to have been burned alive in the Bengal Presidency alone. To this day, the holy spots of Hindu pilgrimage are thickly dotted with little white pillars, each commemorating a *sati*. In spite of strenuous opposition, both from Europeans and natives, Lord William Bentinck carried a regulation in Council on the 4th December 1829 by which all who abetted *sati* were declared guilty of 'culpable homicide'.

Abolition
of *sati*,
1829

The honour of suppressing *thagi* must be shared between Lord William Bentinck and Captain Sleeman. *Thags* were hereditary assassins, who made strangling their profession. They travelled in bands, disguised as merchants or pilgrims, and were sworn together by an oath based on the rites of the bloody goddess Kālī. Between 1826 and 1835, as many as 1562 *thags* were apprehended in different parts of British India, and, by the evidence of approvers, these abominable brother hoods were gradually stamped out.

Suppression
of *thagi*,
1835

Two other historical events are connected with the administration of Lord William Bentinck. In 1833 the Charter of the East India Company was renewed for twenty years, but upon the condition that the Company should abandon its trade and permit Europeans to settle in the country. At the same time, a fourth or 'Law member' was added to the Governor-General's Council, who might not be a servant of the

Creation
of *Charter*,
1833

Company; and a Commission was appointed to revise and codify the law. Macaulay was the first Law-member of Council, and the first President of the Law Commission.

Mysore
protected,
1830. In 1830-31, it was found necessary to take the State of Mysore under British administration. It continued so up to March 1881, when it was restored to native government. In 1834, the frantic misrule of the Rájá of Coorg brought on a sharp and short war. The Rájá Lingaráj was permitted to retire to Vellore, then to Benares, and finally to England, where he died. The brave and proud inhabitants of his mountainous little territory decided to place themselves under the sway of the Company. This was the only annexation effected by Lord William Bentinck, and it was done 'in consideration of the unanimous wish of the people.'

Coorg
annexed,
1834.

Lord
Metcalf,
1835-36. Sir Charles (afterwards Lord) Metcalfe succeeded Lord William as senior member of Council. His short term of office is memorable for the measure which his predecessor had initiated, but which he carried into execution, for giving entire liberty to the press. From this time the Indian Government lost the power of deporting journalists who made themselves formidable by their pens. Public opinion in India, as well as the express wish of the Court of Directors at home, pointed to Metcalfe as the fittest person to carry out the policy of Bentinck, not provisionally, but as Governor-General for a full term.

Lord
Auckland,
1836-42. Party exigencies, however, led to the appointment of Lord Auckland. From this date commences a new era of war and conquest, which may be said to have lasted for twenty years. All looked peaceful until Lord Auckland, prompted by his evil genius, attempted by force to place Sháh Shujá upon the throne of Kábul; an attempt conducted with gross mismanagement, and ending in the annihilation of the British garrison placed in that city.

Afghán-
istán under
the
Duránís,
1747-1826. For the first time since the days of the Sultáns of Ghazní and Ghor, Afghánistán had obtained a national king in 1747 in Ahmad Sháh Durání. This resolute soldier found his opportunity in the confusion which followed the death of the Persian conqueror, Nádir Sháh. Before his own decease in 1773, Ahmad Sháh had conquered a wide empire, from Herát to Pesháwar, and from Kashmír to Sind. His intervention on the field of Pánípat (1761) turned back the tide of Maráthá conquest, and replaced a Mughal Emperor on the throne of Delhi. But Ahmad Sháh never cared to settle down in India.

and alternately kept state at his two Afghan capitals of Kábul and Kandahar. The Duráni kings were prolific in children, who fought to the death with one another on each succession. At last, in 1826, Dost Muhammad, head of the powerful Barakzai family, succeeded in establishing himself as ruler of Kábul, with the title of Amír, while two fugitive brothers of the Duráni line were living under British protection at Ludhiana, on the Punjab frontier.

The attention of the English Government had been directed to Afghán affairs ever since the time of Lord Wellesley, who feared that Zaman Shah, the Afghán Amír, then holding his court at Lahore (1800), might follow in the path of Ahmad Sháh, and overrun Hindustan. The growth of the powerful Sikh kingdom of Ranjit Singh effectually dispelled these alarms. Subsequently, in 1809, while a French invasion of India was still a possibility to be guarded against, Mountstuart Elphinstone was sent by Lord Minto on a mission to Shah Shujá to form a defensive alliance. Before the year expired, Sháh Shujá had been driven into exile, and a third brother, Mahmud Shah, was on the throne. In 1837, when the curtain rises upon the drama of English interference in Afghánistan, the usurper Dost Muhammad, Barakzai, was firmly established at Kábul. His great ambition was to recover Pesháwar from the Sikhs. When, therefore, Captain Alexander Burnes arrived on a mission from Lord Auckland, with the ostensible object of opening trade, the Dost was willing to promise everything if only he could get Peshawar.

But Lord Auckland had another and more important object in view. At this time the Russians were advancing rapidly in Central Asia, and a Persian army not without Russian support, was besieging Herát then as now the bulwark of Afghánistan on the west. A Russian envoy was at Kábul at the same time as Burnes. The latter was unable to satisfy the demands of Dost Muhammad in the matter of Pesháwar, and returned to India unsuccessful. Lord Auckland forthwith resolved upon the hazardous plan of placing a more subservient ruler upon the throne of Kábul.

Shah Shujá, one of the two exiles of Ludhiana, was selected for the purpose. At this time both the Punjab and Sind were independent kingdoms. Sind was the less powerful of the two and accordingly a British army escorting Shah Shujá made its way by that route into southern Afghánistán through the Bolán Pass. Kandahar surrendered, Ghazni was taken by storm. Dost Muhammad fled across the Hindu Kush, and

Our earl,
deal no
with
Kábul
1800-5

Dost M
hammad
1837

I was an
influence,
1837

Sháh
Shujá
installed,
1839.

Sháh Shujá was triumphantly led into the Bala Hissár at Kábul in August 1839. After one more brave struggle, Dost Muhammad surrendered, and was sent to Calcutta as a State prisoner.

Kábul
occupied,
1839-41.

But although we could enthrone Sháh Shujá, we could not win for him the hearts of the Afgháns. To that nation he seemed a degenerate exile thrust back upon them by foreign arms. During two years, Afghánistán remained in the military occupation of the British. The catastrophe occurred in November 1841, when our Political Agent, Sir Alexander Burnes, was assassinated in the city of Kábul. The troops in the cantonments were under the command of General Elphinstone (not to be confounded with the able civilian and historian, the Hon. Mountstuart Elphinstone). Sir William Macnaghten was the political officer. Elphinstone, an old man, proved unequal to the responsibilities of the position. Macnaghten was treacherously murdered at an interview with the Afghán chief Akbar Khán, eldest son of Dost Muhammad.

The
winter
retreat.

After lingering amid disgraceful dissensions and with fatal indecision in their cantonments for two months, the British army set off in the depth of winter, under a fallacious guarantee from the Afghán leaders, to find its way back to India through the passes. When they started, they numbered 4000 fighting men with 12,000 camp followers. A single survivor, Dr. Brydon, reached the friendly walls of Jalálábád, where Sale was gallantly holding out. The rest perished in the snowy defiles of Khurd-Kábul and Jagdalak, from the knives and matchlocks of the Afgháns, or from the effects of cold. A few prisoners, chiefly women, children, and officers, were considerably treated by the orders of Akbar Khán.

Our
garrison
annihil-
ated, 1842.

The first Afghán enterprise, begun in a spirit of aggression, and conducted amid disagreements and mismanagement, had ended in the disgrace of the British arms. The real loss, which amounted only to a single garrison, and cost fewer soldiers than many a victory, was magnified by the horrors of the winter march, and by the completeness of the annihilation.

The shock
in Eng-
land.

Earl
Ellen-
borough
1842-4

the news reached Calcutta, Lord
Ellenborough, whose
with draw in safety the
bád. r counsels

The arm,
of retribu-
tion, 1842.

marching
wed to
with-
ay!

and north to Kashmir. On the east side alone he was hemmed in by the Sutlej, up to which river the authority of the British Government had advanced in 1804. Until his death, in 1839, Ranjit Singh was ever loyal to the engagements which he had entered into with Metcalfe in 1809. But he left no son capable of wielding his sceptre. Lahore was torn by dissensions between rival generals, ministers, and queens. The only strong power was the army of the Central Committee of Generals or *khalas*,¹ which, since our disaster in Afghanistan, burned to measure its strength with the British Sepoys. The French or European General, Avitabile and Court, were foolishly ousted by the Sikh commanders, and the supreme military command was vested in a series of *parshadats* or elective committees of five.

In 1845, the Sikh army, numbering 60,000 men with 150 guns, crossed the Sutlej and invaded British territory. Sir Hugh Gough, the Commander in Chief, together with the Governor General, hurried up to the frontier. Within three weeks, four pitched battles were fought, at Mudki, Ferozshahr, Aliwál, and Sohrón. The British loss on each occasion was heavy, but by the last victory, the Sikhs were fairly driven back into the Sutlej, and Lahore surrendered to the British. The British, however, declined to annex the prostrate province, but appointed a Sikh protectorate. By the terms of peace which we then dictated, the infant son of Ranjit, Duleep Singh, was recognised as Rájá, the Jalandhar Dóh, or *trá* between the Sutlej and the Rávi, was annexed to British territory, the Sikh army was limited to a specified number. Major Henry Lawrence was appointed Resident, to assist the Sikh Council of Regency, at Lahore, and a British force was sent to garrison the Punjab on behalf of the child Rájá. The Governor General, Sir H. Hardinge, received a *pette*, and returned to England in 1848.

Lord Dalhousie succeeded. The eight years' rule of the greatest of Indian proconsuls (1848-56) left more results than that of any Governor-General since. On a high minded statesman, of a most sensitive conscience, earnestly desiring peace, Lord Dalhousie found it against his will to fight two wars, and to annex vast territories. His campaigns in the Punjab and

¹ The *Trá* was the *Khálsa*, literally 'pure' or 'holy'. It was the royal exchequer, and the administrative machinery of the Sikh Government.

His
admini-
strative
reforms.

ended in large acquisitions of territory; while Nágpur, Oudh, and several minor States also came under British rule. But Dalhousie's deepest interest lay in the advancement of the moral and material condition of the country. His system of administration carried out in the conquered Punjab, by the two Lawrences and their assistants, is probably the most successful piece of difficult work ever accomplished by Englishmen. British Burma has prospered under our rule not less than the Punjab. In both cases, Lord Dalhousie himself laid the foundations of our administrative success, and deserves a large share of the credit.

His
Public
Works.

No branch of the administration escaped his reforming hand. He founded the Public Works Department, with a view to creating the network of roads, railways, and canals which now cover India. He opened the Ganges Canal, still the largest work of the kind in the country; and he turned the sod of the first Indian railway. He promoted steam communication with England *via* the Red Sea, and introduced cheap postage and the electric telegraph. It is Lord Dalhousie's misfortune that these benefits are too often forgotten in the recollections of the Mutiny, which followed his policy of annexation, after the firm hand which had remodelled British India was withdrawn. But history is compelled to record not only that no other Governor-General since the time of Lord Wellesley had ruled India with such splendid success from the military and political point of view, but also that no other Governor-General had done so much to improve the internal administration since the days of Warren Hastings.

Second
Sikh war,
1848-49.

Lord Dalhousie had not been six months in India before the second Sikh war broke out. The attempt to govern the Punjab by a Sikh protectorate broke down. The Council of Regency was divided against itself, corrupt and weak. The Queen-Mother had chosen her paramour as prime minister. In 1848, the storm broke. Two British officers were treacherously assassinated at Múltán. Unfortunately, Henry Lawrence was at home on sick leave. The British army was not ready to act in the hot weather; and, despite the single-handed exertions of Lieutenant (afterwards Sir Herbert) Edwardes, this outbreak of fanaticism led to a general rising of the Sikh confederacies.

Chilián-
wála, 1849.

The *khálsá* army again came together, and once more fought on even terms with the British. On the fatal field of Chiliánwála,¹ which our patriotism prefers to call a drawn battle, the British

¹ See articles CHILIANWALA and GUJRAT, *The Imperial Gazetteer of India*.

lost 2400 officers and men, besides four guns and the colours of three regiments (13th January 1849). But before reinforcements could come out from England, bringing Sir Charles Napier as Commander in Chief, Lord Gough had restored his reputation by the crowning victory of Gujrat, which absolutely destroyed the Sikh army. Multan had previously fallen, and the Afghán horse under Dost Muhammad, who had forgotten their hereditary antipathy to the Sikhs in their greater hatred of the British name, were chased back with ignominy to their native hills. The Punjab, annexed by proclamation on the 29th March 1849,¹ became a British Province—a virgin field for the administrative talents of Dalhousie and the two Lawrences. Maharájá Dhulip Singh received an allowance of £58,000 a year, on which he now lives as an English country gentleman in Norfolk.

The first step in the pacification of the Punjab² was a general disarmament, which resulted in the delivery of no fewer than 120,000 weapons of various kinds. Then followed a settlement of the land tax, village by village, at an assessment much below that to which it had been raised by Sikh exactions, and the introduction of a loose but equitable code of civil and criminal procedure. Roads and canals were laid out by Colonel Robert Napier (afterwards Lord Napier of Magdala). The security of British peace, and the personal influence of British officers, inaugurated a new era of prosperity, which was felt to the farthest corners of the Province. It thus happened that, when the Mutiny broke out in 1857 the Punjab remained not only quiet, but loyal.

The second Burmese war, in 1852, arose out of the ill treatment of some European merchants at Rangoon, and the insults offered to the captain of a British frigate who had been sent to remonstrate.³ The lower valley of the Irawadi, from Rangoon to Prome, was occupied in a few months, and as the King of Ava refused to treat, it was annexed by proclamation on the 20th December 1852, under the name of Pegu, to the Provinces of Arakan and Tenasserim acquired in 1826.

Since annexation, the inhabitants of the town of Rangoon have multiplied nearly fifteen fold. The trade of this

¹ In terms of the agreement with Maharája Dhulip Singh, of same date—Aitchison's *Treaties and Engagements*, vol. vi p. 47 (ed. 1876).

² For the annexation and administrative history of the Punjab see article PUNJAB in *The Imperial Gazetteer of India*.

³ For further details, see article BURMA *The Imperial Gazetteer of India*.

port, which four years after annexation (1857-58) only amounted to £2,131,055, had increased to £8,192,025 in 1877-78, and to £13,174,094 in 1883.¹

Its prosperity under our rule.

The towns and rural parts have alike prospered. Before its annexation in 1826, Amherst District was the scene of perpetual warfare between the Kings of Siam and Pegu, and was stripped of inhabitants. In February 1827, a Talaing chief with 10,000 followers settled in the neighbourhood of Maulmain; and after a few years, a further influx of 20,000 immigrants took place. In 1855, the population of Amherst District amounted to 83,146 souls; in 1860, to 130,953; in 1875, to 275,432; and in 1881, to 301,086. Or, to take the case of a seaport, —in 1826, when we occupied that part of the Province, Akyab was a poor fishing village. By 1830, it had developed into a little town with a trade valued at £7000. In 1879, the trade exceeded 2 millions sterling; so that the trade of Akyab had multiplied itself close on three hundred-fold in fifty years.

The Feudatory States.

Lord Dalhousie's dealings with the Feudatory States of India revealed the whole nature of the man. That rulers only exist for the good of the ruled, was his supreme axiom of government, of which he gave a conspicuous example in his own daily life. That British administration was better for the people than native rule, followed from this axiom. He was thus led to regard native chiefs from somewhat the same point of view as the Scotch regarded the hereditary jurisdictions after 1745, namely, as mischievous anomalies, to be abolished by every fair means. Good faith must be kept with rulers on the throne, and with their legitimate heirs. But no false sentiment should preserve dynasties which had forfeited our sympathies by generations of misrule, nor prolong those that had no natural successor. The 'doctrine of lapse' was the practical application of these principles, complicated by the Indian practice of adoption.

Dalhousie's doctrine of 'lapse.'

Hindu doctrine of adoption.

According to Hindu private law, an adopted son entirely fills the place of a natural son, whether to perform the religious obsequies of his father or to inherit his property. In all respects he continues the *persona* of the deceased. But it was argued that, both as a matter of historical fact and as one of political expediency, the succession to a throne stood upon a

¹ See article RANGOON, *The Imperial Gazetteer of India*. For growth of trade in other Burmese ports, see also article AKYAB, *The Imperial Gazetteer of Ind.a*.

different footing It was affirmed, not always with a complete knowledge of the facts, that the Mughal Emperors had asserted an interest in successions to the great fiefs, and demanded heavy payments for recognising them It was therefore maintained that the paramount power could not acknowledge without limitations a right of adoption, which might be used as a fraud to hand over the happiness of millions to a base born impostor Here came in Lord Dalhousie's notion of 'the good of the governed' In his mind, benefits to be conferred through British administration weighed heavier than a superstitious and often fraudulent fiction of inheritance

The first State to escheat to the British Government in accordance with these principles was Satara, which had been reconstituted by Lord Hastings on the downfall of the Peshwa in 1818 The Rájá of Sátára, the last lineal representative of Sivají, died without a male heir in 1848, and his deathbed adoption was set aside (1849) In the same year, the independence of the Rajput State of Karauli was saved by the Court of Directors, who drew a fine distinction between a dependent principality and a protected ally In 1853 Jhánsí suffered the same fate as Satára

But the most conspicuous application of the doctrine of lapse was the case of Nagpur The last of the Maráthá Bhonslas, a dynasty older than the British Government itself, died without a son, natural or adopted, in 1853 His territories were annexed, and became the Central Provinces That year also saw British administration extended to the Berars, or the Assigned Districts, which the Nizam of Haidarábád was induced to hand over to us, as a territorial guarantee for his arrears of subsidy, and for the pay of the Haidarábád contingent which he perpetually kept in arrear The relics of three other dynasties also passed away in 1853, although without any attendant accretion to British territory In the extreme south the titular Nawáb of the Karnátik and the titular Rájá of Tanjore both died without heirs Their rank and their pensions died with them, but compassionate allowances were continued to their families In the north of India, Báji Rao, the ex Peshwa who had been dethroned in 1818, lived on till 1853 in the enjoyment of his annual pension of £80,000 His adopted son, Nána Sáhib, inherited his accumulated savings, but could obtain no further recognition

Lord Dalhousie annexed the Province of Oudh on different grounds Ever since the Nawab Wazír, Shujá ud-Daulá, received back his forfeited territories from the hands of Lord

Clive in 1765, the existence of his dynasty had depended on the protection of British bayonets.¹ Guarded alike from foreign invasion and from domestic rebellion, the long line of Nawábs had sunk into private debauchees and public oppressors. Their one virtue was steady loyalty to the British Government. The fertile districts between the Ganges and the Gogra, which now support a denser population than any rural area of the same size on the globe, had been groaning for generations under an anarchy for which each British Governor-General felt himself in part responsible. Warning after warning had been given to the Nawábs (who had assumed the title of Sháh or King since 1819) that they must put their house in order.

Lord Dal-
housie's
view of the
measure.

What the benevolent Bentinck and the soldierly Hardinge had only threatened, was reserved for Lord Dalhousie, who united honesty of purpose with stern decision of character, to perform. He laid the whole case before the Court of Directors, who, after long and painful hesitation, resolved on annexation. Lord Dalhousie, then on the eve of retiring, felt that it would be unfair to leave the perilous task to his successor in the first moments of his rule. The tardy decision of the Court of Directors left him, however, only a few weeks to carry out the work. But he solemnly believed that work to be his duty to the people of Oudh. 'With this feeling on my mind,' he wrote in his private diary, 'and in humble reliance on the blessing of the Almighty (for millions of His creatures will draw freedom and happiness from the change), I approach the execution of this duty, gravely and not without solicitude, but calmly and altogether without doubt.'

Grounds of
annexa-
tion.

At the commencement of 1856, the last year of his rule, he issued orders to General (afterwards Sir James) Outram, then Resident at the Court of Lucknow, to assume the direct administration of Oudh, on the ground that 'the British Government would be guilty in the sight of God and man if it were any longer to aid in sustaining by its countenance an administration fraught with suffering to millions.' The proclamation was issued on the 13th February 1856. The king, Wájid Alí, bowed to irresistible force, although he refused to recognise the justice of his deposition. After a mission to England, consisting of his mother, brother, and son, by way of protest and appeal, he settled down in the pleasant suburb of Garden Reach near Calcutta. There he still lives (1885) in

¹ For the history of Oudh since 1765, and the misrule which compelled its annexation, see article OUDH, *The Imperial Gazetteer of India*.

the enjoyment of a pension of £120,000 a year Oudh was thus annexed without a blow But this measure, on which Lord Dalhousie looked back with the proudest sense of rectitude, was perhaps the one act of his rule that most alarmed native public opinion

The Marquis of Dalhousie resigned office in March 1856, being then only forty four years of age, but he carried home with him the seeds of a lingering illness, which resulted in his death in 1860 Excepting Cornwallis, he was the first, although by no means the last, of English statesmen who have fallen victims to their devotion to India's needs.

Lord Dalhousie's death, 1860

Lord Dalhousie completed the fabric of British rule in India. The Empire as mapped out by Lord Wellesley and Lord Hastings, during the first quarter of the century, had received the addition of Sind in 1843 The Marquis of Dalhousie finally filled in the wide spaces covered by Oudh, by the Central Provinces, and by smaller States within India, together with the great outlying territories of the Punjab on the North Western Frontier, and the richest part of British Burma beyond the sea.

His work in India

The great Governor General was succeeded by his friend Lord Canning, who, at the farewell banquet in England given to him by the Court of Directors, uttered these prophetic words, 'I wish for a peaceful term of office But I cannot forget that in the sky of India, serene as it is, a small cloud may arise, no larger than a man's hand, but which, growing larger and larger, may at last threaten to burst and overwhelm us with ruin' In the following year, the Sepoys of the Bengal army mutinied, and all the valley of the Ganges from Patna to Delhi rose in rebellion

Earl Canning, 1856-62

The Sepoy Mutiny, 1857

The various motives assigned for the Mutiny appear inadequate to the European mind The truth seems to be that native opinion throughout India was in a ferment, predisposing men to believe the wildest stories, and to rush into action in a paroxysm of terror Panic acts on an oriental population like drink among a European mob The annexation policy of Lord Dalhousie, although dictated by the most enlightened considerations, was distasteful to the native mind. The spread of education, the appearance of the steam-engine and the telegraph wire, seemed simultaneous disclosures of a deep plan to substitute an English for an Indian civilisation.

Causes of the Mutiny

The Bengal Sepoys thought that they could see farther than the rest of their countrymen Most of them were Hindus of

Temper of the Sec. 34

high caste ; many of them were recruited from Oudh. They regarded our reforms on Western lines as attacks on their own nationality, and they knew at first hand what annexation meant. They believed it was by their prowess that the Punjab had been conquered, and that all India was held. The numerous dethroned princes, or their heirs and widows, were the first to learn and to take advantage of this spirit of disaffection and panic. They had heard of the Crimean war, and were told that Russia was the perpetual enemy of England. Our munificent pensions had supplied the funds with which they could buy the aid of skilful intriguers. They had much to gain, and little to lose, by a revolution.

The
'greased'
cartridges,
1857.

In this critical state of affairs, of which the Government had scant official knowledge, a rumour ran through the cantonments that the cartridges of the Bengal army had been greased with the fat of cows and pigs. This was affirmed to be part of a general plot by the British Government to destroy the religion alike of the Hindu and of the Muhammadan Sepoy. As a matter of fact, cow's tallow had been culpably and ignorantly used. Steps were taken to prevent the defiling cartridges from reaching the hands and mouths of the native army. But no assurances could quiet the minds of the Sepoys. Fires occurred nightly in the native lines ; officers were insulted by their men ; confidence was gone, and scarcely the form of discipline remained.

The army
drained of
its talent.

The events which followed form contemporary annals. Any narrative of them beyond the barest summary would involve the criticism of measures on which history has not yet pronounced her calm verdict, and would lead to personal praise or blame of still living men.¹ Each episode of the Mutiny is treated in *The Imperial Gazetteer of India*, under the town or District where it occurred. But it may not be out of place to mention here, that the outbreak of the storm found the native regiments denuded of many of their best officers. The administration of the great Empire, to which Dalhousie put the corner-stone, required a larger staff than the civil service could supply. The practice of selecting the ablest military men for civil posts, which had long existed, received a sudden and vast development. Oudh, the Punjab, the Central Provinces, British Burma, were administered to a large extent

¹ The Mutiny of 1857 has already a copious literature. Sir John Kaye's *History of the Sepoy War* (3 vols.), with its able and eloquent continuation by Colonel Malleon, C.S.I., as *The History of the Indian Mutiny* (3 vols.), forms the standard work.

by picked officers from the Company's regiments. Some skilful commanders remained, but the native army had nevertheless been drained of many of its brightest intellects and firmest wills at the very crisis of its fate.

On the afternoon of Sunday, 10th May 1857, the Sepoys at Meerut (Meerath) broke into open mutiny.¹ They burst into the jail, and rushed in a wild torrent through the cantonments, cutting down a few Europeans whom they met. They then streamed off to the neighbouring city of Delhi to stir up the native garrison and the criminal population of that great city, and to place themselves under the authority of the discredited Mughal Emperor. Meerut was the largest military station in Northern India, with a strong European garrison of foot, horse, and guns, sufficient to overwhelm the mutineers before ever they reached Delhi. But as the Sepoys acted in irrational haste so the British officers, in but too many cases, acted with equally irrational indecision. The news of the outbreak was telegraphed to Delhi, and nothing more was done that night. At the moment when one strong will might have saved India, no soldier in authority at Meerut seemed able to think or act. The next morning the Muhammadans of Delhi rose and all that the Europeans there could do was to blow up the magazine.

A rallying centre and a traditional name were thus given to the revolt, which forthwith spread like wild fire through the North Western Provinces and Oudh down into Lower Bengal. The same narrative must suffice for all the outbreaks although each episode has its own story of sadness and devotion. The Sepoys rose on their officers, usually without warning sometimes after protestations of fidelity. The Europeans, or persons of Christian faith, were frequently massacred, occasionally, also, the women and children. The jail was broken open, the treasury plundered and the mutineers marched off to some centre of revolt, to join in what had now become a national war.

In the Punjab the Sepoys were anticipated by measures of repression and disarmament, carried out by Sir John Lawrence and his lieutenants, among whom Edwards and Nicholson stand conspicuous. The Sikh population never wavered. Crowds of willing recruits came down from the Afghan hills. And thus the Punjab, instead of being itself a source of danger, was able to furnish a portion of its own garrison for the siege of Delhi. In Lower Bengal many of the Sepoys mutinied, and then dispersed in different directions. The native armies of Madras and Bombay remained true to their

¹ See article MEERUT, *The Imperial Gazetteer of India*

colours. In Central India, the contingents of some of the great chiefs sooner or later joined the rebels, but the Muhammadan State of Haidarábád was kept loyal by the authority of its able minister, the late Sir Salar Jang.

The main interest of the Sepoy War gathers round the three cities of Cawnpur, Lucknow, and Delhi. Cawnpur contained one of the great native garrisons of India. At Bithúr, not far off, was the palace of Dundhu Panth, the heir of the last Peshwá (*ante*, pp. 324, 402), who had inherited his savings, but had failed to procure a continuance of his pension; and whose more familiar name of Nána Sáhib will ever be handed down to infamy. At first the Nána was profuse in his professions of loyalty: but when the Sepoys at Cawnpur mutinied on the 6th June, he put himself at their head, and was proclaimed Peshwá of the Maráthás.

The Europeans at Cawnpur, numbering more women and children than fighting men, shut themselves up in an ill-chosen hasty entrenchment, where they heroically bore a siege for nineteen days under the sun of a tropical June. Every one had courage and endurance to suffer or to die; but the directing mind was again absent. On the 27th June, trusting to a safe-conduct from the Nána as far as Allahábád, they surrendered, and, to the number of 450, embarked in boats on the Ganges. Forthwith a murderous fire was opened upon them from the river bank. Only a single boat escaped, and but four men, who swam across to the protection of a friendly Rájá, ultimately survived to tell the tale. The rest of the men were massacred on the spot. The women and children, numbering 125, were reserved for the same fate on the 15th July, when the avenging army of Havelock was at hand.¹

Sir Henry Lawrence, the Chief Commissioner of Oudh, had foreseen the storm. He fortified and provisioned the Residency at Lucknow, and thither he retired with all the European inhabitants and a weak British regiment on 2nd July. Two days later, he was mortally wounded by a shell. Whatever opinion may be formed of Sir Henry Lawrence's capacity as a soldier in his one unfortunate engagement, he clearly perceived the main strategic and political points in the struggle. Lawrence had deliberately chosen his position; and the little garrison held out under unparalleled hardships and against enormous odds, until relieved by Havelock and Outram on 25th September. But the relieving force was itself invested by fresh swarms of rebels; and it was not until November that

¹ See article CAWNPUR, *The Imperial Gazetteer of India*.

Sir Colin Campbell (afterwards Lord Clyde) cut his way into Lucknow, and effected the final deliverance of the garrison¹ (16th November 1857). Our troops then withdrew to more urgent work, and did not finally re-occupy Lucknow till March 1858.

The siege of Delhi began on 8th June, one month after the original outbreak at Meerut. Siege in the proper sense of the word it was not, for the British army, encamped on the historic 'ridge,' at no time exceeded 8000 men, while the rebels within the walls were more than 30,000 strong. In the middle of August Nicholson arrived with a reinforcement from the Punjab, but his own inspiring presence was even more valuable than the reinforcement he brought. On 14th September the assault was delivered, and after six days' desperate fighting in the streets, Delhi was again won. Nicholson fell at the head of the storming party. Hodson, the intrepid leader of a corps of irregular horse, hunted down next day the old Mughal Emperor, Bahádur Shah, and his sons. The Emperor was afterwards sent a State prisoner to Rangoon, where he lived till 1862. As the mob pressed in on the guard around the Emperor's sons, near Delhi, Hodson found it necessary to shoot down the princes (who had been captured unconditionally) with his own hand.²

After the fall of Delhi and the final relief of Lucknow, the war loses its dramatic interest, although fighting went on in various parts of the country for eighteen months longer. The population of Oudh and Rohilkhand, stimulated by the presence of the Begam of Oudh, the Nawab of Bareilly, and Áina Sáhib himself, had joined the mutinous Sepoys *en masse*. In this quarter of India alone, it was the revolt of a people rather than the mutiny of an army that had to be quelled. Sir Colin Campbell (afterwards Lord Clyde) conducted the campaign in Oudh, which lasted through two cold seasons. Valuable assistance was lent by Sir Jang Bahádur of Nepal, at the head of his gallant Gurkhas. Town after town was occupied, fort after fort was stormed, until the last gun had been re-captured, and the last fugitive had been chased across the frontier by January 1859.

In the meanwhile, Sir Hugh Rose (afterwards Lord Strathmore), with another army from Bombay, was conducting an equally brilliant campaign in Central India. His most formidable

¹ See article LUCKNOW, *The Internal Gazetteer of India*.

² See article DELHI CITY, *The Internal Gazetteer of India*.

³ See article BAREILLY, *The Internal Gazetteer of India*.

able antagonists were the disinherited Rání or Princess of Jhání, and Tantiá Topí, whose military talent had previously inspired Nána Sáhib with all the capacity for resistance which he ever displayed. The Princess died fighting bravely at the head of her troops in June 1858.¹ Tantiá Topí, after doubling backwards and forwards through Central India, was at last betrayed and run down in April 1859.

Renewals
of the
Company's
Charter,
1813-15.

The Company's charter had been granted from time to time for periods of twenty years, and each renewal had formed an opportunity for a national inquest into the management of India. The Parliamentary Inquiry of 1813 abolished the Company's monopoly of Indian trade, and compelled it to direct its energies in India to the good government of the people. The Charter Act of 1833 did away with its remaining Chinese trade, and opened up administrative offices in India to the natives, irrespective of caste, creed, or race. The Act of 1853 abolished the patronage by which the Company filled up the superior or covenanted branch of its civil service. It laid down the principle that the administration of India was too national a concern to be left to the chances of benevolent nepotism; and that England's representatives in India must be chosen openly, and without favour, from the youth of England.

Its
privileges
curtailed.

Downfall
of the
Company,
1858.

The Mutiny sealed the fate of the East India Company, after a life of more than two and a half centuries. The original Company received its charter of incorporation from Elizabeth in 1600. Its political powers, and the constitution of the Indian Government, were derived from the Regulating Act of 1773, passed by the Ministry of Lord North. By that statute the Governor of Bengal was raised to the rank of Governor-General; and, in conjunction with his Council of four other members, he was entrusted with the duty of superintending and controlling the Governments of Madras and Bombay, so far as regarded questions of peace and war: a Supreme Court of Judicature was appointed at Calcutta, to which the judges were appointed by the Crown: and a power of making rules, ordinances, and regulations was conferred upon the Governor-General and his Council. Next came the India Bill of Pitt (1784), which founded the Board of Control, strengthened the supremacy of Bengal over the other Presidencies, and first authorized the historical phrase, 'Governor-General-in-Council.'

Its history
epito-
mized,
1773-1858.

Act of
1784.

The new Charter Act which abolished the Company's

¹ See article JHANSI, *The Imperial Gazetteer of India*.

Chinese trade in 1833 introduced successive reforms into the constitution of the Indian Government. It added to the Council a Law member who need not be chosen from among the Company's servants, and was entitled to be present only at meetings for making Laws and Regulations. It accorded the authority of Acts of Parliament to the Laws and Regulations so made, subject to the disallowance of the Court of Directors. It appointed a Law Commission and it gave the Governor General in Council a control over the other Presidencies, in all points relating to the civil or military administration. The Charter of the Company was renewed for the last time in 1853 not for a definite period of years but only for so long as Parliament should see fit. On this occasion the number of Directors was reduced and as above stated, their patronage in regards appointments to the covenanted civil service was taken away to make room for the principle of open competition.

The Act for the better government of India (1858) which finally transferred the entire administration from the Company to the Crown, was not passed without an eloquent protest from the Directors, nor without acrimonious party discussion in Parliament. It enacts that India shall be governed by and in the name of the Queen of England through one of her principal Secretaries of State assisted by a Council of fifteen members. The Governor General received the new title of Viceroy. The European troops of the Company, numbering about 24 000 officers and men were amalgamated with the royal service, and the Indian navy was abolished. By the Indian Councils Act (1861) the Governor General's Council and also the Councils at Madras and Bombay were augmented by the addition of non official members either natives or Europeans for legislative purposes only. By another Act also passed in 1861 High Courts of Judicature were constituted out of the old Supreme Courts at the Presidency towns.

It fell to the lot of Lord Canning both to suppress the Mutiny, and to introduce the peaceful revolution which followed. It suffices to say that he preserved his equanimity unruffled in the darkest hours of peril, and that the strict impartiality of his conduct incurred alternate praise and blame from partisans of both sides. The epithet then scornfully levelled at him of 'Clemency' Canning, is now remembered only to his honour. On 1st November 1858, at a grand *darb* held at Allahabad, he published the Royal Proclamation, which announced that

the Queen had assumed the government of India. This document, which is, in the truest and noblest sense, the Magna Charta of the Indian people, proclaimed in eloquent words a policy of justice and religious toleration; and granted an amnesty to all except those who had directly taken part in the murder of British subjects. Peace was proclaimed throughout India on the 8th July 1859. In the following cold weather, Lord Canning made a viceregal progress through the northern Provinces, to receive the homage of loyal princes and chiefs, and to guarantee to them the right of adoption.

Cost of the Mutiny. The suppression of the Mutiny increased the debt of India by about 40 millions sterling, and the military changes which ensued augmented the annual expenditure by about 10 millions. To grapple with this deficit, a distinguished political economist and parliamentary financier, Mr. James Wilson, was sent out from England as financial member of Council. He re-organized the customs system, imposed an income-tax and a licence duty, and created a State paper currency. He died in the midst of his splendid task; but his name still lives as that of the first and greatest finance minister of India. The Penal Code, originally drawn up by Macaulay in 1837, passed into law in 1860; together with Codes of Civil and Criminal Procedure in 1861.¹

Financial reforms.

Legal reforms.

Lord Canning left India in March 1862, and died before he had been a month in England. His successor, Lord Elgin, only lived till November 1863. He expired at the Himálayan station of Dharmśálá, and there he lies buried.

Lord Elgin, 1862-63.

He was succeeded by Sir John (afterwards Lord) Lawrence, the saviour of the Punjab. The chief incidents of Lord Lawrence's rule were the Bhután war, followed by the annexation of the Bhután Dwárs in 1864, and the terrible Orissa famine of 1866.

Lord Lawrence, 1864-69.

In a later famine in Bundelkhand and Upper Hindustán in 1868-69, Lord Lawrence laid down the principle, for the first time in Indian history, that the officers of the Government would be held personally responsible for taking every possible means to avert death by starvation. An inquiry was conducted into the status of the peasantry of Oudh, and an Act was passed with a view to securing them in their customary rights. After a period of fratricidal war among the sons of Dost Muhammad, the Afghán territories were concentrated in the

Events of his Vice-royalty.

¹ On the subject of Anglo-Indian Codification, *Vide ante*, chap. iv.

hands of Sher Ali, and the latter was acknowledged as Amir by Lord Lawrence. A commercial crisis took place in 1866, which seriously threatened the young tea industry in Bengal, and caused widespread ruin in Bombay. Sir John Lawrence retired in January 1869 after having passed through every grade of Indian service, from an assistant magistracy to the viceroyalty. On his return to England he was raised to the peerage. He died in 1879 and lies in Westminster Abbey.

Lord Mayo succeeded Lord Lawrence in 1869 and urged India on the material progress of India. The Amila *darbâr*, 1869-72 at which Sher Ali was recognised as Amir of Afghanistan, although in one sense the completion of what Lord Lawrence had begun owed its success to Lord Mayo. The visit of His Royal Highness the Duke of Edinburgh in 1869-70 gave great pleasure to the natives of India and introduced a tone of personal loyalty into our relations with the feudatory princes.

Lord Mayo reformed several of the great branches of the administration: created an Agricultural Department, and introduced the system of Provincial Finance. The impulse to local self-government given by the last measure has done much, and will do more to develop and husband the revenues of India, to quicken the sense of responsibility among the English administrators, and to awaken political life among the people. Lord Mayo also laid the foundation for the reform of the Salt Duties. He thus enabled his successors to abolish the old pernicious customs lines which walled off Province from Province and strangled the trade between British India and the Feudatory States. He developed the material resources of the country by an immense extension of roads, railways and canals, thus carrying out the beneficent system of Public Works which Lord Dalhousie had inaugurated. Lord Mayo's splendid vigour defied alike the routine and the vast tasks which he imposed on himself. He personally studied with his own eyes the wants of the far Provinces of the Empire. Put his life of noble labours was cut short by the hand of an assassin, in the course of his tour of the Andaman Islands in 1872.

His successor was Lord Northbrook, who had a prominent scope in the department of finance.

It would be unsuitable for an officer of the Government to do anything beyond the latest summary of the state of the country.

viceroyalty, a famine which threatened Lower Bengal in 1874 was successfully obviated by a vast organization of State relief; the Maráthá Gáekwár of Baroda was dethroned in 1875 for misgovernment and disloyalty, but his dominions were continued to a child selected from the family; and the Prince of Wales made a tour through the country in the cold weather of 1875-76. The presence of His Royal Highness evoked a passionate burst of loyalty never before known in the annals of British India. The feudatory chiefs and ruling houses of India felt for the first time that they were incorporated into the Empire of an ancient and a splendid dynasty.

Prince of
Wales'
tour, 1875-
1876.

Lord
Lytton,
1876-80.
The
'Empress
of India.'

Famine of
1877-78.

Lord Lytton followed Lord Northbrook in 1876. On January 1, 1877, Queen Victoria was proclaimed Empress of India at a *darbár* of unparalleled magnificence, held in the old Delhi cantonment behind the historic 'ridge'—the 'ridge' from which in 1857 the British had reconquered the revolted Mughal capital. But while the princes and high officials of the country were flocking to this gorgeous scene, the shadow of famine was darkening over Southern India. Both the monsoons of 1876 had failed to bring their due supply of rain, and the season of 1877 was little better. This long-continued drought stretched from the Deccan to Cape Comorin, and subsequently invaded Northern India, causing a famine more widespread than any similar calamity since 1770. Despite vast importations of grain by sea and rail, despite the most strenuous exertions of the Government, which incurred a total expenditure on this account of 11 millions sterling, the loss of life from actual starvation and its attendant train of diseases was lamentable. The deaths from want of food, and from the diseases incident to a famine-stricken population, were estimated at $5\frac{1}{4}$ millions.

Afghán
affairs,
1878-81.

In the autumn of 1878, the affairs of Afghánistán again forced themselves into notice. Sher Alí, the Amír, who had been hospitably entertained by Lord Mayo, was found to be favouring Russian intrigues. A British embassy was refused admittance to the country, while a Russian mission was received with honour. This led to a declaration of war. British armies advanced by three routes—the Khaibar (Khyber), the Kuram, and the Bolán; and without much opposition occupied the inner entrances of the passes. Sher

Lord Mayo in 1872. The four Viceroys who have ruled during the past fourteen years, are, happily, still living; their policy forms the subject of keen contemporary criticism; and the administrators, soldiers, and diplomatists who gave effect to that policy still hold possession of the scene.

All fled to Afghán Turkistán, and there died. A treaty was entered into with his son, Yakub Khán, at Gandamak, by which the British frontier was advanced to the crests or further sides of the passes, and a British officer was admitted to reside at Kabul. Within a few months the British Resident, Sir Louis Cavagnari, was treacherously attacked and massacred together with his escort and a second war became necessary. Yakub Khán abdicated, and was deported to India.

At this crisis of affairs a general election in England resulted in a defeat of the Conservative Ministry. Lord Lytton resigned simultaneously with the Home Government and the Marquis of Ripon was nominated as his successor in April 1880. In that year a British brigade received a defeat between Kandahár and the Helmand river from the Herát troops of Ayub Khán. A defeat promptly and completely retrieved by the brilliant march of General Sir Frederick Roberts from Kabul to Kandahár and by the total rout of Ayub Khán's army on 1st September 1880. Abdurrahman Khán the eldest male representative of the stock of Dost Muhammad, was recognised by us as Amir. The British forces retired from Kabul leaving him as our friend in possession of the capital. The withdrawal of our troops from Kandahar was also effected. Soon afterwards Ayub Khán advanced with an army from Herat defeated the Amir Abdurrahman's troops and captured Kandahár. His success was short lived. The Amir Abdurrahman marched south with his forces from Kabul completely routed Ayub Khán, re-occupied Kandahár, and still reigns as undisputed Amir of Afghánistán (1886). In 1884, a Boundary Commission was appointed with the consent of the Amir to settle in conjunction with Russian Commissioners the north western frontier of Afghánistan.

Marquis of
Ripon
1880-81

Afghan
affairs
1880-84

The Native State of Mysore, which had been administered by the British on behalf of the Hindu ruling family since 1831 was replaced under its hereditary dynasty on the 25th March 1881.

Mysore
1881

During the remaining years of Lord Ripon's administration (1881-84) peace was maintained in India. The Viceroy took advantage of this lull to carry out certain important reforms in the internal government of the country. The years 1882-84 will be memorable for these great measures. By the repeal of the Vernacular Press Act, he set free the native journals from the last restraints on the free discussion of public questions.

Lord
Ripon's
internal
admin's
1881-84

Local
Govern-
ment Acts.

His scheme of local self-government developed the municipal institutions which had been growing up since India passed to the Crown. By a series of enactments, larger powers of local self-government were given to rural and urban boards, and the elective principle received a wider application. Where rural boards did not exist, he endeavoured to utilize the local materials available for their formation; and from this point of view he may be said to have extended the principle of local self-government from the towns to the country. Where rural boards already existed he increased their powers; and as far as possible sought to give them a representative basis.

Amend-
ment of
Criminal
Procedure.

An attempt to extend the jurisdiction of the rural criminal courts over European British subjects, independently of the race or nationality of the presiding judge, excited strong public feeling, and ended in a compromise. The principle was asserted in regard to native officers belonging to the Superior Civil Service who had attained to a certain standing, namely District Magistrates and Sessions Judges. At the same time the European community received a further extension of trial by jury, which enables European British subjects to claim a jury, if they see fit to do so, in nearly all cases before the District criminal tribunals.

Depart-
ment of
Agri-
culture,
1881-84.

One of the earliest acts of Lord Ripon's viceroyalty was the re-establishment of the Department of Revenue and Agriculture in accordance with the recommendation of the Famine Commission. This department had been originally instituted by Lord Mayo; but some years after his death, its functions had been distributed between the Finance and Home Departments. It was now reconstituted substantially on its former basis, as a distinct secretariat of the Government of India. It at once took up the recommendations of the Famine Commission; both those bearing on famine relief, and those dealing with organic reforms in the administration of the land revenue. Agricultural improvements, exhibitions of Indian produce, whether in India or in Europe, and works elucidating the raw produce of the country, received its special attention. Its reforms in the administration of the land revenue were largely directed to prevent re-settlements in temporarily settled districts from bearing too heavily on the cultivators. Such re-settlements are in future, except in special cases, to avoid re-measurement and vexatious inquisitions, and are to leave to the landlord or husbandman the entire profits accruing from improvements carried out by himself.

Revenue
reforms.

Henceforth, an enhancement of the land revenue is to be

made mainly on the grounds (1) of a rise in prices (2) of an increase in the cultivated area, and (3) of improvements which have been made at the expense of the Government. The Agricultural Department superintends a variety of important operations bearing on the development of the country and the welfare of the people, in such matters as irrigation, the meteorological service, the extension of agriculture, and the statistical collection.

Lord R. ... Commission with Education
view to ... on a broader basis Comm
This Com ... d collecting data sion 1882-
throughout ... of India, reported 1883.
in 1883 ... Resolution of the
Governor ... encouraging all
grades of ... for the advance of
primary ins ... higher education
The Recomm ... and the Govern
ment Res ... encouragement to the
indigenous ... Provinces had not previously
received a ... the State Department of
Public In ...

The Commission strongly affirmed the principle of extension of high schools and colleges and of the duty of assisting primary education and Municipal funds. They endeavoured to extend in sections of the people particularly the Masses who for various causes had left themselves fully of the system of public instruction in regard to whom the system had proved defective. The general effect of the Commission's labours and of the Government Resolution was to give a more liberal recognition to the school and to schools and colleges conducted by the State.

In 1881 Lord Ripon's Finance Ministry took off the import duties on iron and steel with thereby almost the whole import of iron and steel in India, with the exception, such as those on arms, liquors, &c. In 1884 a committee of the House of Commons reported on railway extension in India, and made recommendations in a Parliamentary Report on the agricultural population in Bengal.

Bill, regulating the relations of landlord and tenant in Bengal, almost ready to be passed by his successor.

Earl of
Dufferin,
1884.

The Marquis of Ripon retired from the viceroyalty at the end of 1884, and was succeeded by the Earl of Dufferin. In the spring of 1885, Lord Dufferin passed the Bengal Tenancy Bill through its final stage in the Legislature; and held a Darbár at Rawál Píndi for the reception of the Amír of Afghánistán. The result of the meeting was to strengthen the British relations with that ruler.

Burmese
affairs,
1885.

During the summer of the same year, 1885, the hostile attitude of the king of Independent Burma forced itself upon the attention of the British Government. After repeated but fruitless remonstrances, a British expedition was despatched from Bengal and Madras to Rangoon. It advanced up the Irawadi valley (November–December 1885), and occupied Mandalay, the capital of Independent Burma. King Thebau, who had inaugurated his reign by a family massacre, and had steadily refused to redress the wrongs of certain British subjects whom he had injured, remained defiant. He vainly sought aid against the English from foreign powers. In the end he surrendered, almost without a blow, was dethroned, and deported for safe custody to British India. The authority of the Viceroy of India was substituted for that of King Thebau throughout Upper Burma by Proclamation on the 1st January 1886. In February 1886, Lord Dufferin proceeded in person to Burma, to settle the administration of the new British Province. As all pacific proposals were rejected, a military force under General Prendergast moved up the Irawadi in a flotilla of steamers. The opposition encountered was insignificant. On November 28 the capital of Mandalay was occupied without fighting; King Thebau surrendered, and was sent as a prisoner to Rangoon.

CHAPTER XVI

BRITISH ADMINISTRATION OF INDIA

THE Act of 1858 which transferred India from the Company to the Crown also laid down the scheme of its government. Under the Company the Governor-General was an autocrat, responsible only to the distant Court of Directors. The Court of Directors had been answerable to the shareholders or Court of Proprietors on the one hand and, through the Board of Control, to the Sovereign and to Parliament on the other. The Act of 1858 did away with these intermediary bodies between the Governor-General and the British Ministry. For the Court of Directors, the Court of Proprietors, and the Board of Control it substituted a Secretary of State aided by a Council appointed by the Crown.

The Secretary of State for India is a Cabinet Minister who comes into and goes out of office with the other members of the Ministry. His Council was originally appointed for life. Its members are now appointed for ten years only¹ but may be re-appointed for another five years for special reasons. The Secretary of State rules in all ordinary matters through the majority of his Council. But in affairs of urgency, and in questions which belong to the Secret Department including political correspondence, he is not required to consult his Council. The Viceroy or Governor-General is appointed by the Crown, and resides in India. His ordinary term of office is five years.

The supreme authority in India is vested by a series of Acts of Parliament in the Viceroy or Governor-General in Council, subject to the control of the Secretary of State in England. Every executive order and every legislative statute runs in the name of the 'Governor-General in Council,' but in

¹ Under 32 and 33 Vict. c. 97.

² The chief of these Acts are 13 Geo. III. c. 63, 33 Geo. III. c. 52, 3 and 4 Will. IV. c. 85, 21 and 22 Vict. c. 106, and 24 and 25 Vict. c. 67.

³ A style first authorized by 33 Geo. III. c. 52, sec. 39.

certain cases,¹ a power is reserved to the Viceroy to act independently. The Governor-General's Council is of a two-fold character.

Executive Council.

First, the ordinary or Executive Council,² usually composed of about six official members besides the Viceroy, which may be compared with the cabinet of a constitutional country. It meets regularly at short intervals, usually once a week, discusses and decides upon questions of foreign policy and domestic administration, and prepares measures for the Legislative Council. Its members divide among themselves the chief departments of State, such as those of Foreign Affairs, Finance, War, Public Works, etc. The Viceroy combines in his own person the duties of constitutional Sovereign with those of Prime Minister;³ and has usually charge of the Foreign Department. As a rule, the Viceroy is himself the initiating Member of Council for Foreign and Feudatory Affairs.

Legislative Council.

Second,⁴ the Legislative Council, which is made up of the same members as the preceding, with the addition of the Governor of the Province in which it may be held; certain officials selected by the Governor-General from Bengal, Madras, Bombay, or other Provinces; and nominated members, representative of the non-official Native and European communities. The official additional members thus appointed to the Legislative Council must not exceed in number the non-officials, and the total of the additional members must not exceed twelve. The meetings of the Legislative Council are held when and as required, usually once a week. They are open to the public; and a further guarantee for publicity is ensured by the proviso that draft Bills must be published a

¹ 'Cases of high importance, and essentially affecting the public interest and welfare' (33 Geo. III. c. 52, sec. 47); 'when any measure is proposed whereby the safety, tranquillity, or interests of the British possessions in India may, in the judgment of the Governor-General, be essentially affected' (3 and 4 Will. IV. c. 85, sec. 49); 'cases of emergency' (24 and 25 Vict. c. 67, sec. 23).

² This is the lineal descendant of the original Council organized under the charters of the Company, first constituted by Parliamentary sanction in 1773 (13 Geo. III. c. 63, sec. 7).

³ The mechanism and working of the Governor-General's Council, and of the Secretariats, and chief Departments of the Indian Administration, are described in Hunter's *Life of the Earl of Mayo*, vol. i. pp. 189-202 (2nd ed.)

⁴ Originally identical with the Executive Council, upon which legislative powers were conferred by 13 Geo. III. c. 63, sec. 36. The distinction between the two Councils was first recognised in the appointment of 'the fourth member' (3 and 4 Will. IV. c. 85, sec. 40).

certain number of times in the *Gazette*. As a matter of practice, these draft Bills have usually been first subjected to the criticism of the several Provincial governments. Provincial Legislative Councils have also been appointed for the Presidencies of Madras and Bombay, and for the Lieutenant Governorship of Bengal. The members of these local Legislative Councils are appointed, in the case of Madras and Bombay, by the Governors of those Provinces, and in Bengal, by the Lieutenant Governor subject to the approval of the Governor General. The Acts of these Provincial Legislative Councils, which can deal only with provincial matters, are subject to sanction by the Governor General.

The Presidencies of Madras and Bombay and the Lieutenant Governorships of Bengal and of the North Western Provinces have each a High Court supreme both in civil and criminal business, but with an ultimate appeal to the Judicial Committee of the Privy Council in England. Of the minor Provinces, the Punjab has a Chief Court with three judges, the Central Provinces and Oudh have each a Judicial Commissioner, who sits alone. British Burma has a Judicial Commissioner and a Recorder. In this Province the Judicial Commissioner has jurisdiction over the territory outside Rangoon (save that in cases of European British subjects the Recorder has the powers of a High Court). The Recorder has jurisdiction in the town of Rangoon and in all criminal cases in any part of Burma where the accused are European British subjects. The Judicial Commissioner and the Recorder of Rangoon sit together as a Special Court for certain purposes. Appeals from the Recorder of Rangoon in civil suits where the subject matter ranges from Rs. 3000 to Rs. 10,000, lie to the High Court at Calcutta. The latter Court also decides references from the 'Special Court' of Rangoon when the members are equally divided in opinion. For Assam, the High Court at Calcutta is the highest judicial authority, except in the three Hill Districts namely the Garo Hills, the Khasi and Jaintia Hills, and the Nagá Hills. In these Districts the Chief Commissioner of Assam is judge without appeal in civil and criminal matters. Special rules apply to the Districts bordering on Bhutan.

The law administered in the Indian Courts consists mainly of—(1) the enactments of the Indian Legislative Councils (Imperial and Provincial), as above described, and of the bodies

The law
of British
India.

¹ Constituted out of the Supreme Courts and the Sudder (Sadar) Courts in 1861 (24 and 25 Vict. c. 104).

which preceded them; (2) statutes of the British Parliament which apply to India; (3) the Hindu and Muhammadan laws of inheritance, and their domestic law, in causes affecting Hindus and Muhammadans; (4) the Customary Law affecting particular castes and races. Much has been done towards consolidating special sections of the Indian law;¹ and in the Indian Penal Code, together with the Codes of Civil and Criminal Procedure, we have memorable examples of such efforts.

But although the Governor-General-in-Council is theoretically supreme over every part of India alike,² his actual authority is not everywhere exercised in the same direct manner. For ordinary purposes of administration, British India is partitioned into Provinces, each with a government of its own; and certain of the Native States are attached to those Provinces with which they are most nearly connected geographically. These Provinces, again, enjoy various degrees of independence. The two Presidencies of Madras and Bombay, including Sind, retain many marks of their original equality with Bengal. They each have an army and a civil service of their own. They are each administered by a Governor appointed direct from England. They have each an Executive and a Legislative Council, whose functions are analogous to those of the Councils of the Governor-General, although subject to his control.³ They thus possess a domestic legislature; and in administrative matters, also, the interference of the Governor-General-in-Council is sparingly exercised.

Of the other Provinces, Bengal, or rather Lower Bengal, occupies a peculiar position. Like the North-Western Provinces and the Punjab, it is administered by a single official with the style of Lieutenant-Governor, who is controlled by no Executive Council; but, unlike those two Provinces, Bengal has a Legislative Council, so far preserving a sign of its early pre-eminence. The other Northern Provinces, Assam, Oudh, and the Central Provinces, whether ruled by a Lieutenant-Governor or a Chief Commissioner, may be regarded from a historical point of view as fragments of the original Bengal Presidency,⁴ which, as thus defined, would be co-extensive with all British India not included under Madras or Bombay. Garrisons on the Madras or Bombay establishment may be posted in out-

¹ *Ante*, chap. iv. p. 117.

² 3 and 4 Will. IV. c. 85, secs. 39 and 65.

³ 24 and 25 Vict. c. 67, sec. 42.

⁴ See article BENGAL PRESIDENCY, *The Imperial Gazetteer of India*.

lying tracts of the old Bengal territories, but civil officers of the Madras and Bombay Services are excluded. The Lieutenant Governors and most of the Chief Commissioners are chosen from the Covenanted Civil Service. In executive matters they are the practical rulers, but excepting the Lieutenant Governor of Bengal, they have no legislative authority.

To complete the total area of territory under British administration, it is necessary to mention besides Bengal the North Western Provinces, the Punjab, Oudh and Assam, certain *quasi* Provinces under the immediate control of the Viceroy. These are—BRITISH BURMA, part of which was annexed in 1826 and part in 1852; the CENTRAL PROVINCES, leased in 1853; ASSAM, annexed in 1826; AJMER, transferred from Rajputana; BERRAR, of the Districts assigned by the Nizam of Hyderabad for the support of the Hyderabad Contingent and the little territory of COOR, in the extreme south.¹ The State of Mysore was under British administration from 1831 to 1881, when it was restored to its native Rājā on his attaining his majority.

Another difference of administration, although now of less importance than in former times, derives its name from the old Regulations or laws and judicial rules of practice which preceded the present system of Acts of the Legislature. From these Regulations certain tracts of country have been from time to time exempted—tracts which, owing to their backward state of civilisation or other causes, seemed to require exceptional treatment. In non Regulation territory, broadly speaking, a larger measure of discretion is allowed to the officials, both in the collection of revenue and in the administration of civil justice, strict rules of procedure yield to the local exigencies, and the judicial and executive departments are to a great extent combined in the same hands.

A wider field is also permitted for the selection of the administrative body, which is not entirely confined to the Covenanted Civil Service but includes military officers on the staff and also uncovenanted civilians. The title of the highest executive official in a District of a Regulation Province is that of Collector Magistrate. In a non Regulation District, the corresponding officer is styled the Deputy Commissioner, and the supreme authority in a non Regulation Province (with the exception of the Punjab) is called, not a Lieutenant Governor, but a Chief Commissioner. The Central Provinces, Assam,

¹ For the constitution of each of these Provinces see the parts I & II in *The Imperial Gazetteer of India*.

and British Burma are examples of non-Regulation Provinces ; but non-Regulation Districts are to be found also in Bengal and the North-Western Provinces. Their existence is always disclosed by the term 'Deputy Commissioner' as the title of the chief executive officer of the District.

The 'District' or territorial unit.

Alike in Regulation and in non-Regulation territory, the unit of administration is the District—a word of very definite meaning in official phraseology. The District officer, whether known as Collector-Magistrate or as Deputy Commissioner, is the responsible head of his jurisdiction. Upon his energy and personal character depends ultimately the efficiency of our Indian Government. His own special duties are so numerous and so various as to bewilder the outsider ; and the work of his subordinates, European and native, largely depends upon the stimulus of his personal example. His position has been compared to that of the French *préfet* ; but such a comparison is unjust in many ways to the Indian District officer. He is not a mere subordinate of a central bureau, who takes his colour from his chief, and represents the political parties or the permanent officialism of the capital. The Indian Collector is a strongly individualized worker in every department of rural well-being, with a large measure of local independence and of individual initiative.

The District Officer or 'Collector-Magistrate.'

As the name of Collector-Magistrate implies, his main functions are two-fold. He is a fiscal officer, charged with the collection of the revenue from the land and other sources ; he also is a revenue and criminal judge, both of first instance and in appeal. But his title by no means exhausts his multifarious duties. He does in his smaller local sphere all that the Home Secretary superintends in England, and a great deal more ; for he is the representative of a paternal and not of a constitutional government. Police, jails, education, municipalities, roads, sanitation, dispensaries, the local taxation, and the imperial revenues of his District, are to him matters of daily concern. He is expected to make himself acquainted with every phase of the social life of the natives, and with each natural aspect of the country. He should be a lawyer, an accountant, a surveyor, and a ready writer of State papers. He ought also to possess no mean knowledge of agriculture, political economy, and engineering.

Duties of the 'Collector-Magistrate.'

Number of Districts in British India.

The total number of Districts in British India is about 235. They vary greatly in size and number of inhabitants. The average area is 3840 square miles, ranging from 14,115 square

miles in Sind (Karachi), 12,045 square miles in Bengal (Lohar daga), and 11,885 square miles in the Central Provinces (Rupur), down to 937 square miles in the North Western Provinces (Tarai), 957 square miles in Madras (Nilgiris), and 989 square miles in Oudh (Lucknow). The average population is 800,723 souls, similarly ranging from 3,051,916 in Bengal (Maimansingh), 2,617,120 in the North Western Provinces (Gorakhpur) and 2,365,035 in Madras (Malabar), down to 91,034 in Madras (Nilgiris), 144,070 in the North Western Provinces (Dehra) and to 231,341 in the Central Provinces (Nimar). Districts from their extreme smallness, or other circumstances which render them quite exceptional—such as the little hill District of Simla, the backward and only partially inhabited tract of Northern Arakan, the Calcutta Suburban District of Howrah,—are not included in the above. The Madras Districts are on an average, the most extensive in area and the most populous. In every other Province but Madras, the Districts are grouped into larger areas, known as Divisions, each under the charge of a Commissioner. But these Divisions are not properly units of administration, as the Districts are. They are aggregates of units formed only for convenience of supervision, so that an intermediate authority may exercise the universal watchfulness which would be impossible for a distant Lieutenant Governor.

The Districts are again partitioned out into lesser tracts, called Subdivisions in Bengal, *taluks* in Madras and in Bombay, and *taluks* in Northern India generally. These Subdivisions are the primary units of fiscal administration. The *thand* or police circle is the unit of police administration over the whole of British India.

The preceding sketch of Indian administration would be incomplete without a reference to the Secretariat, or central bureau of each Province, which controls and gives unity to the whole. From the Secretariat are issued the orders that regulate or modify the details of administration, into the Secretariat come the multifarious reports from the local officers, to be there digested for future reference. But although the Secretaries may enjoy the social life of the Presidency capitals, with higher salaries and better prospects of promotion, the efficiency of our rule rests ultimately upon the shoulders of the District officers, who bear the burden and heat of the day, with fewer opportunities of winning fame or reward. The Secretariat of the Supreme Government of India consists of

of the local government. seven branches, each of which deals with a special department of the administration. The officers who preside over them are named respectively, the Foreign Secretary, the Home Secretary, the Secretary in the Department of Revenue and Agriculture, the Financial Secretary, the Military Secretary, the Public Works Secretary, and the Secretary in the Legislative Department. In the Presidencies, Lieutenant-Governorships, and Chief-Commissionerships, the Provincial Secretariat is formed on the same model, but the Secretaries are only from one to three or four in number.

Land-Tax. **THE LAND-TAX.**—The land furnishes the chief source of Indian revenue, and the collection of the land-tax forms the main work of Indian administration. No technical term is more familiar to Anglo-Indians, and none more obscure to the English public, than that of 'land settlement.' Nor has any subject given rise to more voluminous controversy. It will here suffice to explain the general principles upon which the system is based, and to indicate the chief differences in their application to the several Provinces. That the State should appropriate to itself a share of the produce of the soil, is a maxim of finance which has been recognised throughout the East from time immemorial. The germs of rival systems in India can be traced in the survival of military and other service tenures, and in the poll-tax of Assam and Burma.

Land Settlement.

Ancient land system of India. The early development of the Indian land system was due to two conditions,—a comparatively high state of agriculture, and an organized plan of administration,—both of which were supplied by the primitive Hindu village community. During the lapse of generations, despite domestic anarchy and foreign conquest, the Hindu village preserved its customs, written on the imperishable tablets of tradition. In the ancient Hindu village community, the land was held, not by private owners, but by occupiers under the village corporation: the revenue was due, not from individuals, but from the village community represented by its head-man. The harvest of the hamlet was dealt with as a common fund; and before the general distribution, the head-man was bound to set aside the share of the king. No other system of taxation could be theoretically more just, or in practice less obnoxious, to a primitive people. This ancient land system may still be found in parts of India, both under British and native rule; and it prevailed almost universally before the Muhammadan conquest.

The Musalmáns brought with them the avarice of conquerors,

and a stringent system of revenue collection. Under the ^{Mughal} Empire, as organized by Akbar the Great, the share ^{land tax} of the State was fixed at one third of the gross produce of the soil, and an army of tax collectors intervened between the cultivator and the supreme government. The vocabulary of our own land system is borrowed from the Mughal administration. The *zamindár* himself is a creation of the ^{The} Muhammadans, unknown to the early Hindu system. He ^{was not} was originally a mere tax collector, or farmer of the land revenue, who agreed to pay a lump sum from the tract of country assigned to him. But the Hindu chief or local mag- ^{His two} nate was often accepted by the Mughals as the *zamindár*, or ^{fold on} revenue contractor, for the lands under his control. In this way, the Indian *zamindars* as a body are of mixed origin, and represent in some cases not merely an official status but hereditary rights. If the Hindu village system may be praised for its justice, the Mughal farming system had at least the merit of efficiency. Shah Jahán and Aurangzeb, as we have seen,¹ extracted a larger land revenue than we obtain at the present day.

When the responsibility of governing the country was first ^{The Com} undertaken by the East India Company, an attempt was made ^{to try & eff} to understand the social system upon which the payment of land revenue was based. Elaborate orders were issued to this end in 1769, but the Company's servants were too engrossed with conquest, with the 'annual investment,' and with their private trade, to find time for minute inquiries into the rights of the peasantry. The *zamindár* was conspicuous and useful, ^{The} the village community and the cultivating *ryot* did not force ^{will for} themselves into notice. The *zamindár* seemed a solvent ^{male} person, capable of keeping a contract, and his official position ^{land} as tax collector was confused with the proprietary rights of an English landlord. In Bengal, the *zamindár*, under the Permanent Settlement of 1793, was raised to the status of proprietor, holding at a quit rent payable to the State, fixed in perpetuity. In Madras, under the *ryotwari* system of holding, direct from the State, and in most other parts of India, the actual cultivator has been raised to the same status, subject also to a quit rent, fixed at intervals of thirty years. The aim of ^{Growth of} the British authorities has everywhere been to establish private ^{property} property in the soil, consistently with the punctual payment of the revenue.

The annual Government demand, like the succession duty in

¹ This subject has been fully discussed in the chapter on the Mughal Empire. See also pp. 298, 299, 303, 311, etc.

The English revenue officers adhere to the old theory of a third of the produce, but they make so many deductions in favour of the peasant, as to reduce the Government share in practice to about one seventeenth. This question will be discussed in some detail in dealing with the general comparison of English and Mughal taxation. It must here suffice to say that the Famine Commissioners, the only body who have had the whole evidence before them estimate the land tax throughout British India 'at from 3 per cent to 7 per cent of the gross out turn'. The old native basis of division, although retained in name in some Provinces, has disappeared in practice. Instead of the ruling power taking from 33 to 60 per cent, the average land tax of the British Government throughout India is, according to the Famine Commissioners, only 5½ per cent of the produce of the fields.

The means by which the land revenue is assessed is known as *The Final Settlement*, and the assessor is styled a *Settlement Officer*. In Lower Bengal, the assessment existing in 1793 was declared to be fixed in perpetuity, but throughout the greater part of India the process is ever going on. The details vary in the different Provinces, but, broadly speaking a Settlement may be described as the ascertainment of the agricultural capacity of the land. Prior to the Settlement is the work of a Village Survey, which determines the area of every village and its rule, of every field. Then comes the Settlement Officer, whose duty it is to estimate the character of the soil, the kind of crop, the opportunities for irrigation, the present means of communication, their probable development, and all other circumstances which tend to affect the value of the land and its produce. With these facts before him, he proceeds to assess the Government demand upon the land, according to certain general principles, which may vary in the several Provinces. The final result is a Settlement Report, which records, as in a Domesday Book, the whole agricultural statistics concerning the District.

LOWER BENGAL, and a few adjoining Districts of the North Western Provinces and of Madras, enjoy a Permanent Settlement, i.e. the land revenue has been fixed in perpetuity. When the Company obtained the *diwani* or financial administration of Bengal in 1765, the theory of a Settlement, as described above was unknown. The existing Muhammadan system was adopted in its entirety. Engagements, sometimes yearly, sometimes for a term of years were entered into with the *zamindars*.

a subject of competition among the cultivators, the tenant found himself unprovided with any legal provisions to enable him to resist rack rents. He could only plead ancient but undefined custom: the landlord could urge a proprietary right, based on express sections of the law. The result was a gradual decadence of peasant right during the sixty-five years following the Permanent Settlement of 1793.

The *zamindār* was the revenue-paying unit recognised by the Permanent Settlement. But in a large number of cases the *zamindār* has in effect parted with all his interest in the land, by means of the creation of perpetual leases or *fatnis*. These leases are usually granted in consideration of a lump sum paid down and an annual rent. The *fatmidar* may in turn create an indefinite series of sub-tenures, such as *dar fatnis*, *se fatnis*, etc., beneath his own tenure, and between himself and the actual cultivator. Inter
mediate
tenure
holder.

It has been mentioned that the Permanent Settlement of 1793 was not preceded by any systematic survey. But in the course of the past thirty years, Lower Bengal has been subjected to a professional survey which determined the boundaries of every village, and issued maps on the scale of four inches to the mile. This survey, however, has only a topographical value. Few statistical inquiries were made, and no record obtained of rights in the soil. Even the village landmarks then set up have been suffered to fall into decay. It was not until 1869 that a Statistical Survey of Bengal was, after several costly failures dating as far back as 1769 and 1807, organized on an efficient basis. Imperfect
survey of
Bengal The work was conducted to a successful issue during the ten following years (1869 to 1879), and the results of the survey were published in twenty-two volumes, containing a systematic account of each of the sixty Districts of Bengal and Assam, with their 74 millions of people. Statistical
Survey

By two stringent Regulations in 1799 and 1812, the tenant was placed at the mercy of a rack-renting landlord. If he failed to pay his rent, however excessive, his property was rendered liable to distraint, and his person to imprisonment. At the same time, the operation of the revenue sale law had introduced a new race of *zamindārs*, who were bound to their tenants by no traditions of hereditary sympathy, but whose sole object was to make a profit out of their newly purchased property. The rack-rented peasantry found little protection in our courts until 1859, when an Act was passed which considerably restricted the landlords' powers of enhancement in certain specified cases. Cultivators
oppressed
1799 1812

Law of Law
of 1859

demanding an increased rent from such tenant, and the tenant preferred to leave rather than submit to the enhancement, then the landlord would have to pay to him—first, a substantial compensation for disturbance, and second, a substantial compensation for improvements

Compensation for disturbance

The proposals of the Commissioners were partially, but only partially, embodied in the Bengal Tenancy Act of 1885

Finally, after a long and acrimonious discussion, a Rent Law for Bengal, substantially based upon the Report of the Commission of 1879, was passed in the present year (1885)

Rent Law of 1885

The Permanent Settlement was confined to the three Provinces of Bengal, Behar, and Orissa, according to their boundaries at that time. Orissa proper, which was conquered from the Marathas in 1803, is subject to a temporary Settlement, of which the current term of thirty years will not expire until 1897. The assessment is identical with that fixed in 1838, which was based upon a careful field measurement and upon an investigation into the rights of every landholder and under tenant. The Settlement, however, was made with the landholder, and not with the tenant, and in practice the rights of the cultivators are on the same footing as in Bengal

Orissa Settlement 1803-97

In Assam Proper, or the Brahmaputra valley, the settlement is simple and effective. The cultivated area is artificially divided into *mauzas* or blocks, over each of which is placed a native official or *mauzadar*. Every year the *mauzadar* ascertains the area actually under cultivation and then assesses the fields, according to their character at a prescribed rate.

Assam Settlement 1817

The prevailing system throughout the Madras Presidency is the *ryotwari*, which takes the cultivator or peasant proprietor as its rent-paying unit, as the Bengal system takes the *zamindar*. This system cannot be called indigenous to the country, any more than the *zamindari* is to Bengal. When the British declared themselves heir to the Nawab of the Karnatik at the beginning of the present century they had no adequate experience of revenue management. The authorities in England favoured the *zamindari* system already at work in Bengal,—a system which appeared best calculated to secure prompt payment. The Madras Government was accordingly induced to enter into permanent engagements with *zamindars*, where no *zamindars* could be found, to create substitutes of enterprising contractors. The attempt resulted in utter failure, except in tracts where the *zamindars* happened to be representatives of ancient lines or powerful chiefs. Several chiefs exist in the extreme south and in the north of the

Madras Settlement system

Madras Settlement system

Land
reform of
1859.

The Land Law of 1859 divided the cultivators into four classes:—First, those who had held their holdings at the same rates since 1793. It ordained that the rents of such tenants should not be raised at all. Second, those who had held their land at the same rent for 30 years. It ordained that such tenants should be preserved as if they had held since 1793, unless the contrary was proved. Third, those who had held for 12 years. To them it gave a right of occupancy,

demanding an increased rent from such tenant, and the tenant preferred to leave rather than submit to the enhancement, then the landlord would have to pay to him—first, a substantial compensation for disturbance, and second, a substantial compensation for improvements. Compensation for disturbance

The proposals of the Commissioners were partially, but only partially, embodied in the Bengal Tenancy Act of 1885

Finally, after a long and acrimonious discussion, a Rent Law for Bengal, substantially based upon the Report of the Commission of 1879, was passed in the present year (1885) Rent Law of 1885

The Permanent Settlement was confined to the three Provinces of Bengal, Behar, and Orissa, according to their boundaries at that time Orissa proper, which was conquered from the Marathas in 1803, is subject to a temporary Settlement, of which the current term of thirty years will not expire until 1897 The assessment is identical with that fixed in 1838 which was based upon a careful field measurement and upon an investigation into the rights of every landholder and under tenant The Settlement, however, was made with the landholder, and not with the tenant, and in practice the rights of the cultivators are on the same footing as in Bengal. Orissa Settlement 1803-85

In Assam Proper, or the Brahmaputra valley, the settlement is simple and effective The cultivated area is artificially divided into *mauzás* or blocks, over each of which is placed a native official or *mauzadár* Every year the *mauzadár* ascertains the area actually under cultivation, and then assesses the fields, according to their character, at a prescribed rate Assam Settlement yearly

The prevailing system throughout the Madras Presidency is the *rājatū rī*, which takes the cultivator or peasant proprietor as its rent paying unit, as the Bengal system takes the *zamindār* This system cannot be called indigenous to the country, any more than the *zamindārī* is to Bengal When the British declared themselves heir to the Nawab of the Karnatik at the beginning of the present century, they had no adequate experience of revenue management The authorities in England favoured the *zamindārī* system already at work in Bengal,—a system which appeared best calculated to secure punctual payment The Madras Government was accordingly instructed to enter into permanent engagements with *zamindars* and where no *zamindars* could be found, to create substitutes out of enterprising contractors The attempt resulted in utter failure, except in tracts where the *zamindars* happened to be the representatives of ancient lines or powerful chiefs Several such chiefs exist in the extreme south and in the north of the Rajatu ri Settlement in Madras

Presidency. Their estates have been guaranteed to them on payment of a *peshkash* or permanent tribute, and are saved by the custom of primogeniture from the usual fate of sub-division. Throughout the rest of Madras, the influence of Sir Thomas Munro led to the adoption of the *ráyatwárá* system, which will always be associated with his name.

According to this system, an assessment is made with the cultivator for the land actually taken for cultivation. Neither *samíndár* nor village community intervenes between the cultivator and the State. The early *ráyatwárá* settlements in Madras were based upon insufficient experience. They were preceded by no survey, and they had to adopt the crude estimates of native officials. Since 1858, a department of Revenue Survey has been organized, and the assessment carried out *de novo*.

Nothing can be more complete in theory than a Madras *ráyatwárá* settlement. First, the area of the entire District, whether cultivated or uncultivated, and of each field within the District, is accurately measured. The next step is to calculate the estimated produce of each field, having regard to every kind of both natural and artificial advantage. Lastly, an equitable rate is fixed upon every field. The elaborate nature of these inquiries and calculations may be inferred from the fact that as many as 35 different rates are sometimes struck for a single District, ranging from as low as 6d. to as high as £1, 4s. per acre. The rates thus ascertained by the revenue survey are fixed for a term of thirty years.

But during that period the aggregate rent-roll of a District is liable to be affected by several considerations. New land may be taken up for cultivation, or old land may be abandoned; and occasional remissions may be permitted under no fewer than eighteen specified heads. Such matters are decided by the Collector at the *jamábandí*, or inquest held every year for ascertaining the amount of revenue to be paid by each *ráyat* for the current season. This annual inquiry has sometimes been mistaken for a yearly re-assessment of the *ráyat's* holding. It is not, however, a change in the rates for the land which he already holds, but an inquiry into and record of the changes in his holding, or of any new land he may wish to take up.

Certain of the Madras Districts on the seaboard adjoining Bengal were granted on a Permanent Settlement to *samíndárs*, hereditary native chiefs or revenue-farmers. The land thus permanently settled forms one-eighth of the area of

Sir
Thomas
Munro,
1820.

Madras
method of
assess-
ment :

first,
measure-
ment ;
second,
estimate of
produce ;
third,
fixing the
rates.

Thirty
years'
settlement.

Madras
yearly
jamábandí.

Permanent
Settlement
in Madras.

Madras. Thus, not the other way as by the ordinary theory, the Government has raised the culture of it on a peasant proprietor. This person will improve the natural fertility of the soil. But as population increased under British rule, the value of the land rose and the peasant proprietor has in many cases been able to sublet his holding to poorer cultivators, and thus to live, in whole or part, off the rent. The Government has, during the same period decreased rather than increased its average land tax per acre throughout the Madras Presidency. For as the people multiplied, they were forced back upon inferior soil, and the average Government demand per acre has been proportionately diminished. But the very same process of falling back on the inferior soils has, according to economical principles, created the possibility of levying a rent from the superior soils. This rent is enjoyed by the former cultivators, many of whom are thus growing into petty lardholders, living upon the rent of fields which their fathers tilled with their own hands.

An idea of the increase of population in Madras, and of the extension of cultivation, may be obtained from the following figures — In 1853, the general population was estimated at 22 millions, in 1878, at 31½ millions, showing an increase of 43 per cent, or nearly one half, and in 1881 (after the great famine of 1876-78), at a little over 31 millions. The cultivated land, held by husbandmen direct from the State, had, between 1853 and 1878, increased from 12 to 20 millions of acres, or 66 per cent, exactly two thirds. The area of tillage had, therefore, not only kept pace with the increase of population, but had extended at a ratio of 50 per cent more rapidly. This resulted partly from the fact that the inferior lands, now reclaimed, could not support so large an average of people as the superior lands which were already in cultivation at the commencement of the period. The Government recognised this, and has accordingly increased its rental only from 3 millions to 3½ millions sterling, being only 26 per cent, or one fourth, while the area of cultivation has increased by 66 per cent. The Government, in fact, has reduced its average rental over the total area of cultivation from 5s an acre in 1853 to 3s 10d an acre in 1878, or over 23 per cent, say one fourth. According to the ordinary theory of rent, rates should have risen enormously during that period, and they have risen enormously wherever the land is held by private proprietors.

As regards the Madras Presidency, the following table shows

Reduction of average land-tax. lated thus. During the 25 years ending 1878, the area of cultivation had increased by 66 per cent., or two-thirds; the population by 43 per cent., or nearly one-half; and the Government rental by only 26 per cent., or one-fourth; while the average rates of land-tax per cultivated acre had been actually reduced by about one-fourth, from 5s. an acre in 1853 to 3s. 10d. an acre in 1878, and to 3s. 8d. an acre in 1883. Instead of taking advantage of the increase of population to enhance the rental, the Madras Government has realized the fact that the increase in numbers means a harder struggle for life, and has reduced instead of enhancing, according to the economic laws of rent, the average rates throughout its domains.

Land system of Bombay. Bombay has also a land system of its own, which requires to be distinguished from the *rāyatwārī* of Madras, although resembling it in principle. In the early days of our rule, no regular method existed throughout the Bombay Presidency; and at the present time there are tracts where something of the old confusion survives. The modern

The 'survey tenure' of Bombay. 'survey tenure,' as it is called, dates from 1838, when it was first introduced into one of the *tāluks* of Poona District: it has since been gradually extended over the greater part of the Presidency. As its name implies, the Settlement is preceded by survey. Each field is measured, and an assessment placed upon it according to the quality of the soil and the crop. This assessment holds good for a term of thirty years. The ordinary rates vary in different Districts from 4s. 6d. an acre in the rich black-soil lands of Gujarāt, to 10d. an acre in the hills of the Konkan.

Its rates. Its simplicity. The primary characteristic of the Bombay system is its simplicity. The Government fixes a minimum area as the revenue assessment unit, below which it refuses to recognise sub-divisions. This minimum area, technically called a 'field,' varies from 20 acres upwards, in different Bombay Districts. The 'field' is therefore the unit, and its actual occupier is the only person recognised by the revenue law. He knows exactly what he will have to pay, and the State knows what it will receive, during the currency of the term. The assessment is, in fact, a quit-rent liable to be modified at intervals of thirty years. The Bombay system is also characterized by its fairness to the tenant. He possesses 'a transferable and heritable property, continuable without question at the expiration of a settlement lease, on his consenting to the revised rate.' To borrow a metaphor from English law, his position has been raised from that of a villein to that of a copyholder.

In place of the bare permission to occupy the soil, he has received a right of property in it.

Some of the Bombay peasants have proved unequal to the responsibilities of property which they had not won by their own exertions. In rich districts, the men who were recorded as the actual occupiers are able to let their land to poorer cultivators, and so live off the toil of others upon fields which they themselves had formerly to till. But these proprietary rights give the peasant a power of borrowing which he did not possess before. In certain parts especially in the dry Districts of the high lying Deccan the husbandmen have got hopelessly into debt to the village bankers. The peasant was often improvident the seasons were sometimes unfortunate the money lender was always severe.

Amid the tumults of native rule the usurers lent comparatively small sums. If the peasant failed to pay they could not evict him or sell his holding. Because among other reasons, there was more land than there were people to till it. The native Government moreover could not afford to lose a tenant. Accordingly the bankrupt peasant went on year after year, paying as much interest as the money lender could squeeze out of him until the next Maratha invasion or Muhammadan rebellion swept away the whole generation of usurers, and so cleared off the account. Under our rule there is no chance of such relief for insolvent debtors and our rigid enforcement of contracts together with the increase of the population, has armed the creditor with powers formerly unknown.

For the peasant's holding under the British Government has become a valuable property and he can be readily sold out, as there are always plenty of husbandmen anxious to buy in. The result is twofold. In the first place, the village banker lends larger sums for the security is increased, and in the second place he can push the peasantry to extremities by eviction, a legal process which was economically impossible, and politically impermissible under native rule.

In Bengal, the cry of the peasant is for protection against the landlord. In South western India it is for protection against the money lender. After a careful inquiry, the Government determined to respond to that cry. It has practically said to the village bankers 'A state of things has grown up under British rule which enables you to push the cultivators, by means of our Courts, to extremities unknown under the native dynasties, and repugnant to the customs of India. Henceforth, in considering the security on which you lend money

please to know that the peasant cannot be imprisoned or sold out of his farm to satisfy your claims; and we shall free him from the lifelong burden of those claims by a mild bankruptcy law.' Such is the gist of the Southern India Agriculturists' Relief Acts of 1879 and 1881.

Its provisions for the husbandman; This Act of 1879 provides, in the first place, for small rural debtors of £5 and under. If the Court is satisfied that such a debtor is really unable to pay the whole sum, it may direct the payment of such portion as it considers that he can pay, and grant him a discharge for the balance. The Act gives powers to the Court to go behind the letter of the bond, to cut down interest, and to fix the total sum which may seem to the judge to be equitably due.

As a rural Insolvency Act. To debtors for amounts exceeding £5, it gives the full protection of an Insolvency Act. No agriculturist shall henceforth be arrested or imprisoned in execution of a decree for money. In addition to the old provisions against the sale of the necessary implements of his trade, no agriculturist's immoveable property shall be attached or sold in execution of any decree, unless it has been specifically mortgaged for the debt to which such decree relates. But even when it has been specifically mortgaged, the Court may order the debtor's holding to be cultivated, for a period not exceeding seven years, on behalf of the creditor, after allowing a sufficient portion of it for the support of the debtor and his family. At the end of the seven years, the debtor is discharged.

Rural Insolvency Procedure. If the debtor himself applies for relief under the Insolvency clauses, the procedure is as follows:—His moveable property, less the implements of his trade, are liable to sale for his debts. His immoveable property, or farm, is divided into two parts, one of which is set aside as 'required for the support of the insolvent and members of his family dependent on him,' while the remainder is to be managed on behalf of his creditors. But 'nothing in this section shall authorize the Court to take into possession any houses or other buildings belonging to, and occupied by, an agriculturist.' Village arbitrators or 'conciliators' are appointed by the same Act, and every creditor must first try to settle his claims before them. If the effort at arbitration fails, the 'conciliator' shall give the applicant a certificate to that effect. No such suit shall be entertained by any Civil Court, unless the plaintiff produces a certificate from the local 'conciliator' that arbitration has been attempted and failed. The Act of 1879 has been somewhat modified by the amending Act of 1881.

'Conciliators.'

The North Western Provinces and the Punjab have practically one land system. In those parts of India, the village community has preserved its integrity more completely than elsewhere. Government therefore recognises the village, and not the *zamindar's* estate or the *raja's* field, as the unit of land administration. The village community takes various forms. Sometimes it holds all the village lands in joint-ownership, the share of each co-owner being represented by a fractional part of the gross rental. Sometimes part of the lands is held in common and part in severalty, while sometimes no common lands remain although a joint responsibility for the Government revenue still subsists.

The Settlement in the North Western Provinces and the Punjab is more comprehensive than in Madras or Bombay. In addition to measurement and agricultural assessment it includes the duty of drawing up an exhaustive record of all rights and sub-tenures existing in every village. The proprietors are alone responsible for the revenue, but while the State limits its claims against them, it defines the rights of all other parties interested in the soil. The term of settlement in the North Western Provinces and in the Punjab is thirty years. The principle of assessment is that the Government revenue shall be equal to one half of the rent leaving the other half as the share of the landlord who is liable for due payment and has the trouble of collecting it from the cultivator. The average rate of assessment is 35-50 per acre in the North Western Provinces and 25 in the Punjab. This is at the nominal conversion of 10 rupees to the pound sterling. At the actual value of the rupee (1885) the rates would be 25-70 in the North Western Provinces, and 15-60 in the Punjab per acre.

Oudh, the Indian Province most recently acquired has a land peculiar land system, arising out of its local history. The Oudh *tilukdars* resemble English landlords more closely even than do the *zamindars* of Bengal. In origin, they were not revenue-farmers but territorial magnates whose influence was derived from feudal authority, military command, or hereditary sway. Their present status dates from the pacification after the Mutiny of 1857. The great *tilukdars* were then invited to become responsible each for a gross sum for the estates which they were found to hold prior to our annexation of Oudh. The exceptional position of the *tilukdars* was recognised by conferring upon them, not only the privilege of succession by primogeniture, but also the power of bequest by will—a land right unknown alike to Hindu and Muhammadan law. Land

not comprised in *tálukdárí* estates was settled in the ordinary way with its proprietors or *zamíndárs* for a term of thirty years. The whole of Oudh has since been accurately surveyed.

Land
system of
Central
Provinces.

The Central Provinces contain many varieties of land tenure, from the feudatory chiefs, who pay a light tribute, to the village communities, who are assessed after survey. Population is sparse and agriculture backward, so that the incidence of land revenue is everywhere low. The survey was conducted generally on the Punjab system, adopting the 'estate' as the unit of assessment. But in the Central Provinces the British Government gave proprietary rights to the former revenue-farmers, or fiscal managers of villages, under native rule. It thus created a body of landholders between itself and the cultivators. Of the rental paid by the husbandmen, the Government ordinarily takes one-half as land-tax, and allows one-half to the proprietary body. The current settlement, for a term of thirty years, will expire in 1897.

Land
revenue
of British
India.

The gross land revenue realized from territory under British administration in India, amounted to £21,876,067 in 1882-83. During the ten years ending 1882-83, it averaged £21,283,764, which is raised to about 22 $\frac{3}{4}$ millions by the inclusion of certain local rates and cesses levied on land. This latter figure shows an average of a fraction less than 10d. per cultivated acre. The average annual cost of collecting the land revenue during the ten years ending 1882-83 was £2,945,151, or close on three millions sterling. The highest average rate of assessment estimated per head, is in Bombay, namely, 3s. 10 $\frac{1}{4}$ d. per head of population; the lowest, 1s. 2 $\frac{1}{2}$ d. per head, in Bengal and Assam. The *net* land revenue realized from British India, deducting charges of collection, during the ten years ending March 1883, averaged 18 $\frac{1}{3}$ millions sterling. In 1882-83, the land revenue of British India was 21 $\frac{3}{4}$ millions *gross*, and 18 $\frac{3}{4}$ millions *net*.¹

Salt
admini-
stration.

Sources
of salt.

THE SALT DUTY.—Salt ranks next to land revenue among the items of actual taxation in India; opium being excluded, as paid by the Chinese consumer. Broadly speaking, the salt consumed in India is derived from four sources—(1) importation by sea, chiefly from the mines of Cheshire; (2) solar evaporation in shallow tanks along the seaboard; (3) gatherings from the Salt Lakes in Rájputána; (4) quarrying in the Salt Hills of the Northern Punjab. Until recently, the tax

¹ Parliamentary Return.

THE SALT DUTY

and upon salt varied very much in different parts of the country, and a numerous preventive staff was stationed along continuous barrier hedge, which almost cut the peninsula into two fiscal sections. The reforms of Sir J Strachey in 1878, by which the Equalization of salt duty higher rates were reduced while the lower rates were raised, and their subsequent equalization over the whole country, have effectually abolished this engine of oppression. Communication is now free and it has been found that prices are lowered by thus bringing the consumer nearer to his market, even though the rate of taxation be increased. In the Punjab and Rajputana salt administration has become, as in Lower Bengal a simple matter of weighing quantities and levying a uniform tax. In Bombay also the manufacture is now conducted with a minimum of expense at large central depots in Gujarat (Guzerat) under a thorough system of exercise supervision. Along the eastern coast however from Orissa to Cape Comorin the process of evaporating sea water is carried on as a private industry although under official supervision and on Government account.

The process of manufacture in Madras is exceedingly simple and at the same time free from temptations to smuggling. The Process of manufacture season lasts from about January to July in which latter month the downpour of rain usually puts a stop to operations. A site is selected in the neighbourhood of one of the back waters or inlets which abound along the coast. Before commencing, the proprietor of the salt pan must each year obtain the consent of the Collector of the District and must engage to supply a certain quantity of salt. The first step is to form a series of pans or reservoirs of varying degrees of shallowness by banking up the earth with interconnecting channels. Into the outer and deepest of these pans the sea water is baled by means of a lever and bucket lift, and there allowed to stand for some days until it has by evaporation acquired the consistency of brine. The brine is then passed through the channels into the remainder of the series of gradually shallowing pans. At last it becomes crystallized salt, and is scraped off for conveyance to the wholesale depot. It is estimated that, in a favourable season this process may be repeated *de novo* from twelve to fifteen times, according as the weather permits. But a single shower of rain will spoil the whole operation at any stage.

Like the poppy cultivation in Bengal, the manufacture of salt in Madras is a monopoly, which can be defended by the

not comprised in *tálukdárí* estates was settled in the ordinary way with its proprietors or *zamíndárs* for a term of thirty years. The whole of Oudh has since been accurately surveyed.

Land
system of
Central
Provinces.

The Central Provinces contain many varieties of land tenure, from the feudatory chiefs, who pay a light tribute, to the village communities, who are assessed after survey. Population is sparse and agriculture backward, so that the incidence of land revenue is everywhere low. The survey was conducted generally on the Punjab system, adopting the 'estate' as the unit of assessment. But in the Central Provinces the British Government gave proprietary rights to the former revenue-farmers, or fiscal managers of villages, under native rule. It thus created a body of landholders between itself and the cultivators. Of the rental paid by the husbandmen, the Government ordinarily takes one-half as land-tax, and allows one-half to the proprietary body. The current settlement, for a term of thirty years, will expire in 1897.

Land
revenue
of British
India.

The gross land revenue realized from territory under British administration in India, amounted to £21,876,067 in 1882-83. During the ten years ending 1882-83, it averaged £21,283,764, which is raised to about 22 $\frac{3}{4}$ millions by the inclusion of certain local rates and cesses levied on land. This latter figure shows an average of a fraction less than 10d. per cultivated acre. The average annual cost of collecting the land revenue during the ten years ending 1882-83 was £2,945,151, or close on three millions sterling. The highest average rate of assessment estimated per head, is in Bombay, namely, 3s. 10 $\frac{1}{4}$ d. per head of population; the lowest, 1s. 2 $\frac{1}{2}$ d. per head, in Bengal and Assam. The *net* land revenue realized from British India, deducting charges of collection, during the ten years ending March 1883, averaged 18 $\frac{1}{3}$ millions sterling. In 1882-83, the land revenue of British India was 21 $\frac{3}{4}$ millions *gross*, and 18 $\frac{3}{4}$ millions *net*.¹

Salt
admini-
stration.

Sources
of salt.

THE SALT DUTY.—Salt ranks next to land revenue among the items of actual taxation in India; opium being excluded, as paid by the Chinese consumer. Broadly speaking, the salt consumed in India is derived from four sources—(1) importation by sea, chiefly from the mines of Cheshire; (2) solar evaporation in shallow tanks along the seaboard; (3) gatherings from the Salt Lakes in Rájputána; (4) quarrying in the Salt Hills of the Northern Punjab. Until recently, the tax

¹ Parliamentary Return.

THE SALT DUTY

ed upon salt varied very much in different parts of the untry, and a numerous preventive staff was stationed along continuous barrier hedge, which almost cut the peninsula to two fiscal sections

The reforms of Sir J Strachey in 1878, by which the higher rates were reduced while the lower rates were raised, and their subsequent equalization over the whole country, have effectually abolished this engine of oppression. Communication is now free and it has been found that prices are lowered by thus bringing the rate of taxation nearer to his market, even though the rate of taxation be increased. In the Punjab and Rajputana salt administration has become, as levying a uniform tax. In Bombay also the manufacture is now conducted with a minimum of expense at large central depots in Gujarat (Guzerat) under a thorough system of excise supervision. Along the eastern coast however from Orissa to Cape Comorin the process of evaporating sea water is carried on as a private industry although under official supervision and on Government account.

The process of manufacture in Madras is exceedingly simple and at the same time free from temptations to smuggling. The season lasts from about January to July, in which latter month the downpour of rain usually puts a stop to operations. A site is selected in the neighbourhood of one of the back waters or inlets which abound along the coast. Before commencing, the proprietor of the salt pan must each year obtain the consent of the Collector of the District and must engage to supply a certain quantity of salt. The first step is to form a series of pans or reservoirs of varying degrees of shallowness by banking up the earth with interconnecting channels. Into the outer and deepest of these pans, the sea water is baled by means of a lever and bucket lift and there allowed to stand for some days until it has by evaporation acquired the consistency of brine. The first step is through the channels into the remainder of the series of gradually shallowing pans. At last it becomes crystallized salt, and is scraped off for conveyance to the wholesale depot. It is estimated that, in a favourable season this process may be repeated *de novo* from twelve to fifteen times, according as the weather permits. But a single shower of rain will spoil the whole operation at any stage.

Like the poppy cultivation in Bengal, the manufacture of salt in Madras is a monopoly, which can be defended by the

Working of the monopoly in Madras. circumstances of the case. No one is compelled to manufacture, and rights of property in a salt-pan are strictly respected; while the State endeavours, by means of a careful staff of supervisors, to obtain the maximum of profit with a minimum of interference. The system as at present carried on has been gradually developed from the experience of nearly a century. The manufacturers belong to the same class as the ordinary cultivators; and, as a rule, their condition is somewhat more prosperous, for they possess a hereditary privilege carrying with it commercial profits. They do not work upon a system of advances, as is the case with so many other Indian industries; but they are paid at a certain rate when they bring their salt to the Government depôt. This rate of payment, known as *kudivaram*, is at present fixed at an average of 1 *ánna* 5·8 *pies* (or about 2½d.) per *maund* of 82½ lbs.; the other expenses of the Salt Department for supervision, etc., raise the total cost to 3 *ánna*s 5·6 *pies* (or about 5¼d.) per *maund*. The price charged to the consumer by the Madras Government, up to March 1882, was Rs. 2. 8. (or about 5s.) per *maund*, the balance being net profit.

Cost of salt in Madras.

Duty of salt.

Equalization of duty. The equal rate of salt duty which now prevails throughout all continental India is Rs. 2 per *maund*, or 5s. 5d. a cwt. In British Burma, only 3 *ánna*s per *maund*, or 6d. a cwt., are charged for local consumption, and a transit duty of 1 per cent. *ad valorem* for salt sent across the frontier. In the salt tracts on the west of the Indus, excluding the Kalábágh mines, a special rate of 8 *ánna*s per local *maund* of 103 lbs. is charged. The total salt revenue of British India in 1882–83 was returned at £6,177,781, the average for ten years being £6,627,194.

Excise administration. EXCISE DUTIES in India are not a mere tax levied through the private manufacturer and retailer, but (like salt) a species of Government monopoly. The only excisable articles are intoxicants and drugs; and the object of the State is to check consumption, not less than to raise revenue. The details vary in the different Provinces, but the general plan of administration is the same. The right to manufacture, and the right to retail, are both monopolies of Government, let out to private individuals upon strict conditions. Distillation of country spirits is permitted under two systems—either to the highest bidder under official supervision; or only upon certain spots set apart for the purpose. The latter is known as the *sadr* or central distillery system. The right of sale is also farmed out to the

Central distillery system.

highest bidder, subject to regulations fixing the quantity of Rice beer liquor that may be sold at one time. The brewing of beer from rice and other grains, a process universal among the hill tribes and other aboriginal races, is practically untaxed and unrestrained. The numerous European breweries at the hill stations pay a tax at the rate of 6d a gallon. A large business in brewing is now done at Simla, Marri (Murree), Kasauli, Massuri, Naini Tal, Solin, and in the Nilgiris. An attempt is being made to establish breweries on the plains.

Excise duties are also levied upon the sale of a number of intoxicating or stimulant drugs, of which the most important are opium and *ganja* or *bhang*. Opium is issued for local consumption in India from the Government mint-tories at Patná and Benares, and sold through private retailers at a monopoly price. This drug is chiefly consumed in Assam, Burma, and the Punjab. *Ganja* is an intoxicating preparation made from the flowers and leaves of Indian hemp (*Cannabis sativa*, var *mata*). The cultivation of hemp for this purpose is chiefly confined to a limited area in Rujshahi District, Bengal, and to the inner valleys of the Himalayas, whence the drug is imported under the name of *charas*. Its use is a frequent cause, not only of crime, but also of insanity. Government attempts to check consumption—first, by fixing the retail duty at the highest rate that will not encourage smuggling, and second, by continually raising that rate as experience allows. Strictly speaking, *ganja* consists of the flowering and fruiting heads of the female plant, *bhang* or *siddhi*, of the dried leaves and small stalks, with a few fruits, while *charas* is the resin itself, collected in various ways as it naturally exudes.

No duty is at present levied upon tobacco in any part of British India. The plant is universally grown by the cultivators for their own smoking, and, like everything else, was subject to taxation under native rule, but the impossibility of accurate excise supervision has caused the British Government to abandon this impost. The total excise revenue of British India in 1882-83 was returned at £3,609,561, the average for ten years being £2,774,073.

THE MUNICIPALITIES at present existing in India are a creation of the Legislature; indeed, a recent branch of our system of administration. Their origin is to be traced, not to the native *panchayat*, but to the necessity for relieving the District officer from some of the details of his work. The

The old
'Council
of Five';

panchayat or elective Council of Five is one of the institutions most deeply rooted in the Hindu mind. By it the village community was ruled, the head-man being only its executive official, not the legislator or judge. By it caste disputes were settled; by it traders and merchants were organized into powerful guilds, to the rules of which even European outsiders have had to submit. By a development of the *panchayat*, the Sikh army of the *khálsá* was despotically governed, when the centralized system of Ranjít Singh fell to pieces at his death.

Muni-
cipalities
succeed it.

The village organization was impaired or broken up under Mughal rule. Municipal institutions have gradually developed in place of the old Hindu mechanism of rural government, which had thus worn out or disappeared. Police, roads, and sanitation are the three main objects for which a modern Indian municipality is constituted. In rural tracts, these departments are managed (in different Provinces) by the Collector, or by one of his subordinate staff, or by a Local Fund Board. Within municipal limits, they are delegated to a Committee, who, until lately, derived their practical authority from the Collector's sanction, implied or expressed. Except in the larger towns, the municipalities can scarcely be said as yet to exhibit the attributes of popular representation or of vigorous corporate life. But the Local Government Acts, passed during Lord Ripon's Viceroyalty (*ante*, p. 428), have given a new impulse to the rural and municipal boards. As education advances, they will doubtless be further developed.

Municipal
statistics.
1877-83.

In 1876-77, excluding the three Presidency capitals, there were altogether 894 municipalities in British India, with 12,381,059 inhabitants, or just 7 per cent. of the total population. Out of an aggregate number of 7519 members of municipal committees, concerning whom information is available, 1794 were Europeans and 5725 natives; 1863 were *ex-officio*, 4512 were nominated by Government, and 1144 elected, the last class being almost confined to the North-Western and Central Provinces. The financial statistics of these municipalities are given in a later section of this chapter.

In 1882-83, the municipalities in British India, exclusive of the three Presidency cities, numbered 783, with 12,923,494 inhabitants. The passing of the Local Self-Government Acts (1882-84) has extended the elective principle, in a larger or smaller measure, all over India. The three great municipalities in the Presidency towns of Calcutta, Madras, and Bombay administered a population in 1877 of 1½ million. Their governing bodies aggregated 176 members, of

INDIAN FINANCE.

122 were natives. Eighty of the members were elected ratepayers. In 1882-83, the municipalities of Calcutta, Bombay, and Madras governed a population of $1\frac{1}{2}$ million, members of the three municipal bodies numbered 171, of whom 93 were elected.

FINANCE — It is difficult to present a view of Indian Imperial finance, which shall be at once concise and intelligible. The subject is full of controversies, and obscured by different

1. Note on Indian Statistics

It may here be convenient to explain the considerations which have led to the selection of the years for which statistics are given in this and the following chapters. The Indian returns are rendered with great promptitude by the Government of India in India itself. But these returns deal with a dozen Provinces and Administrations covering an area equal to Europe less Russia. A considerable interval necessarily elapses between the local issue of the returns by the Indian Government and their final compilation and revision for Parliamentary purposes. During this revision, the totals are frequently altered owing to inter-provincial adjustments and other operations of account. The final presentation to Parliament is, however, the only authoritative English source of Indian statistics. It has therefore been adopted so far as possible in the present work. The latest return, in its final shape, as presented to both Houses of Parliament by command of Her Majesty, which has reached the author before the sheets went to press in the summer of 1885, is the Blue Book entitled the *Statistical Abstract relating to British India from 1873-74 to 1882-83*. This admirable compilation of Mr. Charles Prinsep, Statistical Reporter in the India Office, has therefore been accepted as fixing the period to which information should be brought down in the present work — namely, the 31st March 1885.

But the present author has also been guided in his selection of dates by other considerations—(1) The only two Census enumerations of the Indian population as a whole were taken respectively in 1872 and in 1881. These years are, therefore the two great landmarks in Indian statistics. (2) The first edition of the present work took the year 1877, or in some cases 1878, as the latest period for which the final presentment of Indian statistics was available when it was written. The author has felt that it may be convenient to enable the reader to compare the progress during the quinquennial interval (1878 to 1883). He has therefore, in most cases, given the two sets of figures for 1877-78 and 1882-83. (3) In some departments it has been found practicable to bring down the final figures to 1884, and even to March 1885. This has only been done when it seemed to the author that the later statistics were required to exhibit really salient facts. In conclusion, the author begs it will be believed that in each case careful consideration has been devoted to the selection of the years for which the statistics are given. The individual considerations in different departments are too numerous to specify. It should always be remembered that the final presentment to Parliament of Indian statistics and accounts, available to the author when the sheets went to the press, refers to the decade ending 1882-83.

presentments of the same sets of accounts. In the first place, the aggregate revenue and expenditure are officially returned according to a system which, although necessary for Indian purposes, is apt to mislead the English critic. The Indian Government is not a mere tax-collecting agency, charged with the single duty of protecting person and property. Its system of administration is based upon the view that the British power is a paternal despotism, which owns, in a certain sense, the entire soil of the country, and whose duty it is to perform the various functions of a wealthy and an enlightened proprietor. It collects its own rents. It provides, out of its own capital, facilities for irrigation, means of communication, public buildings, schools, and hospitals. It also takes on itself the businesses of a railway owner, and of a manufacturer on a grand scale, in the case of opium and salt. These departments swell the totals on both sides of the balance-sheet with large items, neither of the nature of taxation nor of administrative expenditure.

Its ob-
scurities.

The 'busi-
ness' of
the Indian
Govern-
ment.

Changes
in system
of account.

In the second place, the methods of keeping the Indian public accounts have been subjected to frequent changes during recent years, to such an extent as to vitiate all comparative statements for long periods of time. The commercial traditions, inherited from the days of the Company, regulated the Indian accounts until about the year 1860. From that date efforts have been made to bring the methods of Indian accounting into conformity with the English system of public accounts. It results that the same entries represent different facts at different periods. Thus, under the Company, the items usually represented the *net* sums; they now represent the gross sums. At one period, the gross receipts are shown, with a *per contra* for the charges of collection or for refunds. At another time, important classes of charges have been transferred from the Imperial to the Provincial Budgets, to be brought back again after an interval of a few years to the Imperial Budget, and again transferred to Local Finance. Capital expenditure on public works, at one period charged to current revenue, is at another period excluded, as being 'extraordinary' or 'reproductive.'

The result-
ing ob-
scurities.

The entire net income of the railways, whether the property of the State or of guaranteed companies, has now been entered as Imperial revenue, and the interest to shareholders as Imperial expenditure. The Indian accounts represent, therefore, not only the Indian taxation and the cost of administration. They represent the trade expenses and profits of the Government as a great railway owner, canal maker, opium manufacturer, salt

ment in and the same would show that also represents the gross and even the net revenue as an account of different periods.

The following pages will first endeavour to exhibit the actual taxation of British India, as compared with that of the Mughal Empire. They will then show the gross revenue and expenditure of British India, whether of the nature of taxation or otherwise, and analyze its principal items.

THE ACTUAL TAXATION paid by the people of British India during the ten years ending 1879 averaged 35½ millions. The subjoined tables show the gross items exclusive of the opium duty which is paid by the Chinese consumer, tributes from foreign or feudatory States, forest receipts, and the Mint. The actual taxation arranges itself under seven branches, as given in Statement I on the next page, from 1860 to 1879.

This table was compiled from a special Parliamentary Return, and shows the net taxes, after deducting drawbacks and items not of the nature of actual taxation. Statement II shows the revenue from the same items during the four following years, 1880-83, but without deductions or drawbacks. The average of these four years is 40½ millions, without deductions or drawbacks, against 35½ millions, after deductions and drawbacks, during the ten years ending 1879.

The net taxation of British India that is to say, the sum realized, less the cost of collection, averaged 32 millions during the ten years ending 1879. Returns of net taxation, however, depend much upon the method on which they are prepared. But the final accounts as presented to Parliament enable us to arrive accurately at the gross taxation paid by the Indian people, which, as above shown, was 35½ millions during the ten years ending 1879, or a rate of 3s. 8d. per head.

This rate contrasts alike with that now paid by the people in England, and with that formerly paid in India under the Mughal Empire. The 34 millions of people in Great Britain and Ireland pay 68 millions of Imperial taxation, but heavy local and municipal burdens. The revenue of the

¹ Computed from the last 10 years ending 1879.

² Computed from the last 10 years ending 1879.

³ The gross revenue of the British Empire, including India, was 1,250 millions in 1879.

STATEMENT I.

ACTUAL TAXATION OF BRITISH INDIA, 1869-79.
Compiled from the Parliamentary Return dated 8th July 1880.

	1869-70.	1870-71.	1871-72.	1872-73.	1873-74.	1874-75.	1875-76.	1876-77.	1877-78.	1878-79.
Land Revenue, . . .	£ 21,088,019	£ 20,622,823	£ 20,520,337	£ 21,348,669	£ 21,037,912	£ 21,296,793	£ 21,503,742	£ 19,857,152	£ 19,869,667	£ 22,330,586
Excise, . . .	2,253,655	2,374,465	2,369,109	2,323,788	2,286,637	2,346,143	2,493,232	2,523,045	2,457,075	2,619,349
Assessed Taxes, . . .	1,110,224	2,072,025	825,241	580,139	20,136	2,747	510	310	86,110	900,920
Provincial Rates,	238,504	2,638,835
Customs, . . .	2,429,185	2,610,789	2,575,990	2,653,890	2,628,495	2,678,479	2,721,389	2,483,345	2,622,296	2,326,561
Salt, . . .	5,888,707	6,106,280	5,966,595	6,165,630	6,150,662	6,227,301	6,244,415	6,304,658	6,460,082	6,941,120
Stamps, . . .	2,379,316	2,510,316	2,476,333	2,608,512	2,699,936	2,758,042	2,835,368	2,838,628	2,993,483	3,110,510
Total, . . .	£ 35,149,106	£ 36,296,698	£ 34,733,605	£ 35,680,628	£ 34,823,778	£ 35,309,505	£ 35,798,656	£ 34,007,138	£ 34,727,217	£ 40,867,911

Total for Ten Years ending 1879, . . . £357,394,242
Deduct Refunds, Drawbacks, and adjusting Payments, as
per Parliamentary Statement, . . . 4,379,234
Gross Taxation for Ten Years ending 1879, . . . £353,015,008
Yearly Average of Gross Taxation, . . . £35,301,500

STAT LMLN I II

ACTUAL TAXATION OF BRITISH INDIA FROM 1879-80 TO 1882-83
Compiled from the Fifteenth Parliamentary Statistical Abstract relating to British India

	1879-80	1880 81	1881 82.	1882 83.	Total for the Four Years.
Land Revenue *	£21 861 150	£21 112 995	£21 918 022	£21 876 047	£86 798 214
Salt	7 266 413	7 115 988	7 375 620	6 177 781	27 935 802
Stamps	3 193 739	3 250 581	3 381 372	3 379 681	13 205 373
Excise	2 838 021	3 135 226	3 477 774	3 609 561	13 010 082
Customs,	2 280 793	2 539 617	2 361 388	1 296 119	8 177 912
Assessed Taxes	785 318	558 720	536 829	517 811	2 398 679
Provincial Rates	2 882 125	2 776 370	2 895 490	2 683 015	11 237 000
Total	£41 107 559	£40 489 492	£41 925 995	£39 540 015	£163 063 061

Average actual taxation, without allowing for refunds and drawbacks during the four years 1879 83 £40 765 765. It must be remembered, in comparing recent taxation in India with previous totals, that the value of the rupee has greatly declined, while the official conversion into pounds sterling is still made at the old nominal rate of ten rupees to the pound. The purchasing power of the taxation received in recent years is therefore less than the totals in sterling would appear to indicate.

* Including Land Revenue due to Irrigation

a civilised government is Japan. The author has a personal acquaintance with the Japanese revenues, but German statistics show that over 11 millions sterling are there raised from a population of 34 million people, or deducting certain taxes a taxation of about 6s a head. In India, where we try to govern on a higher standard of efficiency, the rate of annual gross taxation averaged 3s 8d a head for the ten years ending 1879, and 4s 1d per head for the four years ending 1883-4.

If, instead of dealing with the Imperial revenues as a whole, we concentrate our survey on any one Province, we find the facts brought out in a still stronger light. To take a single instance. After a patient scrutiny of the records, it was found that, allowing for the change in the value of money, the revenue of Orissa represented eight times the quantity of staple food which our own revenue now represents.¹ The revenue of Orissa supported a magnificent court with a costly seraglio, swarms of priests, a large army, and a costly worship. Under our rule, Orissa does little more than defray the local cost of protecting person and property, and of irrigation works. In Orissa, the Rájá's share of the revenue amounted, with dues, to 60 per cent, and the mildest Native Governments demanded 33 per cent. The Famine Commissioners estimate the land tax throughout British India 'at a rate from 3 per cent to 7 per cent of the gross out turn.' After deductions are allowed for the cost of cultivation, the risks of the season, the maintenance of the husbandman and his family. Of the balance, Government nominally takes one third or a half, but how small a proportion this bears to the crop may be seen from the returns collected by the Famine Commissioners.

Their figures deal with 176 out of the 199 millions of people in British India. These 176 millions cultivate 188 millions of acres, grow 331 millions sterling worth of produce, and now pay 18½ millions of land revenue. While, therefore, they raise over £1, 15s worth of produce per acre, they pay to Government under 2s. of land tax per acre. Instead of thus paying 5½ per cent as they do now, they would under the Mughal rule have been called upon to pay from 33 to 50 per cent of the crop. The two systems, indeed, proceed

¹ The evidence on which these statements are based, was published in Hunter's *Orissa*, vol. 1, pp. 323-329 (Smith, Elder, & Co., 1872).

² *Report of the Indian Famine Commission*, part II, p. 90, as presented to Parliament, 1880.

upon entirely different principles. The Native Governments, write the Famine Commissioners, often taxed the land 'to the extent of taking from the occupier the whole of the surplus after defraying the expenses of cultivation.'¹ The British Government objects to thus 'sweeping off the whole margin of profit.'

Increase of
population.

Taxation
in Native
States.

What becomes of the surplus which our Government declines to take? It goes to feed an enormously increased population. The tax-gatherer now leaves so large a margin to the husbandman, that the Province of Bengal, for example, feeds three times as many mouths as it did in 1780, and has a vast surplus of produce, over and above its own wants, for exportation. 'In the majority of Native Governments,' writes the highest living authority on the question,² 'the revenue officer takes all he can get; and would take treble the revenue we should assess, if he were strong enough to exact it. In ill-managed States, the cultivators are relentlessly squeezed: the difference between the native system and ours being, mainly, that the cultivator in a Native State is seldom or never sold up, and that he is usually treated much as a good bullock is treated, *i.e.* he is left with enough to feed and clothe him and his family, so that they may continue to work.' John Stuart Mill studied the condition of the Indian people more deeply than any other political economist, and he took an indulgent view of native institutions. His verdict upon the Mughal Government is that, 'except during the occasional accident of a humane and vigorous local administrator, the exactions had no practical limit but the inability of the peasant to pay more.'

Incidence
of taxation
in British
India.

The Famine Commission, after careful inquiries, state³ that throughout British India the landed classes pay revenue at the rate of 5s. 6d. per head, including the land-tax for their farms, or 1s. 9d. without it. The trading classes pay 3s. 3d. per head; the artisans, 2s.—equal to four days' wages in the year; and the agricultural labourers, 1s. 8d. The whole taxation, including the Government rent for the land, averaged, as we have seen, 3s. 8d. per head during the ten years ending 1879.

¹ *Report of the Indian Famine Commission*, part ii. p. 90, as presented to Parliament, 1880.

² Report by Mr. (now Sir) Alfred Lyall, C.B., formerly Governor-General's Agent in Rājputāna, afterwards Foreign Secretary to the Government of India, now Lieutenant-Governor of the North-Western Provinces and Oudh; quoted in the Despatch of the Governor-General in Council to the Secretary of State, 8th June 1880. 'Condition of India,' Blue Book, pp. 36, 37.

³ *Report of the Famine Commission*, part ii. p. 93 (folio, 1880).

But the Famine Commissioners declare that 'any native of India who does not trade or own land, and who chooses to drink no spirituous liquor, and to use no English cloth or iron, need pay in taxation only about 7d a year on account of the salt he consumes. On a family of three persons, the charge amounts to 1s 9d, or about four days' wages of a labouring man and his wife'¹

GROSS REVENUES.—But it should always be borne in mind that the actual taxation of the Indian people is one thing, and the gross revenues of India are another. As explained in a previous paragraph of this chapter, the revenues include many items not of the nature of taxation. The following table, compiled from the *Parliamentary Abstract for 1882-83* (the latest received by the author before sending these sheets to the press), exhibits the gross imperial revenue and expenditure of India for that year, according to the system of accounts adopted at the time. For the reasons already given, it is practically impossible to analyse these gross totals in such a way as to show the actual amount raised by taxation, and the actual amount returned in protection to person and property. The actual taxation has therefore been dealt with in the two separate statements already given. It is equally impossible to compare the gross totals with those for previous years, owing to changes that have been made from time to time in the system of entering the accounts. The only profitable plan is to take some of the items, and explain their real meaning.

Gross
balance
sheet of
British
India.

The list of items shows how large a portion of the gross revenue is not of the nature of taxation proper. Public works, including railways and irrigation and navigation canals, alone yielded in 1882-83 upwards of 12 millions sterling or over 17 per cent of the total. Adding the items of post office and telegraphs, which also represent payment for work done or services supplied, the proportion would rise to over 19½ per cent. Then the sum of 9½ millions gross, or nearly 7½ millions net, derived from opium, being an additional 13½ per cent of the gross revenue, is not a charge upon the native taxpayer, but a contribution to the Indian exchequer by the Chinese consumer of the drug. Add to these the tributes from Feudatory States, produce of the forests, etc., and upwards

Analysis
of Indian
revenues
in 1883

Not of the
nature of
taxation

[Sentence continued on page 467]

¹ Report of the Famine Commissioners, part ii, p. 93 (11th, 1880)

GROSS IMPERIAL REVENUE AND EXPENDITURE OF BRITISH INDIA FOR 1882-83.
Computed from the Eighteenth Parliamentary Abstract relating to British India.

REVENUE		EXPENDITURE	
Land Revenue,	£21,876,047	Land Revenue,	£3,042,491
Opium,	9,499,594	Opium,	2,287,816
Salt,	6,177,781	Salt,	449,030
Stamps,	3,379,681	Stamps,	123,398
Excise,	3,609,561	Excise,	94,431
Customs,	1,296,119	Customs,	154,982
Provincial Rates,	2,683,015	Provincial Rates,	53,455
Assessed Taxes,	517,811	Assessed Taxes,	12,853
Forest,	938,228	Forest,	567,318
Registration,	285,849	Registration,	184,501
Tributes from Native States,	689,945	Tributes from Native States,	1,194,010
Post office,	977,797	Post office,	625,279
Telegraphs,	545,315	Telegraphs,	89,280
Mint,	185,882	Mint,	1,563,882
Law and Justice,	656,934	Law and Justice,	3,255,071
Police,	227,642	Police,	2,642,892
Marine,	222,422	Marine,	490,200
Education,	198,538	Education,	1,145,970
Medical,	56,010	Medical,	161,477
Scientific and Minor Departments,	75,680	Scientific and Minor Departments,	692,872
Interest,	693,864	Interest,	513,791
State and Guaranteed Railways,	10,829,661	State and Guaranteed Railways,	481,816
Irrigation & Navigation Canals, } e.g., Reproductive Public Works, {	1,394,439	Irrigation & Navigation Canals, } e.g., Reproductive Public Works, {	1,500,000
Non-productive Public Works,	830,582	Non-productive Public Works,	685,761
Military,	1,592,183	Military,	211,908
Superannuation Funds,	395,260	Superannuation Funds,	2,203,771
Stationery and Printing,	57,838	Stationery and Printing,	507,573
Miscellaneous,	321,533	Miscellaneous,	11,741,747
		Reproductive Expenses and Charges against Capital, Interest, etc., on Non-productive Public Works,	7,165,747
		Military,	17,440,250
		Interest,	4,468,132
		Refunds and Drawbacks,	316,606
		Assignments and Compensations,	1,105,087
		Exchange,	3,081,433
		Miscellaneous,	281,394
Total Revenue,		Total Expenditure,	£70,621,224
		Deduct Provincial Adjustments,	1,202,626
		Net Expenditure,	£69,418,598

Sentence continued from page 465]

of one third of the total gross revenue is accounted for The whole revenue of British India of the nature of actual taxation, including Land Revenue, Excise, Assessed Taxes, Provincial Rates, Customs Salt, and Stamps amounted in 1878 to 34½ millions or 3s 7½d per head In 1882-83, the gross actual taxation of British India was upwards of 39½ millions, or within a fraction of 4s per head the average for the four years ending 1882-83 being a fraction over 4s 1d per head, without allowing for deductions or drawbacks The revenue from taxation

The land revenue amounting to over 21½ millions in 1882-83 forms by far the largest item Whether it should be properly regarded as a tax or only as rent is a problem for political economists to settle but in any case it is paid without question as an immemorial right of the State It yielded in 1882-83 31 per cent or nearly one third of the gross revenue Nature of the land tax

Of the other items of taxation excise and stamps are practically creations of British rule The excise is a tax upon intoxicating liquors and deleterious drugs levied both on the manufacture and on the sale according to different systems in different Provinces Like the corresponding duty in England, it is voluntarily incurred and presses hardest upon the lowest classes But unlike the English excise it can hardly be called an elastic source of revenue for the rate is intentionally kept so high as to discourage consumption No duty whatever is levied upon tobacco Stamps as in England form a complex item The greater part is derived from fees on litigation and only a comparatively trifling amount from stamps proper on deeds of transfer, etc Excise Stamps

Customs are divided into import and export duties, both of which have been so greatly lightened in recent years, that their permanent maintenance may be considered doubtful Duties on exports have been altogether abolished, with the single exception of that on rice, which brings in from £500,000 to over £800,000 per annum The average for the ten years ending 1882-83 was £615,349 but there has been a steady increase since 1878 This export duty is levied at the rate of 3 annas a munda, or about 6d per cwt., being equivalent to an *ad valorem* rate of about 10 per cent The 1½ million sterling received from customs are practically made up of nearly half a million sterling levied on imported liquors, and about three quarters of a million sterling levied on exported rice The receipts from all other import Customs

customs in 1882-83 were under £13,000, and those from all other exports were just over £3000; total, under £16,000, from all imports and exports, excepting imported liquors and exported rice.

Cotton
Duties.

The import duty on cotton goods was finally abolished in March 1882, having been reduced in 1878, and again in 1879. Imported cotton manufactures had previously formed the most important item of the customs revenue. From 1874 to 1882 the duty on cotton goods varied from nearly a million in 1878 to over half a million in 1881-82, the average being about three-quarters of a million sterling during the nine years preceding the total abolition of the duty.

The Salt
Tax.

The salt tax, which yields about $6\frac{1}{2}$ millions a year, is a problem of greater difficulty. It is an impost upon an article of prime necessity, and it falls with greatest severity upon the lowest classes. On the other hand, it may be urged that it is familiar to the people, is levied in a manner which arouses no discontent; and is the only means available of spreading taxation proper over the community. The reforms of 1878 and 1882, referred to on a previous page, have equalized the incidence of the salt tax over the entire country, with the incidental result of abolishing arbitrary and vexatious customs lines. As stated on a previous page, the rate is now a uniform one of Rs. 2 per *maund*, or 5s. 5d. per cwt., throughout British India, except in Burma where the rate is 3 *ánná*s per *maund*, and in the trans-Indus tracts of the Punjab, where a special rate is levied of 8 *ánná*s per local *maund* of 103 lbs.

Indian
Expendi-
ture, 1872-
1882.

GROSS EXPENDITURE.—Putting aside the cost of collection and civil administration, which explain themselves, the most important charges are the Army, Interest on Debt, Famine Relief, Loss by Exchange, and Public Works, to which may be added the complex item of Payments in England. Military expenditure has averaged about 18 millions during the ten years ending 1882-83, and in 1882-83 was $17\frac{1}{2}$ millions. Of the $17\frac{1}{2}$ millions, about $13\frac{1}{2}$ represent payments in India, and 4 millions payments in England. In 1877-78, the total of the Indian Public Debt (exclusive of capital invested on railways and other productive public works) was returned at over $134\frac{2}{3}$ millions sterling, being just 13s. $6\frac{1}{4}$ d. per head of the population. In 1882-83 it was returned at over $159\frac{1}{4}$ millions, or 16s. per head of the population. Part of this was of the nature of obligations or deposits not bearing interest. The charge for

Army ex-
penditure.

Public
Debt.

interest was 5 millions in 1877-78, and 4½ millions sterling in 1882-83. This low charge for interest is due, in part, to the proportion of debt which does not bear interest. The above 'Public Debt' is independent of 126½ millions sterling invested in railways and productive works in 1877-78, which had increased to over 134 millions thus invested in 1882-83.

In 1840, the public debt amounted to only 30 millions, ^{It grew} and gradually rose to 52 millions in 1857. Then came the Mutiny, which added upwards of 40 millions of debt in four years. The rate of increase was again gradual, but slow, till about 1874, when famine relief conspired with public works to cause a rapid augmentation which has continued to the present time. The most significant feature in this augmentation is the large proportion of debt contracted in England.

No charge has recently pressed harder upon the Indian ex- ^{Famine}chequer than that of Famine Relief. Apart from loss by reduced ^{Relief}revenue, the two famines of 1874 and 1877-78 have caused a direct expenditure on charitable and relief works amounting in the aggregate to just over 14 millions. From 1878-79 to 1882-83 the expenditure on 'Famine Relief' is returned at 3½ millions (of which the greater portion was expended on Public Works, in the nature of insurance against famine, and not on actual relief), making a total of nearly 17½ millions during the ten years 1874 to 1883 inclusive. This amounts to an annual charge of 1¾ million sterling for 'Famine Relief'.

Loss by exchange is an item which has lately figured largely ^{Loss by}in the accounts, and is due to the circumstance that large ^{exchange}payments in gold require to be made in England by means of the depreciated rupee. In 1869-70, the loss by exchange was more than balanced by an entry of gain by exchange on the other side of the ledger. In 1876-77, the loss amounted to a little over two millions, and in 1882-83 to over three millions sterling.

The expenditure on Public Works is provided from three ^{Public}sources—(1) the capital of private companies, with a Govern- ^{Works ex-}ment guarantee, (2) loans for the construction of railways and ^{pends}canals, (3) current revenue applied towards such works as are not directly remunerative. In 1877-78, the capital raised for guaranteed railways amounted to 97½ millions sterling, and the capital invested on State railways and other productive public works to 29 millions sterling total, 126½ millions sterling on railways and productive works. In 1882-83 the capital of the guaranteed railways was reduced to 69½ millions ^{of railways}sterling, the capital invested on State railways and other pro-

ductive public works amounted to $64\frac{1}{2}$ millions: total on railways and productive public works, $134\frac{3}{8}$ millions sterling in 1882-83. During the interval, 35 millions sterling of capital had been transferred from the guaranteed to the State railway account, owing to the purchase of the East India line by the Government.

Local
finance.

Independent of imperial finance, and likewise independent of certain sums annually transferred from the Imperial exchequer to be expended by the provincial governments, there is another Indian budget for local revenue and expenditure. This consists of an income derived mainly from cesses upon land, and expended to a great extent upon minor public works. In 1877-78, local revenue and expenditure were each returned at about $3\frac{1}{2}$ millions, and in 1882-83 at about 4 millions.

Municipal
finance.

Yet a third budget is that belonging to the municipalities. The three Presidency towns of Calcutta, Madras, and Bombay had in 1876-77 a total municipal income of £668,400, of which £519,322 was derived from taxation, being at the rate of 7s. per head of population. In addition, there were 894 minor municipalities, with a total population of 12,381,059. Their aggregate income was £1,246,974, of which £979,088 was derived from taxation, being at the rate of 1s. 7d. per head. In 1882-83, the total municipal revenue of the three capital towns was £1,073,715, and of the 783 minor municipalities, £1,623,522; grand total, £2,697,237. It should be remembered that these figures refer to the period before the development of municipal institutions under Lord Ripon's legislation bore fruit. In the Presidency towns, rates upon houses, etc., are the chief source of income; but in the District municipalities, excepting in Bengal and Madras, octroi duties are more relied upon. The chief items of municipal expenditure are conservancy, roads, and police.

Constitution
of the
army.

THE INDIAN ARMY.—The constitution of the Indian army is based upon the historical division of British India into the three Presidencies of Bengal, Madras, and Bombay. There are still three Indian armies, each composed of both European and Native troops, and each with its own Commander-in-Chief and separate staff, although the Commander-in-Chief in Bengal exercises supreme authority over the other two. There may also be said to be a fourth army, the Punjab Frontier Force, which, until 1885, was under the orders of the Lieutenant-Governor of the Province.

The Bengal army garrisons Bengal Proper and Assam, the North Western Provinces and Oudh, a portion of Central India and Rájputána, and the Punjab. In 1877-78 its total strength was 104,216 officers and men, of whom 63,933 were native troops. In 1882-83, the Bengal army numbered 105,270 officers and men, of whom 66,081 were native troops. In the Bengal native army, the distinguishing feature is the presence of 6 batteries of artillery, and an exceptionally large proportion of cavalry, both of which arms are massed in the Punjab.

The Madras army extends beyond the limits of that Presidency into Mysore, the Nizám's Dominions, the Central Provinces, also to Burma across the Bay of Bengal, and to the Andaman convict settlements. In 1877-78, its total strength was 47,026 officers and men, of whom 34,293 were native troops. In 1882-83, the Madras army numbered 46,309 of all ranks, of whom 34,283 were natives. In the Madras native army, the distinguishing features are the large proportion of sappers and miners, the small proportion of cavalry, and the entire absence of artillery.

The Bombay army occupies Bombay Proper and Sind, the Native States of Central India, and the outlying station of Aden in the Red Sea. In 1877-78, its total strength was 38,355 officers and men, of whom 26,645 were native troops. In 1882-83, the Bombay army numbered 38,897 officers and men, of whom 27,041 were natives.

The total established strength of the European and Native army in British India in 1877-78 (exclusive of native artificers and followers) consisted of 189,597 officers and men, of whom 64,276 were Europeans, and 124,871 were native troops. The four chief arms of the service were thus composed — (1) Artillery, 12,239 European and 901 native, (2) cavalry, 4347 European and 18,346 native, (3) engineers, 357 European (all officers) and 3239 native, (4) infantry, 45,962 European and 102,183 native. In 1882-83, the total European and Native army in British India consisted of 190,476 officers and men, of whom 63,071 were Europeans, and 127,405 were native troops. The artillery consisted of 11,329 Europeans and 1861 natives, the cavalry of 4311 Europeans and 18,375 natives, besides a bodyguard of 202 troopers, engineers, 284 Europeans (all officers) and 3251 natives, and infantry, 45,766 Europeans and 103,716 natives.

Police.

POLICE.—Excluding the village watch, still maintained as a subsidiary police in many parts of the country, the regular police of all kinds in British India in 1882 consisted of a total strength of 145,421 officers and men, being an average of 1 policeman to about 6 square miles of area, or to about 1369 of the population. The total cost of maintenance was £2,378,143, of which £2,201,437 was payable from imperial or provincial revenues. The former figure gives an average cost of about £2, 15s. per square mile of area, and threepence per head of population. The average pay of each constable was Rs. 7 a month, or £8, 8s. a year.

Jails.

In 1882–83, the total number of places of confinement in British India, including central and District jails and lock-ups, was 452; the total number of prisoners admitted during the year, or remaining over from the previous year, was 391,319; the daily average was 97,218. The places of transportation for all British India are the Andaman and Nicobar Islands, where there are two penal establishments, containing, in 1882, a daily average of 11,454 convicts.

Educa-
tion.In ancient
India.

PUBLIC INSTRUCTION in India is directly organized by the State, and is assisted by grants-in-aid, under careful inspection. But at no period of its history has India been without some system of popular education, independent of State organization or aid. The origin of the Deva-Nāgari alphabet is lost in antiquity, though it is generally admitted not to be of indigenous invention. Inscriptions on stone and copper, the palm-leaf records of the temples, and in later days the widespread manufacture of paper, indicate not only the general knowledge, but also the common use, of the art of writing.

Village
schools.Sanskrit
śols.

From the earliest times the Brāhman caste preserved, first by oral tradition, then in manuscript, a literature unrivalled in its antiquity and for the intellectual subtlety of its contents. The Muhammadan invaders introduced the profession of the historian, and attained a high degree of historical excellence, compared with European writers of the same mediæval period. Throughout every change of dynasty, vernacular instruction has been given, at least to the children of respectable classes, in each large village. On the one hand, the *śols* or seminaries for teaching Sanskrit philosophy at Benares and Nadiyā recall the schools of Athens and Alexandria; on the other, the importance attached to instruction in accounts reminds one of the picture which Horace has left of a Roman education.

Even at the present day, a knowledge of reading and writing, taught by the Buddhist monks, is as widely diffused throughout Burma as in many countries of Europe. Our own efforts to stimulate education have been most successful, when based upon the existing indigenous institutions.

During the early days of the East India Company's rule, the promotion of education was not recognised as a duty of Government. Even in England at that time education was entirely left to private and mainly to clerical enterprise. A State system of instruction for the whole people is an idea of the latter half of the present century. But the enlightened mind of Warren Hastings anticipated this idea by founding the Calcutta Madrasa for Muhammadan teaching (1781) and by extending his patronage alike to Hindu *pandits* and European students. Lord Wellesley's schemes of imperial dominion led to the establishment of the college of Fort William for English officials. Of the Calcutta seminaries the Sanskrit College was founded in 1824, when Lord Amherst was Governor General, the Medical College, by Lord William Bentinck in 1835, the Hughli Madrasa, by a wealthy native gentleman in 1836. The Sanskrit College at Benares had been established in 1791, the Agra College in 1823.

Meanwhile, the Christian missionaries made the field of vernacular education their own. Discouraged by the authorities, and under the Company liable to deportation, they not only devoted themselves with courage to their special work of evangelization but they were also the first Europeans to study the vernacular dialects spoken by the people. Nearly two centuries ago, the Jesuits at Madura in the extreme south, had so mastered Tamil as to leave works in that language which are still acknowledged as classical by native authors. About 1810, the Baptist mission at Serampur, above Calcutta, raised Bengali to the rank of a literary prose dialect. The interest of the missionaries in education, which has never ceased to the present day, although now comparatively overshadowed by Government activity, had two distinct aspects. They studied the vernacular, in order to preach to the people, and to translate the Bible; they also taught English, as the channel of Western knowledge.

After long and acrimonious controversy between the advocates of English and of vernacular teaching, the present system was based, in 1854, upon a comprehensive despatch sent out by Sir C. Wood (afterwards Lord Halifax). In the midst of the tumult of the Mutiny, the three Indian Universities

Our first efforts at education

Calcutta Madrasa and other Colleges

Vernacular Schools

State system of education

Indian Universities

were founded at Calcutta, Madras, and Bombay in 1857.¹ Schools for teaching English were by degrees established in every District; grants-in-aid were extended to the lower vernacular institutions, and to girls' schools. A Department of Public Instruction was organized in every Province, under a Director, with a staff of Inspectors. In some respects this scheme may have been in advance of the time; but it supplied a definite outline, which has gradually been filled up. A network of schools was extended over the country, graduated from the indigenous village institutions up to the highest colleges. All received some measure of pecuniary support, granted under the guarantee of regular inspection; while a series of scholarships at once stimulated efficiency, and opened a path to the university for the children of the poor.

Education
Commis-
sion of
1882-83.

In 1882-83, an Education Commission, appointed by Lord Ripon's Government, endeavoured to complete the scheme inaugurated in 1854 by the Despatch of Lord Halifax. It carefully examined the condition of education in each Province, indicated defects, and laid down principles for further development. The results of its labours have been to place public instruction on a broader and more popular basis, to encourage private enterprise in teaching, to give a more adequate recognition to the indigenous schools, and to provide that the education of the people shall advance at a more equal pace along with the instruction of the higher classes. Female education and the instruction of certain backward classes of the community, such as the Muhammadans, received special attention. The general effect of the Commission's recommendations is to develop the Department of Public Instruction into a system of truly national education for India, conducted and supervised in an increasing degree by the people themselves.

Educa-
tional
statistics,
1878-83.

In 1877-78, the total number of educational institutions of all sorts in British India was 66,202, attended by an aggregate of 1,877,942 pupils, showing an average of one school to every 14 square miles, and one pupil to every 100 of the population. In 1882-83, the total number of inspected schools of all classes in British India had risen to 109,216, with an aggregate of 2,790,773 scholars, showing an average of one school to every 8 square miles of area, and one pupil to every 71 of the population. Male pupils numbered 2,628,402, showing one boy at school to every 38 of the male population; and female pupils, 162,371, or one girl at school to every 610

¹ By Act II. of 1857 for Calcutta; by Act XXII. of 1857 for Bombay; and by Act XXVII. of 1857 for Madras.

females. These figures, however, only include State inspected or aided schools and pupils. The Census Report of 1881 returned 2,879,571 boys and 155,268 girls as under instruction throughout British India, besides 7,646,712 males and 277,207 females able to read and write, but not under instruction. The figures are evidently below the truth, and it will be remarked that the Census returns the total number of girls attending school at 5000 less than those returned as attending the State-inspected schools alone.

In 1877-78, the total expenditure upon education from all ^{Education} sources was £1,612,775, of which £782,240 was contributed ^{national} by the provincial governments, £258,514 was derived from ^{finance,} local rates, and £32,008 from municipal grants. These items may be said to represent State aid, while endowments yielded £37,218, subscriptions £105,853, and fees and fines £277,239. The degree in which education has been popularized, and private effort has been stimulated, may be estimated from the fact that in Bengal the voluntary payments now greatly exceed the Government grants. In 1882-83, the total educational expenditure throughout British India amounted to £2,102,500, of which £578,629 was contributed by the provincial governments, £347,376 was derived from local rates, £62,122 from municipal grants, £93,924 from subscription, £45,672 from Native States, £58,675 from endowments, £216,022 from fees and fines, and the remainder from other sources.

Madras, out of 28,575 candidates, 9715 passed; and at Bombay, out of 11,871 candidates, 3557 passed. Total passed entrance examination in the ten years ending 1882-83, 23,472. Many fall off at this stage, and very few proceed to the higher degrees. During the same ten years ending 1882-83, 1036 graduated B.A. and only 281 M.A. at Calcutta; 896 B.A. and 22 M.A. at Madras; 456 B.A. and 34 M.A. at Bombay: total of B.A.'s and M.A.'s in the ten years, 2725. Calcutta possesses the great majority of graduates in law and medicine, while Bombay is similarly distinguished in engineering. In 1877-78, the total expenditure on the Universities was £22,093; and in 1882-83, £21,790.

colleges. The colleges or institutions for higher instruction may be divided into two classes,—those which teach the arts course of the Universities, and those devoted to special branches of knowledge. According to another principle, they are classified into those entirely supported by Government, and those which only receive grants-in-aid. The latter class comprises the missionary colleges. In 1877-78, the total number of colleges, including medical and engineering colleges and Muhammadan *madrasas*, was 82, attended by 8894 students. Of these, as many as 35 colleges, with 3848 students, were in Lower Bengal; and 21 colleges, with 1448 students, in Madras. In the same year, the total expenditure on the colleges was £186,162, or at the rate of £21 per student. In 1882-83, the total number of colleges, including medicine and engineering colleges and Muhammadan *madrasas*, was 96, attended by 8707 students. Of these, 34 colleges with 3754 students were in Bengal, 32 colleges with 2329 students were in Madras, and 9 colleges with 1203 students were in Bombay. In the same year, the total expenditure on colleges in British India was £173,213, or a fraction under £20 per student.

boys' schools; The boys' schools include many varieties, which may be sub-divided either according to the character of the instruction given, or according to the proportion of Government aid which they receive. The higher schools are those in which English is not only taught, but is also used as the medium of instruction. They educate up to the standard of the entrance examination at the Universities, and generally train those candidates who seek employment in the upper grades of Government service. One of these schools, known as the *zila* or District school, is established at the head-quarters station of every District; and many others receive grants-in-aid. The total number of high schools in 1882-83 was 530,

upper
schools;

of which 492 were for males and 117 for females in the year comprising 1882-83.

The middle schools are intermediate between the primary and the high schools, generally speaking, they are found in the smaller towns and villages, and they are recognised to be a distinct class. Some of them teach English and others teach only the vernacular. This class includes the quarters of every district. In 1877-78 there were 117 middle schools with an attendance of 11,117. The expenditure on both primary and middle schools in 1882-83, £491,202.

The lower or primary schools are dotted over the whole country. Their extension is the best system.

No uniformity prevails in the several Provinces. In Bengal, primary instruction was reorganised by Sir G. Campbell in 1877. Inaugurated by Sir G. Campbell in 1877, the grant in aid rules was enforced. Of the reproach has been made of the number of primary schools in Bengal was only 2451, attended by 64,777. The number of schools had risen to 16,422 being an increase of 15,971. By March 1883, when Sir G. Campbell received their full development the primary schools in Bengal had increased to 63,897, and the pupils to 1,110,623. This is an increase of over seventeen fold in the eleven years ending 1882-83. In 1877-78 the expenditure on primary schools in Bengal from all sources was £78,000, thus showing how Government contributed only £7,000, in primary education. The State aid stimulates private outlay in primary education. The total expenditure in 1882-83 was returned at £318,680. This increase, however, is more apparent than real, and results from a large number of schools previously private being brought under the inspection of the Education Department, and included in its financial statements. The North Western Provinces owe their system of primary instruction to their great Lieutenant Governor Mr. Thomason, whose constructive talent can be traced in every branch of the

administration. In addition to the *tahsili* or middle schools already referred to, a scheme was drawn up for establishing *halkabandi* or primary schools in every central village (whence their name), to which the children from the surrounding hamlets might resort. The system in the North-Western Provinces has been developed by means of the educational cess added to the land revenue. Sir William Muir, during his long service in the North-Western Provinces, ending in the Lieutenant-Governorship, did much for both the primary and the higher education of the people.

in Bombay; In Bombay, the primary schools are mainly supported out of local funds raised by a cess added to the land revenue.

in Burma; In British Burma, on the other hand, primary education is still left to a great extent in the hands of the Buddhist monks, who receive little or no aid from Government. These monastic schools are only open to boys; but there are also lay teachers who admit girls to mixed classes. The local administration shows a wise disposition to avail itself of the indigenous monastic system. Government has comparatively few schools of its own in Burma, the deficiency being supplied by several missionary bodies, who obtain State aid.

in Madras. In some localities of the Madras Presidency, also, the missionaries possess a practical monopoly of primary education at the present day.

Primary education finance. In 1877-78, the amount of money expended upon lower and primary schools in British India was £406,135, or just one-fourth of the total educational budget. In 1882-83, the total expenditure on lower and primary schools throughout British India was £911,121, or a little less than one-half (£2,105,653) of the total educational expenditure of the year. Under the recommendations of the Education Commission of 1882-83, the importance assigned to primary instruction, and the proportion of the public educational funds devoted to it, will constantly tend to increase.

Girls' schools. Of late years something has been done, although not much, to extend the advantages of education to girls. In this, as in other educational matters, the missionaries have been the pioneers of progress. In a few exceptional places, such as Tinneveli in Madras, the Khási Hills of Assam, and among the Karen tribes of Burma, female education has made real progress; for in these localities the missionaries have sufficient influence to overcome the prejudices of the people. But elsewhere, even in the large towns and among the English-speaking classes, all attempts to give a modern education to

Vernacular press.

First newspaper.

The theological period.

The political period.

Statistics of native journalism.

Closely connected with the subject of education is the steady growth of the vernacular press, which is ever active in issuing both newspapers and books. The missionaries were the first to cast type in the vernacular languages, and to employ native compositors. The earliest vernacular newspaper was issued in Bengali by the Baptist Mission at Serampur, in 1818. For many years the vernacular press preserved the marks of its origin, being limited almost exclusively to theological controversy. The missionaries were encountered with their own weapons by the Theistic sect of the Brahma Samáj, and also by the orthodox Hindus. So late as 1850, most of the vernacular newspapers were still religious or sectarian rather than political. But during the last twenty-five years, the vernacular press has gradually risen into a powerful engine of political discussion.

The number of newspapers published in the several vernaculars is estimated at 250 to 300, and their aggregate sale at over 250,000 copies.¹ But the circulation proper, that is, the actual number of readers, is very much larger. In Bengal, the vernacular press suffers from the competition of English newspapers, some of which are entirely owned and written by natives. In the North-Western Provinces and Punjab, from Lucknow to Lahore, about 100 newspapers are printed in Hindustání or Urdu, the vernacular of the Muhammadans throughout India. Many of them are conducted with considerable ability and enterprise, and may fairly be described as representative of native opinion in the large towns. The Bombay journals are about equally divided between Maráthí and Gujarátí. Those in the Maráthí language are characterized by the traditional independence of the race of Sivají; the Gujarátí newspapers are the organs of the Pársís, and of the trading community generally. The vernacular newspapers of Madras, printed in Támil and Telugu, are politically unimportant, being still for the most part devoted to religion.

Books.

As regards books, or rather registered publications, in the vernacular languages, Lower Bengal takes the lead; the Punjab, Bombay, the North-Western Provinces, and Madras follow in order. In a previous chapter, the exact number of works published in the native languages of India in the various

¹ The above estimate must be regarded as the result of intelligent inquiry, and not as an actual enumeration. Steps are now (1885) being taken to procure accurate returns of the vernacular press. But the ephemeral existence of many native newspapers, and other features of vernacular journalism, render the undertaking not free from difficulty.

departments of literature, has been stated. The following figures refer to the years 1878 and 1882-83, and comprise the whole registered publications, both in the native languages and in English. There is probably a considerable number of minor works which escape registration.

Total of registered publications in 1878, 4913. Of these, 576 ^{book} ^{statistics} were in English or European languages, 3148 in vernacular dialects of India, and 673 in the classical languages of India, and 1875 673 were bilingual or in more than one language. No fewer than 2495 of them were original works, 2078 were republications, and 340 were translations. Religion engrossed 1502 of the total, poetry and the drama 779, fiction 182, natural science 249, besides 43 works on philosophy or moral science. Language or grammar was the subject of 612, and history had only 11, of no fewer than 249 separate works. History had only 96 books devoted to it, biography 22, politics 7, and travels or voyages 2. These latter number contrasted with the 1502 books on religion indicate the working of the Indian mind.

In 1882-83, the registered publications numbered 6198, of which 655 were in English or European languages, 4208 in vernacular dialects of India, 626 in the classical languages of India, and 709 bilingual or in more than one language. Of the total number of published works in 1882-83, 1160 were returned as educational, and 5035 as non-educational works. Original works numbered 3146, republications 2547, and translations, 505. Publications relating to religion numbered 1641, poetry and the drama, 1089, fiction 238, natural and mathematical science, 281, philosophy and moral science, 160, history, 143, languages, 784, law 338, and medicine 235. Politics were represented in 1882-83 by only 11 publications, travels and voyages by only 4, while works classed as miscellaneous numbered 1231.

Dr. C. C. Chatterjee

CHAPTER XVII.

AGRICULTURE AND PRODUCTS.

Agriculture.

The work of almost the whole people.

THE cultivation of the soil forms the occupation of the Indian people in a sense which it is difficult to realize in England. As the land-tax forms the mainstay of the imperial revenue, so the *rāyat* or cultivator constitutes the unit of the social system. The village community contains many members besides the cultivator, but they all exist for his benefit, and all are maintained from the produce of the village fields. Even in considerable towns, the traders and handicraftsmen frequently possess plots of land of their own, on which they raise sufficient grain to supply their families with food. According to the returns of the general Census of 1872, the adult males directly engaged in agriculture amount to nearly 35 millions, or 56·2 per cent. of the total. To these must be added almost all the day-labourers, who number $7\frac{1}{2}$ million males, or 12·3 per cent.; thus raising the total of persons directly supported by cultivation to 68·5 per cent.; being more than two-thirds of the whole adult males. The Census of 1881 returned a total of 51,274,586 males as engaged in agriculture throughout British and Feudatory India. Adding to these $7\frac{1}{4}$ million of adult day-labourers, there is a total of upwards of $58\frac{1}{2}$ million persons directly supported by cultivation, or 72 per cent. of the whole male population engaged in some specified occupation.¹ The number of persons indirectly connected with agriculture is also very great. The Famine Commissioners estimate that 90 per cent. of the rural population live more or less by the tillage of the soil. India is, therefore, almost exclusively a country of peasant farmers.

¹ For reasons fully explained in the *Note on Indian Statistics* in the last chapter, the years ordinarily selected for population statements are the Census years 1872 and 1881; and for other details, 1877-78 and 1882-83. The last year for which the final Parliamentary presentment of Indian returns had been received by the author when these sheets went to press in the summer of 1885, ended on 31st March 1883.

The increase in the population has, however, developed a large landless class. The cultivated area no longer suffices to allow a plot of land for each peasant, and multitudes now find themselves ousted from the soil. They earn a poor livelihood as day labourers, and according to the Census of 1881, comprise 7,248,491, or one eighth of the entire adult male population. There is still enough land in India for the whole people, but the Indian peasant clings to his native District, however overcrowded. Migration or emigration has hitherto worked on too small a scale to afford a solution of the difficulty.

Agriculture is carried on in the different Provinces with an infinite variety of detail. Everywhere the same perpetual assiduity is found but the inherited experience of generations has taught the cultivators to adapt their simple methods to differing circumstances. The deltaic swamps of Bengal and Burma, the dry uplands of the Karnatik, the black soil plains of the Deccan, the strong clays of the Punjab, the desert sand of Sind or Rájputáná, require their separate modes of cultivation. In each case the Indian peasant has learned, without scientific instruction, to grow the crops best suited to the soil. His light plough, which he may be seen carrying a field on his shoulders, makes but superficial scratches, but what the furrows lack in depth, they gain by repetition, and in the end pulverize every particle of mould. Where irrigation is necessary, native ingenuity has devised the means. Although in this as in other matters connected with agriculture, a wide field remains for further development and improvement. The inundation channels in Sind, the wells in the Punjab and the Deccan, the tanks in the Karnatik, the terraces cut on every hillside, water at the present day a far larger area than is commanded by Government canals. Manure is copiously applied to the more valuable crops, whenever manure is available, its use being limited only by poverty and not by ignorance. The scientific rotation of crops is not adopted as a principle of cultivation. But in practice it is well known that a succession of exhausting crops cannot be taken in consecutive seasons from the same field, and the advantage of fallows is widely recognised. A mutation of crops takes the place of their rotation.

The *petit culture* of Indian husbandmen is in many respects well adapted to the soil, the climate, and the social conditions of the people. The periodicity of the seasons usually allows of two, and in some places of three, harvests in the year. For

inexhaustible fertility, and for retentiveness of moisture in a dry season, no soil in the world can surpass the *regar* or 'black cotton-soil' of the Deccan. In the broad river basins, the floods annually deposit a fresh top-dressing of silt, thus superseding the necessity of manures. The burning sun and the heavy rains of the tropics combine, as in a natural forcing-house, to extract the utmost from the soil. A subsequent section will deal with possible improvements in Indian agriculture—improvements now necessary in order to support the increasing population. As the means of communication improve and blunt the edge of local scarcity, India is probably destined to compete with America as the granary of Great Britain.

Rice.

The name of rice has from time immemorial been closely associated with Indian agriculture. The rice-eating population is estimated at 67 millions, or over one-third of the whole.¹ If, however, we except the deltas of the great rivers, and the long strip of land fringing the coast, rice may be called a rare crop throughout the remainder of the peninsula. But where rice is grown, it is in an almost exclusive sense the staple crop.

Statistics
of rice
cultivation
in different
Provinces.

In British Burma, out of a total cultivated area of 2,833,520 acres, in 1877-78, as many as 2,554,853 acres, or 90 per cent., were under rice. In 1882-83, the cultivated area in British Burma had risen to 3,746,279 acres, of which 3,380,996 acres, or 90 per cent., were under rice. Independent Burma, on the other hand, grows no rice, but imports largely from British territory. For Bengal, unfortunately, no general statistics are available. But taking Rangpur as a typical District, it was there found that $1\frac{1}{2}$ million acres, out of a classified total of a little more than $1\frac{3}{4}$ million acres, or 88 per cent., were devoted to rice. Similar proportions hold good for the Province of Orissa, the deltas of the Godāvarī, Kistna, and Kāveri (Cauvery), and the lowlands of Travancore, Malabar, Kānara, and the Konkan. Throughout the interior of the country, except in Assam, which is agriculturally a continuation of the Bengal delta, the cultivation of rice occupies but a subordinate place. In the North-Western Provinces and Oudh, rice is grown in damp localities, or with the help of irrigation, and forms a favourite food for the upper classes; but the local supply requires to be supplemented by importation from Bengal. In Madras generally, the area under rice in 1883 amounted to about 43 per cent. of the whole food-

¹ *Report of the Indian Famine Commission*, part ii. 81 (1880).

grain area. In Bombay proper, the corresponding proportion is only 14 per cent, and in the outlying Province of Sind, 17 per cent. In the Central Provinces, the proportion rises as high as 55 per cent, but in the Punjab it falls to 3 per cent. In scarcely any of the Native States, which cover the centre of the peninsula, is rice grown to a large extent.

Rice is in fact a local crop, which can only be cultivated profitably under exceptional circumstances although under those circumstances it returns a larger pecuniary yield than any other food grain in India. According to the Madras system of classification rice is a wet crop, i.e. it demands steady irrigation. In a few favoured tracts the requisite irrigation is supplied by local rainfall but more commonly by the periodical overflow of the rivers either directly or indirectly through artificial channels. It has been estimated that rice requires 36 to 40 inches of water in order to reach its full development. But more important than the total amount of water, is the period over which that amount is distributed. While the seedlings are in an early stage of growth 2 inches of water are ample, but when the stem is strong, high floods are almost unable to drown it. In some Districts of Bengal a long stemmed variety of rice is grown, which will keep its head above 12 feet of water.

Throughout Bengal, there are two main harvests of rice in a year—(1) the *mus* or early crop sown on comparatively high lands, during the spring showers and reaped between July and September. (2) the *mon* or winter crop sown in low lying lands, from June to August usually transplanted and reaped from November to January. The latter crop comprises the finer varieties, but the former is chiefly retained by the cultivators for their own food supply. Besides these two great rice harvests of the Bengal year, there are several intermediate ones in different localities. The returns from Rangpur District specify no fewer than 295 distinct varieties of rice! The average outturn per acre in Bengal has been estimated at 15 *maunds*, or 1200 lbs., of cleaned rice. In 1877-78, when famine was raging in Southern India, the exports of rice from Calcutta (much of it to Madras) amounted to nearly 17 million cwt.

In British Burma, there is but a single harvest in the year, corresponding to the *am* of Bengal. The grain

See Hurst's *Statistics of India*, vol. vi. pp. 234-237.

is reddish in colour, and of a coarse quality; but the average out-turn is much higher than in Bengal, reaching in some places an average of 2000 and 2500 lbs. per acre. In 1877-78, the Burmese export of rice exceeded 13 million cwts.; and in 1882-83 it exceeded $21\frac{1}{2}$ million cwts., of an estimated aggregate value of over $5\frac{1}{2}$ millions sterling.

Hill cultivation.

Besides being practically the sole crop grown in the deltaic swamps, rice is also cultivated on all the hills of India, from Coorg to the Himalayas. The hill tribes practise one of two methods of cultivation. They either cut the mountain slopes into terraces, to which sufficient water is conveyed by an ingenious system of petty canals; or they trust to the abundant rainfall, and scatter their seeds on clearings formed by burning patches of the jungle. In both cases, rice is the staple crop, wherever the moisture permits. It figures largely in the nomadic system of hill cultivation.

Area under rice.

The tables on the next page show the comparative area under rice and the two great other classes of food-grains for all India. But the figures must be taken as only approximate estimates.

Wheat.

Recent exports of wheat to Europe have drawn attention to the important place which this crop occupies in Indian agriculture. It is grown to some extent in almost every District. But, broadly speaking, it may be said that wheat does not thrive where rice does; nor, indeed, anywhere south of the Deccan. The great wheat-growing tracts of India are in the north. The North-Western Provinces in 1883 had 97 per cent. of the food-grain area under wheat, barley, and millets; and about 57 per cent. under wheat alone. In the Punjab, the proportion of wheat and barley is 61 per cent. Wheat is also largely grown in Behar, and to a less extent in the western Districts of Bengal. In the Central Provinces, wheat covers a large proportion of the food-grain area, being the chief cereal in the Districts of Hoshangábád, Narsinghpur, and Sagar. In Bombay, the corresponding proportion was only 15 per cent., and in Sind, 12 per cent. The wheat returns vary from year to year, but disclose a tendency upwards. Their significance may be learned from the fact, that in Great Britain the area under wheat is only 3 million acres, or less than one-half the amount in a single Indian Province, the Punjab. It has been estimated that the total area under wheat in India is equal to the total area under the same crop in the United States.

Out-turn of wheat.

Nor is the out-turn contemptible, averaging about 13 bushels

[Sentence continued on page 488.]

RATIO OF AREA UNDER THE THREE PRINCIPAL CLASSES OF INDIAN FOOD GRAINS

I

1878

Province	Ratio of Area under principal Food Grains			Total Population (first schedule)	Population existing in 1878
	Wheat or Barley	Millet	Rice		
	Per cent	Per cent	Per cent	Millions	Millions
Punjab	54	41	5	18½	1
North Western Provinces	—	34	9	44	4
Bengal and Assam	No figures available			74	4½
Central Provinces	27	39	34	—	3
Bihar	17	62	1	—	1
Bombay	7	83	10	1½	2
Madras	—	—	3	30	10
Mysore	—	84	17	4	1

II

1883

Province	Ratio of Area under principal Food Grains			Total Population (1881)	Population existing in 1883
	Wheat or Barley	Millet	Rice		
	Per cent	Per cent	Per cent	Millions	Millions
Punjab	61	35	—	18½	1
North Western Provinces	47	No figures available		44	4
Bengal	No figures available			74	4½
Assam	—	—	50	—	—
Central Provinces	45	—	—	—	—
Bihar	47	—	—	—	—
Bombay	15	71	14	1½	—
Madras	—	57	43	30	10
Mysore	4	—	96	4	1

a Where a column is left blank, the separate figures are not available

A B — It will be observed that in the second table, where separate figures are not available, the ratio is that which one principal class bears to the other, and not to the total food grain area of the District. The figures for the second table are derived from the Local Administration Reports for 1883-84, except in the case of Bihar and Mysore, for which the figures are for 1881-82 (Mysore) and 1882-83 (Bihar). They are not, in all cases, strictly comparable with the figures in the first table, which were taken from the Famine Commissioners' Report.

Sentence continued from page 486.]

per acre in the Punjab, as compared with an average of $15\frac{1}{2}$ bushels for the whole of France. The quality, also, of the grain is high enough to satisfy the demands of English millers. The price of Indian wheat in Mark Lane varies considerably from year to year; the best qualities averaging somewhat lower than Australian or Californian produce. The abolition, in 1873, of the old Indian export duty on wheat, laid the foundation of the Indo-European wheat-trade, which, since this wise measure, has attained to large dimensions. The low prices of wheat in England in 1884 gave a check to the trade—a check which is believed to be temporary.

Wheat
cultiva-
tion.

According to the system of classification in Upper India, wheat ranks as a *rabí* crop, being reaped at the close of the cold weather in April and May. Wherever possible, it is irrigated; and the extension of canals through the Doáb has largely contributed to the substitution of wheat for inferior cereals.

Millets.

Taking India as a whole, it may be broadly affirmed that the staple food-grain is neither rice nor wheat, but millet. Excluding special rice tracts, varieties of millet are grown more extensively than any other crop, from Madras in the south, at least as far as Rájputána in the north. The two most common kinds are great millet (*Sorghum vulgare*), known as *joár* or *javári* in the languages derived from the Sanskrit, as *jouna* in Telugu, and as *cholam* in Tamil; and spiked millet (*Pennisetum typhoideum*), called *bájra* in the north and *kambu* in the south. In Mysore and the neighbouring Districts, *ragí* (*Eleusine corocana*), called *náchani* in Bombay, takes the first place. According to the Madras system of classification, these millets all rank as 'dry crops,' being watered only by the local rainfall, and sown under either monsoon; farther north, they are classed with the *kharíf* or autumn harvest, as opposed to wheat.

Chief
varieties.

Statistics
of millet
cultiva-
tion;
in Madras;

The following statistics show the importance of millet cultivation throughout Southern and Central India. In Madras, in 1875-76, *cholam* covered 4,610,000 acres; *ragí*, 1,636,000 acres; *varagu* or *auricalu* (*Paspalum miliaceum*), 1,054,000 acres; *kambu*, 2,909,000 acres; *samai* or millet proper (*Panicum frumentaceum*), 1,185,000,—making a total of 11,384,000 acres under 'dry crops,' being 52 per cent. of the cultivated area. The proportion was 67 per cent. of the food-grain area in 1879. In 1882-83, the area under millets and inferior cereal crops was returned at 10,942,384 acres. In the upland

region of Mysore, the proportion under 'dry crops,' chiefly *ragi*, rises to 77 per cent of the cultivated area, or 84 per cent of the food grain area. The total under all millets, *jowar*, and *bajra* in Bombay and Sind may be taken at about 83 per cent, in the Central Provinces, 39 per cent, in the Punjab, 41 per cent, and in the North Western Provinces, 34 per cent of the total food grain area. It should be remembered that these figures vary from year to year.

Indian corn is cultivated to a limited extent in all parts of the country, barley, in the upper valley of the Ganges through out the Punjab and in the Himalayan valleys oats only as an experimental crop by Europeans. *Jowar* and *ragi*, but not *bajra*, are valuable as fodder for cattle.

Pulses of many sorts form important staples. In Madras, *Pisum*, the area under pulses in 1875 was 2,057,000 acres or 9 per cent, in Bombay about 830,000 acres, in the Punjab, 4,000,000 acres, or 21 per cent. The area under pulses in 1882-83 was returned as under—In Madras 1,955,946 acres, and in 1882-83 was returned as under—In Madras 1,776,773 acres, or over 8 per cent in the Punjab, 3,664,952 acres or 15½ per cent of the cultivated area. The principal varieties of pulses grown, with many native names but generically known to Europeans as gram and *dal* are—*Cicer arietinum*, *Phaseolus Mungo* and *P. radiatus*, *Dolichos biflorus*, *D. sinensis* and *D. Lablab*, *Cajanus indicus*, *Ervum Lens*, *Lathyrus sativus*, and *Pisum sativum*.

Oil seeds also form an important crop in all parts of the country, oil being universally required, according to native custom, for application to the person for food and for lamps. In recent years, the cultivation of oil seeds has received an extraordinary stimulus owing to their demand in Europe especially in France. But as they can be grown after rice etc. as a second crop, this increase has hardly tended to diminish the production of food grains. The four chief varieties grown are mustard or rape seed, linseed, *til* or gingelly (*Sesamum*) and castor oil. Bengal and the North Western Provinces are at present the chief sources of supply for the foreign demand, but gingelly is largely exported from Madras, and, to a less extent, from Burma. Area in 1875 under oil seeds—In Madras, about 1,200,000 acres, or nearly 6 per cent of the cultivated area, in Bombay, 628,000 acres, in the Central Provinces, 1,358,571 acres, or nearly 9 per cent; in the Punjab, 780,000 acres, or 4 per cent. Area under oil seeds in 1882-83—In Madras, 1,063,988 acres, or 4.7 per cent.

of the total cultivation ; in Bombay, 1,336,385 acres, or 6·1 per cent. ; in the Central Provinces, 1,600,225 acres, or 11·3 per cent. ; and in the Punjab, 1,039,633 acres, or 4·4 per cent. of the area under cultivation. In the year 1877-78, the total export of oil-seeds from India amounted to 12,187,020 cwts., valued at £7,360,284 ; in 1878-79, to 7,211,790 cwts., valued at £4,682,512 ; and in 1882-83, to 13,147,982 cwts., valued at £7,205,924.

Vege-
tables.

Vegetables are everywhere cultivated in garden plots for household use, and also on a larger scale in the neighbourhood of great towns. Among favourite native vegetables, the following may be mentioned :—The egg-plant, called *brinjál* or *baigan* (*Solanum melongena*), potatoes, cabbages, cauliflower, radishes, onions, garlic, turnips, yams, and a great variety of cucurbitaceous plants, including *Cucumis sativus*, *Cucurbita maxima*, *Lagenaria vulgaris*, *Trichosanthes dioica*, and *Benicasa cerifera*. Of these, potatoes, cabbages, and turnips are of recent introduction. Almost all English vegetables can be raised by a careful gardener. Potatoes thrive best on the higher elevations, such as the Khásí Hills, the Nílگیرis, the Mysore uplands, and the slopes of the Himálayas ; but they are also grown on the plains and even in deltaic Districts. They were first introduced into the Khásí Hills in 1830. They now constitute the principal crop in these and other highland tracts. The annual export from the Khásí Hills to Bengal and the Calcutta market is estimated at considerably over 7000 tons, valued at £50,000.

Fruits.

Among the cultivated fruits are the following :—Mango (*Mangifera indica*), plantain (*Musa paradisiaca*), pine-apple (*Ananassa sativa*), pomegranate (*Punica Granatum*), guava (*Psidium Guyava*), tamarind (*Tamarindus indica*), jack (*Artocarpus integrifolia*), custard-apple (*Anona squamosa*), *pápaw* (*Carica Papaya*), shaddock (*Citrus decumana*), and several varieties of fig, melon, orange, lime, and citron. The mangoes of Bombay, of Múltán, and of Maldah in Bengal, and the oranges of the Khásí Hills enjoy a high reputation ; while the guavas of Madras and other Provinces make an excellent preserve.

Spices.

Among spices, for the preparation of curry and other hot dishes, turmeric and chillies hold the first place, and are very widely cultivated. Next in importance come ginger, coriander, aniseed, black cummin, and fenugreek. The pepper vine is confined to the Malabar coast, from Kánara to Travancore. Cardamoms are a valuable crop in the same locality, and also in the Nepálese Himálayas. The *pán* creeper (*Piper*

Petle), which furnishes the 'betel leaf,' is grown by a special caste in most parts of the country. Its cultivation requires constant care, but is highly remunerative. The areca palm, which yields the 'betel nut,' is chiefly grown in certain favoured localities, such as the deltaic Districts of Bengal, the Konkan of Bombay, and the highlands of Southern India.

Besides 'betel nut' (Areca Catechu), the palms of India Palms include the cocoa nut (*Cocos nucifera*), the bastard date (*Phoenix sylvestris*), the palmyra (*Borassus flabelliformis*), and the true date (*Phoenix dactylifera*). The cocoa nut, which loves a sandy soil and a moist climate, is found in greatest perfection along the strip of coast line which fringes the south-west of the peninsula, where it ranks next to rice as the staple product. The bastard date grown largely in the country round Calcutta, and in the north-east of the Madras Presidency, supplies both the jaggery sugar of commerce and intoxicating liquor for local consumption. Spirit is also distilled from the palmyra palm in many Districts especially in the Bombay Presidency and in the south of Madras. The true date is almost confined to Sind.

Sugar is manufactured both from the sugar cane and from Sugar the bastard date palm. The best cane is grown in the North Western Provinces, on irrigated land. It is an expensive crop, requiring much attention, and not yielding a return within the year. The profits are proportionately large. In Bengal, the manufacture from the cane has declined during the present century, but in Jessor District, the making of date sugar is a thriving and popular industry.¹ The preparation of sugar is almost everywhere in the hands of natives, the exceptions being a few large concerns, such as the Aska factory in the Madras District of Ganjam, the Cossipur factory in the suburbs of Calcutta, the Rosa factory at Shahjahanpur, and the Ashta gram factory in Mysore. These factories use sugar cane instead of the date juice, and have received honourable notice at exhibitions in Europe.

Cotton holds a most important place among Indian agricultural products. From the earliest times, cotton has been grown in sufficient quantities to meet the local demand, and in the last century there was some slight export from the country, which was carefully fostered by the East India Company. But the present importance of the crop dates from the crisis in Lancashire caused by the American War. The American War 1861-65.

¹ A full account of the manufacture will be found in *Herbert's Sugar and its Uses*, vol. II pp. 250-295.

Prior to 1860, the exports of raw cotton from India used to average less than 3 millions sterling a year; but after that year they rose by leaps, until in 1866 they reached the enormous total of 37 millions. Then came the crash, caused by the restoration of peace in the United States; and the exports steadily fell to just under 8 millions in 1879. Since then the trade has recovered, and the total value of raw cotton exports in 1882-83 amounted to 16 millions sterling. The fact is that Indian cotton has a short staple, and is inferior to American cotton for spinning the finer qualities of yarn. But while the cotton famine was at its height, the cultivators were intelligent enough to make the most of their opportunity. The area under cotton increased enormously, and the growers managed to retain in their own hands a fair share of the profit.

Cotton
Districts.

The principal cotton-growing tracts are—the plains of Gujarát and Káthiáwár, whence Indian cotton has received in the Liverpool market the historic names of *Surat* and *Dholera*; the highlands of the Deccan; and the deep valleys of the Central Provinces and Berar. The best native varieties are found in the Central Provinces and Berar, passing under the trade names of Hinganghát and Amráoti. These varieties have been successfully introduced into the Bombay District of Khándesh. Experiments with seed from New Orleans have been conducted for several years past on the Government farms in many parts of India. But it cannot be said that they have resulted in success except in the Bombay District of Dhárwár, where exotic cotton has now generally supplanted the indigenous staple.

Cotton
area in
Bombay;

in 1876;

and 1883.

In 1875-76, the area under cotton in the Bombay Presidency, including Sind and the Native States, amounted to 4,516,587 acres, with a yield of 2,142,835 cwts. Of this total, 583,854 acres, or 13 per cent., were sown with exotic cotton, including seed procured from the Central Provinces and also from New Orleans, with a yield of 248,767 cwts. The average yield was about 53 lbs. per acre, the highest being in Sind and Gujarát (Guzerát), and the lowest in the Southern Maráthá country. In 1875-76, the total exports were 3,887,808 cwts., from the Bombay Presidency, including the produce of the Central Provinces and the Berars, valued at £10,673,761. In 1882-83, the total area under cotton in the Bombay Presidency, including Sind and the Native States, was 5,698,862 acres, yielding 3,141,421 cwts. of cleaned cotton. Of this area 796,608 acres were sown with exotic cotton, yielding an out-turn of 420,494 cwts. The exports of raw cotton from

Bombay and Sind in 1882-83, including the produce of the Central Provinces and Berar, were 4,996,739 cwt., valued at £13,134,693, besides cotton twist and yarn and manufactured piece goods to the value of £2,183,205

In 1877-78, the area under cotton in the Central Provinces Cotton cultivation in Central Province 1878. was 837,083 acres, or under 6 per cent of the total cultivated area, chiefly in the Districts of Nágpur, Wardhá, and Ráipur. The average yield was about 59 lbs per acre. The exports from the Central Provinces to Bombay, including re-exports from Berar, were about 300,000 cwt. valued at £672,000. In 1877-78 the area under cotton in Berar In Berar was 2,078,273 acres, or 32 per cent of the total cultivated area, chiefly in the two Districts of Akola and Amráoti. The average yield was as high as 67 lbs of cleaned cotton per acre. The total export was valued at £2,354,946, almost entirely railway borne. In 1882-83, the area under cotton in the Central Provinces had decreased to 612,687 acres, or 4 per cent of the then cultivated area. In the same year, the area under cotton in Berar was 2,139,188 acres or 32 per cent of the cultivated area.

In Madras, the average area under cotton is about In Madras 1,500,000 acres, chiefly in the upland Districts of Bellary and Karnúl, and the low plains of Kistnár and Tinnevelly. The total exports in 1876-77 were 460,000 cwt., valued at about 1 million sterling. In 1882-83, cotton was grown on 1,456,423 acres in Madras. In the same year, the total value of the cotton exports from Madras, raw and manufactured, was £1,898,351. In Lower Bengal the cultivation of in Bengal cotton seems on the decline. The local demand has to be met by imports from the North Western Provinces and the bordering hill tracts, where a short stapled variety of cotton is extensively cultivated. The total area under cotton in Lower Bengal is estimated at only 162,000 acres, yielding 138,000 cwt. of cleaned cotton. Of this, 31,000 acres are in Sáran, 28,000 in the Chittagong Hill Tracts, and 20,000 in Cuttack. Throughout in the N.W. Provinces and Punjab the North Western Provinces, and also in the Punjab sufficient cotton is grown to meet the wants of the village weavers.

The total export of raw cotton from Indian ports in 1878-79 It was was 2,966,569 cwt., valued at £7,914,091, besides cotton cotton exports. twist and yarn to the value of £937,698, and cotton manufactures valued at £1,644,125. By 1882-83 the exports of 1878-79 raw cotton from all Indian ports had increased to 6,170,173 1883 cwt., valued at £16,055,758, besides cotton twist and yarn to the value of £1,874,461 and cotton manufactures valued

at £2,093,146. Total value of cotton exports in 1882-83, raw and manufactured, £20,023,368.

Cotton-cleaning.

1877;

and 1883.

The cotton-mills of Bombay will be treated of in the next chapter under 'Manufactures.' But apart from weaving and spinning, the cotton trade has given birth to other industries, for cleaning the fibre and pressing it into bales for carriage. In 1876-77, there were altogether 2506 steam gins for cleaning cotton in the Bombay Presidency, besides 22 in the Native States. In addition, there were 130 full-presses worked by steam power, and 183 half-presses worked by manual labour. In 1882-83, there were altogether 2787 steam gins for cleaning cotton in the Bombay Presidency, 96 steam cotton presses, and 141 cotton presses worked by manual labour. The total amount of capital invested in the cotton industry in the Bombay Presidency is estimated at about £900,000. Cotton gins and presses are also numerous at the chief marts in the North-Western and Central Provinces, and Berar.

Jute.

The jute area of Bengal.

Jute ranks next to cotton as a fibre crop. The extension of its cultivation has been equally rapid, but it is more limited in area, being practically confined to Northern and Eastern Bengal. In this tract, which extends from Purniah to Goalpará, for the most part north of the Ganges and along both banks of the Brahmaputra, jute is grown on almost every variety of soil. The chief characteristic of the cultivation is that it remains entirely under the control of the cultivator. Practically a peasant proprietor, he increases or diminishes his cultivation according to the state of the market, and keeps the profits in his own hands. The demand for jute in Europe has contributed more than any administrative measure to raise the standard of comfort throughout Eastern Bengal.

The jute plant.

The plant that yields the jute of commerce is called *pát* or *koshá* by the natives, and belongs to the family of mallows (*Corchorus olitorius* and *C. capsularis*). It sometimes attains a height of 12 feet. The seed is generally sown in April, the favourite soil being *chars*, or alluvial sandbanks thrown up by the great rivers; and the plant is ready for cutting in August. When it first rises above the ground, too much water will drown it; but at a later stage, it survives heavy floods. After being cut, the stalks are tied up in bundles, and thrown into standing water to steep. When rotted to such a degree that the outer coat peels off easily, the bundles are taken out of the water, and the fibre is extracted and carefully washed. It now appears as a long, soft, and silky thread; and all that remains to do is to make it up into bales for export. The

Preparation of fibre.

final process of pressing is performed in steam presses at the central river marts, principally at Howrah or in the outskirts of Calcutta. The trade is to a great extent in the hands of natives. *Beparis* or travelling hucksters go round in boats to all the little river marts, to which the jute has been brought by the cultivators. By their agency the produce is conveyed to a few great centres of trade, such as Sirájganj and Náringanj, where it is transferred to wholesale merchants, who ship it to Calcutta by steamer or large native boats, according to the urgency of demand.

In 1872-73 when speculation was briskest it is estimated that about 1 million acres were under jute distributed over 16 Districts which had a total cultivable area of 23 million acres. The total export from Calcutta in that year was about 7 million cwt., valued at £4,142,548. In 1878-79 the total export of raw jute from India was 6,021,382 cwt., valued at £3,800,426 besides jute manufactures to the value of £1,098,434. In 1880-83 the total exports of raw jute from Indian ports amounted to 10,348,909 cwt. of the value of £5,846,926, besides jute manufactures principally in the shape of gunny bags, of the aggregate value of £1,487,831. The total number of steam jute mills in Bengal either private property or owned by joint stock companies in 1882-83 was 18, affording employment to 41,263 persons.

Jute is an exhausting crop to soils without river inundation. This fact is well known to the cultivators who generally allow jute fields to lie fallow every third or fourth year. A fear has sometimes been expressed that the profits derived from jute may have induced the peasantry to neglect their grain crops. But the apprehension seems to be groundless. For the most part, jute is grown on flooded lands which would otherwise often lie untilled. It only covers a very small portion of the total area, even of the jute Districts, say 4 per cent., and the fertility of the rice fields of Eastern Bengal is such that they could support a much denser population than at present. Jute, in short, is not a rival of rice but a subsidiary crop, from which the cultivator makes a certain additional income in hard cash.

Indigo is one of the oldest, and, until the introduction of tea, ranked as the most important, of the Indian staples grown by European capital. In Bengal proper, its cultivation has greatly declined since the first half of this century. English indigo planters have forsaken the Districts of Hughli, the Twenty-four Parganas, Dacca, Banipur, Ranpur, and

Mechan-
ism of jute
trade

Jute out-
turn in
exports,
1873.

1878

1883

Affects the
the human
man

its dec-
e
in Lower
Bengal

Indigo. Pabná, now dotted with the sites of ruined old factories. In Nadiyá, Jessor, Murshidábád, and Maldah, the industry is still carried on; but it has not recovered from the depression and actual damage caused by the indigo riots of 1860, and the emancipation of the peasantry by the Land Act of 1859. Indigo of a superior quality is manufactured in Midnapur, along the frontier of the hill tracts.

Its cultivation in Behar;

The cultivation on the old scale still flourishes in Behar, from which is derived one-half of the total exports from Calcutta. Complete statistics of area are not available, as there are many small indigo concerns throughout the country in native hands. Some years ago, it was estimated that in Tirhut alone there were 56 principal concerns, with 70 out-works, producing annually about 20,000 *maunds* of dye; in Sāran, 30 principal concerns and 25 outworks, producing about 12,000 *maunds*; in Champāran, 7 large concerns, producing also 12,000 *maunds*.¹ The Behar Indigo Planters' Association, the responsible mouthpiece of the Behar indigo interest, has at present (1885) 73 factories belonging to the Association in the Indigo Districts of Behar. Under these head factories there are 220 out-factories, most of them in charge of European assistants. The area under indigo cultivation in the above concerns is approximately 250,000 acres, giving employment to 75,900 persons, exclusive of a large staff (Native and European) for management and supervision. The estimated outlay, at the rate of a little over £3 per acre, is about £750,000 annually spent in the Districts.² It has been estimated that the total amount of money annually distributed by the planters of Behar cannot be less than 1 million sterling.

in N.-W.

Provinces; Across the border of Bengal, in the North-Western Provinces, indigo is grown and manufactured to a considerable extent by native cultivators. In the Punjab, also, indigo is an important native crop, especially in the Districts of Múltán, Muzaffargarh,

in Madras.

and Dera Ghází Khán. In Madras, the total area under indigo is about 300,000 acres, grown and manufactured entirely by the natives, chiefly in the north-east of the Presidency, extending along the coast from Kistna to South Arcot, and inland to Karnúl and Cuddapah.

¹ The factory *maund* of indigo weighs 74 lbs. 10 oz.

² The author takes this opportunity of thanking Mr. E. Macnaghten, Officiating Secretary to the Behar Indigo Planters' Association, for the foregoing figures, and for other valuable materials, referring to as late a period as June 1885. They have, as far as possible, been incorporated in passing these pages through the press.

In 1877-78, the total export of indigo from all India was 120,605 cwts, valued at £3 494 334, in 1878-79, 105 051 cwts, valued at £2,960 463. In 1882-83 the export of indigo was 141,041 cwts, of the value of £3 912 997.

In Bengal, indigo is usually grown on low lying lands, with sandy soil, and liable to annual inundation, in Behar, on comparatively high land. A common practice is for the planter to obtain from the *amindar* or landlord a lease of the whole village area for a term of years and then to require the *ryots* or cultivators to grow indigo on a certain portion of their farms every year under a system of advances. The seed, of which an excellent kind comes from Cawnpur, is generally sown about March and the crop is ready for gathering by the beginning of July. A second crop is sometimes obtained in September. When cut the leaves are taken to the factory, to be steeped in large vats for about ten hours until the process of fermentation is completed. The water is then run off into a second vat and subjected to a brisk beating, the effect of which is to separate the particles of dye and cause them to settle at the bottom. Finally the sediment is boiled, strained, and made up into cakes for the Calcutta market. In recent years, steam has been introduced into the factories for two purposes to maintain an equable temperature in the vats while the preliminary process of fermentation is going on and to supersede by machinery the manual labour of beating.

In the middle of the present century the abuses connected with indigo-planting became a serious problem for the Indian Legislature. In some Districts, particularly in Lower Bengal, in the neighbourhood of Calcutta indigo planting was worked by a system of advances to the cultivators which plunged them into a state of hopeless hereditary indebtedness to the planters. The Land Law of 1859 (Act x) by defining and improving the legal status of the cultivator throughout Bengal gave a death blow to this system in Districts in which it had been abused. The results on indigo-planting in several Districts around Calcutta have been described in a previous paragraph.

The system pursued in Behar had, from an early period been different. Instead of compelling the cultivator to give up his best lands to indigo by the pressure of hereditary indebtedness, the Behar planters to a large extent obtained lands of their own on lease, or by purchase, and cultivated at their own risk or by hired labour. This system has, however, its own complications, and for a time gave rise to strained relations between the planters, the native landholders, and the tenants.

Behar
Indigo
Planters'
Associa-
tion.

In 1877, the Government of Bengal expressed dissatisfaction at the condition of the Indigo Districts of Behar, and proposed to issue a Commission of Inquiry. A responsible Association was, however, formed by the planters themselves, in communication with the Bengal Government, to readjust, as far as necessary, the relations between the planters, native landholders, and cultivators. The Association thus formed has been productive of much good, both by preventing the occurrence of disputes, and by arbitrating between the parties when disputes arise. In 1881, the Lieutenant-Governor of Bengal publicly thanked the Association for its 'most cordial and loyal co-operation in correcting the abuses which he had occasion to mention in 1877.' The Annual Reports from the District Officers since that year have been satisfactory. During 1884, the Secretary to the Association stated that every dispute referred to the Association had been amicably adjusted. The relations between capital and labour and land in overcrowded tracts, almost entirely dependent on the local crops raised, are, however, always apt to be strained.

Opium,

The opium of commerce is grown and manufactured in two special tracts: (1) the valley of the Ganges round Patná and Benares; and (2) a fertile table-land in Central India, corresponding to the old kingdom of Málwá, for the most part still under the rule of native chiefs, among whom Sindhia and Holkar rank first. In Málwá, the cultivation of poppy is free, and the duty is levied as the opium passes through the British Presidency of Bombay; in Bengal, the cultivation is a Government monopoly. Opium is also grown for local consumption throughout Rájputána, and to a very limited extent in the Punjab and the Central Provinces. Throughout the rest of India it is absolutely prohibited. In the Ganges valley, the cultivation is supervised from two agencies, with their head-quarters at Patná and Gházípur, at which two towns alone the manufacture is conducted.

in Bengal
and
Malwá.

in Ráj-
putána.

Bengal
out-turn;
1872;

and 1883.

In the year 1872, the Bengal area under poppy was 560,000 acres; the number of chests of opium sold was 42,675; the sum realized was £6,067,701, giving a net revenue of £4,259,376. The whole of this was exported from Calcutta to China and the Straits Settlements. In 1882-83, the number of chests of Bengal opium sold was 56,400, the sum realized was £7,103,925, the net revenue being £4,821,712. The amount of opium exported from Bombay raises the average exports of opium to about 11 or 12 millions sterling, of which about 7 or 8 millions represents net profit to Government. In 1878-79, 91,200 chests of opium

were exported from India, of the value of £12,993,985, of which £7,700,000 represented the net profit to Government. In 1882-83, 91,798 chests of Bengal and Malwa opium were exported, of the value of £11,481,379, of which £7,216,778 represented the net profit to Government

Under the Bengal system, annual engagements are entered into by the cultivators to sow a certain quantity of land with poppy, and it is a fundamental principle that they may engage or refuse to engage, as they please. As with most other Indian industries, a pecuniary advance is made to the cultivator before he commences operations, to be deducted when he delivers over the opium at the subordinate agencies. He is compelled to make over his whole produce, being paid at a fixed rate, according to quality. The best soil for poppy is high land which can be easily manured and irrigated. The cultivation requires much attention throughout. From the commencement of the rains in June until October, the ground is prepared by repeated ploughing, weeding, and manuring. The seed is sown in the first fortnight of November, and several waterings are necessary before the plant reaches maturity in February.

After the plant has flowered, the first process is to remove the petals, which are preserved, to be used afterwards as coverings for the opium-cakes. The juice is then collected during the month of March, by scarifying the capsules in the afternoon with an iron instrument, and scraping off the exudation next morning. The quality of the drug mainly depends upon the skill with which this operation is performed. In the beginning of April, the cultivators bring in their opium to the subordinate agencies, where it is examined and weighed, and the accounts are settled. The final process of preparing the drug in balls for the Chinese market is conducted at the two central agencies at Patna and Ghazipur. This generally lasts until the end of July, but the balls are not dry enough to be packed in chests until October.

Tobacco is grown in every District of India for local consumption. The soil and climate are favourable, but the quality of native cured tobacco is so inferior, as to scarcely find a market in Europe. The principal tobacco-growing tracts are Rangoon and Tishut in Bengal, Kaira in Bombay, the delta of the Godavari, and Coimbatore and Madurai Districts in Madras. The two last mentioned Districts supply the raw material for the well known 'Trichinopoly cheroot,' almost the only form of Indian tobacco that finds favour with Europeans, the produce of the *linkets* or alluvial islands in the Godavari is manufactured into 'Coimbatore.' The tobacco of Northern Bengal is lar-

exported to British Burma; for the Burmese, who are great smokers, do not grow sufficient for their own needs. The manufacture of tobacco in Madras, Burma, and Bengal, is now making progress under European supervision, and promises to supply an important new staple in the exports of India.

Tobacco
trade;
1877;

In 1876-77, the total registered imports of tobacco into Calcutta from the inland Districts were 521,700 *maunds*, valued at £261,000, of which more than half came from the single District of Rangpur. Tobacco is also grown for export in the Chittagong Hill Tracts. The tobacco of Tirhut is chiefly exported towards the west. The total area under tobacco in that District is estimated at 40,000 acres, the best quality being grown in *parganā* Saressa of the Tājpur Sub-division. In 1882-83, the imports of tobacco from the inland Districts into Calcutta were 650,583 *maunds*, of an estimated value of £540,601.

and 1883.

Tobacco-
curing.

During the past ten years, a private firm, backed by Government support, has been growing tobacco in Northern India, and manufacturing it for the European market. The scene of its operations is two abandoned stud-farms, at Gházipur in the North-Western Provinces, and at Pusa in Tirhut District, Bengal. In 1878-79, about 240 acres were cultivated with tobacco, the total crop being about 160,000 lbs. Five English or American curers were employed. Some of the produce was exported to England as 'cured leaf;' but the larger part was put upon the Indian market in the form of 'manufactured smoking mixture.' This mixture is in demand at regimental messes and canteens, and has also found its way to Australia. The enterprise may now be said to have passed beyond the stage of experiment. An essential condition of success is skilled supervision in the delicate process of tobacco-curing. Tobacco to the value of £128,330 was exported from India in 1878-79, and to the value of £117,156 in 1882-83.

Uncer-
tainty of
Indian
crop
statistics.

Before proceeding to crops of a special character, such as coffee, tea, and cinchona, it may be well to give a general view of the area covered by the staples of Indian agriculture. The table on the opposite page must be taken as approximate only. It represents, however, the best information available (1882-83). Its figures show various changes from the estimates in 1875, incorporated in some of the foregoing paragraphs. But it is necessary to warn the reader, that Indian agricultural returns do not always stand the test of statistical analysis. In most cases the local returns have to be accepted without the possibility of verification; alike in the preceding pages, and in this tabular statement. Steps are now being taken to secure a higher degree of trustworthiness in such returns.

APPROXIMATE AREA IN ACRES OCCUPIED BY THE PRINCIPAL CROPS IN SOME INDIAN PROVINCES IN 1877-78
AND 1882-83

	Madras.		Bombay and Sind		Punjab	Central Provinces.		British Burma	Mysore	Tihar		
	1877-78	1882-83	1877-78	1882-83	1877-78	1882-83	1877-78	1882-83	877-8	1881-82*	1877-78	1882-83
Rice	4,600,000	5,608,750	1,070,000	7,871,315	4,000,000	775,367	4,550,000	4,460,542	5,000,000	554,32	31,000	22,827
Wheat	36,000	27,051	9,500	1,625,544	7,000,000	6,731,57	3,600,000	3,619,704	11,000	27,058	575,008	46,31
Maize and other grains	10,600,000	10,747,384	6,736,000	17,408,725	6,000,000	8,505,142	5,400,000	5,68,174	3,400,000	319,500	2,760,000	2,302,542
Pulses	1,600,000	1,955,945	945,000	1,767,777	3,200,000	3,664,951	5		3,400,000	319,500	2,760,000	2,302,542
Oil seeds.	200,000	1,663,583	268,000	2,336,385	2,000,000	37,633	1,600,000	1,600,225	15,000	147,454	460,000	445,000
Cotton	1,000,000	1,456,473	1,400,000	2,640,748	6,000,000	2,600,63	8,400,000	6,268,7	15,000	20,893	2,020,000	2,130,188
Tobacco	60,000	8,707	4,000	59,377	80,000	66,790	48,000	27,866	17,000	12,566	17,000	24,722
Opium	120,000	50,74	24,000	17,735	110,000	162,703	85		700			
Sugarcane	21,000	4,716	24,000	66,300	30,000	40,045	100,000	53,938	4,000	24,076	5,000	4,500

* No later statistics available for Mysore than those for 1881-82, the last year in which the State was under British administration.

in 1877-78 were 33,399,352 lbs, valued at £1,355 643, of Coffee which about one half was consigned to the United Kingdom ^{exports, 1878}
 In 1878-79, the exports amounted to 38,336,000 lbs, valued at £1,548,481 In 1882-83, the exports amounted to 40,768,896 lbs, but the value had slightly decreased to £1,419,131 The decrease in value was mainly due to a fall in prices in London, owing to an overstocked market Nearly two-thirds of the coffee exports in 1882-83 were to the United Kingdom, and over one fourth to France

Considerable judgment is required to select a suitable site ^{Sites for coffee gardens} for a coffee garden for the shrub will only thrive under special circumstances, which it is not very easy to anticipate before hand It is essential that the spot should be sheltered from the full force of the monsoon, and that the rainfall, though ample, should not be excessive The most desirable elevation ^{elevation} is between 2500 and 3500 feet above sea level The climate must be warm and damp conditions which are not conducive to the health of Europeans Almost any kind of forest land will do, but the deeper the upper stratum of decomposed vegetable matter the better

The site chosen for a garden is first cleared with the axe, ^{clearing} of jungle and undergrowth, but sufficient timber trees should be left to furnish shade In the month of December, the berries are sown in a nursery, which has previously been dug manured, weeded and watered as carefully as a garden Between June and August the seedlings are planted out in pits dug in prepared ground at regular intervals an operation ^{cultivation} which demands the utmost carefulness in order that the roots may not be injured In the first year weeding only is required, in the second year, the shrubs are topped to keep them at an average height of about three feet in the third year they commence to bear, but it is not until the seventh or eighth year that the planter is rewarded by a full crop The season for blossoming is March and April, when the entire shrub burgeons in a snowy expanse of flower, with a most delicate fragrance Gentle showers or heavy mists at this season contribute greatly to the fecundity of the blossoms

The crop ripens in October and November The berries ^{picking} are picked by hand, and collected in baskets to be 'pulped' on ^{pulping} the spot This operation is performed by means of a revolving iron cylinder, fixed against breastwork at such an interval that only the 'beans' proper pass through, while the husks are rejected The beans are then left to ferment for about twenty four hours, when their saccharine covering is washed off

Coffee. The cultivation of coffee is confined to Southern India, although attempts have been made to introduce the plant both into British Burma and into the Bengal District of Chittagong. The coffee tract may be described as a section of the landward slope of the Western Gháts, extending from Kánara in the north to Travancore in the extreme south. This tract includes almost the whole of Coorg, the Districts of Kadur and Hassan in Mysore, and the Nilgiri Hills enlarged by the recent annexation of the Wainád. Within the last few years, the cultivation has extended to the Shevaroy Hills in Salem District, and to the Palni Hills in Madura.

Coffee area.

Introduction into India. Unlike tea, coffee was not introduced into India by European enterprise; and even to the present day its cultivation is largely conducted by natives. The Malabar coast has always enjoyed a direct commerce with Arabia, and yielded many converts to Islám. One of these converts, Bába Budan, is said to have gone on a pilgrimage to Mecca, and to have brought back with him the coffee berry, which he planted on the hill range in Mysore still called after his name. According to local tradition, this introduction of the berry happened about two centuries ago. The shrubs thus sown lived on, but the cultivation did not spread until the beginning of the present century.

The State of Mysore and the Bába Budan range also witnessed the first opening of a coffee-garden by an English planter about forty-five years ago. The success of this experiment led to the extension of coffee cultivation into the neighbouring tract of Manjarábád, also in Mysore, and into the Wainád Sub-division of the Madras District of Malabar. From 1840 to 1860, the enterprise made slow progress; but since the latter date, it has spread with great rapidity along the whole line of the Western Gháts, clearing away the primeval forest, and opening a new era of prosperity to the labouring classes.

Its progress, 1840-60.

Coffee statistics, 1878-82; area: The following statistics relate to the years 1878 and 1882. In 1877-78, there were under coffee—in Mysore, 128,438 acres, almost confined to the two Districts of Hassan and Kadur; in Madras, 58,988 acres, chiefly in Malabar, the Nilgiris, and Salem; in Coorg, 45,150 acres: total, 232,576 acres, exclusive of Travancore. In 1881-82, the latest year for which statistics are available for Mysore, the total area under coffee cultivation in that State was 159,165 acres; in Madras (in 1882-83), 61,481 acres; and in Coorg, 48,150 acres. The average out-turn is estimated at about 5 or 6 cwt. per acre of mature plant. The total Indian exports (from Madras)

in 1877-78 were 33,399,352 lbs, valued at £1,355 643, of which about one half was consigned to the United Kingdom. In 1878-79, the exports amounted to 38,336,000 lbs, valued at £1,548,481. In 1882-83, the exports amounted to 40,768,896 lbs, but the value had slightly decreased to £1,419,131. The decrease in value was mainly due to a fall in prices in London, owing to an overstocked market. Nearly two-thirds of the coffee exports in 1882-83 were to the United Kingdom, and over one fourth to France.

Considerable judgment is required to select a suitable site for a coffee garden for the shrub will only thrive under special circumstances which it is not very easy to anticipate before hand. It is essential that the spot should be sheltered from the full force of the monsoon, and that the rainfall, though ample, should not be excessive. The most desirable elevation is between 2500 and 3500 feet above sea level. The climate must be warm and damp conditions which are not conducive to the health of Europeans. Almost any kind of forest land will do, but the deeper the upper stratum of decomposed vegetable matter the better.

The site chosen for a garden is first cleared with the axe of jungle and undergrowth, but sufficient timber trees should be left to furnish shade. In the month of December, the berries are sown in a nursery, which has previously been dug manured, weeded, and watered as carefully as a garden. Between June and August, the seedlings are planted out in pits dug in prepared ground at regular intervals, an operation which demands the utmost carefulness in order that the roots may not be injured. In the first year, weeding only is required, in the second year, the shrubs are 'topped', to keep them at an average height of about three feet, in the third year they commence to bear, but it is not until the seventh or eighth year that the planter is rewarded by a full crop. The season for blossoming is March and April, when the entire shrub burgeons in a snowy expanse of flower, with a most delicate fragrance. Gentle showers or heavy mists at this season contribute greatly to the fecundity of the blossoms.

The crop ripens in October and November. The berries are picked by hand, and collected in baskets to be 'pulped' on the spot. This operation is performed by means of a revolving iron cylinder, fixed against a breastwork at such an interval that only the 'beans' proper pass through, while the husks are rejected. The beans are then left to ferment for about twenty-four hours, when their saccharine covering is washed off.

Coffee.

The cultivation of coffee is confined to Southern India, although attempts have been made to introduce the plant both into British Burma and into the Bengal District of Chittagong. The coffee tract may be described as a section of the landward slope of the Western Gháts, extending from Kánara in the north to Travancore in the extreme south.

Coffee area.

This tract includes almost the whole of Coorg, the Districts of Kadur and Hassan in Mysore, and the Nilgiri Hills enlarged by the recent annexation of the Wainád. Within the last few years, the cultivation has extended to the Shevaroy Hills in Salem District, and to the Palni Hills in Madura.

Introduction into India.

Unlike tea, coffee was not introduced into India by European enterprise; and even to the present day its cultivation is largely conducted by natives. The Malabar coast has always enjoyed a direct commerce with Arabia, and yielded many converts to Islám. One of these converts, Bába Budan, is said to have gone on a pilgrimage to Mecca, and to have brought back with him the coffee berry, which he planted on the hill range in Mysore still called after his name. According to local tradition, this introduction of the berry happened about two centuries ago. The shrubs thus sown lived on, but the cultivation did not spread until the beginning of the present century.

Its progress, 1840-60.

The State of Mysore and the Bába Budan range also witnessed the first opening of a coffee-garden by an English planter about forty-five years ago. The success of this experiment led to the extension of coffee cultivation into the neighbouring tract of Manjarábád, also in Mysore, and into the Wainád Sub-division of the Madras District of Malabar. From 1840 to 1860, the enterprise made slow progress; but since the latter date, it has spread with great rapidity along the whole line of the Western Gháts, clearing away the primeval forest, and opening a new era of prosperity to the labouring classes.

Coffee statistics, 1878-82; area;

The following statistics relate to the years 1878 and 1882. In 1877-78, there were under coffee—in Mysore, 128,438 acres, almost confined to the two Districts of Hassan and Kadur; in Madras, 58,988 acres, chiefly in Malabar, the Nilgiris, and Salem; in Coorg, 45,150 acres: total, 232,576 acres, exclusive of Travancore. In 1881-82, the latest year for which statistics are available for Mysore, the total area under coffee cultivation in that State was 159,165 acres; in Madras (in 1882-83), 61,481 acres; and in Coorg, 48,150 acres. The average out-turn is estimated at about 5 or 6 cwts. per acre of mature plant. The total Indian exports (from Madras)

Exports.

in 1877-78 were 33,399,352 lbs., valued at £1,355,643 of Coffee, which about one-half was consigned to the United Kingdom. ^{Exports, 1878}
In 1878-79, the exports amounted to 38,336,000 lbs., valued at £1,548,481. In 1882-83 the exports amounted to 40,769,896 lbs., but the value had slightly decreased to £1,410,131. The decrease in value was mainly due to a fall in prices in London, owing to an over-stocked market. Nearly two-thirds of the coffee exports in 1882-83 were to the United Kingdom, and over one-fourth to France.

Considerable judgment is required to select a suitable site for a coffee-garden for the shrub will only thrive under special circumstances, which it is not very easy to anticipate beforehand. It is essential that the spot should be sheltered from the full force of the monsoon, and that the rainfall, though ample, should not be excessive. The most desirable elevation is between 2500 and 3500 feet above sea level. The climate must be warm and damp, conditions which are not conducive to the health of Europeans. Almost any kind of forest land will do, but the deeper the upper stratum of decomposed vegetable matter the better. ^{Site for coffee-garden, elevation}

The site chosen for a garden is first cleared with the axe, of jungle and undergrowth, but sufficient timber trees should be left to furnish shade. In the month of December, the berries are sown in a nursery, which has previously been dug manured, weeded, and watered as carefully as a garden. Between June and August, the seedlings are planted out in pits dug in prepared ground at regular intervals, an operation which demands the utmost carefulness in order that the roots may not be injured. In the first year, weeding only is required, in the second year, the shrubs are 'topped,' to keep them at an average height of about three feet, in the third year they commence to bear, but it is not until the seventh or eighth year that the planter is rewarded by a full crop. The season for blossoming is March and April, when the entire shrub burgeons in a snowy expanse of flower, with a most delicate fragrance. Gentle showers or heavy mists at this season contribute greatly to the fecundity of the blossoms. ^{clearing, cultivation,}

The crop ripens in October and November. The berries are picked by hand, and collected in baskets to be 'pulped' on the spot. This operation is performed by means of a revolving iron cylinder, fixed against a breastwork at such an interval that only the 'beans' proper pass through, while the husks are rejected. The beans are then left to ferment for about twenty-four hours, when their saccharine covering is washed off ^{picking, pulping,}

- Coffee; After drying in the sun for six or eight days, they are ready to be put in bags and despatched from the garden. But before being shipped, they have yet to be prepared for the home market. This is done at large coffee-works, to be found at the western ports and in the interior of Mysore. The berries are here 'peeled' in an iron trough by broad iron wheels, worked by steam power; and afterwards 'winnowed,' graded, and sorted for the market.
- peeling.
- Tea. The cultivation of tea in India commenced within the memory of men still living, and the industry now surpasses even indigo as a field for European capital. Unlike coffee-planting, the enterprise owes its origin to the initiation of Government, and it was slow to attract the attention of the natives. Early travellers reported that the tea-plant was indigenous to the southern valleys of the Himálayas; but they were mistaken in the identity of the shrub, which was the *Osyris nepalensis*. The real tea (*Thea viridis*), a plant akin to the camellia, grows wild in Assam, being commonly found throughout the hill tracts between the valleys of the Brahmaputra and the Bárák. It there sometimes attains the dimensions of a large tree; and from this, as well as from other indications, it has been plausibly inferred that Assam is the real home of the plant, which was thence introduced at a prehistoric date into China.
- Home of the tea-plant, Assam.
- Discovered 1826. The discovery of the tea-plant growing wild in Assam is generally attributed to two brothers named Bruce, who brought back specimens of the plant and the seed, after the conquest of the Province from the Burmese in 1826. In January 1834, under the Governor-Generalship of Lord William Bentinck, a committee was appointed 'for the purpose of submitting a plan for the introduction of tea-culture into India.' In the following year, plants and seed were brought from China, and widely distributed throughout the country. Government itself undertook the formation of experimental plantations in Upper Assam, and in the sub-Himálayan Districts of Kumáun and Garhwál in the North-Western Provinces. A party of skilled manufacturers was brought from China, and the leaf which they prepared was favourably reported upon in the London market. Forthwith private speculation took up the enterprise.
- State experiments, 1834-49. The Assam Tea Company, still the largest, was formed in 1839, and received from the Government an extensive grant of land, with the nurseries which had been already laid out. In Kumáun, retired members of the civil and military services came forward with equal eagerness. Many fundamental mis-
- Private Companies, 1839-51.

takes as to site, soil, and methods of manufacture were made in those early days, and bitter disappointment was the chief result. But while private enterprises languished, Government steadily persevered. It retained a portion of its Assam gardens in its own hands until 1849, when the Assam Company began to emerge from their difficulties. Government also carried on the business at Lumfun, under the able management of Dr Jameson, as late as 1855.

The real progress of tea planting on a great scale in Assam dates from about 1851, and was greatly assisted by the promulgation of the Waste Land Rules of 1854. By 1859 there were already 51 gardens in existence, owned by private individuals, and the enterprise had extended from its original headquarters in Lakhimpur and Sibsagar as far down the Brahmaputra as Kamrup. In 1856 the tea plant was discovered wild in the District of Cachar in the Barak valley, and Euro-Cachar perni capital was at once directed to that quarter. At about the same time, tea planting was introduced into the neighbourhood of the Himalayan sanitarium of Darjiling, among the Darjiling Sikkim Himalayas.

The success of these undertakings engendered a wild spirit of speculation in tea companies, both in India and at home, which reached its climax in 1865. The industry recovered but slowly from the effects of the disastrous crisis, and did not again reach a stable position until 1869. Since that date it has rapidly but steadily progressed, and has been ever opening new fields of enterprise. At the head of the Bay of Bengal in Chittagong District, side by side with coffee on the Nilgiri Hills, on the forest-clad slopes of Chutia Nagpur, amid the low lying jungle of the Bhutan Dwarfs, and even in Arakan, the energetic pioneers of tea planting have established their industry. Different degrees of success may have rewarded them, but in few cases have they abandoned the struggle. The market for Indian tea is practically inexhaustible. There is no reason to suppose that all the suitable localities have yet been tried, and we may look forward to the day when India will not only rival, but supersede, China in her staple product.

The total exports of tea in 1877-78 from British India ports amounted to 33½ million lbs., valued at a little over 3 millions sterling. During the next five years the exports had risen to 58½ million lbs. in 1882-83, valued at 3½ millions sterling. The detailed figures for all India, including exports across the frontier by land, will be presently given.

The progress of the tea industry in the various Provinces may best be illustrated by a review of the statistics of the production in the two years 1877-78 and 1882-83.

Provincial statistics of tea, 1878.	In 1877-88, the total area taken up for tea in Assam, including both the Brahmaputra and the Bārak valleys, was 736,082 acres, of which 538,961 acres were fit for cultivation; the total number of separate estates was 1718; the total out-turn was 23,352,298 lbs., at the average rate of 286 lbs. per acre under mature plant.
Assam.	In Bengal, the area taken up was 62,642 acres, of which 20,462 acres were under mature plant, including 18,120 acres in the single District of Dárrjiling; the number of gardens was 221; the out-turn was 5,768,654 lbs., at the rate of 282 lbs. per acre under mature plant.
Bengal.	In the North-Western Provinces there were, in 1876, 25 estates in the Districts of Kumáun and Garhwál, with an out-turn of 578,000 lbs., of which 350,000 lbs. were sold in India to Central Asian merchants; and in 1871, 19 estates in Dehra Dún, with 2024 acres under tea, and an out-turn of 297,828 lbs.
N.-W. Provinces.	In the Punjab there were, in 1878, 10,046 acres under tea, almost entirely confined to Kángra District, with an out-turn of 1,113,106 lbs., or 111 lbs. per acre.
Punjab.	In Madras, the area under tea on the Nilgiris was 3160 acres; the exports from the Presidency were 183,178 lbs., valued at £19,308.
Madras.	In 1882-83, the area actually under cultivation in Assam was 178,851 acres, of which 156,707 acres were under mature, and 22,144 acres under immature plant. Besides the area already occupied with tea, some 600,000 acres have been taken up for plantation purposes, and immense tracts yet untouched are still available. The present (1884) depressed state of the tea market, due, it is said, to over-production and attention to quantity rather than to quality, has, however, for the present checked the further appropriation of land for tea.
Provincial statistics of tea, 1882-83.	The total out-turn from 1017 tea estates in Assam in 1882-83 is returned at 45,472,941 lbs., of which 28,089,805 lbs. were manufactured in the Brahmaputra valley or Assam proper, and 17,383,136 lbs. in the Surmá valley Districts of Cachar and Sylhet. Average out-turn, 290 lbs. per acre of mature plant. The figures given above for 1882-83 show a larger area under plant, and a very considerable increase in out-turn, over that of any previous year. Approximate value of tea exports from Assam into Bengal, £2,232,524.
Assam.	In Bengal the area under tea cultivation in 1882-83 was 48,091 acres, of which 36,079 acres were under mature, and

12,012 acres under immature plant. There were also 16,093 Bengal acres taken up for tea, but not actually under plant. The total number of plantations was 300, with an outturn of 11,170,564 lbs., being at the rate of 309 lbs. per acre of mature plant. More than three fourths of the Bengal tea come from Dárrjiling and Jilpaiguri Districts, on the lower slopes or submontane tracts of the Himalayas. The cultivation, however, is rapidly extending in other localities, as in Chittagong, on the east coast of the Bay of Bengal and in the elevated plateau of Chittur Nagpur. In the Punjab out of Punjab 11,058 acres under tea in 1882-83 no fewer than 10,075 acres were in Kangra District. The total outturn in 1882-83 is not returned but may be estimated at about 1 million lbs. In Madras 5337 acres were under tea in 1882-83, but the Madras outturn is not stated although the exports amounted to 309,548 lbs. valued at £37,905.

The following figures exhibit the exports of tea in 1878 and 1883. In 1877-78 the total export of tea by sea from British India amounted to 33,656,713 lbs. valued at £3,061,867. In 1882-83 the amount was 36,233,345 lbs., valued at £3,738,842. With the exception of Madras which exported 309,548 lbs. of tea in 1882, valued at £32,305 and Chittagong, at which an export trade in tea has sprung up, the whole exports of Indian tea are shipped from Calcutta. The bulk of the tea goes to the United Kingdom which absorbed 53,415,603 lbs., valued at £3,389,406 from Bengal in 1882-83. The Calcutta Tea Syndicate, established a few years ago with a view to opening new markets for Indian tea, has succeeded in establishing a firm, and it is hoped an increasing trade in tea with the Australian colonies and the United States. Exports to Australia, which in 1881-82 amounted to 871,913 lbs. valued at £63,404, were forced up in 1882-83 to 2,713,268 lbs., valued at £177,167. Similarly the exports to the United States increased from 197,666 lbs., valued at £14,675 in 1871-72, to 671,264 lbs., valued at £50,903 in 1882-83. The effect of this sudden expansion of trade however was to diminish the export of tea to the United States and it fell from 1,000,000 lbs. in 1871-72 to 600,000 lbs. in 1882-83. The transference of export from the United States to Australia was a result of the fact that the United States had a large surplus of tea in 1882-83, the exports of Indian tea to the United States were 1,000,000 lbs., valued at £19,922 in 1882-83, and the exports of Indian tea to the United States in 1877-78 were 1,000,000 lbs., valued at £19,922 in 1877-78.

The following figures exhibit the exports of tea by sea from British India in 1877-78 and 1882-83.

almost the whole was, till recently, sent to the United Kingdom.

Tea cultivation. The processes of cultivation and manufacture are very similar throughout the whole of India, with the exception that in Upper India the leaf is prepared as green tea for the markets of Central Asia. Three main varieties are recognised—Assam, China, and hybrid. The first is the indigenous plant, sometimes attaining the dimensions of a tree; yielding a strong and high-priced tea, but difficult to rear. The China variety, originally imported from that country, is a short bushy shrub, yielding a comparatively weak tea and a small out-turn per acre. The third variety is a true hybrid, formed by crossing the two other species. It combines the qualities of both in varying proportions, and is the kind most sought after by planters.

Seed. In all cases, the plant is raised from seed, which in size and appearance resembles the hazel-nut. The seeds are sown in carefully prepared nurseries in December and January, and at first require to be kept shaded. About April, the seedlings are sufficiently grown to be transplanted, an operation which continues into July.

Sites for tea-gardens. The site selected for a tea-garden should be well-drained and comparatively elevated land; as it is essential that water should not lodge round the roots of the plants. In Assam, which may be taken as the typical tea district, the most favourite situation is the slopes of low hills, that everywhere rise above the marshy valleys. On the summit may be seen the neat bungalow of the planter, lower down the coolie lines, while the tea bushes are studded in rows with mathematical precision all round the sides. The best soil is virgin forest land, rich in the decomposed vegetable matter of ages. Great pains are expended to prevent this fertile mould from being washed away by the violence of the tropical rains. In bringing new land into condition, the jungle should be cut down in December, and burned on the spot in February. The ground is then cleaned by the plough or the hoe, and marked out for the seedlings by means of stakes planted at regular intervals of about 4 feet from each other.

Work of a tea-garden; For the first two years, the work of the planter is to keep the young shrubs clear of weeds. Afterwards, it is necessary to prune the luxuriance of the bushes in the cold season every year. The prunings should be buried round the roots of the plant for manure. The plants begin to come into bearing in the third year, and gradually reach their maximum yield in their tenth year. The produce consist of the 'flushes';

or successive shoots of young leaves and buds, which first appear in the beginning of the rainy season. There are from five to seven full flushes in the season from March to November. The bushes are picked about every ten days by the women and children, who are paid by weight on bringing their baskets to the factory, when the operation of manufacture forthwith begins.

The leaf is first spread out lightly on trays or mats in order that it may 'wither,' i.e. become limp and flaccid. Under favourable conditions, this result is effected in a single night, but sometimes the natural process has to be accelerated by exposure to the sun or by means of artificial heat. The next operation is known as 'rolling,' performed either by the manual labour of coolies or by machinery. The object of this is to twist and compress the leaf into balls and set up fermentation. The final stage is to arrest fermentation by drying, which may be effected in many ways usually by the help of machinery. The entire process of manufacture after 'withering,' does not take more than about four hours and a half. All that now remains is to sort the tea in sieves according to size and quality, thus distinguishing the various grades from Flowery Pekoe to Broken Congou and to pick it for shipment in the well known tea chests.

The introduction of the quinine yielding cinchona into India is a remarkable example of success rewarding the indefatigable exertions of a single man. When Mr Clement Markham undertook the task of transporting the seedlings from South America to India in 1860, cinchona had never before been reared artificially. The experiment in arboriculture has not only been successfully conducted, but it has proved remunerative from a pecuniary point of view. A cheap substitute has been provided for the fever-stricken population of the Indian plains, while the surplus bark sold in Europe more than repays interest upon the capital expended. These results have been produced from an expenditure of about £100,000.

The head quarters of cinchona cultivation in Southern India are on the Nilgiri Hills, where Government owns four plantations, from which seeds and plants are annually distributed to the public in large quantities, and there are already several private plantations, rivalling the Government estates in area, and understood to be very valuable properties. The varieties of cinchona most commonly cultivated are *C. officinalis* and *C. succirubra*; but experiments are

being conducted with *C. calisaya*, *C. pubescens*, *C. lanceolata*, and *C. pitayensis*. Now that the success of the enterprise is secure, the Madras Government is curtailing its own operations. No fresh land is being taken up, but the plantations are kept free from weeds. The quinologist's department has been abolished, and the bark is sold in its raw state.

Spread of
cinchona ;

From the central establishment of the Government on the Nilgiris, cinchona has been introduced into the Palni Hills in Madura District, into the Wainád, and into the State of Travancore. The total area under cinchona in Government and private plantations in 1882-83 was 2607 acres. Plantations have also been opened by Government near Merkára in Coorg, on the Bába Budan Hills in Mysore, and in Tsit-taung (Sitang) District in British Burma. Failure has attended the experiments made at Mahábaleshwar in the Bombay Presidency, and at Nongklao in the Khásí Hills, Assam.

in
Southern
India ;

in Bengal.

But the success of the Government plantation at Dárjiling, in Northern Bengal, rivals that of the original plantation on the Nilgiris. The area has been gradually extended, and the bark is manufactured into quinine on the spot by a Government quinologist. The species mostly grown is *C. succirubra*, which yields a red-coloured bark, rich in its total yield of alkaloids, but comparatively poor in quinine proper. Efforts are being made to increase the cultivation of *C. calisaya*, which yields the more valuable bark ; but this species is difficult to propagate.

Cinchona.
Alkaloids.

The febrifuge, as issued by the Bengal Government, is in the form of a white powder, containing the following alkaloids :—Quinine, cinchonidine, cinchonine, quinamine, and what is known as amorphous alkaloid. It has been authoritatively described as 'a perfectly safe and efficient substitute for quinine in all cases of ordinary intermittent fever.' It has been substituted for imported quinine, in the proportion of three-fourths to one-fourth, at all the Government dispensaries, by which measure alone an economy of more than £20,000 a year has been achieved ; and it is now eagerly sought after by private druggists from every part of the country.

Cinchona
statistics,
1877-78.

The following show the out-turn and financial results of the two large Government plantations in 1877-78 and in 1882-83 :—In 1877-78, the crop on the Nilgiris gave 138,808 lbs. of bark, of which 132,951 lbs. were shipped to England, and the rest supplied to the Madras and Bombay medical departments. At Dárjiling, the crop in 1877-78 amounted to 344,225 lbs.

of bark, which was all handed over to the quinologist, and yielded 5162 lbs of the febrifuge

In 1882-83 the four Government plantations on the Nilgiri Hills comprised a total area of 847 acres, with 765,763 full grown plants. The total out turn of bark (exclusive of stocks in hand) was 129 713 lbs. The quantity shipped to the home market was 62,518 lbs, realizing £9768, while 69 377 lbs. were sold locally by public auction, realizing £10,639 or an average of 3s 1¹/₂d per lb. The total proceeds from the Nilgiri plantations in 1882-83, including sale of seeds, plants, etc., was £20 842, expenditure, £8335 leaving a profit of £12,507. In the Government plantations in Dárrjiling District, the area in 1882 was 2294 acres, with 4 711,168 full grown plants. The out turn of the year, 396 980 lbs of dry bark, was the heaviest ever yielded. By far the greater proportion was converted locally into cinchona febrifuge by the Government quinologist, while about 42,000 lbs of bark were forwarded to London at the request of the Secretary of State to be there converted into various forms of febrifuge, and returned to India for trial by the Medical Department. The revenue derived from the Dárrjiling sales to the public, to the medical and other departments, and from sale of seeds, plants, etc., amounted to £15 280 in 1882-83, the operations of the year resulting in a direct profit of £6628, equal to a dividend of 6½ per cent on the capital outlay. Total profit from the Nilgiri and Dárrjiling plantations in 1882-83, £19 135.

These profits, however, do not represent the whole of the gains. In Bengal alone, the cost of an equal quantity of quinine would have amounted to £40 132, while the cost of the febrifuge produced was only £6898, showing a saving of £33,734. The total saving effected since the opening of the factories up till the end of the year 1882-83, is stated to be £235 000, or more than double the cost of the plantations. Besides the Government cinchona estates, a number of private plantations have been established, covering an area of about 2500 acres with about 2½ millions of full grown plants.

Sericulture in India is a stationary, if not a declining industry. The large production in China, Japan, and the Mediterranean countries controls the European markets, and on an average of years, the imports of raw silk into India exceed the exports. The East India Company from the first took the greatest pains to foster the production of silk. As early as 1767, two years after the grant of the financial administration of Bengal had been conferred upon the Company, we find

the Governor, Mr. Verelst, personally urging the *zamíndárs*, gathered at Murshidábád for the ceremony of the *Punyá*, 'to give all possible encouragement to the cultivation of mulberry.' In 1769, a colony of reelers was brought from Italy to teach the system followed in the filatures at Novi. The first silk prepared after the Italian method reached England in 1772, and Bengal silk soon became an important article of export. Similar efforts started at Madras in 1793 were abandoned after a trial of five years. The silk-worm is said to have been introduced into Mysore by Tipu Sultán, and for many years continued to prosper. But recently the Mysore worms have been afflicted by an epidemic; and despite the enterprise of an Italian gentleman, who imported fresh breeds from Japan, the business has dwindled to insignificance.

Italian
reelers,
1769.

Tipú's ex-
periments,
1795.

Bengal
factories,
1799-1833.

Bengal has always been the chief seat of mulberry cultivation. When the trading operations of the Company ceased in 1833, they owned 11 head factories in that Province, each supplied by numerous filatures, to which the cultivators brought in their cocoons. The annual export of raw silk from Calcutta was then about 1 million lbs. But in those days the weaving of silk formed a large portion of the business of the factories. In 1779, Rennel wrote that at Kasimbázár alone about 400,000 lbs. weight of silk was consumed in the local European factories. In 1802, Lord Valentia describes Jangipur as 'the greatest silk station of the Company, with 600 furnaces, and giving employment to 3000 persons.' Under the new Charter of 1833, the Company's silk trade and its commerce with China were to cease. But it could not suddenly throw out of employment the numbers of people employed upon silk production, and its factories were not entirely disposed of until 1837.

Silk area
of Bengal.

When the Company abandoned the trade on its own account, sericulture was taken up by private enterprise, and still clings to its old head-quarters. At the present time, the cultivation of the mulberry is mainly confined to the Rájsháhí and Bardwán Divisions of Lower Bengal. This branch of agriculture, together with the rearing of the silk-worms, is conducted by the peasantry themselves, who are free to follow or abandon the business. The destination of the cocoons is twofold. They may either be sent to small native filatures, where the silk is roughly wound, and usually consumed in the hand-loom of the country; or they may be brought to the great European factories, which generally use steam machinery, and consign their produce direct to Europe.

The exports vary considerably from year to year, being

determined partly by the local yield, and still more by the prices ruling in Europe. The following are the returns for 1877-78 and 1882-83. In 1877-78, about 1½ million lbs. of silk were exported, viz. —Raw silk, 658,000 lbs., 1751, silk or the outer covering of the cocoon, 823,000 lbs., the gate value was £750,439. In the same year, the imports of raw silk (chiefly received at Bombay and Rangoon) were a little over 2 million lbs., valued at £1,780,069. By 1882-83, the imports of raw and manufactured silk had considerably exceeded the exports of the Indian production. In that year the exports of raw silk amounted to only 665,818 lbs., valued at £596,836, besides silk manufactures valued at £306,928. On the other hand the imports of foreign silk into British Indian ports in the same year amounted to 2,386,150 lbs., valued at £1,074,156, besides 9,671,761 yards of manufactured silk, and 2989 lbs. of silk thread valued at £977,768.

The cultivation of the mulberry is chiefly carried on in the Bengal Districts of Rájsháhí, Boorjá Malákh, Murshidábad, Barham, Bardwán, and Midnapur. No complete statistics are available, but in Rájsháhí alone the area under mulberry is estimated at 80,000 acres. The mulberry grown as food for the silk worms is not the fruit tree with which we are familiar in England, but a comparatively small shrub. Any fairly good land that does not grow rice will grow mulberry. But the shrubs must be preserved from floods, and the land generally requires to be artificially raised in square plots with broad trenches between, like a chess board. The mulberry differs from most Indian crops in being a perennial, i.e. it will yield its harvest of leaves for several years in succession, provided that care be taken to preserve it. It is planted between the months of November and January. Three growths of silk worms are usually obtained in the year—in November, March, and August.

Besides the silk worm proper (*Bombyx mori*), fed upon the fruit of mulberry, several other species of silk yielding worms abound in the jungles of India, and are utilized, and in some cases domesticated, by the natives. Throughout Assam, especially, an inferior silk is produced in this way, which has from time immemorial furnished the common dress of the people. These 'wild silks' are known to commerce under the general name of *tasar* or *tusser*, but they are really the result of several distinct varieties of worms, fed on various kinds of plants. The worm that yields *tasar* silk is *Choristoneura* (or *Choristoneura*), identified as the caterpillar of *Anthracis*. It feeds indiscriminately upon the

Mulberry cultivated in Bengal

baer (*Zizyphus jujuba*), and other forest trees; but in a state of semi-domestication, it is exclusively reared upon the *ásan* (*Terminalia tomentosa*), which grows conveniently in clumps. The cocoons are sometimes collected in the jungle, but more frequently bred from an earlier generation of jungle cocoons. The worms require constant attention while feeding, to protect them from crows and other birds. They give three crops in the year—in August, November, and May—of which the second is by far the most important.

in Central
Provinces; The *tasar* silk-worm is also found and utilized throughout the Central Provinces, in the hills of the Bombay Presidency, and along the southern slopes of the Himálayas. During the past twenty years, repeated attempts have been made to raise this industry out of its precarious condition, and to introduce *tasar* silk into the European market. That the raw material abounds is certain; but the great difficulty is to obtain it in a state which will be acceptable to European manufacturers. Native spun *tasar* thread is only fit for native hand-loom.

in Assam. Assam, two distinct qualities of silk are made, the *eritá* and *mugá*. The former is obtained from the cocoons of *Phalœna cynthia*; and the worm is fed, as the native name implies, upon the leaves of the castor-oil plant (*Ricinus communis*). This variety may be said to be entirely domesticated, being reared indoors. *Mugá* silk is obtained from the cocoons of *Saturnia assamungis*. The moth, which is remarkable for its size, is found wild in the jungle; but the breed is so far domesticated that cocoons are brought from one part of the Province to another, and the *sím* tree is artificially propagated to supply the worms with food.

Lac. The collection of lac is in a somewhat similar position to that of *tasar* silk. The lac insect abounds on certain jungle trees in every part of the country; and from time immemorial it has been collected by the wild tribes, in order to be worked up into lacquered ware. But European enterprise has not yet placed the industry upon a stable and an organized basis. Although lac is to be found everywhere, foreign exportation is almost entirely confined to Calcutta, which draws its supplies from the hills of Chutiá Nágpur, and in a less degree from Assam and Mirzápur in the North-Western Provinces. Lac is known to commerce both as a gum (shell-lac) and as a dye. In 1878, the total exports of lac of all kinds were 104,717 cwts., valued at £362,244. In 1879, the total exports were 91,985 cwts., valued at £300,072. In 1882-83, the exports of lac of all kinds was 138,844 cwts., of the value of £699,113.

Lac
statistics,
1878-1883.

Lac (*lak*) is a cellular, resinous incrustation of a deep orange colour, secreted by an insect (*Coccus lacca*) round the branches of various trees, chiefly *lusum* (*Schleichera trijuga*), *palis* (*Butea frondosa*), *fisal* (*Ficus religiosa*), and *baer* (*Lizyphus jujuba*). The principal component is resin, forming about 60 or 70 per cent, from which is manufactured the shell lac of commerce. Lac-dye is obtained from the small cells of the incrustation, and is itself a portion of the body of the female insect. The entire incrustation, while still adhering to the twig, is called stick lac. In order to obtain the largest quantity of dye, the stick lac should be gathered before the young come out, which happens twice in the year—in January and July. The dye is first extracted by repeated processes of washing and straining, while the shell lac is worked up from what remains in a hot and semi liquid state.

For all articles in which a fast colour is not required, lac-dye can never compete with the cheaper and less permanent aniline dyes, while for more lasting colours cochineal is preferred. Lac-dye, however, is said to be superior even to cochineal in resisting the action of human perspiration, and it is probable that in the event of the supply of cochineal falling off, lac-dye might be used in its stead to produce the regimental scarlet. It has largely replaced cochineal of late years in dyeing officers' coats, and a further extension of its use for similar purposes seems possible. The chief establishment in India for manufacturing lac was for long near Dorandá in Lohárdigí District, Chutrá Nágpur, to which stick lac is brought in from all the country round as far as the Central Provinces. The annual out turn is about 6000 cwt. of shell lac, made from double that quantity of raw material. In 1877-78, this factory had for a time to cease working, owing to the depressed state of the market in Europe.

The efforts of Government to improve the native methods of agriculture, by the establishment of model farms under skilled European supervision, have not been generally successful. In too many cases, the skilled agriculturists from Europe have been gardeners rather than farmers. In other cases, believing only in their own maxims of high cultivation—deep ploughing, subsoil drainage, manuring and rotation of crops—they have despised the ancient rules of native experience, and have not adapted their Western learning to the circumstances of a tropical country. Nevertheless, many

valuable experiments have been made, and much information, chiefly of a negative character, has been gained.

The small
success
attained.

Saidápet
Farm.

The Government model farms have been abandoned in Bengal, in Assam, and in the Punjab. In the North-Western Provinces, the propagation of flowers, fruits, vegetables, and trees is still prosecuted (1885). In Bombay there are (or were lately) three model farms; and in the Central Provinces one, on which the common crops of the country are raised at a loss. The Saidápet (Sydapet) farm, near the city of Madras, is the only establishment at which experiments have been conducted on a scale and with a perseverance sufficient to yield results of value. This farm was started by a former Governor, Sir William Denison, in 1865, and has been for the past thirteen years under the able management of Mr. Robertson, Agricultural Reporter to the Madras Government. It covered in 1884 an area of 300 acres in a ring fence, of which 139 acres were under crop, and 36 acres under timber, chiefly casuarina. Important experiments have been made, of which some produced encouraging results, indicating the general direction in which improvements may be effected in the agricultural practice of the Presidency. It has been proved that many of the common 'dry crops' can be profitably cultivated for fodder at all seasons of the year. Those most strongly recommended are yellow *cholan* (*Sorghum vulgare*), guinea grass (*Panicum jumentosum*), and horse-gram (*Dolichus biflorus*). Sugar-cane and rice also yield excellent fodder, when cut green. Attention has been given to subsoil drainage, deep ploughing, the fertilizing powers of various manures, and the proper utilization of irrigation water.

It is right to mention, however, that doubts are entertained as to whether the results of the experiments at the Madras Government Farm are equal to the outlay upon them. [Since these pages went to press, the farming operations at Saidápet have been given up, except so far as required for the practical instruction of agricultural pupils.] A School of Agriculture has been established at Saidápet, in connection with the model farm, with subordinate branches in the Districts, so as to diffuse as widely as possible the agricultural lessons that have been already learned. At the end of 1882-83, the school was attended by 69 pupils. In 1882-83, the expenditure on the farm was returned at £1083, as against receipts amounting to £559. The expenditure on the School of Agriculture in the same year was £2484, against receipts amounting to only £33, 8s.

To many it seems doubtful whether such experiments can be made to yield profitable results. The *Hindu Patriot* put the case in very pithy words. 'The native cultivators have nothing to learn so far as non-scientific agriculture is concerned, and the adoption of scientific agriculture is wholly beyond their means. If the only alternative lay between a strictly scientific and an altogether unscientific husbandry, a candid observer would have to concur in the *Hindu Patriot's* conclusion. But the choice is not thus limited. In England one little improvement takes place in one district, another small change for the better in another. Strictly scientific farming trebles the produce: a field which produces 730 lbs. of wheat without manure can be made to yield 2347 lbs. by manure. But the native of India has neither the capital nor the knowledge required to attain this result. It therefore, the problem before him was to increase his crops threefold even his best wishers might despair of his success. But the task before him is a much less ambitious one: namely to gradually increase by perhaps 10 or 20 per cent. the produce of his fields, and not by 300 per cent. at a stroke.

Wheat land in the North Western Provinces which now gives only 840 lbs. an acre yielded 1140 lbs. in the time of Akbar, and would be made to produce 1800 lbs. in East Norfolk. The average return of food grains in India shows about 700 lbs. per acre. In England wheat averages over 1700 lbs. Mr Hume the late Secretary to the Government of India in its Department of Agriculture declares that 'with proper manuring and proper tillage every acre broadly speaking, of land in the country can be made to yield 30, 50 or 70 per cent. more of every kind of crop than it at present produces, and with a fully corresponding increase in the profits of cultivation.

The first impediment to better husbandry is the fewness and weakness of the cattle. 'Over a great portion of the Empire,' writes the late Secretary to the Agricultural Department in India, 'the mass of the cattle are starved for six weeks every year. The hot winds roar, every green thing has disappeared, no hot weather forage is grown, the last year's fodder has generally been consumed in keeping the well bullocks on their legs during the irrigation of the spring crops, and all the husbandman can do is just to keep his poor brutes alive on the chopped leaves of the few trees and shrubs he has access to, the roots of grass and herbs that he digs out of the edges of fields, and the like. In good years, he just succeeds, in

Is success possible?

The 1 to 10 fold of improved husbandry

Out turn of crop

The three impediments (1) Want of cattle

bad ~~the~~ weakly ones die of starvation. But then come the rains. Within the week, as though by magic, the burning sands are carpeted with rank, luscious herbage, the cattle *will* eat and over-eat; and millions die of one form or other of cattle disease, springing out of this starvation followed by sudden repletion with rank, juicy, immature herbage.' Mr. Hume estimates 'the average annual loss of cattle in India by preventable disease' at 10 million beasts, worth $7\frac{1}{2}$ millions sterling. He complains that, up to the time when he wrote, no real attempt had been made to bring veterinary knowledge within reach of the people, or to organize a system of village plantations which would feed their cattle through the summer. The Department of Agriculture, as re-established under Lord Ripon's Government, has endeavoured to remedy these omissions, particularly in regard to the diffusion of veterinary knowledge. The statistics and breeds of agricultural stock will be given on a subsequent page.

(2) Want
of manure.

The second impediment to improved husbandry is the want of manure. If there were more stock, there would be more manure; and the absence of firewood compels the people to use up even the droppings of their cattle for fuel. Under such circumstances, agriculture ceases to be the manufacture of food, and becomes a mere spoliation of the soil. Forage crops, such as lucerne, guinea-grass, and the great stemmed millets, might furnish a large supply of cattle food per acre. Government is considering whether their cultivation could not be promoted by reducing the irrigation rates on green fodder crops. A system of village plantations would not only supply firewood, but would yield leaves and an undergrowth of fodder sufficient to tide the cattle over their six weeks' struggle for life each summer. In some Districts, Government has land of its own which it could thus plant; in others, it is only a sleeping partner in the soil. In Switzerland, the occupiers of *allmends*, or communal lands, are, at least in some cantons, compelled by law to keep up a certain number of trees. It seems a fair question whether plantations ought not in many parts of India to be made an incident of the land tenure. They would go far to solve the two fundamental difficulties of Indian agriculture—the loss of cattle, and the want of manure. The system of State Forestry at present pursued will be described in a subsequent section.

Utiliza-
tion of
manure.

Meanwhile, the natives set an increasing value on manure. The great cities are being converted from centres of disease into sources of food-supply. For a time, caste prejudices

stood in the way of utilizing the night soil 'Five years ago,' writes the Secretary to the Poona Municipality, 'agriculturists would not touch the *poudrette* when prepared, and could not be induced to take it away at even a nominal charge. At present, the output of manure is not enough to keep pace with the demand, and the peasants buy it up from four to six months in advance.' At Amritsar, in the Punjab, 30,000 donkey loads were sold in one year. A great margin still exists for economy, both in the towns and villages, but the husbandman is becoming more alive to the utilization of every source of manure, and his prejudices are gradually giving way under the stern pressure of facts.

The third impediment to improved agriculture in India is ^{(3) Want of water} the want of water. Sir J. Caird believes that if only one third of the cultivated area were irrigated, India would be secure against famine. An extension of irrigation would alone suffice to raise the food supply annually by more than $1\frac{1}{2}$ per cent. in most years, and thus more than keep pace with the general increase of the population. Since India passed to the Crown, great progress has been made in this direction. Money has been invested by millions of pounds, 200 millions of acres are now under cultivation, and in the five British Provinces which require it most, 28 per cent. of the cultivated area, or say one third, was in 1883 artificially supplied with water. Those Provinces are the Punjab, the North West, Oudh, Sind, and Madras. Looking to what has of late years been done, and to what yet remains to be done by wells and petty works with the aid of loans from the State, we may still reckon on a vast increase of food from irrigation. The pecuniary and statistical aspects of irrigation will be dealt with hereafter.

Having thus summarized the three impediments to improved husbandry, it may be profitable to examine in detail the three subjects immediately connected with them, namely, the Agricultural Stock of India, Forests, and Irrigation.

Throughout the whole of India, excepting in Sind and the western Districts of the Punjab, horned cattle are the only ^{Agricultural stock,} beasts used for ploughing. The well known humped breed of cattle predominates everywhere, being divided into many varieties. Owing partly to unfavourable conditions of climate and soil, partly to the insufficiency of grazing ground, and partly to the want of selection in breeding, the general condition of the cattle is miserably poor. As cultivation advances,

Want of
fodder.

the area of waste land available for grazing steadily diminishes, and the prospects of the poor beasts are *becoming worse* rather than better. Their only hope lies in the introduction of fodder crops as a regular stage in the agricultural course.

Famous
breeds.

There are, however, some fine breeds which are carefully fostered. In Mysore, the *amrit mahál*, a breed said to have been formed by Haidar Alí for military purposes, is kept up by the local authorities. In the Madras Districts of Nellore and Karnúl, the indigenous breed has been greatly improved under the stimulus of cattle shows and prizes, founded by British officials. In the Central Provinces there is a high-class breed of trotting bullocks, in great demand for wheeled carriages. The large and handsome oxen of Gujarát (Guzerát) in Bombay, and of Hariáná in the Punjab, are excellently adapted for drawing heavy loads in a sandy soil. The statistics of live stock for various Provinces of India will be given in the form of a table on p. 523.

Buffaloes.

The worst cattle are to be found always in deltaic tracts, but here their place is to a large extent taken by buffaloes. These last are more hardy than ordinary cattle, their character being maintained by crossing the cows with wild bulls, and their milk yields the best *ghí*, or clarified butter. In British Burma, the returns show that the total number of buffaloes is nearly equal to that of cows and bullocks. Along the valley of the Indus, and in the sandy desert which stretches into Rájputána, camels supersede cattle for all agricultural operations. In the Punjab, the total number of camels was 125,584 in 1883.

Camels.

Horses.

The breed of horses has generally deteriorated since the demand for the native strains, for military purposes, declined upon the establishment of British supremacy. In Bengal proper, and in Madras, it may be broadly said that native breeds do not exist. The chief breeds in Bombay are those of the Deccan and of Káthiáwár, in both of which Provinces Government maintains establishments of stallions. The Punjab, however, is the chief source of remounts for our Native cavalry; the total number of horses in that Province in 1883 being returned at 76,238, in addition to 33,773 ponies. About the beginning of the present century, a stud department was organized by Government to breed horses for the use of the Bengal army. This system was abolished as extravagant and inefficient by Lord Mayo in 1871. Remounts are now obtained in the open market; but the Government still maintains a number of stallions, including horses imported from England,

Government
stud.

or half English bred, and high class Arabs. Excellent horses are bred by the Baluchi tribes along the western frontier.

Horse fairs are held yearly, in the various Provinces of India. The principal ones in the Punjab, the part of India which furnishes the main supply of the Native cavalry remounts, are at Rawalpindi, Dera Ghazi Khan, Jhang, Dera Ismail Khan, and Muzaffargarh. The number of horses exhibited varies greatly from year to year, but about 5000 may be expected for sale at these five fairs. Prizes to the amount of about £1500 are awarded. The average price of remounts for the Native cavalry has risen of late years from £17 to about £22. Horse shows are also held at Shahpur Gajrat, Rohtak, and Jalalabad which are ordinarily well attended and successful. In recent years much attention has been paid in the Punjab to the breeding of mules for military purposes, and the value of these animals has been conspicuously proved in the course of the operations in Afghanistan. In 1882-83, the Government maintained 152 donkey stallions, of which 34 were imported from Europe, 74 from Arabia, and the remainder were of various native breeds. Some of the mules bred reach the height of 15 hands. The best ponies come from Burma, Manipur (the original home of the game of polo), and Bhutan.

The catching of wild elephants is now either a Government monopoly, or is conducted under strict Government supervision. The chief source of supply is the north east frontier, especially the range of hills running between the valleys of the Brahmaputra and the Barak. During the year 1877-78, about 260 elephants were captured in the Province of Assam, yielding £3600 to Government. Of these, 170 were captured by lessees of the privilege, and 90 by the Government kheda department. In 1882-83, the number of elephants caught was 475, yielding a Government revenue of £8573. Elephants are also captured to a smaller extent in the mountains bordering Orissa, in Mysore and Coorg, among the Western Ghats, and in Burma, for the timber trade. They are used by Government for transport, and are eagerly bought up by native chiefs and landowners as objects of display. The wild elephant will be treated of in the subsequent chapter on Indian zoology.

Sheep and goats are commonly reared in the wilder parts of the country for the sake of their wool. Both their weight for the butcher and their yield of wool are exceedingly low. In Mysore, and at the Saidapet farm, near Madras, attempts have been made to improve the breed of sheep by

Pigs.

crossing with merino rams, although without much success, except at Saidápet. Pigs of great size and most repulsive appearance are everywhere reared, but are eaten only by the lowest of out-castes.

Statistics of Live Stock.

The table on the opposite page summarizes the information collected regarding live stock in those parts of India where the statistics can be obtained with some approximation to accuracy. But they must be regarded as intelligent estimates rather than as verified returns.

Forests.

Destruction of jungle.

The forests of India are beginning to receive their proper share of attention, both as a source of natural wealth and as a department of the administration. Up to about twenty-five years ago, the destruction of forests by timber-cutters, by charcoal-burners, and above all, by nomadic cultivation, was allowed to go on everywhere unchecked. The extension of tillage was considered as the chief care of Government, and no regard was paid to the improvident waste of jungle on all sides. But as the pressure of population on the soil became more dense, and the construction of railways increased the demand for fuel, the question of forest conservation forced itself into notice. It was recognised that the inheritance of future generations was being recklessly sacrificed. The importance of forests, as affecting the general meteorology of a country, was also being taught by bitter experience in Europe. On many grounds, therefore, it became necessary to preserve what remained of the forests in India, and to repair the mischief of previous neglect, even at considerable expense.

Growth of the Forest Department, 1844-67.

In 1844 and 1847, the subject was actively taken up by the Governments of Bombay and Madras. In 1864, Dr. Brandis was appointed Inspector-General of Forests to the Government of India; and in the following year the first Forest Act passed the Legislature (No. VII. of 1865). The regular training of candidates for the Forest Department in the schools of France and Germany dates from 1867. In the interval which has since elapsed, sound principles of forest administration have been laid down and gradually enforced. Indiscriminate timber-cutting has been prohibited; the burning of the jungle by the hill tribes has been confined within bounds; large areas have been surveyed and demarcated; plantations have been laid out; and forest conservation has become a reality in India.

From a botanical point of view, the forests may be divided

[Sentence continued on page 524.]

APPROXIMATE NUMBERS OF LIVE STOCK AND OF CERTAIN AGRICULTURAL IMPLEMENTS IN
SIX INDIAN PROVINCES IN 1882-83

	Mad as.	Bombay and Sind	Punjab	Central Provinces	Bihar	Prithi Durga
Bullocks						
Cows,	3 687 782	3 344 518			1 540 007	917,861
Buffaloes,	3 453 129	3 321 728	6 121 417		299 064	687,360
Horses,	1 483 938	1 534 053		5 356 477	8 746	
Ponies	7 941				27 476	8,366
Donkeys,	30 189	137 774	76 238	13 335	27 707	
Elephants	124 731	78 179	33 773	90 514		
Camels,	481		251 068	24 660		
Sheep and Goats	50					
Pigs,	8 941 813	3 170 692	175 584	59	4	1 685
Carts,	254 557		3 864 013	8 8592	936	
Ploughs,	313 528	417 751	41 161	123 439	404 006	25 782
	2 013 011	1 058 357	92 555	313 637	5 515	136,353
			1 803 278	897 769	119 562	212 380
					109 687	356,903

Sentence continued from p. 522.]

Indian
timber-
trees.

Teak.

Sál.

Deodára.

into several distinct classes, determined by varying conditions of soil, climate, and rainfall. The king of Indian forest trees is the teak (*Tectona grandis*), which rivals the British oak as material for ship-building. The home of the teak is in the Bombay Gháts, Kánara, Cochin, Travancore, and the Burmese peninsula, where it flourishes under an excessive rainfall. Second to teak is the *sál* (*Shorea robusta*), which is indigenous along the lower slopes of the Himálayas from the Sutlej basin east to Assam, among the hills of Central India, and in the Eastern Gháts down to the Godávarí river. On the Himálayas of North-Western India, the distinguishing timber-tree is the *deodára* (*Cedrus Deodara*); while on the North-Eastern Himálayan frontier its place is occupied by *Pinus Kasya* and other trees, such as oak and chestnut, of a temperate zone.

South
Indian
forests.

The three
forest-
belts.

Sandal-
tree.

These noble trees supply the most valuable timber, and form the chief care of the Forest Department. But they are only the aristocracy of countless species, yielding timber, firewood, and other products of value. In the south of the peninsula, the mountain range of the Western Gháts, from Travancore northwards into Kánara, is clothed with an inexhaustible wealth of still virgin forest. Here there are three separate vegetations. (1) An evergreen belt on the seaward face of the mountains, where grow the stately *pún* (*Calophyllum inophyllum*), valuable as spars for ships, the *anjalli* or wild jack (*Artocarpus hirsuta*), and a variety of ebony (*Diospyros Ebenum*). (2) A belt of mixed forest, varying from 10 to 40 miles in width, which yields teak, blackwood (*Dalbergia latifolia*), and *Lagerstroemia microcarpa*, and here and there continuous avenues of lofty bamboos. (3) A dry belt, extending over the central plateau, in which the vegetation declines in size and abundance. The precious sandal-wood (*Santalum album*), limited almost entirely to Mysore and Kánara, thrives best on a stony soil, with a light rainfall. In the Bombay Presidency, the chief forest areas, excluding Kánara, are to be found in the mountainous extension of the Western Gháts, known as the Sahyádrí range, and in the delta of the Indus in the outlying Province of Sind.

Sind
forests.

The Sind river-valley forests present many peculiar features. They are locally reported to have been formed as game preserves by the Mírs or Musalmán rulers, and are divided into convenient blocks or *belás*, fringing the entire course of the Indus. Being absolute State property, their management is embarrassed by no difficulties, excepting those caused by

the uncontrollable floods of the river. They furnish abundant firewood, but little timber of value, their chief produce being *babul* (*Acacia arabica*), *bahán* (*Populus euphratica*), and tamarisk (*Tamarix dioica*). In the Punjab, the principal forests of Punjab forests *deodara* (*Cedrus Deodara*) lie beyond the British frontier, in the Himálayan valleys of the great rivers, but many of them have been leased from the bordering States, in order to secure a supply of firewood and railway sleepers. On the Punjab plains, the only woods are those growing on the *rikhs* or upland plateaux which rise between the converging river basins. The chief trees found here are varieties of *Prosopis*, *Capparis*, and *Salvadora* but the Forest Department is now laying out more valuable plantations of *sissu* (*Dalbergia Sissoo*), *baer* (*Zizyphus jujuba*), and *kikar*.

The North Western Provinces present the Himalay in type of forest in Kumaun and Garhwal where the characteristic Forests of N W Provinces, trees are the *chil* (*Pinus excelsa*) and *chir* (*Pinus longifolia*), with but little *deodara*. Farther west occurs a forest belt of *sal*, which may be said to form the continuous boundary between Nepál and British territory. Owing to the facility of water communication and the neighbourhood of the great cities of Hindustán, these *sal* forests have long ago been stripped of their valuable timber, and are but slowly recovering under the care of the Forest Department. Oudh and Northern Bengal of Oudh and N Bengal, continue the general features of the North Western Provinces but the hill station of Dárpiling is surrounded by a flora of the temperate zone.

Calcutta has, from its foundation drawn its supply of fire wood from the inexhaustible jungles of the Sundarbans, Sundarban forests which have recently been placed under forest conservancy rules. This tract, extending over 5000 square miles is a dismal swamp, half land, half sea or fresh water, overgrown by an almost impenetrable jungle of timber trees and under wood. The most valued wood is the *sundari* (*Heretiera littoralis*), which is said to give its name to the tract. Assam and Chittagong, like the Malabar coast and British Burma, still possess vast areas of virgin forest although the more accessible tracts have been ruthlessly laid waste. Beside *sal* and *Pinus Kasya*, the timber trees of Assam include *nahor* or *ndgeswar* (*Mesua ferrea*) *sum* (*Artocarpus Chaplasha*), and *járu* (*Lagerstroemia Flos Regiæ*) *Assam forests* *Ficus elastica*, yielding the caoutchouc of commerce, was formerly common, but now the supply is chiefly brought from beyond the frontier. Plantations of teak, *tun* (*Cedrela Toona*), *sissu*, and *Ficus elastica* are

Burmese forests. now being formed and guarded by the Forest Department. In Burma, the importance of teak exceeds that of all the other timber-trees together. Next comes iron-wood (*Xylia dolabri-formis*), and *Acacia Catechu*, which yields the cutch of commerce. Throughout the centre of the peninsula, forests cover a very extensive area; but their value is chiefly local, as none of the rivers are navigable. Towards the east, *sál* predominates, and in the west there is some teak; but fine timber of either species is comparatively scarce. Rájputána has a beautiful tree of its own, the *Anogeissus pendula*, with small leaves and drooping branches.

Central India. From the administrative point of view, the Indian forests are classified as 'reserved' or as 'open.' The reserved forests are those under the immediate control of officers of the Forest Department. They are managed as the property of the State, with a single eye to their conservancy and future development as a source of national wealth. Their limits are demarcated after survey; nomadic cultivation by the hill tribes is prohibited; cattle are excluded from grazing; destructive creepers are cut down; and the hewing of timber, if permitted at all, is placed under stringent regulations. The open forests are less carefully guarded; but in them, also, certain kinds of timber-trees are preserved. A third class of forest lands consists of plantations, on which large sums of money are spent annually, with a view to the rearing and development of timber-trees.

Forest administration. 'Reserved' forests. 'Open' forests. 'Plantations.'

Forest finance, 1873-1883. It is difficult to present, in a summary view, the entire financial aspects of the labours of the Forest Department. In 1872-73, the total area of reserved forests in India was estimated at more than 6,000,000 acres; and the area has probably been doubled since that date. In the same year, the total forest revenue was £477,000, as compared with an expenditure of £295,000, thus showing a surplus of £182,000.

1873. By 1877-78, the revenue had increased to £664,102, of which £160,308 was derived from British Burma, and £126,163 from Bombay. The forest exports in that year included—teak, valued at £406,652; lac and lac-dye, £362,008; caoutchouc, £89,381; and gums, £183,685.

1878. By the end of 1882-83, the total forest revenue had further increased to £963,859, of which £250,389 was derived from British Burma, £209,035 from Bombay, £101,340 from the North-Western Provinces and Oudh, £97,765 from the Central Provinces, £90,644 from Madras, £76,671 from the Punjab, £69,396 from Bengal, £24,861 from Assam, £28,704 from Berar, and £13,802 from Coorg. From each of these Pro-

vinces a surplus profit was realized over working expenses. A small forest revenue is also obtained from tracts in Ajmere and in Baluchistan, but not sufficient, up to 1883, to cover the expenses of the Department. Total forest expenditure in 1882-83, £577 726, showing a surplus of £386,133. Average forest revenue for ten years ending 1882-83 £703 424 per annum, average expenditure, £467,624, average surplus, £235,800. But the above figures fail to exhibit the true working of the Forest Department, which is gradually winning back for India the fee simple of her forest wealth, when it was on the point of being squandered beyond the possibility of redemption.

The practice of nomadic cultivation by the hill tribes may be conveniently described in connection with forest conservation, of which it is the most formidable enemy. In all the great virgin forests of India in Arakan, on the north east frontier of Assam and Chittagong throughout the Central Provinces, and along the line of the Western Ghâts, the aboriginal tribes raise their crops of rice, cotton, and millets by a system of nomadic tillage. A similar method has been found in Madagascar, and indeed, from its simplicity and its appropriateness it may fairly be regarded the most primitive form of agriculture followed by the human race. Known as *taungya* in Burma, *jum* on the north east frontier, *dahya* in Central India, *kul* in the Himalayas, and *kumari* in the Western Ghâts, it is practised without material differences by tribes of the most diverse origin.

The essential features of such husbandry are the burning down of a patch of forest, and sowing the crop with little or no tillage in the clearing thus formed. The tribes of the Bombay coast break up the cleared soil with a sort of hoe pick and spade, or even with the plough, in other parts of India, the soil is merely scratched, or the seed scattered on the surface without any cultivation. In some cases, a crop is taken off the same clearing for two or even three years in succession, but more usually the tribe moves off every year to a fresh field of operations. Every variety of implement is used, from the bill hook, used alike for hewing the jungle and for turning up the soil, to the plough. Every degree of permanence in the cultivation may be observed, from a one year's crop to the stage at which an aboriginal tribe, such as the Kandhs, visibly passes from nomadic husbandry to regular tillage. To these nomadic cultivators the words rhetorically used by Tacitus of the primitive Germans are strictly applicable

Forest-clearing
by fire :

—*Arva per annos mutant; et superest ager.* The wanton destruction wrought by them in the forest is incalculable. In addition to the timber-trees deliberately burned down to clear the soil, the fire thus started not unfrequently runs wild through the forest, and devastates many square miles. Wherever timber has any value from the proximity of a

Restraints
on it.

market, the first care of the Forest Department is to prohibit these fires, and to assign heavy penalties for any infringement of its rules. The success of a year's forest operations is mainly estimated by the degree in which the reserves have been saved from the flames.

Merits of
nomadic
tillage.

But vast tracts of country yet remain in which it would be equally useless and impossible to place restraints upon nomad cultivation. The system yields a larger return for the same amount of labour than permanent plough-husbandry. A virgin soil, manured many inches deep with ashes, and watered by the full burst of a tropical rainfall, returns forty and fifty-fold of rice, which is the staple grain thus raised. In addition to rice, Indian corn, millet, oil-seeds, and cotton, are sometimes grown in the same clearing, the seeds being all thrown into the ground together, and each crop ripening in succession at its own season. Except to the eyes of a forest officer, a patch of nomadic tillage is a very picturesque sight. Men, women, and children all work together with a will, for the trees must be felled and burned, and the seed sown, before the monsoon breaks. Save on the western coast and the Ghâts (where the plough is occasionally used), the implement generally employed for all purposes is the *dáo* or hill-knife, which performs the office alike of axe, hoe, dibbler, and sickle.

Irrigation.

In a tropical country, where the rainfall is capricious in its incidence and variable in its amount, the proper control of the water-supply becomes one of the first cares of Government. Its expenditure on irrigation works may be regarded as an investment of the landlord's capital, by which alone the estate can be rendered profitable. Without artificial irrigation, large tracts of country would lie permanently waste, while others could only be cultivated in exceptionally favourable seasons. Irrigation is to the Indian peasant what high cultivation is to the farmer in England. It augments the produce of

Its function
in India,

his fields in a proportion far larger than the mere interest upon the capital expended. It may also be regarded as an insurance against famine. When the monsoon fails for one or two seasons in succession, the cultivator of 'dry lands' has no

hope, while abundant crops are raised from the fortunate fields commanded by irrigation works. This contrast was painfully realized in Southern India during the terrible years of 1876 to 1878, the limit between famine and plenty being marked by the boundaries of the irrigated and non irrigated areas. It would, however be an error to conclude that any outlay will absolutely guarantee the vast interior of the peninsula from famine. Much indeed can be done and much is being done, ^{during famine} year by year to store and distribute the scanty and irregular water supply of this inland plateau. But engineering possibilities are limited not only by the expense but by the unalterable laws of nature. A table land with only a moderate rainfall and watered by few perennial streams broken by many hill ranges, and marked out into no natural drainage basins can never be completely protected from the vicissitudes of the Indian seasons.

Irrigation is everywhere dependent upon the two supreme ^{Irrigation} considerations of water supply and land level. The sandy ^{areas,} desert which extends from the hills of Rajputana to the basin of the Indus is as hopelessly closed to irrigation from its almost entire absence of rainfall as is the confused system of hill and valley in Central India with its unmanageable levels. Farther west in the Indus valley irrigation becomes possible and in no part of India has it been conducted with greater perseverance and success. The entire Province of Sind and ^{Sind} several of the lower Districts of the Punjab are absolutely dependent upon the floods of the Indus. Sind has been compared to Egypt and the Indus to the Nile but the conditions of the Indian Province are much the less favourable of the two. In Sind the average rainfall is barely 10 inches in the year, the soil is a thirsty sand worst of all, the river does not run in confined banks but wanders at its will over a wide valley. The rising of the Nile is a beneficent phenomenon which can be depended upon with tolerable accuracy, and which the industry of countless generations has brought under control for the purposes of cultivation. The inundation of the ^{The uncontrollable} Indus is an uncontrollable torrent, which sometimes does as ^{Indus.} much harm as good.

Broadly speaking no crop can be grown in Sind except under irrigation. The cultivated area of over two million acres may be regarded as entirely dependent upon artificial water supply, although not entirely on State irrigation works. The water is drawn from the river by two classes of canals—(1) inundation channels which only fill when the Indus is in flood, and

^{Irrigation}
^{in Sind}
¹⁸⁷⁷⁻⁸³

Irrigation in Sind, (2) perennial channels, which carry off water by means of dams at all seasons of the year. The former are for the most part the work of ancient rulers of the country, or of the cultivators themselves; the latter have been constructed since the British conquest. In both cases, care has been taken to utilize abandoned beds of the river. Irrigation in Sind is treated as an integral department of the land administration. In 1876-77, about 900,000 acres were returned as irrigated from works for which capital and revenue accounts are kept. The chief of these are the Ghár, Eastern and Western Nára, Sukkur (Sakhar), Phuleli, and Pinyari Canals; the total receipts were about £190,000, almost entirely credited under the head of land revenue. In the same year, about 445,000 acres were irrigated from works for which revenue accounts only are kept, yielding about £75,000 in land revenue. The total area 'usually irrigated' in Sind was returned in 1880 at about 1,800,000 acres, out of a cultivated area of 2,250,000 acres.

1883. The actual area cultivated by means of canal irrigation in Sind in 1882-83 was 1,673,293 acres, including *jagír* or revenue-free lands; the area assessed for Government revenue being 1,508,292 acres. The gross assessed revenue from all sources amounted to £294,898, and the maintenance charges to £135,118, leaving a net revenue of £159,780. The net actual receipts from productive irrigation works returned 4·25 per cent., and those from ordinary irrigation works, 12·95 per cent. on the capital outlay incurred up to the end of the year. Total capital outlay up to the end of 1882-83, £958,012, of which £623,267 had been expended on productive works, and £334,745 on ordinary irrigation works.

Irrigation in Bombay, In the Bombay Presidency, irrigation is conducted on a comparatively small scale, and mainly by private enterprise. Along the coast of the Konkan, the heavy local rainfall, and the annual flooding of the numerous small creeks, permit rice to be grown without artificial aid. In Gujarát (Guzerát) the supply is drawn from wells, and in the Deccan from tanks; but both of these are liable to fail in years of deficient rainfall. Government has now undertaken a few comprehensive schemes of irrigation in Bombay, conforming to a common type. The head of a hill valley is dammed up, so as to form an immense reservoir, and the water is then conducted over the fields by channels, in some cases of considerable length. In 1876-77, the total area in Bombay (excluding Sind) irrigated from Government works was about 180,000 acres, yielding a revenue of about £42,000. In the same year, the expenditure

on irrigation (inclusive of Sind) was £65,000 under the head of extraordinary, and £170,000 under the head of ordinary, total, £235,000. In 1882-83, the area irrigated by Government works in Gujarat and the Deccan amounted to 28,735 acres from productive works, and 138,468 acres from works not classed as productive. Total Government irrigation, 167,203 acres, yielding a revenue of £77,746, against an expenditure of £37,171, leaving a surplus of £30,575. Besides these Government works, irrigation is carried on to a much larger extent in Bombay by private individuals from tanks, ponds, and watercourses. Ordinary irrigated area in Bombay (exclusive of Sind) 550,000 acres, out of a total cultivated area of 22½ million acres.

In some parts of the Punjab, irrigation is only one degree less necessary than in Sind, but the sources of supply are more numerous. In the northern tract under the Himalayas, and in the upper valleys of the Five Rivers, water can be obtained by digging wells from 10 to 30 feet below the surface. In the south, towards Sind, 'inundation channels' are usual. The upland tracts which rise between the basins of the main rivers are now in course of being supplied by the perennial canals of the Government. According to the returns for 1878-79, out of a grand total of 23,523,504 acres under cultivation, 5,340,724 acres were irrigated by private individuals, and 1,808,005 acres by public 'channels,' total area under irrigation, 7,148,729 acres, or 30 per cent of the cultivated area. The three principal Government works in the Punjab are the Western Jumna Canal, the Bari Doab Canal, and the Sirhind. The three main branches of which, and some of its distributaries, were opened in November 1882. An account of each of these works is given in separate articles in *The Imperial Gazetteer of India*¹.

Up to the close of 1877-78, the capital outlay on the three great Punjab Canals was £3,645,189, the total income in that year was £263,053, of which £171,504 was classified as direct, and £91,549 as indirect, the total revenue charges on works in operation were £224,316, of which £146,419 was for maintenance, and £77,897 for interest, thus showing a surplus of £38,737. On the Western Jumna Canal, taken singly, the net profit was £83,112 in 1877-78. By the end of 1883-84, the gross revenue from the Bari Doab and Western Jumna Canal, together with the Indus and Sutlej Inundation Canals, amounted to £428,416, and the

¹ See articles JUMNA CANAL, Eastern and Western, BARI DOAB CANAL, SIRHIND CANAL, in *The Imperial Gazetteer of India*.

Punjab
Canal
finance,
1884.

working expenses to £197,032, thus yielding a net revenue of £231,384, equal to a return of nearly 5 per cent. on the capital of the canals opened. This is exclusive of the Muzaffargarh Inundation Canal, which has no capital account, but which in 1882-83 yielded a return of £22,035, against working expenses amounting to £15,365, leaving a surplus of revenue over expenditure of £6670. Irrigation from the Sirhind Canal had only just commenced, but the revenue will increase in proportion to the rate of progress in constructing the distributary channels. This work, together with the completion of branch-distributaries, is being pushed on as rapidly as possible.

Punjab
Canal
statistics,
1884.

The capital outlay on the three great Punjab canals, exclusive of contributions by Native States towards the construction of the Sirhind Canal, amounted at the close of 1883-84 to £5,033,284, the capital expended during the latter year being £282,524. Area irrigated from Government canals in 1883-84:—Western Jumna Canal, 472,426 acres; Bári Doáb Canal, 390,860 acres; Sirhind Canal, 5030 acres; inundation canals, 783,752 acres: total, 1,652,068 acres. The ordinary irrigated area in the Punjab, from Government works as well as by private individuals, may now be taken at about 8 million acres, out of a total cultivated area of over 23 million acres.

Irrigation
in the
N.-W.
Provinces.

The North-Western Provinces present, in the great *doáb*, or high land between the Ganges and the Jumna, a continuation of the physical features to be found in the Punjab. The local rainfall, indeed, is heavier, but before the days of artificial irrigation almost every drought resulted in a terrible famine. It is in this tract that the British Government has been perhaps most successful in averting such calamities. In Sind, irrigation is an absolute necessity; in Lower Bengal, it may be regarded almost as a luxury; in the great river basins of Upper India, it serves the twofold object of averting famines caused by drought; of introducing more valuable crops and higher methods of agriculture.

Concerning private irrigation from wells in the North-Western Provinces, details are not available. The great Government works are the Ganges Canal, the Eastern Jumna Canal, the Agra Canals, and the Lower Ganges Canal.¹ Up to the close of 1877-78, the total outlay had been £5,673,401.

Four great
canals of
the Doábs,
1878-83.
1878.

The gross income in that year was £438,136, of which £337,842 was derived from water-rates, and £100,294 from enhanced land revenue; the working expenses amounted to

¹ A full account of each of these works will be found under article GANGES CANAL, *The Imperial Gazetteer*, vol. iii.

£143,984, leaving £294,152 for surplus profits, or 6.77 per cent on the total capital expended on works in operation. Canals
 The total area irrigated in the North Western Provinces was 1,461,428 acres. Of this total, 415,659 acres were under wheat, and 139,375 under sugar cane.

The total capital outlay on the four main canals just mentioned in the North Western Provinces up to 1882-83, was £6,499,741, of which £138,677 were expended during 1882-83. The four great canals, 1882-83

The other canals in the N W Provinces, not classed as productive works, included, in 1882-83, the following—namely, the Dūn Canal, the Rohilkhand and Bijnor Canal, the Bundelkhand irrigation works, the Cawnpur branch of the Lower Ganges Canal, and the Betwa Canal constructed as a famine insurance work. Minor canals N W P
 Total capital expended on all Government canals in the North Western Provinces up to the end of 1882-83, £6,890,769, of which £232,341 was spent during the latter year. These canals may all be considered as practically complete, with the exception of the Lower Ganges and Agra Canals, in which some of the distributaries are as yet (1884) unfinished, and the Betwa Canal, which was under construction at the end of 1882-83.

The gross revenue of the canals in the N W Provinces, including water rates, increased land revenue due to the canals, navigation charges in 1882-83, was £645,918, the charges against revenue amounted to £215,813, thus leaving a net revenue of £430,105, or over 6 per cent on the total capital outlay, exclusive of the Betwa Canal. Deducting from this the interest charges for the year, which amounted to £249,601, there remained a clear profit or surplus of £180,504. The total area irrigated during 1882-83 was 1,974,175 acres, of which 1,462,023 were supplied by the Ganges and Lower Ganges Canals, or their branches. Total canal revenue in N W P, 1883
 Of the irrigated area, 728,385 acres were under wheat, 662,693 acres under other food crops, 316,145 acres under indigo, 198,322 acres under sugar cane, and 52,493 acres under cotton. Besides the canal irrigation, a vast area in the North Western Provinces is supplied with water from wells, tanks, and miscellaneous works. The total area ordinarily irrigated in the North Western Provinces (excluding Oudh) may be estimated at 7 to 8 million acres. Irrigated area, 1883

No irrigation works have yet been introduced into Oudh by Government. A fair local rainfall, the annual overflow of the rivers, and an abundance of low lying swamps, combine to furnish a water supply which is ample in all ordinary years. According to the Settlement returns, out of a total cultivated area of 8,276,174 acres, 2,957,377 acres, or 35 per cent, are Irrigation in Oudh

irrigated by private individuals. But this figure probably includes low lands watered by natural overflow.

Irrigation
in Bengal
Proper.

Embank-
ments.

Throughout the greater part of Bengal Proper there is scarcely any demand for artificial irrigation, but Government has undertaken to construct works in those exceptional tracts where experience has shown that drought or famine is to be feared. In the broad valleys of the Ganges and the Brahmaputra, and along the deltaic seaboard, flood is a more frequent calamity than drought; and embankments here take the place of canals. The Public Works Department in Lower Bengal has over 2000 miles of embankments under its charge, upon which £79,105 was expended in 1877-78, either as direct outlay or in advances to landowners. The wide expanse of Northern Bengal and Behar, stretching from the Himálayas to the Ganges, is also rarely visited by drought; although, when drought does come, the excessive density of the population brings the danger of famine very near. In Sáran District it has been found necessary to carry out a scheme for utilizing the discharge of the river Gandak.

The Orissa
Canals.

The great irrigation works in Lower Bengal are two in number, and belong to two different types:—(1) In the delta of Orissa, an extensive system of canals has been constructed on the pattern of those lower down the Coromandel coast. They store up the water by means of a weir or anicut thrown across the Mahánadi river.¹ The Orissa works are intended to avert the danger of both drought and flood, and also to be useful for navigation. In average seasons, *i.e.* in five years out of six, the local rainfall is sufficient for the rice crop, which is here the sole staple of cultivation; and therefore it is not to be expected that these canals will be directly or largely remunerative. But, on the other hand, if they save the Province from a repetition of the disastrous year 1865-66, the money will not have been expended in vain. A canal, originally designed as a branch of the Orissa works, runs through Midnapur District and debouches on the Húglí.

The Son
Canal.

(2) In South Behar, the flood discharge of the Son has been intercepted, after the system of engineering followed in the North-West, so as to irrigate the thirsty strip of land along the south bank of the Ganges, where distress has often been severely felt.² In this case, also, the expenditure must be regarded rather as an insurance fund against famine than as reproductive outlay. The works are not yet complete,

¹ See article MAHANADI, *The Imperial Gazetteer*.

² See article SON CANALS, *The Imperial Gazetteer*.

but the experience already gained proves that irrigation is wanted even in ordinary seasons

Up to the close of the year 1877-78, the capital expenditure on all the State irrigation works in Lower Bengal was £4,653,903, the gross income for the year was £49,477, the working expenses were £70,286 and the estimated interest on capital, at $4\frac{1}{2}$ per cent, amounted to £203,971, thus showing a deficit of £224,780. The area irrigated was about 400,000 acres.

By the end of 1882-83, the total direct capital outlay (excluding interest) on State navigation and irrigation canals in Bengal was £5,331,726, the gross income for the year was £207,444 (including the Calcutta Canals and Nadiya river works, for which capital and revenue accounts are not kept), and the working expenses £514,898, showing a deficit of £307,454. Adding to this the amount of interest on capital, which in 1882-83 amounted to £211,550, calculated at 4 per cent, the total net deficit for the year amounted to £519,004. The four chief navigation and irrigation canals, however, returned a surplus (excluding interest) of £15,527 of revenue over working expenses. The great deficit of current expenditure over current revenue occurred in the Orissa coast canals, embankments, drainage works, etc. The area irrigated from Government canals in the Lieutenant Governorship of Bengal is about 450,000 acres. Including private works, about 1 million acres out of a total estimated area of $5\frac{1}{2}$ million acres under cultivation, are irrigated in Lower Bengal.

In the Madras Presidency, and generally throughout Southern India, facilities for irrigation assume a decisive importance in determining the character of agriculture. Crops dependent on the rainfall are distinguished as 'dry crops' comprehending the large class of millets. Rice is grown on 'wet land,' which means land capable of being irrigated. Except on the Malabar or western coast, the local rainfall is nowhere sufficiently ample, or sufficiently steady, to secure an adequate water supply. Everywhere else, water has to be brought to the fields from rivers, from tanks, or from wells. Of the total cultivated area of Madras, 17 per cent. was returned by the Famine Commissioners in 1878 as *assessed* as 'wet land,' or $5\frac{1}{2}$ millions of acres out of an estimated cultivated area of 32 millions. But the *actual* irrigated area from all sources, including tanks and wells, was returned by the Famine Commissioners at about 7 millions of acres.

From time immemorial, the industrious population of the Madras Districts has made use of all the means available

Irrigation
in Bengal,
1878-83

Irrigation
in Bengal,
1882-83

Irrigation
in Madras

'Dry' and
'wet' land

Petty
native
works

to store up the rainfall, and direct the river floods over their fields. The upland areas are studded with tanks, which sometimes cover square miles of ground; the rivers are crossed by innumerable anicuts or dams, by which the floods are diverted into long aqueducts. Most of these works are now the property of Government, which annually expends large sums of money in maintenance and repairs, looking for remuneration only to the augmented land revenue. The average rate of assessment is 9s. 6d. per acre on irrigated land, as compared with only 2s. 3d. per acre on unirrigated land.

Works in
the Madras
deltas,
1878-83.

It is therefore not only the duty, but the manifest advantage, of Government to extend the facilities for irrigation in Madras, wherever the physical aspect of the country will permit. The deltas of the Godávári, the Kistna, and the Káveri (Cauvery), have within recent years been traversed by a network of canals, and thus guaranteed against risk of famine.¹ Smaller works of a similar nature have been carried out in other places; while a private company, with a Government guarantee, has undertaken the more difficult task of utilizing on a grand scale the waters of the Tungabhadra² amid the hills and vales of the interior. The *assessable* irrigated area in the Presidency, of 5½ million acres, yielded in 1878 a land revenue of 2 millions sterling. Of this total, 1,680,178 acres, with a revenue of £759,778, were irrigated in 1878 by eight great systems, for which revenue and capital accounts were kept. The minor works consisted of about 35,000 tanks and irrigation canals, and about 1140 anicuts or dams across streams. The whole area under irrigation from public and private sources in Madras was in 1878, as already stated, about 7 million acres, out of a total cultivated area of 32 million acres.

1878.

Madras
irrigation
works,
1882-83.

In 1882-83, the Madras irrigation scheme included seven main systems, classified as productive public works; namely, —the Godávári delta system, the Kistna delta system, the Penner (Ponnaiyár) anicut system, the Sangam anicut project (under construction), the Karnúl canal (purchased from the Madras Irrigation Company in July 1882), the Káveri delta system, and Srivaikuntham anicut system. An account of each of these works separately will be found in *The Imperial Gazetteer of India*. Irrigation and navigation works, not classified as productive, include those known as the Chedambaram tank system, the Pálár anicut system, the Pelandorai anicut system, the Madras water-supply and iriga-

¹ See article GODAVARI RIVER, *The Imperial Gazetteer*.

² See article TUNGABHADRA, *The Imperial Gazetteer*.

tion extension project, and the Buckingham Canal. There are also a number of minor irrigation and protective works, for which neither capital nor revenue accounts are kept. The area irrigated by productive public works in Madras in 1882-83 was 1,757,579 acres, and that by all other Government irrigation works, 2,615,590 acres, making a total of 4,373,169 acres.

The acquisition of the Karnul Canal during 1882 materially raised the outlay invested in productive public works, and greatly reduced the returns yielded in former years by this class of works in Madras. The total capital outlay, direct and indirect, incurred on productive public works up to the end of 1882-83, amounted to £3,990,552. The gross revenue, including share of enhanced land revenue, amounted to £360,062, the maintenance charges, direct and indirect, was £107,197, leaving a net revenue of £252,865, equal to 6.34 per cent on the total capital outlay up to the end of the year. If, however, the outlay on the Singam anicut works (which had not commenced to earn revenue in 1882-83), and the purchase money for the Karnul canal, be excluded from the account, the net returns would be 12 per cent on the capital outlay, against 13½ per cent obtained during the previous year. With regard to irrigation and navigation canals not classified as productive, the capital outlay, direct and indirect, incurred up to the end of 1882-83, amounted to £988,907. The gross revenue during 1882-83, including share of land revenue debitable to these works, was £31,319, the expenditure was £27,520, leaving a net revenue of £3799, equal to 0.38 per cent on the total capital outlay.

In Mysore, tanks, anicuts, and wells dug in the dry beds of rivers afford the means of irrigation. Since the late disastrous famine of 1876-78, comprehensive schemes of throwing embankments across river valleys have been undertaken by Government. The whole area under irrigation from public and private sources in Mysore is ¾ of a million acres, out of a total cultivated area of 4 to 5 million acres.

In the Central Provinces, irrigation still remains a private enterprise. According to the Settlement returns, out of a total cultivated area of 13,610,503 acres, 804,378 acres, or 6 per cent, are irrigated by private individuals. The only Government work is a tank in the District of Nimár. In 1882-83, the area irrigated by private individuals was returned at 770,583 acres, and by Government works, 238 acres from the Nimár tank, out of a total of 14,165,212 acres of cultivated area.

In British Burma, as in Lower Bengal, embankments take the

place of canals; and are classed as 'irrigation works' in the reports. Within the last few years, Government has spent £318,000 in Burma under this heading, to save the low rice-fields along the Irawadi from destructive inundation.

Statistics
for British
India,
1868 to
1883.

The foregoing paragraphs have given the Provincial statistics of irrigation, so far as available. The differences in the local systems, and the variety of sources from which the outlay on irrigation works is derived, render a single generalized statement for all India misleading. Apart from private irrigation works, and certain classes of Government works, the capital expended by the Government on irrigation is returned at 19 millions sterling during the sixteen years ending 1882-83. Including 1 $\frac{3}{4}$ million sterling expended on the Madras Irrigation Company's works (taken over by Government), the total outlay would amount to nearly 21 millions sterling during the same period. This statement, although it altogether fails to disclose the whole expenditure on Indian irrigation, suffices to show the magnitude of the operations involved.

The following table shows the extent of cultivation and the average area irrigated in the Provinces for which the facts can be obtained. They were specially collected by the Indian Famine Commission, and published in its Report of 1880. But they must be taken as only approximate estimates. They differ from data obtained from other sources; as may be seen by comparing the figures in the table with the later ones given in the foregoing Provincial paragraphs.

ORDINARY AREA OF CULTIVATION AND OF IRRIGATION IN CERTAIN PROVINCES, AS ESTIMATED IN 1880.

Province.	Area ordinarily cultivated.	Area ordinarily irrigated.	Percentage of irrigation to cultivation.
	Acres.	Acres.	
Punjab,	21,000,000	5,500,000	26·2
North-Western Provinces and Oudh,	36,000,000	11,500,000	32·0
Bengal,	54,500,000	1,000,000	1·8
Central Provinces,	15,500,000	770,000	5·0
Berar,	6,500,000	100,000	1·5
Bombay,	24,500,000	450,000	1·8
Sind,	2,250,000	1,800,000	80·0
Madras,	32,000,000	7,300,000	23·0
Mysore,	5,000,000	800,000	16·0
Total for the Provinces for which the facts were ascertained,	197,250,000	29,220,000	14·8

It will be seen from the preceding table that irrigation is most resorted to in the Provinces with the scantiest or most precarious rainfall. In Sind, tillage depends almost entirely on an artificial water supply, and four fifths of the cultivated area are ascertained to be irrigated. In Northern India, the deficient rainfall of the Punjab and the high lying *dodbs*, or intermediate river plains of the North Western Provinces, also demands a large measure of irrigation. The irrigated area, accordingly, amounts to from over one fourth to one third of the whole cultivation. In Madras, it is under one fourth, in Mysore, it is one sixth, in the Central Provinces, it is one twentieth. But the dry uplands of Bombay, the Central Provinces, and Berar, where the proportion of irrigated lands sinks to about one sixtieth, undoubtedly require a larger artificial water supply than they possess at present. The black soil of these tracts, however, is very retentive of moisture. To a certain extent it stores up and husband the rainfall. It thus lessens the necessity for irrigation. In Bengal, where the irrigated area is only 18 per cent of the cultivated area, the abundant rainfall and the inundations of the Ganges, the Brahmaputra, the Mahanadi, and of the river systems connected with these main arteries, take the place of canals or an artificial water supply.

FAMINES—In any country where the population is dense and the means of communication backward, the failure of a harvest, whether produced by drought, by flood, by blight, by locusts, or by war, causes intense distress. Whether such distress shall develop into famine is merely a matter of degree, depending upon a combination of circumstances—the comparative extent of the failure, the density of the population, the practicability of imports, the facilities for transport, the resources of private trade, and the energy of the administration.

Drought, or a failure of the regular rainfall, is the great cause of famine. No individual foresight, no compensating influences, can prevent those recurring periods of continuous drought with which large Provinces of India are afflicted. Even an average rainfall in any one year, if irregularly distributed, or at the wrong seasons, may affect the harvest to a moderate degree, so also may flood or blight. The total failure of one monsoon may result in a general scarcity. But famine proper, or widespread starvation, is usually caused by a succession of seasons of drought. The cultivators of India are seldom dependent upon a single harvest, or upon the crops of one year. In the event of a partial failure, they can draw for their

food-supply either upon their own grain pits or upon the stores of the village merchants. The first sufferers, and those who also suffer most in the end, are the class who live by daily wages. But small is the number that can hold out, either in capital or credit, against a second year of insufficient rainfall; and even the third season sometimes proves adverse. The great famines in India have been caused by drought, and usually by drought continued over two or three years.

Water-supply.

It becomes necessary to inquire into the means of husbanding the water-supply. That supply can be derived only from three sources—(1) Local rainfall; (2) natural inundation; and (3) artificial irrigation from rivers, canals, tanks, or wells. Any of these sources may exist separately or together. In only a few parts of India can the rainfall be entirely trusted, as both sufficient in its amount and regular in its distribution. These favoured tracts include the whole strip of coast beneath the Western Ghâts, from Bombay to Cape Comorin; the greater part of the Provinces of Assam and Burma; together with the deltaic districts at the head of the Bay of Bengal. In these Provinces the annual rainfall rarely, if ever, falls below 60 to 100 inches; artificial irrigation and famine are there alike unknown.

Favoured Provinces.

The irrigation area of India.

The rest of the Indian peninsula may be described as liable, more or less, to drought. In Orissa, the scene of the most intense famine of recent times, the average rainfall exceeds 60 inches a year; in Sind, which has been exceptionally free from famine under British rule, the average drops to less than 10 inches. The local rainfall, therefore, is not the only element to be considered. Broadly speaking, artificial irrigation has protected, or is now in course of protecting, certain fortunate regions, such as the eastward deltas of the Madras rivers and the upper valley of the Ganges. The rest, and by far the greater portion, of the country is still exposed to famine. Meteorological science may possibly teach us to foresee what is coming.¹ But it may be doubted whether administrative efforts can do more than alleviate the calamity when once famine has declared itself. Lower Bengal and Oudh are watered by natural inundation as much as by the local rainfall; Sind derives its supplies mainly from canals filled by the floods of the Indus; the Punjab and the North-Western Provinces are dependent largely upon wells; the Deccan, with the entire south, is the land of tanks and reservoirs. But in all these Provinces, when the rainfall has failed over a series of

¹ See the chapter on Indian Meteorology at the end of this volume.

and of
1866.

million sterling. Again, in 1865-66, which will ever be known as the year of the Orissa famine, the Government attempted to organize relief works and to distribute charitable funds. But on neither of these occasions can it be said that its efforts were successful. In Orissa, especially, the admitted loss of one-fourth of the population proves the danger to which an isolated Province is exposed. The people of Orissa died because they had no surplus stocks of grain of their own; and because importation, on an adequate scale, was physically impossible by sea or land.

Famine of
1873-74.

Passing over the prolonged drought of 1868-70 in the North-Western Provinces and Rájputána, we come to the Behar scarcity of 1873-74, which first attracted the interest of England. Warned by the failure of the rains, and watched and stimulated by the excited sympathy of the public in England, the Government carried out a costly but comprehensive scheme of relief. By the expenditure of $6\frac{1}{2}$ millions sterling, and the importation of 1 million tons of rice, all loss of life was prevented. The comparatively small area of distress, and the facilities of communication by rail and river, allowed of the accomplishment of this feat, which remains unparalleled in the annals of Indian famine.

Famine of
1876-78.

The famine of 1876-78 is the widest spread and the most prolonged that India has experienced. The drought commenced in Mysore by the failure of the monsoon in 1875; and the fear of distress in the North-Western Provinces did not pass away until 1879. But it will be known in history as the great famine of Southern India. Over the entire Deccan, from Poona to Bangalore, the south-west monsoon failed to bring its usual rainfall in the summer of 1876. In

Failure of
rain, 1876.

the autumn of the same year, the north-east monsoon proved deficient in the south-eastern Districts of the Madras Presidency. The main food crop perished throughout an immense tract of country; and, as the harvest of 1875 had also been short, prices rapidly rose to famine rates. In November 1876, starvation was already at work, and Government adopted measures to keep the people alive. The next eighteen months, until the middle of 1878, were devoted to one long campaign against famine. The summer monsoon of 1877 proved a failure; some relief was brought in October of that year by the autumn monsoon; but all anxiety was not removed until the arrival of a normal rainfall in June 1878.

Failure of
rain, 1877.

Meanwhile the drought had reached Northern India, where it found the stocks of grain already drained to meet the famine

FAMINE OF 1876-78.

in the south Bengal, Assam, and Burma were the only Provinces which escaped in that disastrous year. The North Western Provinces, the Punjab, Rajputana, and the Central Provinces suffered from drought throughout the summer of 1877, and, from its consequences, far into the following year.

When once famine gets ahead of relief operations, the flood of distress bursts its embankments, and the people simply perish. Starvation and the long attendant train of famine diseases sweep away their hundreds of thousands. In 1876-78, the importation of grain was left free and within twelve months 268,000 tons were brought by land, and 166,000 tons by sea, into the distressed Districts of Southern India.

The total expenditure of Government upon famine relief in 1876-78 may be estimated at 11 millions sterling, not including the indirect loss of revenue, nor the amount debited against the State of Mysore. For this large sum of money there is but little to show in the shape of works constructed.

The largest number of persons in receipt of relief at one time in Madras was 2,591,900 in September 1877, of these only 634,581 were nominally employed on works, while the rest were gratuitously fed. From cholera alone, the deaths were returned at 357,430 for Madras, 58,648 for Mysore, and 57,252 for Bombay. Dr Cornish, the Sanitary Commissioner of Madras, well illustrated the effects of the famine by the returns of births and deaths over a series of years.

In 1876, when famine, with its companion cholera, was already beginning to be felt, the births registered in Madras numbered 632,113, and the deaths 680,381. In 1877, the year of famine, the births fell to 477,447, while the deaths rose to 1,556,312. In 1878, the results of the famine showed themselves by a still further reduction of the births to 348,346, and by the still high number of 810,921 deaths. In 1879 the births recovered to 476,307, still below the average, and the deaths diminished to 548,158. These figures are only approximate, but they serve to show how long the results of famine are to be traced in the vital statistics of a people.

With regard to the deaths, the Famine Commissioners thus report: 'It has been estimated, and in our opinion on substantial grounds, that the mortality which occurred in the Provinces under British administration during the period of famine and drought extending over the years 1877 and 1878 amounted, on a population of 197 millions, to $5\frac{1}{2}$ millions in excess of the deaths that would have occurred had the country been ordinarily healthy; and the statistical returns have not

certain what has long been suspected, that starvation and distress greatly check the fecundity of the population. It is probable that from this cause the number of births during the same period has been lessened by 2 millions; the total reduction of the population would thus amount to about 7 millions. Assuming the ordinary death-roll, taken at the rate of 35 per thousand, on 190 millions of people, the abnormal mortality of the famine period may be regarded as having increased the total death-rate by about 40 per cent.'

Famine
a weak
check on
popula-
tion.

But when estimated over a period of years, the effect of famine as a check upon the population is small. The Famine Commissioners calculate that, taking the famines of the past thirty years, as to which alone an estimate of any value can be made, the abnormal deaths caused by famine and its diseases have been less than 2 per thousand of the Indian population per annum. As a matter of fact, cultivation quickly extended after the famine of 1877-78, and there were in Bombay and Madras 120,000 more acres under tillage shortly after the long protracted scarcity than before it.

Famine of
1876-78
sum-
marized.

The famine of 1876-78 affected, directly, a population of 58½ million persons, and an area of 257,300 square miles. The average number daily employed by the State on relief works was 877,024. The average number of persons daily in receipt of gratuitous State relief was 446,641, besides private charities. Land revenue was remitted to close on 2 millions sterling. The famine lasted from 12 months in the North-Western Provinces, to 22 months in Madras. Its total cost, including both outlay and loss of revenue, is officially returned at £11,194,320.¹ A Commission was appointed to inquire into the causes of famine in India, and the means of averting or alleviating those calamities. Its report, presented to both Houses of Parliament in 1880, is replete with carefully collated facts regarding the past, and with wise suggestions for the future.

During the seven years which have elapsed since the great calamity of 1878, up to the time when these pages went to the press (June 1885), there has been no scarcity in India sufficiently intense or widespread to deserve the name of famine. Almost every season has brought a partial failure of the rains in one Province or another. But improved means of communication, and prompt measures for dealing with the distress, have prevented local scarcity from developing in any year into general famine.

¹ *Report of the Indian Famine Commission*, part i. p. 24 (1880).

CHAPTER XVIII.

MEANS OF COMMUNICATION.

THE means of communication in India may be classified under four headings—(1) railways, (2) roads, (3) rivers, and (4) canals. Internal communications

The existing system of railway communication in India dates from the administration of Lord Dalhousie. The first Indian line of rail was projected in 1843 by Sir Macdonald Stephenson, who was afterwards active in forming the East Indian Railway Company. But this scheme was blighted by the financial panic that followed soon afterwards in England. Bombay, the city which has most benefited by railway enterprise, saw the first sod turned in 1850, and the first line of a few miles opened as far as Thána (Tanna) in 1853. The elaborate minute, drawn up by Lord Dalhousie in the latter year, substantially represents the railway map of India at the present day, although filled in by Lord Mayo's extensions of 1869 and by subsequent lines. Indian railways
Their history,
1843-71

Lord Dalhousie's scheme consisted of well chosen trunk lines, traversing the length and breadth of the peninsula, and connecting all the great cities and military cantonments. These trunk lines were to be constructed by private companies, to whom Government should guarantee a minimum of 5 per cent. interest on their capital expended, and from whom it should demand in return a certain measure of subordination. The system thus sketched out was promptly carried into execution, and by 1871 Bombay was put into direct railway communication with the sister Presidencies of Calcutta and Madras. The task remaining for Lord Mayo in 1870 was the development of traffic by means of feeders, which should tap the districts of production, and thus open up the entire country. This task he initiated by the construction of minor State lines on a narrower gauge, and therefore at a cheaper rate, than the existing guaranteed railways. Lord Dalhousie's trunk lines, 1853
Lord Mayo's branch lines 1870

Four
classes of
Indian
lines.

'Guaran-
teed' rail-
ways.

The railways of India are now divided into four classes. In the first place, there are the railways constructed by guaranteed companies, for the most part between 1855 and 1875. These guaranteed railways, as a rule, follow the main lines of natural communication, and satisfy the first necessities of national life, both commercial and political. In the second place, there is a system of branch State lines, constructed during the last fifteen years, and some of them destined to yield fruit only in the future. The third class comprises railways worked by private companies under a system of Government concessions. The fourth class are railways within Native States.

The four
systems.

(1) Guar-
anteed
railways.

Each of these classes of railways has been constructed on a different system in regard to the method by which the capital was raised. The four systems may be briefly, although not accurately, described as follows. The guaranteed lines were constructed by companies formed in England, who raised their capital from their own shareholders under a guaranteed interest of 5 per cent. from the Government of India. Profits in excess of 5 per cent. were to be shared between the Government and the Company, but the Government reserved the right of buying up the lines at their market value after certain terms of years. The construction of guaranteed railways was carried out by the Company's staff under the supervision of Government.

(2) State
railways.

(3) 'As-
sisted.'

The State railways were constructed from capital raised by the Government direct; and they were executed by engineers in Government employ. The 'assisted' railway companies are a more recent development. They raise their capital under a guarantee of a low interest from Government, with free grants of land, or other concessions. The guarantee is usually for a limited period; but, as presently explained, different arrangements are made in each case.

(4) Native
State
railways.

The Native State lines are constructed from capital found by the individual State. The execution and management of these lines have, as a rule, been conducted by a staff employed by the Government of India, or by the trunk railway companies to which they serve as feeders.

Guaran-
teed lines.

The guaranteed lines, including the East Indian, which was transferred to Government on 1st January 1880, the Eastern Bengal Railway similarly transferred in 1883, and the Sind, Punjab, and Delhi Railway to be taken over by Government in January 1886, comprise the following:—(1) The East Indian, running up the valley of the Ganges from Calcutta (Howrah) as far as Delhi, with a branch to Jabalpur. (2) The Eastern

Bengal Railway, traversing the richest portion of the Gangetic valley, and connected with the Northern Bengal State Railway (3) The Great Indian Peninsula, which starts from Bombay, and sends one arm north east to Jabalpur, with a branch to Nagpur, and another south east to the frontier of Madras (4) The Madras line, with its terminus at Madras city, and two arms running respectively to the Great Indian Peninsula junction at Raichur and to Beypur on the opposite coast, with branches to Bangalore and Bellary (5) The Oudh and Rohilkhand, with its numerous branches, connecting Lucknow with Cawnpur, Benares, Aligarh, Moradabad, Bareilly, Saharanpur, and Hardwar (6) The Bombay, Baroda, and Central India, which runs due north from Bombay through the fertile plain of Gujrat, to Ahmadabad, where it joins the Rajputana Malwa State Railway, and ultimately connects with the East India and Sind, Punjab, and Delhi systems at Delhi and at Agra (7) The Sind, Punjab and Delhi, consisting of three sections, one in Lower Sind, another from Delhi to Lahore, and the third from Lahore to Multan (8) The South Indian (the only guaranteed line on the narrow gauge), in the extreme south, from Tinnevely to Madras city, with branches to Arcotum, Erode, Negapatam, Tuticorin, and Pondicherry

The State lines are too numerous to be individually described. They include the extension from Lahore to Peshawar on the north west frontier, the 'missing link,' from Multan to Haidarabad, thus bringing the Punjab into direct connection with its natural seaport at Karachi (opened throughout in 1878), the Rajputana Malwa State Railway connecting Ahmadabad with Delhi, Agra, and Khandwa, and the Northern Bengal State railway. The last named line starts from Saraghat opposite the Damukdiba station of the Eastern Bengal Railway, whence it runs northwards to the foot of the Himalayas. A small 2 feet gauge railway is thence carried up to the sanitarium of Darjiling, now within twenty four hours' journey of Calcutta. Among other State lines, the following may be specified. The Tirhut State Railway with its various branches intersects Northern Behar, and is intended to extend to the Nepal frontier on one side, and to Assam on the other. The Dacca and Maimansingh Railway will open out Eastern Bengal, the Nagpur Chhatísgarh Railway taps the great wheat growing Districts of the Central Provinces. Shorter State lines or branches from the trunk railways are numerous. In British Burma, a State line runs up the Irawadi valley from Rangoon to Prome, with an extension to the frontier station of

The eight
great lines
guaranteed

The State
railways.

MEANS OF COMMUNICATION.

Allan-myo. A second line up the Sittaung valley to Taungngu, is open for more than half its length, and the remainder is expected to be opened in 1886.

Of the assisted railway companies, the principal are the Bengal and North-Western, running from the Sonpur station of the East Indian Railway to Bahraich in Oudh; the Bengal Central line from Calcutta to Khúlná bordering on the Sundarbans; the various branches of the Southern Maráthá Railway in the Deccan, of which 214 miles out of a sanctioned length of $718\frac{1}{2}$ miles were open in March 1885; the Rohilkhand and Kumáun line; the Assam line to the recently-opened coal measures in Lakhimpur District; the little 2 feet gauge Dárlíng-Himálayan Railway (above mentioned); two short lines from the East Indian Railway to the shrine of Tarakeswar in Húglí District, and to Deogarh in the Santál Parganás, which are annually resorted to by large numbers of pilgrims from all parts of India. Other lines belonging to the assisted class are projected or have commenced construction. It is proposed to make on this system the Nágpur-Bengal line, which will connect the Chhatisgarh wheat plateau with the Húglí river, and thus complete an almost straight line of communication between Calcutta and Bombay. The Bhopál-Gwalior line will also be made on the assisted system; together with other lines belonging to the inner circle of communication in the interior of India.

The
'assisted'
system.

The principle adopted in the assisted system is for Government to guarantee a low rate of interest, or to give a guarantee for a limited period. The Company has therefore the keenest inducement to make the railway pay, as its profits, above the low guaranteed rate, depend on its own exertions, and on the economical working of the line. The Government recoups itself for the money advanced under the low guarantee before the line has begun to pay, by taking a share of the profits of the line when they exceed the guaranteed interest. This is the general principle of the assisted railways in India. But it is worked out differently in the case of almost every separate line; especially as regards the rate of interest guaranteed, and the duration or limits of guarantee.

Native
railways.

Besides these there are $663\frac{1}{2}$ miles of railway now (1885) opened in Native States, which have been constructed at the expense of the chiefs. The principal of these are the Pooné Railway, and the Bhaunagar-Gondal Railway in Western India; the Bhopál-Itársi line in Central India, the Jodhpur

Rajputána, the Nizam's Railway in Haidarabad, the Mysore Railway in Southern India, and the Rájputra Patiala line in the Punjab. The railways passing through the States of Gwalior and Holkar are not included in this list, as they were constructed, not at the cost of the chiefs themselves, but out of the proceeds of a loan made to the Government by the Maharajas Sindhia and Holkar, and are worked entirely by Government in connection with the Rajputana Malwa Railway.

The two following paragraphs exhibit the railway statistics of India for the years 1878 and 1885. They indicate the progress which has been made during the seven years, since the materials for the first edition of this book were compiled. Railway statistics, 1878 and 1885,

In 1878, the total mileage open for traffic was 8215 miles, of which 6044 miles belonged to guaranteed railways, and 2171 miles to State railways, total capital expended, £115,059,434, being £95,430,863 on the former, and £19,628,591 on the latter class, number of passengers conveyed, 38,519,792, number of tons of goods and minerals, 8,171,617, number of live stock, 594,249, gross receipts, £10,404,753, gross expenses, £5,206,938, net earnings, £5,197,815, of which only £195,787 is credited to the State railways, percentage of gross expenses to gross receipts, 50.04, varying from 34.97 in the case of the East Indian main line to an average of 78.27 for all the State lines. These figures showed 1 mile of railway to every 109 square miles of area in 1878, as compared with the area of British India, or to 180 square miles, as compared with the area of the entire peninsula. The average cost of construction per mile was almost exactly £14,000. The guaranteed railways embracing the great trunk lines throughout India, are on the 'broad gauge' of 5 feet 6 inches, the State lines follow, as a rule, the narrow or metre gauge of 3.281 feet. On 31st March 1879, the total length opened was 8545 miles, and the capital invested, 120 millions sterling.

The total extent of railways open for traffic in India on the 31st March 1885 was 12,004 miles, of which 6906 miles were in the hands of companies, either guaranteed or assisted, 4434 miles were State lines, either Imperial or Provincial, and 664 miles belonged to Native States. On the same date, the extent of railway line under construction was 3555 miles, of which 963 miles were in the hands of companies, 2125 miles were under construction by the State, and 467 miles by Native States. Railway statistics, 1885

The capital outlay on railways and connected steamer services

Railway capital

further deterioration. A staff of engineers is constantly employed to watch the shifting bed, to assist the scouring action of the current, and to advertise the trading community of the depth of water from time to time. In the year 1882-83, a total sum of £11,667 was expended on this account, while an income of £18,296 was derived from tolls.

The artificial water channels of India may be divided into two classes: (1) Those confined to navigation, (2) those constructed primarily for purposes of irrigation. Of the former class, the most important examples are to be found in the south of the peninsula. On both the Malabar and the Coromandel coasts, the strip of low land lying between the mountains and the sea affords natural facilities for the construction of an inland canal running parallel to the shore. In Malabar, the salt water lagoons or lakes, which form so prominent a feature in the local geography, merely required to be supplemented by a few cuttings to supply continuous water communication from the port of Calicut to Cape Comorin. On the east coast the Buckingham Canal, running north from Madras city as far as the delta of the Kistna, has recently been completed without any great engineering difficulties. In Bengal there are a few artificial canals, of old date, but of no great magnitude, in the neighbourhood of Calcutta. The principal of these form the system known as the Calcutta and Eastern Canals, which consist for the most part of natural channels artificially deepened, in order to afford a safe boat route through the Sundarbans. Up to the close of the year 1877-78, a capital of £360,332 had been expended by Government on the Calcutta Canals, the gross income in 1877-78 was £44,120, after deducting cost of repairs, etc., charged to revenue account, and interest at the rate of 4½ per cent, a net profit was left amounting to £8,748. In 1882-83, the tolls on the Calcutta Canals realized £53,372. The Hujli Tidal Canal in Midnapur District, which cuts off a difficult corner of the Hugli river, yielded a net revenue of £3,171 in the same year. In 1882-83, this canal only yielded a net profit of £446, owing to the cost of dredging operations, and the consequent closing of the canal for a portion of the year.

Most of the great irrigation works, both in Northern and Southern India, have been so constructed as to be available also for navigation. The general features of these works have been already described. So far as regards Bengal, navigation

whether water carriage is able to compete, as regards the more valuable staples, with communication by rail. But for cheap and bulky staples, or for slow subsidiary traffic, it is difficult to overrate the economic importance of the Indian rivers.

The
Ganges.

The
Brahma-
putra.

Minor
streams

River
trade.

The
Nadiyā
rivers.

After the East Indian Railway was fairly opened, through steamers ceased to ply upon the Ganges; and the steam flotilla on the Indus shrank to insignificance when through communication by rail became possible between Multán and Karachi. On the Brahmaputra and its tributary the Bārak, and on the Irawadi, steamers still run secure from railway competition. But it is in the Gangetic delta that river navigation attains its highest development. There the population may be regarded as half amphibious. Every village can be reached by water in the rainy season, and every family keeps its boat. The main channels of the Ganges and Brahmaputra, and their larger tributaries, are navigable throughout the year. During the rainy months, road carriage is altogether superseded. All the minor streams are swollen by the rainfall on the hills and the local downpour; while fleets of boats sail down with the produce that has accumulated in warehouses on the river banks.

The statistics of this subject belong rather to the department of internal trade,¹ but it may be mentioned here that the number of laden boats registered in Bengal in the year 1877-78 was 401,729. These formed but a fraction of the real total. Boat-racing forms a favourite native sport in the deltaic and eastern Districts. It is conducted with great spirit and rivalry by the villagers. In some places, the day concludes with an illuminated boat procession by torchlight.

The great majority of the Bengal rivers require no attention from Government, but the network known as the three Nadiyā rivers is kept open for traffic only by close supervision. These three rivers, the Bhāgirāthī, Jalangī, and Mátābhāngā, are all offshoots of the Ganges, which unite to make up the head-waters of the Huglí.² In former times, the main volume of the Ganges was carried to the sea by one or other of these channels. But they now receive so little water as to be navigable only in the rainy season, and then with difficulty. Since the beginning of the present century, Government has undertaken the task of preventing these Huglí head-waters from

¹ Dealt with in next chapter.

² See article HUGLI RIVER, *The Imperial Gazetteer*, for an account of the engineering history of these rivers. It is also given in greater detail in Hunter's *Statistical Account of Bengal*, vol. ii. pp. 19-32.

further deterioration. A staff of engineers is constantly employed to watch the shifting bed, to assist the scouring action of the current, and to advertise the trading community of the depth of water from time to time. In the year 1882-83, a total sum of £11,667 was expended on this account, while an income of £18,296 was derived from tolls.

The artificial water channels of India may be divided into two classes (1) Those confined to navigation, (2) those constructed primarily for purposes of irrigation. Of the former class, the most important examples are to be found in the south of the peninsula. On both the Malabar and the Coromandel coasts the strip of low land lying between the mountains and the sea affords natural facilities for the construction of an inland canal running parallel to the shore. In Malabar, the salt water lagoons or lakes, which form so prominent a feature in the local geography, merely required to be supplemented by a few cuttings to supply continuous water communication from the port of Calicut to Cape Comorin. On the east coast the Buckingham Canal running north from Madras city as far as the delta of the Kistna, has recently been completed without any great engineering difficulties. In Bengal there are a few artificial canals, of old date, but of no great magnitude, in the neighbourhood of Calcutta. The principal of these form the system known as the Calcutta and Eastern Canals which consist for the most part of natural channels artificially deepened in order to afford a safe boat route through the Sundarbans. Up to the close of the year 1877-78 a capital of £360,332 had been expended by Government on the Calcutta Canals the gross income in 1877-78 was £44,120, after deducting cost of repairs, etc., charged to revenue account, and interest at the rate of 4½ per cent, a net profit was left amounting to £8748. In 1882-83, the tolls on the Calcutta Canals realized £53,372. The Hujli Tidal Canal in Midnapur District, which cuts off a difficult corner of the Hughli river, yielded a net revenue of £3171 in the same year. In 1882-83, this canal only yielded a net profit of £446, owing to the cost of dredging operations, and the consequent closing of the canal for a portion of the year.

Most of the great irrigation works, both in Northern and Southern India, have been so constructed as to be available also for navigation. The general features of these works have been already described. So far as regards Bengal, navigation

on the Orissa Canals in 1877-78 yielded £3384, and in 1882-83, £10,847; on the Midnapur Canal, £10,692 in 1877-78, and £10,642 in 1882-83; and on the Son Canals, £5965 in 1877-78, and £3906 in 1882-83; the aggregate being considerably larger than was derived from irrigation. In Madras, boat tolls in the Godāvāri delta brought in £4496 in 1877-78, and £6295 in 1882-83. In the Kistna delta, tolls realized £1718 in 1877-78, and £3956 in 1882-83. The works of the Madras Irrigation Company on the Tungabhadra were not made available for navigation until 1879, and they were taken over by Government in 1882. Their navigation receipts in that year amounted to £1068.

on Madras
canals.

CHAPTER XIX

COMMERCE AND TRADE

FROM the earliest days India has been a trading country. The industrial genius of her inhabitants even more than her natural wealth and her extensive seaboard distinguished her from other Asiatic lands. In contrast with the Arabian peninsula on the west, with the Malayan peninsula on the east, or with the equally fertile empire of China, India has always maintained an active intercourse with Europe. Philology proves that the precious cargoes of Solomon's merchant ships came from the ancient coast of Malabar. The brilliant mediæval republics of Italy drew no small share of their wealth from their Indian trade. It was the hope of participating in this trade that stimulated Columbus to the discovery of America, and Da Gama to the circumnavigation of the Cape of Good Hope. Spices, drugs, dyes, and rare woods, fabrics of silk and cotton, jewels, and gold and silver,—these were the temptations which allured the first adventurers from Europe.

The East and the West were then separated by a twelve month's voyage, full of hardships and perils. A successful venture made the fortune of all concerned, but trade was a lottery, and not far removed from piracy. Gradually, as the native kingdoms fell, and the proud cities of mediæval India sank into ruin, the legendary wealth of India was found to rest upon an unstable basis. It has been reserved for our own day to discover, by the touchstone of open trade, the real source of her natural riches, and to substitute bales of raw produce for boxes of curiosities. The cotton, grain, oil seeds, and jute of India now support a large population in England.

Before entering on the statistics of Indian trade, it is well to apprehend the function which commerce has now to perform in India. The people have in some Provinces outgrown the food producing powers of the soil, in many others, they are pressing heavily upon these powers. Agriculture, almost their sole industry, no longer suffices for their support. New

Trade of India

Ancient

Mediæval

Modern

The modern function of trade in India

on Madras
canals.

on the Orissa Canals in 1877-78 yielded £3384, and in 1882-83, £10,847; on the Midnapur Canal, £10,692 in 1877-78, and £10,642 in 1882-83; and on the Son Canals, £5965 in 1877-78, and £3906 in 1882-83; the aggregate being considerably larger than was derived from irrigation. In Madras, boat tolls in the Godávari delta brought in £4496 in 1877-78, and £6295 in 1882-83. In the Kistna delta, tolls realized £1718 in 1877-78, and £3956 in 1882-83. The works of the Madras Irrigation Company on the Tungabhadra were not made available for navigation until 1879, and they were taken over by Government in 1882. Their navigation receipts in that year amounted to £1068.

CHAPTER XIX

COMMERCE AND TRADE

From the earliest days India has been a trading country. The industrial genius of her inhabitants even more than her natural wealth and her extensive seaboard distinguished her from other Asiatic lands. In contrast with the Arabian peninsula on the west, with the Malayan peninsula on the east, or with the equally fertile empire of China, India has always maintained an active intercourse with Europe. Philology proves that the precious cargoes of Solomon's merchant ships came from the ancient coast of Malabar. The brilliant mediæval republics of Italy drew no small share of their wealth from their Indian trade. It was the hope of participating in this trade that stimulated Columbus to the discovery of America, and Da Gama to the circumnavigation of the Cape of Good Hope. Spices, drugs, dyes, and rare woods, fabrics of silk and cotton, jewels and gold and silver, —these were the temptations which allured the first adventurers from Europe.

The East and the West were then separated by a twelve month's voyage, full of hardships and perils. A successful venture made the fortune of all concerned, but trade was a lottery, and not far removed from piracy. Gradually, as the native kingdoms fell, and the proud cities of mediæval India sank into ruin, the legendary wealth of India was found to rest upon an unstable basis. It has been reserved for our own day to discover, by the touchstone of open trade, the real source of her natural riches, and to substitute bales of raw produce for boxes of curiosities. The cotton, grain, oil seeds, and jute of India now support a large population in England.

Before entering on the statistics of Indian trade, it is well to apprehend the function which commerce has now to perform in India. The people have in some Provinces outgrown the food producing powers of the soil, in many others, they are pressing heavily upon these powers. Agriculture, almost their sole industry, no longer suffices for their support. New

Trade of India

Ancient

Mediæval

Modern

The modern function of trade in India

New
industries
necessary.

industries have become a necessity for their well-being. Commerce and manufactures have therefore obtained an economical importance which they never had before in India; for they represent the means of finding employment and food for the rapidly increasing population. A popular sketch of the social aspects of Indian trade will therefore be first given, before arranging in more logical sequence the facts and figures connected with its recent history and development.

Large
sea-borne
trade
impossible
under the
Mughals.

Their
capitals,

merely
royal
camps.

A large external trade was an impossibility under the Mughal Emperors. Their capitals of Northern India, Agra and Delhi, lay more than a thousand miles from the river's mouth. But even the capitals of the seaboard Provinces were chosen for military purposes, and with small regard to the commercial capabilities of their situation. Thus, in Lower Bengal, the Muhammadans under different dynasties fixed in succession on six towns as their capital. Each of these successive capitals was on a river bank; but not one of them possessed any foreign trade, nor indeed could have been approached by an old East Indiaman. They were simply the court and camp of the king or the viceroy for the time being. Colonies of skilful artisans settled round the palaces of the nobles to supply the luxurious fabrics of oriental life. After the prince and court had in some new caprice abandoned the city, the artisans remained, and a little settlement of weavers was often the sole surviving proof that the decaying town had once been a capital city. The exquisite muslins of Dacca and the soft silks of Murshidábád still bear witness to the days when these two places were successively the capital of Bengal. The artisans worked in their own houses. The manufactures of India were essentially domestic industries, conducted by special castes, each member of which wove at his own hereditary loom, and in his own village or homestead.

Growth of
trading
cities
under
British
rule.

One of the earliest results of British rule in India was the growth of great mercantile towns. Our rule derived its origin from our commerce; and from the first, the East India Company's efforts were directed to creating centres for maritime trade. Other European nations, the Portuguese, the Dutch, the Danes, and the French, competed with us as merchants and conquerors in India, and each of them in turn attempted to found great seaports. The long Indian coast, both on the east and the west, is dotted with decaying villages which were once the busy scenes of those nations' early European trade. Of all their famous capitals in India, not one has now the

commercial importance of Cardiff or Greenock, and not one of them has a harbour which would admit at a low tide a ship drawing 20 feet.

The truth is, that it is far easier to pitch a camp and erect a palace, which, under the native dynasties, was synonymous with founding a capital, than it is to create a centre of trade Emporia of commerce must grow of themselves, and cannot be called suddenly into existence by the fiat of the wisest autocrat. It is in this difficult enterprise in which the Portuguese the Dutch, the Danes, and the French had successively failed that the British in India have succeeded. We make our appearance in the long list of races who have ruled that splendid empire not as temple builders like the English, nor as palace and tomb builders like the Musalmans, nor as fort builders like the Maráthas nor as church builders like the Portuguese but in the more commonplace capacity of town builders as a nation that had the talent for selecting sites on which great commercial cities would grow up, and who have in this way created a new industrial life for the Indian people.

Calcutta and Bombay the two commercial capitals of India, are the slow products of British rule. Formerly, the industries of India were essentially domestic manufactures, each man working at his hereditary occupation, at his own loom or at his own forge. Under British rule a new era of production has arisen in India—an era of production on a great scale, based upon the co operation of capital and labour, in place of the small household manufactures of ancient times based on To Englishmen, who have from our youth grown up in the midst of a keen commercial civilisation it is not easy to realize the change thus implied.

The great industrial cities of British India are the type of this change. Under native rule, the country had reached what political economists of Mill's school called 'the stationary stage of civilisation. The husbandmen simply raised the food grains necessary to feed them from one harvest to another. If the food crops failed in any district, the local population had no capital and no other crops where with to buy food from other districts, so, in the natural and inevitable course of things they perished. Now, the peasants of India supplement their food supply with more profitable crops than the mere foodstuffs on which they live. They also raise an annual surplus of grain for exportation, which is available for India's own wants in time of need. Accordingly,

there is a much larger aggregate of capital in the country; that is to say, a much greater national reserve or staying power. The so-called 'stationary stage' in India has disappeared, and the Indian peasant is keenly alive to each new demand which the market of the world may make upon the industrial capabilities of his country; as the history of his trade in cotton, jute, wheat, and oil-seeds proves.

Summary
of Indian
exports,
1700-1885.

At the beginning of the last century, before the English became the ruling power in India, the country did not produce £1,000,000 a year of staples for exportation. During the first three-quarters of a century of our rule, the exports slowly rose to about £10,000,000 in 1834. During the half century since that date, the old inland duties and other remaining restrictions on Indian trade have been abolished. Exports have multiplied by eight-fold. In 1880, India sold to foreign nations £66,000,000 worth, and in 1884-85, upwards of £80,000,000 worth of strictly Indian produce, which the Indian husbandman had raised, and for which he was paid. In 1880, the total foreign trade of India, including both exports and imports, exceeded £122,000,000. In 1884-85, the total foreign import and export trade of India, excluding treasure and Government stores, was over £136,000,000, or including treasure and Government stores, nearly £155,000,000.

India's
balance of
trade.

India has more to sell to the world than she requires to buy from it. During the five years ending 1879, the staples which she exported exceeded by an annual average of over £24,000,000 the merchandise which she imported.¹ During the next five years ending 31st March 1884, the gross surplus of exports of merchandise over imports rose to 30 millions sterling per annum.²

What
she does
with the
balance.

About one-third of this favourable balance of trade India receives in hard cash. During the five years ending 1879, she accumulated silver and gold, exclusive of re-exports, at the rate of £7,000,000 per annum, and during the next five years ending March 1884 at the rate of £11,000,000 per annum. With another third she pays interest at low rates for the capital with which she has constructed the material framework of her industrial life, — her railways, irrigation works,

¹ This calculation deals with the *gross* surplus of exports over imports, without going into the question of re-exports of foreign goods. The total 'merchandise' exported, during the five years ending 1879, averaged £63,000,000; the total 'merchandise' imported averaged £38,000,000. *Vide post*, Table at p. 562, entitled *Foreign Trade of India*.

² This also is the gross surplus, with out deductions for re-exports.

cotton mills, coal mines, indigo factories, tea gardens, docks, steam navigation lines, and debt. For that capital she goes into the cheapest market in the world, London, and she remits the interest, not in cash, but in her own staples, which the borrowed capital has enabled her to bring cheaply to the seaboard. With the remaining third of her surplus exports, she pays the home charges of the Government to which she owes the peace and security that alone have rendered possible her industrial development.

The Home Charges include not only the salaries of the supervising staff in England and the pensions of the military and civil services who have given their life's work to India, but the munitions of war a section of the army, including the cost of its recruitment and transport stores for public works, and the *materiel* for constructing and working the railways. That *materiel* can be bought more cheaply in England than in India and India's expenditure on good government is as essential an item for her industrial development, and repays her as high a profit as the interest which she pays in England for the capital with which she has constructed her dockyards and railways. But after paying for all the Home Charges for the interest of capital raised in England for Indian railways, and other reproductive works, and for the *materiel* required for their construction and maintenance India has still a surplus of £11 000 000 from her export trade for which she receives payment in silver and gold.

The
'Home
Charges

India's
yearly
savings

The trade of India may be considered under four heads—
(1) sea borne trade with foreign countries (2) coasting trade
(3) frontier trade, chiefly across the northern mountains, (4)
internal traffic within the limits of the Empire

Division
of Indian
trade

The sea borne trade most powerfully attracts the imagination, and we have the most trustworthy statistics regarding it. With an extensive seaboard, India has comparatively few ports. Calcutta monopolizes the commerce, not only of Lower Bengal, but of the entire river systems of the Ganges and the Brahmaputra. Bombay is the sole outlet for the products of Western India, Gujarat (Guzerât), the Deccan, and the Central Provinces, Karachi (Kurrachee) performs a similar office for the valley of the Indus, and Rangoon for that of the Irawadi. These four ports have been chosen as the termini where the main lines of railway debouch on the sea. In the south of India alone is the sea borne trade distributed along the coast.

Sea borne
trade

The four
great
ports

The south-western side has a line of fair-weather ports, from Goa to Cochin. On the south-east there is not a safe harbour, nor a navigable river-mouth; although ships anchor off the shore at Madras, and in several other roadsteads, generally near the mouths of the rivers. A Madras harbour has, however, been under construction during several years; and, in spite of destructive cyclones and storm-waves, the work is now well advanced. Since these sheets went to press, a project has been put forward for constructing docks at Madras, to cover 25 acres, protected by groins thrown out at right angles from the beach, and by a breakwater (1885).

Of the total foreign trade of India, Calcutta and Bombay till recently controlled about 40 per cent. each. Madras had 6 per cent., Rangoon 4 per cent., and Karáchi 2 per cent., leaving a balance of only 8 per cent. for all the remaining ports of the country. In 1884-85, Bombay had 43·51 per cent. of the foreign trade; Calcutta, 36·97 per cent.; Madras, 5·43 per cent.; Rangoon, 4·67 per cent.; and Karáchi, 3·79 per cent., leaving only 5½ per cent. for the minor ports, of which the principal are—Chittagong, Maulmain, Akyab, Tuticorin, and Coconada. Calcutta and Bombay form the two central depôts for collection and distribution, to a degree without a parallel in other countries. The growth of their prosperity is an index of the development of Indian commerce.

Minor
ports.

The two
centres.

Early
Portu-
guese
trade,
1500-1600.

When the Portuguese, the pioneers of Eastern adventure, discovered the over-sea route to India, they were attracted to the Malabar coast, where they found wealthy cities already engaged in active commerce with Persia, Arabia, and the opposite shore of Africa. From Malabar they brought back pepper and other spices, and the cotton calicoes which took their name from Calicut. Fixing their head-quarters at Goa, they advanced northwards to Surat, the ancient port not only for Gujarát but for all Western Upper India. But with the Portuguese, the trading instinct was subordinate to the spirit of proselytism and to the ambition of territorial aggrandizement.

Dutch
monopoly,
1600.

English
factories,
1625.

The Dutch superseded them as traders, and organized a colonial system upon the basis of monopoly and forced labour, which survives in Java to this day. Last of all came the English, planting factories at various points along the Indian coast-line, and content to live under the shadow of the native powers. Wars with the Portuguese, with the Dutch, and with the French, first taught the English their own strength; and as the Mughal Empire fell to pieces,

they were compelled to become rulers in order to protect their commercial settlements. Our Indian Empire has grown out of trade, but, meanwhile, our Indian trade has grown even faster than our empire.¹

'The Governor and Company of Merchants of London ^{English} trading to the East Indies' was incorporated by Royal ^{trade,} Charter on 31st December 1600, having been directly called ^{1600 1700} into existence by the grievance of monopoly prices imposed upon pepper by the Dutch. Its first voyage was undertaken in 1601 by five ships, whose cargoes consisted of £28,742 in bullion and £6860 in goods, the latter being chiefly cloth, lead, tin, cutlery, glass, quicksilver, and Muscovy hides. Their destination was 'Atcheen in the Fir East' (Sumatra). The first English factory was established at Bintam in Java, in 1603. The return cargoes partly captured from the Portuguese, comprised raw silk, fine calicoes, indigo, cloves, and mace. The earliest English factories on the mainland of India were founded at Masulipatam in 1610 and Surat in 1612-15. In 1619, ten ships were despatched to the East by the Company, with £62,490 in precious metals and £28,508 in goods, the proceeds, brought back in a single ship, were sold for £108,887. The English made no great advance in trade during the 17th century. By the massacre of Amboyna (1623) the Dutch drove the English Company out of the Spice Islands, and the period of its great establishments (*aurangis*) for weaving had not yet commenced in India.

Early in the 18th century, our affairs improved. During the ^{Our trade} twenty years ending 1728, the average annual exports from ^{advances,} England of the East India Company were £442,350 of bullion ¹⁷⁰⁰⁻⁶⁴ and £92,288 of goods. The average imports were valued at £758,042, chiefly consisting of calicoes and other woven goods, raw silk, diamonds, tea, porcelain, pepper, drugs, and salt petre. In 1772, the sales at the India House reached the total value of 3 millions sterling, the shipping owned by the Company was 61,860 tons. From 1760 onwards, the Custom House returns of trade with the East Indies are given in Macpherson's *History of Commerce*. But they are deceptive for comparative purposes, as they include the trade with China as well as with India.

In 1834, when the Company's monopoly of trade with China ^{Statistics} as well as with India ceased, the exports from India were valued ^{for 1834} at £9,674,000, and the imports at £2,576,000. Shortly after

¹ The history of the early European settlements in India has been already dealt with in chapter xiv pp 356-377

Inland
duties
abolished,
1836-48.

that date, trade was freed from many vexatious restrictions. Inland duties were mostly abolished in Bengal in 1836, in Bombay in 1838, and in Madras in 1844; the inland sugar duties in 1836 and the inland cotton duties in 1847. The navigation laws were repealed in 1848. The effect of these reforms, and the general progress of Indian commerce, may be seen in the table below. It exhibits the foreign trade of the country, in millions sterling, for each of the nine quinquennial periods between 1840 and 1884.

Before, however, entering on the items of Indian trade, the method which has been adopted in dealing with them ought to be explained. Many of those items may be regarded as agricultural productions, and as manufactures or native industries, as well as articles of export or internal trade. In such cases it has been deemed best to deal with them in each of these aspects, even at the cost of repetition. Thus cotton is treated of alike in the chapter on agriculture, and in those on trade and on manufactures. This plan will be most convenient to those who wish to consult the individual chapters, without the necessity of reading the whole volume.

FOREIGN TRADE OF INDIA FOR FORTY-FIVE YEARS, CLASSIFIED
ACCORDING TO QUINQUENNIAL PERIODS, IN MILLIONS
STERLING.

PERIODS.	IMPORTS.			EXPORTS.		
	Cotton Manufactures.	Total Merchandise.	Treasure.	Raw Cotton.	Total Merchandise.	Treasure.
1840-44,	3'19	7'69	2'74	2'34	14'62	0'48
1845-49,	3'75	9'14	3'07	1'68	17'00	1'32
1850-54,	5'15	11'06	4'79	3'14	20'10	1'00
1855-59,	6'94	15'58	11'27	3'11	25'85	0'92
1860-64,	10'92	23'97	17'07	15'56	43'17	1'02
1865-69,	15'74	31'70	17'62	25'98	57'66	1'80
1870-74,	17'56	33'04	8'56	17'41	57'84	1'59
1875-79,	19'29	38'36	9'81	11'52	63'13	2'81
1880-84,	22'48	47'95	12'61	14'29	79'97	1'26
Average in millions sterling,	11'67	24'27	9'72	10'55	42'15	1'36

Steadiness
of its
growth.

The preceding table shows a rapid and steady growth, which only finds its parallel in the United Kingdom. The exceptional imports of silver from 1855 to 1859 were required to pay for the Mutiny; those from 1859 to 1864 represent the

price of the cotton sent to Manchester during the American war

Before examining in detail the history of some of the chief staples of trade, it may be convenient to give in this place, as an illustration of the steady growth of Indian foreign trade, the statistics of three years, 1877-78, which was a year of inflation despite the incidence of famine in Southern India, of 1882-83, and of 1884-85. In 1877-78, the total foreign sea borne trade exceeded 126 millions sterling in value. The transactions on behalf of Government, such as stores equipments, and munitions of war, show an import of £2,138,182, and an export of £366,15. The imports of merchandise were £39,326,003 and of treasure £17,355,460, total imports, £56,681,463. The exports of merchandise were £65,185,713, and of treasure £2,155,136, total exports, £67,340,849. Indian trade in 1878

These figures exhibit an excess of exports over imports amounting to £10,659,386, and an excess of treasure imported to the amount of £15,200,324. By far the larger share of the trade of 1878, amounting to 61 per cent, was conducted with the United Kingdom, next came China, with 13 per cent, and then the following countries in order — France, Straits Settlements, Ceylon, Italy, United States, Mauritius, Austria, Persia, Arabia, Turkey, Egypt, Australia, Aden, East Coast of Africa. The total number of vessels that entered and cleared in 1877-78 was 12,537, with an aggregate of 5,754,379 tons, or an average of 459 tons each. Of the total tonnage 76 per cent was British, 7 per cent British Indian, and 15 per cent foreign, American, Italian, and French being best represented in the latter class. Excess of exports.
In India's chief customers.

The total value of the Indian foreign seaboard trade in 1882-83, including merchandise, treasure, Government stores, etc., exceeded 150 millions sterling, or 24 millions in excess of the total value of the trade in 1877-78. The imports of private merchandise amounted to £50,003,041, and of treasure to £13,453,157, total private imports, £63,456,198, or £6,774,735 above the imports of 1877-78. The exports of merchandise amounted to £83,400,865, and of treasure to £980,859, total exports, £84,381,724, or £17,040,875 above the exports of 1877-78. Excess of exports over imports in 1882-83 (exclusive of Government transactions), £20,925,526. The Government transactions, such as stores, equipments, munitions of war, railway plant, etc., show an import of £2,092,670, and an export of £145,458, including £61,200 of Government treasure. Indian trade in 1882-83

Suez Canal
trade,
1882-83.

Of the private imports, £47,172,542, or 74·3 per cent., came in 1882 *via* the Suez Canal, and £16,283,656, or 25·7 per cent., by other routes. Of the exports, £44,438,288, or 52·7 per cent., went *via* the Canal, and £39,943,436, or 47·3 per cent., by other routes. Of the total import and export private trade, aggregating £147,837,922, £91,610,830, or 61·9 per cent., passed through the Suez Canal, and £56,227,092, or 38·1 per cent., by other routes. The total number of sailing and steam vessels that entered and cleared British Indian ports from foreign countries in 1882-83, was 11,715 with an aggregate burthen of 7,071,884 tons, or an average of 513 tons each. Of the total shipping, 4257 vessels with a total of 5,366,770 tons were returned as British, 2525 with 361,189 tons as British Indian, 1834 with 1,168,293 tons as foreign, and 3099 with 175,632 tons as native craft, in 1882-83.

Indian
trade in
1884-85.

The figures for 1884-85 show a steadily increasing trade. In that year, the total value of the private sea-borne foreign export and import trade was returned at over 152 millions, or 26 millions over the total sea-borne trade in 1877-78, and of 2 millions over that of 1882-83. The imports of private merchandise in 1884-85 amounted to £53,147,919, and of treasure to £13,878,841; total private imports, £67,026,760, or £10,345,297 in excess of the imports of 1877-78, and £3,570,562 in excess of those for 1882-83. The exports of merchandise amounted to £83,115,443, and of treasure to £1,885,679; total private exports, £85,001,122, or £17,660,273 over the exports of 1877-78, and of £619,398 over those for 1882-83. Excess of exports over imports in 1884-85, £17,974,362. The Government imports in the shape of stores, materials of war, railway plant, treasure, etc., amounted to £2,563,111, and the exports to £138,007.

Suez Canal
trade,
1884-85.

Of the private trade, merchandise and treasure to the value of £51,605,827, or 76·99 per cent. of the imports, were, in 1884, imported *via* the Suez Canal, while £47,530,200, or 55·9 per cent. of the total exports, were exported by the same route. Of the total import and export private trade in 1884-85, £99,136,025, or 65·2 per cent., passed through the Suez Canal, and £52,891,855, or 34·8 per cent., proceeded by other routes. The total number of sailing and steam vessels that entered and cleared British Indian ports with cargoes from and to foreign countries in 1884-85, was 8222, with an aggregate burthen of 5,814,904 tons, or an average of 707 tons each.

Statistics are not yet (July 1885) available to exhibit in detail the total value and distribution of the foreign trade of India in 1884-85. The figures in the following paragraphs and tables refer to 1882-83, the latest year for which the final returns, as printed by command of Parliament, have been received.

Of the entire trade in 1882-83 £81,770,117, or 55.31 per cent, was conducted with the United Kingdom, £17,684,973, or 11.96 per cent, with China, £7,757,818, or 5.25 per cent, with France, £5,409,804, or 3.66 per cent, with Italy, and £5,330,471, or 3.44 per cent, with the Straits Settlements, and then the following countries in order—the United States of America, 2.89 per cent, Austria, 2.17 per cent, Australia, 2.02 per cent, Ceylon, 1.85 per cent, Egypt, 1.69 per cent, Belgium, 1.51 per cent, Persia, 1.39 per cent, Cape and East Coast of Africa, 1.19 per cent, Arabia, 1.05 per cent, Mauritius, 1.00 per cent, Turkey, 0.73 per cent, and Aden, 0.48 per cent.

As regards imports into India, the first thing to notice is the enormous predominance of two items—cotton goods and treasure. During the forty-five years ending 1883-84, cotton goods formed 33 per cent, or exactly one third of the total, and treasure an additional 30 per cent. Next in order come metals (copper, which is largely used by native smiths, slightly exceeding iron). Government stores, including munitions of war, boots, liquor, and clothing for soldiers, and railway plant, liquors, entirely for European consumption, coal, for the use of the railways and mills, railway plant for the guaranteed and assisted companies, salt, provisions, machinery and mill work, and manufactured silk. It will thus be seen that, with the exception of Manchester goods, no articles of European manufacture are in large demand for native consumption, but only for the needs of our English administration, and few raw materials, except coal, copper, iron, mineral oil, and salt.

England's export trade to India thus mainly depends upon piece goods. In the beginning of the 17th century, the industry had not been introduced into England. The small British demand for cotton-goods or calicoes was met by circuitous importations from India itself, where cotton weaving is an immemorial industry. In 1641, 'Manchester cottons,' in imitation of Indian calicoes and chintzes, were still made of wool. Cotton is said to have been first manufactured

Distribution of Indian trade,

Analysis of Indian imports

History of cotton goods trade

Manchester, 1641

[Sentence continued on page 568

FOREIGN SEA-BORNE TRADE OF BRITISH INDIA FOR 1882-83.

IMPORTS.			
Articles.	Quantities.	Value.	
Apparel,	£769,752
Arms, Ammunition, etc.,	79,577
Books, Paper, and Stationery,	625,431
Coal, Coke, etc., . . . tons	628,824	...	1,019,883
Cotton Twist and Yarn, . . lbs.	49,392,375	£3,378,190	
Cotton Piece-Goods and Manufactures, } yards	1,642,798,990	21,431,872	
Total Cotton Goods,	24,810,062
Drugs and Medicines,	391,673
Dyes,	206,640
Fruits and Vegetables,	211,435
Glass, and Manufactures of,	483,743
Gums and Resins,	117,921
Hardware, Cutlery, and Plate,	791,791
Horses,	186,815
Ivory,	212,107
Jewellery and Precious Stones,	307,189
Liquors { Ale, Beer, and Porter, gals.	1,170,554	£272,323	
Spirits,	949,169	674,969	
Wines and Liqueurs, . . "	418,169	387,322	
Total Liquors,	2,537,892	...	1,334,614
Machinery and Mill Work,	1,342,398
Metals { Iron, tons	157,597	£1,870,494	
Steel,	10,645	163,415	
Brass, cwts.	11,962	64,688	
Copper, "	450,098	1,938,376	
Spelter, "	127,383	125,669	
Tin, "	42,718	277,306	
Lead, "	73,583	101,104	
Quicksilver, . . . lbs.	354,689	37,100	
Unenumerated,	37,834	
Total Metals,	4,615,986
Oils,	1,050,897
Paints and Colours,	234,450
Perfumery,	63,336
Porcelain and Earthenware,	170,002
Provisions,	1,087,186
Railway Plant and Rolling Stock, ¹	1,116,434
Salt, tons	338,065	...	515,184
Silk (raw) and Thread, . . lbs.	2,386,150	£1,074,156	
Silk Manufactures, . . . yards	9,671,261	977,768	
Total Silk,	2,051,924
Spices, lbs.	510,854
Sugar, cwts.	672,672	...	1,086,961
Tea, lbs.	2,751,085	...	193,052
Tobacco,	83,608
Umbrellas,	232,829
Wood, and Manufactures of,	99,384
Wool (raw), lbs.	2,781,257	£68,931	
Wool, Manufactures of, . . yards	6,932,779	984,873	
Total Wool & Woollen Goods,	1,053,804
All Other Articles,	2,946,119
Total Merchandise,	£50,003,041
Treasure,	13,453,157
Total Merchandise and Treasure, }	£63,456,198
Government Imports,	2,092,670
GRAND TOTAL OF IMPORTS,	£65,548,868

¹ Exclusive of material for East Indian and other State railways.

FOREIGN SEA BORN TRADE OF BRITISH INDIA FOR 1882-83

EXPORTS		
Articles	Quantity	Value
Coffee cwts	364 008	£1 419 131
Coin and Manufactures of } (excluding Cordage) }	173 209	152 129
Cotton (raw)	6 170 173	£16 035 738
Cotton Twist and Yarn		1 874 464
Cotton Manufactures		2 093 146
Total Cotton & Cotton Goods		20 023 368
Drugs and Medicines		154 463
Indigo cwts	141 041	£3 912 997
Other Dyes (except Lac)		258 436
Total Dyes (except Lac)		4 171 433
Rice (including Paddy) cwts	31 238 288	£8 476 327
Wheat	14 193 763	6 088 814
Other Grains	1 165 826	319 571
Total Grain	46 617,877	14 884 712
Gums and Resins	282 416	356 931
Hemp and Manufactures of		44 236
Hides and Skins No	26 539 988	4 444 946
Horns		181 785
Ivory and Manufactures of		112 469
Jewellery and Precious Stones		63 177
Jute (raw) cwts	10 348 909	£5 846 976
Jute Manufactures of { bags	66 737 631	1 487 831
yards	4 601 247	
Total Jute and Jute Goods		7 334 757
Lac (dye shell etc) cwts	138 844	699 113
Oils		443 764
Opium chests	91 798	11 481 379
Saltpetre cwts	399 562	388 766
Seed	13 147 082	7 205 924
Silk (raw) lbs	663 488	£596 838
Silk Manufactures of		306 928
Total Silk and Silk Goods		903 766
Spices lbs	20 947 105	417 91
Sugar cwts	1 428 360	989 009
Tea lbs	58 233 345	3 738 842
Tobacco		117 156
Wood and Manufactures of		50 370
Wool (raw) lbs	26 380 327	£1 002 833
Wool Manufactures of		183 348
Total Wool & Woollen Goods		1 186 181
All Other Articles		2 427 607
Total Merchandise ¹		£83 400 863
Treasure		580 839
Total Merchandise and } Treasure }		£84,381 724
Government Exports		145 458
GRAND TOTAL OF } EXPORTS }		£84 527 182

1 & 12. { Indian Produce or Manufacture £80 598 155
 { Foreign Merchandise 2 802 710

£83 400 865

Sentence continued from page 565.]

Cotton
introduced
1676.

in England in 1676. To foster the nascent industry, a succession of statutes were passed prohibiting the wear of imported cottons; nor was it until after the inventions of Arkwright and others, and the application of steam as a motive power, had secured to Manchester the advantage of cheap production, that these protective measures were entirely removed. In the present century, Lancashire rapidly improved on her instructors. During the five years 1840-45, the annual import of cotton manufactures into India averaged a little over £3,000,000 sterling. In each subsequent quinquennial period, there has been a steady increase, until in 1877-78 the import reached the total of £20,000,000 sterling, and in 1882-83 nearly £21,500,000, or an increase of more than seven-fold in forty-four years.

Cotton-
goods
imports,
1840-83.

Imports of
treasure.

The importation of treasure is perhaps still more extraordinary, when we bear in mind that it is not consumed in the using, but remains permanently in the country. During the same period of forty-four years, the net import of treasure, deducting export, has reached the enormous aggregate of $358\frac{3}{4}$ millions sterling, or a fraction under £1, 8s. per head of the 256 million inhabitants of British and Feudatory India. By far the larger portion of this was silver; but the figures for gold, so far as they can be ascertained, are by no means inconsiderable.

Proportion
of gold to
silver.

During the ten years ending 1875, when the normal value of silver as expressed in gold was but little disturbed, the total net imports of treasure into India amounted to just 99 millions. Of this total, $62\frac{1}{2}$ millions were in silver, and $36\frac{1}{2}$ millions in gold, the latter metal forming more than one-third of the whole. On separating the re-exports from the imports, the attraction of gold to India appears yet more marked. Of the total imports of gold, only 7 per cent. was re-exported, while for silver the corresponding portion was 19 per cent. Roughly speaking, it may be concluded that India then absorbed annually about 5 millions of silver, and 3 millions sterling of gold; say a total hoard of 7 to 8 millions sterling of the precious metals each year during the decade ending 1875.

Gold and
silver cir-
culation.

The depreciation of silver which has since taken place has caused an increase in the import of silver, and a corresponding decrease in the export of gold. The figures since 1876 do not show the normal state of things. But even in 1877-78, when the value of silver in terms of gold touched a low point, although India drew upon its hoards of gold for export to the amount of more than 1 million sterling, she at the

same time imported $1\frac{1}{2}$ million, showing a net import of half a million of gold. It has been estimated that the gold circulation of India amounts to 1,620,000 of gold *mohars* (Rs 16 to Rs 20 each), worth about three millions sterling, as compared with £158,000,000 of silver and £2,960,000 of copper. In addition, 10 million sovereigns are said to be hoarded in India, mainly in the Bombay Presidency, where the stamp of St. George and the Dragon is valued as a religious symbol. As already stated, the net accumulation of silver and gold in India, after allowing for re-exports, averaged 7 millions sterling during the five years ending 1879, and rose to an average of 11 millions sterling during the next quinquennial period ending 31st March 1884.

Turning to the exports, the changes in relative magnitude demand detailed notice. In 1877-78, raw cotton for the first time for many years fell into the second place, being surpassed by the aggregate total of food grains. In 1882-83, raw cotton had again advanced into the first place among the exports, exceeding the value of food grains by upwards of a million sterling. Oil seeds show as a formidable competitor to cotton, jute nearly doubles indigo, hides and tea come close behind, while exports of cotton manufactures exceed coffee in value by upwards of half a million. The imports of sugar, in value although not in quantity, exceed the exports, the trade in raw silk is about equally balanced, while spices, once the glory of Eastern trade, were exported in 1877-78, to the value of only £226,515, as compared with imports of spices of twice that value (£488,884). In 1882-83, spices were exported to nearly the same value as the imports, namely, exports £417,391, and imports £510,854.

The export of raw cotton has been subject to excessive variations. At the close of the last century, cotton was sent to England in small quantities, chiefly the produce of the Central Provinces, collected at Mirzāpur and shipped at Calcutta, or the produce of Gujarat (Guzerāt) despatched from Surat. In 1805, the cotton from Surat was valued at £108,000. In the same year, only 2000 bales of East Indian cotton were imported into Great Britain. But this figure fails to show the average, for by 1810, the corresponding number of bales had risen to 79,000, to sink again to 2000 in 1813 and to rise to 248,000 in 1818. Bombay did not begin to participate in this trade until 1825, but has now acquired the practical monopoly, since the railway diverted to the west the produce of

Analysis
of Indian
exports

Export of
raw cotton

Its history
1805-34

the Central Provinces. In 1834, when the commerce of India was thrown open, 33,000,000 lbs. of cotton were exported.

Export of raw cotton since 1840; and since 1865.

Analysing the exports of cotton during the forty-five years since 1840, we find that in the first quinquennial period they averaged $2\frac{1}{3}$ millions sterling in value, and did not rise perceptibly until 1858, when they first touched 4 millions. From that date increase was steady, even before the American exports were cut off by the war in 1861. During the American war, India made the most of her opportunity, although quality did not keep pace with the enhanced price. The export of raw cotton reached its highest value at $37\frac{1}{2}$ millions sterling in 1865, and its highest quantity at 803,000,000 lbs. in 1866.

Thenceforth the decline has been constant, although somewhat irregular, the lowest figures both of quantity and value being those of 1878-79, when the exports amounted to 2,966,569 cwts., valued at £7,914,091. The principal feature of the trade in 1877-78 was the comparatively small amount shipped to the United Kingdom, and the even distribution of the rest among continental ports. Indian cotton has a short staple, which is ill-suited for the finer counts of yarn spun in the Lancashire mills. In 1877-78, out of a total of nearly $3\frac{1}{2}$ million cwts., less than $1\frac{1}{2}$ million cwts. was consigned to England; of the remainder, France took 611,000 cwts.; Italy, 434,000; Austria, 407,000; China, 209,000; and Germany, 109,000. The export of raw cotton in 1878-79 amounted in value to £7,914,091, and of twist and cotton goods, to £2,581,823. In 1882-83, out of a total export of over 6 million cwts. of raw cotton, 2,865,065 cwts. were shipped to the United Kingdom, 937,934 cwts. to Italy, 764,550 cwts. to Austria, 585,766 cwts. to France, 333,708 cwts. to Belgium, 114,412 cwts. to Germany, and 364,519 cwts. to Hong-Kong. In 1882-83, raw cotton was exported to the value of £16,055,758; cotton twist and yarn, £1,874,464; and cotton manufactures, £2,093,146. Total cotton exports, £20,023,368.

Export of jute;

Second in importance to cotton as a raw material for British manufacture comes jute. At the time of the London Exhibition of 1851, jute fibre was almost unknown, while attention was even then actively drawn to reha or China grass, which remains to the present day unmanageable by any cheap process. From time immemorial, jute has been grown in the swamps of Eastern Bengal, and has been woven into coarse fabrics for bags and even clothing. As early as 1795, Dr. Roxburgh called attention to the commercial value of the plant, which he

grew in the Botanical Gardens of Calcutta, and named 'jute,' after the language of his Orissa gardeners, the Bengali word being *pat* or *koshta*. In 1828-29, the total exports of jute in 1828 were only 364 cwts, valued at £62. From that date the trade steadily grew, until in the quinquennial period ending 1847-48 in 1848 the exports averaged 234,055 cwts. The Crimean war, which cut off the supplies of Russian flax and hemp from the Forfar shire weavers, made the reputation of jute. Dundee forthwith adopted the new fibre as her speciality, and the Bengal cultivators as readily set themselves to meet the demand.

Taking quinquennial periods, the export of raw jute rose from an average of 969,724 cwts. in 1858-63 to 2,628,100 cwts in 1863-68, and 4,858,162 cwts in 1868-73. The highest figures reached prior to 1882 were in the year 1872-73, with 7,080,912 cwts, valued at £4,330,759. A falling off subsequently took place, partly owing to the competition of the weaving mills in the neighbourhood of Calcutta, but the trade continued on a permanent basis. By far the greater bulk of the exports is consigned to the United Kingdom, and a large proportion direct to Dundee. In 1877-78, out of a total of 5,450,276 cwts, 4,493,483 cwts were sent to the United Kingdom, 845,810 cwts to the United States, 110,983 cwts to 'other countries,' chiefly France, which has prosperous weaving mills at Dunquerque. Later history
1858-78

In 1882-83, the exports of raw jute had increased to and 10,348,909 cwts valued at £5,846,926, being considerably higher both in quantity and value than the figures for any previous year. Of this quantity 7,834,136 cwts valued at £4,709,299 were exported to the United Kingdom, 2,002,731 cwts valued at £814,847 to the United States, 184,508 cwts valued at £116,042 to Germany, 147,644 cwts valued at £89,454 to Austria. Jute manufactures to the number of 60,737,654 gunny bags, valued at £1,431,581, were exported in 1882-83, Australia taking nearly one third of the total number of bags, and upwards of one half of the total value. Including 4,601,247 yards of gunny cloth, and 1346 cwts of rope and twine, the total export trade of raw and manufactured jute amounted in 1882-83 to £7,334,757 in value.

The export of raw jute is almost monopolized by Calcutta, although Chittagong, which is nearer the producing Districts, is beginning to take a share in the business.

The export of grain, as already noticed, reached in 1878 a higher total than that of cotton, although cotton again has taken the first place in exports. The two staple cereals are Export of 100 l
grams.

cent, were exported from British Burma, 7,855,151 cwt, or 25 1 per cent, from Bengal, 1,448,540 cwt from Madras, 552,537 cwt from Bombay, and 71,473 cwt from Sind

An export duty is levied on rice in India at the rate of *3 annis* per *maund*, or about 6d per cwt. A similar duty on wheat was repealed in 1873, and that trade has since rice

In 1874-75, the export of wheat was about 1 million cwt. Export of wheat

Forthwith it increased year by year, until in 1877-78 it exceeded 6½ million cwt, valued at nearly 3 millions sterling

In 1878-79, the quantity fell to 1 million cwt, valued at £520,138, owing to the general failure of the harvest in the producing Districts But as railways open up the country, and the cultivators find a steady market in England, India

America and Russia in the wheat trade of the world The Punjab is a great and rapidly developing wheat growing tract in India, but up till recently the supplies have chiefly come from the North Western Provinces and Oudh, being collected at Cawnpur, and thence despatched by rail to Calcutta As

indicated below, Bombay has now taken the place of Calcutta in the exportation of wheat the opening of the Rajputana Malwa Railway having put Bombay in direct communication with the Punjab wheat tract In 1877-78, out of the Wheat total of 6,340,150 cwt, Bengal exported 4,546,062 cwt, trade in Bombay 1 159 443, and Sind 607 470 The chief countries of destination were—the United Kingdom 5,731,349 cwt, the Mauritius, 154 888, and France 116 674

Since 1877-78 the wheat export trade has rapidly extended, and in the year 1882-83 it stood at 14,193 763 cwt, valued in 1882 83 at £6 088,934 Nearly one half of the total exports, or 6 575,160 cwt went to the United Kingdom, 3 567 712 cwt to France, 1,458,898 cwt to Belgium, 799,550 cwt to Egypt, 578,246 cwt to Holland, 176 063 cwt to Italy, 494,095 cwt to Gibraltar, and 163 358 cwt to Malta. Of the total wheat, Bombay exported 6,957,752 cwt, or 49 2 per cent, Calcutta, 4 439,405 cwt, or 31 4 per cent, and Karachi, 2,732,275 cwt, or 19 3 per cent, the small balance being sent from Madras and Rangoon

It is said that Italy is beginning to utilize the hard, white Indian wheat for the manufacture of macaroni

Oil seeds were freed in 1875 from their former export duty Exports of oil seeds in of 3 per cent *ad valorem* During the ten previous years, the average annual export was only about 4 million cwt, but 1877-78

- Oil-seeds in 1877-78. the fiscal change, coinciding with an augmented demand in Europe, has since trebled the Indian export. In 1877-78, the export of oil-seeds amounted to 12,187,020 cwts., valued at 7 $\frac{1}{3}$ millions sterling. Of this, Bengal contributed 7,799,220 cwts., and Bombay 3,179,475 cwts. Linseed and rape are consigned mainly to the United Kingdom, while France takes almost the entire quantity of *til* or gingelly. In 1879, the export of oil-seeds fell to 7 $\frac{1}{4}$ million cwts., valued at
- in 1882-83. £4,682,512. In 1882-83, exports of oil-seeds had again increased to 13,147,982 cwts., valued at £7,205,924, of which 5,898,383 cwts., valued at £3,397,840, went from Bombay, and 5,592,896 cwts., valued at £2,817,140, from Bengal. The principal countries of destination were—the United Kingdom, 6,409,134 cwts.; France, 3,923,964 cwts.; Belgium, 1,001,164 cwts.; Egypt, 631,388 cwts.; Italy, 445,773 cwts.; United States, 321,688 cwts.; and Holland, 254,014. Besides oil-seeds, British India exported in 1882-83, 3,644,632 gallons of expressed oil, and 201,116 cwts. of oil-cake, of the total value of £445,529.
- Exports of indigo in 1877-78; In actual amount, although not in relative importance, indigo holds its own, notwithstanding the competition of aniline dyes. The export of 1877-78 amounted to 120,605 cwts., valued at £3,494,334. Of this total, Bengal sent 99,402 cwts., and Madras 16,899 cwts. In 1878-79, the export of indigo amounted to 105,051 cwts., valued at £2,960,463. In
- 1882-83; 1882-83, the exports of indigo amounted to 141,041 cwts., of the value of £3,912,997, of which 99,715 cwts., valued at £3,023,540, were sent from Bengal; and 33,474 cwts., valued at £763,096, from Madras. The most noticeable feature in this trade is the diminishing proportion sent direct to England, and the wide distribution of the remainder. In 1882-83, only
- its destination, 1882-83. 60,645 cwts. were consigned direct to the United Kingdom; 27,285 cwts., or about one-fifth, to the United States; 16,076 cwts. to Egypt, thence probably re-shipped to Europe; 15,513 cwts. to France; 8394 cwts. to Austria; 6077 cwts. to Persia; 4033 cwts. to Turkey; and 1607 cwts. to Italy.
- Safflower. Of other dyes, the export of safflower has fallen off, being only in demand in the United Kingdom, and as a rouge in China and Japan; the export in 1877-78 was 3698 cwts., valued at £14,881. In 1882-83, the exports of safflower
- Myrobalams. amounted to 3008 cwts., value £9203. The export of myrobalams, on the other hand, was greatly stimulated by the Russo-Turkish War, which interrupted the supply of valonica and galls from Asia Minor. The quantity rose from 286,350 cwts.

in 1875-76 to 537,055 cwts in 1877-78, valued in the latter year at £230,526 In 1882-83, the exports of myrobolams were 471,167 cwts, value £184,697 Practically the whole is sent to the United Kingdom Turmeric exports amounted to 146,865 cwts in 1877-78, valued at £123,766, of which the United Kingdom took about one half In 1882-83, the exports of turmeric had dropped to 63 570 cwts, valued at £37,207 Lac-dye, like other kinds of lac, shows a depressed trade, the Lac exports in 1877-78 having been 9570 cwts, valued at £29,009 In 1882-83, the exports of lac dye had fallen to 3927 cwts, valued at £4610, the whole of which was sent to the United Kingdom and the United States

No Indian export has made such steady progress as tea, Exports of which has multiplied more than seven fold in the space of tea fifteen years In 1867-68, the amount was only 7,811,429 lbs, by 1872-73, it had reached 17,920,439 lbs, in 1878-79, without a single step of retrogression, it had further risen to 34,800,027 lbs, valued at £3,170 118 and in 1882-83, to a total of 58,233,345 lbs, of the value of £3 738,842 Until recently, Indian tea was practically confined to the United Kingdom, but markets have recently been opened out in Australia and the United States The exports to the United Kingdom in 1882-83 amounted to 54,108,114 lbs, to Australia 2,772,461 lbs, and to the United States 676,507 lbs Indian tea has now a recognised position in the London Indian and market, generally averaging about 4d per lb higher in China tea value than Chinese tea, but it has failed to win acceptance in most other countries, excepting Australia Its growing importance as compared with Chinese tea appears from the following figures In 1872 the imports of Indian tea into England were to those of Chinese tea as 1 to 97, in 1874, as 1 to 75, in 1876, as 1 to 56, and in 1878, as 1 to 47 The exports of coffee from India are stationary, if not declining The highest amount during the past fifteen years was 507,296 cwts. in 1871-72, the lowest amount 298,587 cwts in 1877-78, valued at £1,338,499 In 1878-79, the export of coffee was 342,268 cwts, valued at £1,548,481 The export of coffee had slightly increased by 1882-83 to 364,008 cwts, t showed a decrease in value to £1,419,131

Among manufactured goods, cotton and jute deserve notice, Export of cotton is consumed locally The value of Indian cotton manufactures, goods exported in 1877-78 was £1,142,732, in 1879-80, in 1877 78, £44,125, and in 1882-83, £2,093,146. The exports of

Export of cotton manufactures, in 1882-83. twist and yarn, spun in the Bombay mills, increased from 3 million lbs. in 1874-75 to $15\frac{1}{2}$ million lbs. in 1877-78, valued at £682,058. The chief places of destination were — China, 13,762,133 lbs.; Aden, 1,181,120 lbs.; and Arabia, 393,371 lbs. The export of twist and yarn in 1878-79 was valued at £937,698. By 1882-83, the exports of twist and yarn, nearly all from Bombay, had increased to 44,859,175 lbs., value £1,874,464, chiefly to China, Japan, Java, and Aden. Indian-made piece-goods belong to two classes. Coloured goods, woven in hand-looms, are annually exported from Madras to Ceylon and the Straits, to the value of about £230,000, the quantity being about 8 million yards; while in 1877-78, grey goods from the Bombay mills were sent to Aden, Arabia, Zanzibar, and the Mekran coast, amounting to over 10 million yards, and valued at £141,509. By 1882-83, the export of grey goods from Bombay had increased to 41,799,370 yards; value £466,260.

Exports of jute manufactures. Jute manufactures consist of gunny-bags, gunny cloth, and rope and twine, almost entirely the produce of the Calcutta mills. In these, the value of the exports tends to increase faster than the quantity, having multiplied nearly four-fold in the five years ending 1882-83. In 1877-78, the total export of jute manufactures was valued at £771,127, and in 1879-80 at

Gunny-bags, in 1877-78; £1,098,434. Gunny-bags, for the packing of wheat, rice, and wool, were exported in that year to the number of more than $26\frac{1}{2}$ millions, valued at £729,669. Of this total, £298,000 (including by far the most valuable bags) was sent to Australia, £162,000 to the Straits, £80,000 to the United States, £77,000 to Egypt, £32,000 to China, and £81,000 to other countries, which comprises a considerable quantity destined for England. In 1878-79, the export of gunny-bags had increased to $45\frac{1}{3}$ millions. Of gunny cloth in pieces, nearly 3 million yards were exported, almost entirely to the United States; in 1878-79, these exports had increased to upwards of $4\frac{1}{2}$ million yards. Of rope and twine, 4428 cwts. were exported in 1877-78, valued at £5443.

Gunny-bags, in 1882-83. By 1882-83, the number of gunny-bags exported had increased to 66,737,654, of a value of £1,431,584, the principal countries to which they were sent being Australia, China, the Straits Settlements, and the United States. Gunny cloth to the extent of 4,601,247 yards was also exported in the same year to the value of £55,802; as were also rope and twine, 1346 cwts., valued at £1872. The total export of Indian jute manufactures in 1882-83 was valued at £1,487,831, or double the figure (£771,127) for 1877-78.

The following statistics, being taken from Indian returns, do not in all cases show the real origin of the imports or the ultimate destination of the exports, but primarily the countries with which India has direct dealings. London still retains its pre-eminence as the first Oriental mart in the world, whither buyers come from the other countries of Europe to satisfy their wants. To London Germans come for wool, Frenchmen for jute, and all nations for rare dyes, spices, and drugs.

The opening of the Suez Canal restored to the maritime cities of the Mediterranean a share of the Eastern business which they once monopolized. But on the other hand the advantage of being able to obtain a return freight will tend to the certainty of being able to obtain a return freight. As the result of these conflicting influences the trade of India with the United Kingdom while in actual amount it remains pretty constant shows a relative decrease as compared with the total trade.

Taking merchandise only the average value of English exports and imports during the two years 1867-69 amounted to slightly more than 58 millions sterling out of a total of nearly 86 millions being 66 per cent. Ten years later the India's average value of English trade for 1877-79 was still 58 trade with England millions but the total value had risen to 100 millions and the proportion had therefore fallen to 56½ per cent. In 1882-83, the total value of the English private imports and exports of merchandise had risen to 75½ millions but the proportion to the total trade of a little less than 133½ millions (excluding Government stores and private and Government treasure) had fallen to 56·7 per cent. Next to the United Kingdom comes China, with an Indian trade of about 15½ millions (imports and exports), or 11½ per cent. Of this nearly 11½ millions represent opium, the only other articles which China takes from India with being raw cotton cotton twist and gunny bags. In return, China sends silver copper raw silk and silk goods sugar and tea the balance of trade being adjusted through England. It is said that Chinese tea is now only consumed in India by natives, or sent across the frontier into Central Asia. The annual quantity imported into India is about 2½ million lbs, and the price is extremely low.

The trade with the Straits may be regarded as a branch India's of the Chinese trade. The exports are valued at over 3½ trade millions sterling, of which more than a half consists of opium, Straits, the rest being principally made up by rice and gunny bags. The imports are tin, areca nuts, pepper, and raw silk.

valued altogether at less than one-half of the exports. The trade with Ceylon is merely a form of coasting trade, large quantities of rice being shipped in native craft along the Madras coast to feed the Tamil coolies in that island. The imports are hardly a sixth of the exports in value. With Mauritius, rice is exchanged for sugar to a large amount.

Of European countries, France and Italy alone deserve notice beside England. In 1877-78, the Indian exports to France reached the large total of nearly 6 millions sterling, consisting chiefly of oil-seeds (rape and gingelly), indigo, cotton, silk, and coffee. The direct imports in the same year were valued at only £451,000, principally apparel and millinery, brandy and wines, and silk goods; but the same articles are also sent in considerable, although unascertained, quantities *via* England. In 1882-83, the exports to France amounted to £7,207,962, and the direct imports to £484,367. The trade with Italy shows a steady increase; the Indian exports to Italy having risen from £1,100,000 in 1877-78 to £3,383,507 in 1882-83, and the return imports from £250,000 to £444,433. The exports are cotton, silk, oil-seeds (sesamum), and hides; the imports—corals, glass beads and false pearls, spirits and wines, and silk goods.

The trade with the United States comes next to that with Italy, aggregating a total for exports and imports of £4,277,560. The exports are indigo, hides, raw jute and gunny-bags, lac, saltpetre, and linseed; the imports are almost confined to mineral oils. In 1878-79, the import of ice (formerly an important item in the trade with the United States) fell off greatly, under competition from local manufacture at Calcutta and Bombay, and it has now entirely ceased; while the imports to India of American kerosene oil rose to 3 million gallons in 1878-79, and to the enormous quantity of 20 million gallons in 1882-83.

The trade of India with Australia was formerly limited to the export of rice, gunny-bags, and castor-oil, and the import of copper and horses. A little coal is sent from Australia, and a little coffee from India. Hitherto Australia has preferred to drink Chinese tea; but a considerable development of trade in this and other Indian products has taken place since the Melbourne and other Colonial Exhibitions. The total exports to Australia in 1882-83 aggregated £1,088,918; return imports, £476,591.

The following tables summarize the private foreign trade of India in 1877-78 and 1882-83:—

The opening of the Suez Canal in 1869, while it has stimulated every department of trade into greater activity, has not materially changed its character. The use of the Canal implies steam power. In 1871-72, the first year for which statistics are available the total number of steamers trading with India which passed through the Canal was 422, with a tonnage of 464 198. Every subsequent year shows an increase until the great fall in trade in 1878-79. In 1877-78, the number of steamers passing through the Canal was 1137, with a burthen of 1 617,839 tons or 64 per cent of the total steam tonnage. Although there was a considerable falling off in the two following years, the Canal trade speedily recovered itself, and in 1880-81 1459 steamers of 2 133 872 tons passed the Canal. The highest figures hitherto reached were in 1881-82, when 1989 steamers of 2 887 988 tons passed the Canal. In the following year 1882-83 the number of Canal steamers was 1645 of 2 585 900 tons.

As might be anticipated the imports to India being for the most part of small bulk and high value first felt the advantages of this route. In 1875-76 85 per cent of the imports from Europe and Egypt (excluding treasure) passed through the Canal but only 29 per cent of the exports. The export trade however has rapidly increased showing that such bulky commodities as cotton grain oil seeds, and jute now largely participate in the advantages of rapid transport afforded by the Canal. In 1877-78 the import trade at the Canal amounted to 74 per cent of the total imports into British India, and the Canal exports to 36 per cent of the total exports. In 1882-83 while the import trade via the Canal remained stationary at 74 per cent, the proportion of both exports had increased to 52 per cent. The proportion of both import and export trade passing through the Suez Canal has increased from 45 per cent in 1877-78 to 61 per cent in 1882-83. The Canal has reduced the length of the voyage from London to Calcutta by about thirty six days. The route round the Cape was more than 11 000 miles, and occupied nearly three months, that through the Canal is less than 8000 miles, and takes from 30 to 45 days.

Sir R. Temple, when Finance Minister in 1872, drew up a valuable State Paper, in which he placed in a clear light the various means by which the apparent excess of exports over imports is liquidated. His conclusions were based on special materials reaching from 1835 to 1871. They are therefore

summarized here without attempting to extend them to the period which has since elapsed. The balance of trade during recent years has already been dealt with at pp. 558-9.

Indian
commerce
for thirty-
six years.

During the thirty-six years between 1835 and 1871, the value of merchandise exported from India amounted to £1,012,000,000, say one thousand millions sterling; the value of merchandise imported into India amounted to £583,000,000, showing an excess of £429,000,000 in the exports. The value of treasure imported in the same period was £312,000,000, against £37,000,000 exported, being a net import of £275,000,000. Deducting this from the excess of

The
balance ;
how
accounted
for.

merchandise exports, a balance of £154,000,000 has to be accounted for otherwise than in the ordinary operations of trade. The first item to be considered is freight. Next come all payments made in England, whether by the Indian Government or by private persons resident in India. During the thirty-six years taken, the aggregate amount of payments in England on Government account (now represented by the Secretary of State's bills) amounted to £113,000,000. These bills are drawn to meet charges due in England under such heads as civil and military pensions, interest on debt and on railway capital, military stores, etc.; and they are bought by bankers or merchants, who require to meet their own payments in India. They operate, financially, as if treasure had been sent to India, and thus reduce the apparent balance of trade at one stroke from £154,000,000 to £41,000,000.

Govern-
ment re-
mittances.

Private re-
mittances.

The remaining item to be considered is the remittances to England on private account, which it is impossible to ascertain with any pretension to accuracy. In 1872, this item was estimated at £3,500,000 a year; but in former years it had been much less, and it is now probably much more. It includes such divers matters as the savings of officials, profits of trade and planting, interest on capital invested, etc. Together with freightage, it would make up the balance of £41,000,000 yet unaccounted for, and thus finally equalize and account for the balance of India's foreign trade.

Balance
from
Chinese
trade.

The phenomena of the trade between India and China are to be explained on the same principles. In 1872-73, the total exports from India to China were valued at £12,074,347, to which opium alone contributed £10,529,673. The total imports from China were valued at only £1,355,171, showing an excess of £10,719,176 in exports, for which India receives no direct return from China. In this case, China pays her debt to India by the excess of her exports to England, which

are there placed to the credit of India. During the twenty years between 1852 and 1871, the aggregate balance of trade in favour of China in her dealings with England amounted to £112,000,000. This amount was available to settle China's equally unfavourable balance with India, and was in fact paid by China for Indian opium, as certainly as if the opium had been sent to China *via* England. It is evident, therefore, that if the Chinese were to greatly increase their imports of English goods, the exchanges of India might be seriously affected.

The foreign trade of India is practically monopolized by Coasting trade five ports, namely, Calcutta, Bombay, Madras, Rangoon, and Karáchi, but the entire seaboard along both sides of the peninsula is thronged by native craft which do a large coasting business. In the Gulfs of Kachchh (Cutch) and Cambay, on the Malabar coast, and in the southern Districts facing Ceylon, a large portion of the inhabitants are born sailors, conspicuous alike for their daring and for their skill in navigation. In 1873-74, which may be regarded as a normal year, the total number of vessels engaged in the coasting trade which cleared and entered was 294,374, with an aggregate of 10,379,862 tons, the total value of both coasting exports and imports was £34,890,445. Of the total number of vessels 280,913, with Statistics of coast trade and shipping, 1874. 4,843,668 tons, were native craft. Bombay and Madras divided between them nearly all the native craft, while in Bengal and Burma, a large and increasing proportion of the coasting traffic is carried in British steamers.

In 1877-78, the year of famine, the number of ships in in 1878 creased to 319,624, the tonnage to 15,732,246 tons, and the value to £67,814,446. By far the largest item was grain, of which a total of 1,137,690 tons, valued at 13 millions sterling, was thrown into the famine-stricken Districts from the seaboard. Next in importance came raw cotton and cotton Staples of the coast trade, 1878. goods. The trade in raw cotton in 1877-78 amounted to 387,438 cwts., valued at £957,900, much of which was merely transhipped from one port to another within the Bombay Presidency. Cotton twist and yarn in the same year amounted to 17,425,993 lbs., valued at £965,038, of which the greater part was sent from Bombay to Bengal and Madras. The total value of the exports coastwise of cotton piece goods was £620,866, including about 24 million yards of grey goods sent from Bombay to Bengal and to Sind in nearly equal proportions, and about 2 million yards of coloured goods from Madras. Stimulated by the activity of the grain trade caused by the

summarized here without attempting to extend them to the period which has since elapsed. The balance of trade during recent years has already been dealt with at pp. 558-9.

Indian
commerce
for thirty-
six years.

During the thirty-six years between 1835 and 1871, the value of merchandise exported from India amounted to £1,012,000,000, say one thousand millions sterling; the value of merchandise imported into India amounted to £583,000,000, showing an excess of £429,000,000 in the exports. The value of treasure imported in the same period was £312,000,000, against £37,000,000 exported, being a net import of £275,000,000. Deducting this from the excess of merchandise exports, a balance of £154,000,000 has to be accounted for otherwise than in the ordinary operations of trade. The first item to be considered is freight. Next come all payments made in England, whether by the Indian Government or by private persons resident in India. During the thirty-six years taken, the aggregate amount of payments in England on Government account (now represented by the Secretary of State's bills) amounted to £113,000,000. These bills are drawn to meet charges due in England under such heads as civil and military pensions, interest on debt and on railway capital, military stores, etc.; and they are bought by bankers or merchants, who require to meet their own payments in India. They operate, financially, as if treasure had been sent to India, and thus reduce the apparent balance of trade at one stroke from £154,000,000 to £41,000,000. The remaining item to be considered is the remittances to England on private account, which it is impossible to ascertain with any pretension to accuracy. In 1872, this item was estimated at £3,500,000 a year; but in former years it had been much less, and it is now probably much more. It includes such divers matters as the savings of officials, profits of trade and planting, interest on capital invested, etc. Together with freightage, it would make up the balance of £41,000,000 yet unaccounted for, and thus finally equalize and account for the balance of India's foreign trade.

The
balance;
how
accounted
for.

Govern-
ment re-
mittances.

Private re-
mittances.

Balance
from
Chinese
trade.

The phenomena of the trade between India and China are to be explained on the same principles. In 1872-73, the total exports from India to China were valued at £12,074,347, to which opium alone contributed £10,529,673. The total imports from China were valued at only £1,355,171, showing an excess of £10,719,176 in exports, for which India receives no direct return from China. In this case, China pays her debt to India by the excess of her exports to England, which

are there placed to the credit of India. During the twenty years between 1852 and 1871, the aggregate balance of trade in favour of China in her dealings with England amounted to £112,000,000. This amount was available to settle China's equally unfavourable balance with India, and was in fact paid by China for Indian opium, as certainly as if the opium had been sent to China *via* England. It is evident, therefore, that if the Chinese were to greatly increase their imports of English goods, the exchanges of India might be seriously affected.

The foreign trade of India is practically monopolized by Coasting trade five ports, namely, Calcutta, Bombay, Madras, Rangoon, and Karachi, but the entire seaboard along both sides of the peninsula is thronged by native craft which do a large coasting business. In the Gulfs of Kachchh (Cutch) and Cambay, on the Malabar coast, and in the southern Districts facing Ceylon, a large portion of the inhabitants are born sailors, conspicuous alike for their daring and for their skill in navigation. In 1873-74, which may be regarded as a normal year, the total number of vessels engaged in the coasting trade which cleared and entered was 294,374, with an aggregate of 10,379,862 tons, the total value of both coasting exports and imports was £34,890,445. Of the total number of vessels 280,913, with Statistics of coast trade and shipping, 1874, 4,843,668 tons, were native craft. Bombay and Madras divided between them nearly all the native craft, while in Bengal and Burma, a large and increasing proportion of the coasting traffic is carried in British steamers.

In 1877-78, the year of famine, the number of ships in in 1878 creased to 319,624, the tonnage to 15,732,246 tons, and the value to £67,814,446. By far the largest item was grain, of which a total of 1,137,690 tons, valued at 13 millions sterling, was thrown into the famine-stricken Districts from the seaboard. Next in importance came raw cotton and cotton Staples of the coast trade, 1878 goods. The trade in raw cotton in 1877-78 amounted to 387,438 cwts., valued at £957,900, much of which was merely transhipped from one port to another within the Bombay Presidency. Cotton twist and yarn in the same year amounted to 17,425,993 lbs., valued at £965,038, of which the greater part was sent from Bombay to Bengal and Madras. The total value of the exports coastwise of cotton piece goods was £620,866, including about 24 million yards of grey goods sent from Bombay to Bengal and to Sind in nearly equal proportions, and about 2 million yards of coloured goods from Madras. Stimulated by the activity of the grain trade caused by the

Indian
coasting
trade,
1877-78.

famine, the exports of gunny-bags from Calcutta coastwise, rose to a total value of nearly £960,000. The trade in areca-nuts in 1877-78 amounted to nearly 44 million lbs., valued at over £500,000. Burma consumes most of these, obtaining its supplies from Bengal; while Bombay gets considerable quantities from Madras, from the Konkan and Goa, and from Bengal. Sugar (refined and unrefined) figures to the large amount of £900,000 in 1877-78, of which the greater part came from Bengal. The movements of treasure coastwise showed a total of just 5 millions sterling, being exceptionally augmented by the conveyance of silver to Burma in payment for rice supplied to Madras.

Coasting
trade in
1878-79,
and in
1882-83.

The growth and increasing importance of the coasting trade of India may be illustrated by a comparison of the statistics for 1878-79, the year after the famine, when trade may be said to have returned to its normal condition; with those for 1882-83, the latest year for which full details are available.

In 1878-79.

In 1878-79, a total of 4080 steamers, of 3,614,349 tons, entered the coast ports with cargoes, while 97,767 sailing vessels, of 2,151,673 tons, also entered with cargoes. Total number of vessels with cargoes entered, 101,847, of 5,766,022 tons. The number of vessels which cleared with cargoes in the same year, was 3981 steamers, of 3,412,546 tons, and 84,597 sailing vessels, of 1,940,196 tons. Total number of vessels cleared with cargoes, 88,578, of 5,352,742 tons. Grand total of vessels entered and cleared, 190,425, of 11,118,764 tons. The steam coasting trade is almost entirely monopolized by British or British Indian vessels. Of the 8061 steamers which entered or cleared Indian ports coastwise in 1878-79, only 46 were foreign, while not a single one was native; average tonnage of each steamer, 871 tons. Of the 182,364 sailing vessels, 177,567 were small native craft, of an average of only a little over 18 tons each; 2792 were foreign vessels, of an average burthen of 62 tons; while 2005 were British or British Indian sailing ships, of an average of 342 tons. The total value of the private coasting trade in 1878-79 was—Imports, merchandise, £21,978,011, and treasure, £3,777,852; total, £25,755,863. Exports, merchandise, £23,172,328, and treasure, £2,442,657; total, £25,614,985. Total of private imports and exports, merchandise, £45,150,339, and treasure, £6,220,509; grand total, £51,370,848. Government imports in 1878-79 comprised—stores, £436,407, and treasure, £2,644,480; total, £3,080,887. The exports comprised—

stores, £316,206, and treasure, £1,891,763, total, £2,207,969 Co
Grand total Government imports and exports, £5,288,556 tra

The figures of the coasting trade for 1882-83 show that In
4780 steamers with cargoes, of 5,040,898 tons, entered Indian
103,203 sailing vessels, of 2,070,626 tons, entered Indian
coast ports, while 4735 steamers, of 4,925,967 tons,
and 93,383 sailing vessels, of 1,931,639 tons, cleared during
the year. Total vessels entered and cleared with cargoes,
9515 steamers, of 9,966,865 tons, 196587 sailing vessels,
of 4,002,265 tons, total vessels of all classes, entered
and cleared, 206,101 tonnage, 13,969,130 Of the 9515
coasting steamers which entered or cleared Indian ports in
1882-83, 9439 were British or British Indian, and 76 foreign,
with a total of 9,966,865 tons, or an average of 1047
tons each Sailing vessels included—265 British, with an
average of 692 tons, British Indian, 3060, average 1186
tons, foreign, 2990, average 414 tons, and native craft,
190,271, average 175 tons The total value of the private
coasting trade in 1882-83 was—Imports, merchandise,
£25,419,831, and treasure £4,066,557, total, £29,486,388
Exports, merchandise, £24,524,241, and treasure, £3,316,125,
total, £27,840,366 Total value of private imports and exports,
merchandise, £49,944,072, and treasure, £7,382,682, grand
total, £57,326,754 This total, however, includes £5,217,328
of re-imports, and £6,035,678 of re-exports, grand total,
£11,253,006 representing re-exports and re-imports of the
foreign trade given in the previous section of this chapter
The Government imports in 1882-83 comprised—stores,
£459,985, and treasure, £1,882,411 total, £2,342,396
The exports comprised—stores, £338,026, and treasure,
£2,497,265, total, £2,835,291 Grand total of Government
imports and exports, by coasting vessels, £5,197,687
Comparing the figures for the two years, it will be seen that Com-
the number of vessels engaged in carrying cargoes coastwise Parison
increased by 15,676, and the tonnage by 2,850,366 tons, between of the two
1878-79 and 1882-83 The increase was principally in the years
steam traffic. Of the private trade, imports of merchandise in
the same period increased by £3,441,820, and of treasure by
£288,705, total, £3,730,525 Exports of merchandise
increased by £1,351,913, and of treasure by £873,468, total,
£2,225,381. Including both imports and exports, the value
of the merchandise carried coastwise showed an increase of
£4,793,733, and of treasure by £1,162,173, grand total
increase of private merchandise and treasure, £5,955,906.

Indian
coasting
trade,
1877-78.

famine, the exports of gunny-bags from Calcutta coastwise, rose to a total value of nearly £960,000. The trade in areca-nuts in 1877-78 amounted to nearly 44 million lbs., valued at over £500,000. Burma consumes most of these, obtaining its supplies from Bengal; while Bombay gets considerable quantities from Madras, from the Konkan and Goa, and from Bengal. Sugar (refined and unrefined) figures to the large amount of £900,000 in 1877-78, of which the greater part came from Bengal. The movements of treasure coastwise showed a total of just 5 millions sterling, being exceptionally augmented by the conveyance of silver to Burma in payment for rice supplied to Madras.

Coasting
trade in
1878-79,
and in
1882-83.

The growth and increasing importance of the coasting trade of India may be illustrated by a comparison of the statistics for 1878-79, the year after the famine, when trade may be said to have returned to its normal condition; with those for 1882-83, the latest year for which full details are available.

In 1878-
79.

In 1878-79, a total of 4080 steamers, of 3,614,349 tons, entered the coast ports with cargoes, while 97,767 sailing vessels, of 2,151,673 tons, also entered with cargoes. Total number of vessels with cargoes entered, 101,847, of 5,766,022 tons. The number of vessels which cleared with cargoes in the same year, was 3981 steamers, of 3,412,546 tons, and 84,597 sailing vessels, of 1,940,196 tons. Total number of vessels cleared with cargoes, 88,578, of 5,352,742 tons. Grand total of vessels entered and cleared, 190,425, of 11,118,764 tons. The steam coasting trade is almost entirely monopolized by British or British Indian vessels. Of the 8061 steamers which entered or cleared Indian ports coastwise in 1878-79, only 46 were foreign, while not a single one was native; average tonnage of each steamer, 871 tons. Of the 182,364 sailing vessels, 177,567 were small native craft, of an average of only a little over 18 tons each; 2792 were foreign vessels, of an average burthen of 62 tons; while 2005 were British or British Indian sailing ships, of an average of 342 tons. The total value of the private coasting trade in 1878-79 was—Imports, merchandise, £21,978,011, and treasure, £3,777,852; total, £25,755,863. Exports, merchandise, £23,172,328, and treasure, £2,442,657; total, £25,614,985. Total of private imports and exports, merchandise, £45,150,339, and treasure, £6,220,509; grand total, £51,370,848. Government imports in 1878-79 comprised—stores, £436,407, and treasure, £2,644,480; total, £3,080,887. The exports comprised—

stores, £316,206, and treasure, £1,891,763, total, £2,207,969
Grand total Government imports and exports, £5,288,556
The figures of the coasting trade for 1882-83 are as follows:
4780 steamers with cargoes of 1,032,203 sailing
103,203 sailing

The figures of the coasting trade for 1882-83 show that 4780 steamers with cargoes, of 5,040,898 tons, and 103,203 sailing vessels, of 2,070,626 tons, entered Indian coast ports, while 4735 steamers, of 4,925,967 tons, and 93,383 sailing vessels, of 1,931,639 tons, cleared during the year. Total vessels entered and cleared with cargoes, 9515 steamers, of 9,966,865 tons, 196587 sailing vessels, of 4,002,265 tons, total vessels of all classes, entered and cleared, 206,101, tonnage, 13,969,130. Of the 9515 coasting steamers which entered or cleared Indian ports in 1882-83, 9439 were British or British Indian, and 76 foreign, with a total of 9,966,865 tons, or an average of 1047 tons each. Sailing vessels included—265 British, with an average of 692 tons, British Indian, 3060, average 1186 tons, foreign, 2990, average 414 tons, and native craft, 190,271, average 175 tons. The total value of the private coasting trade in 1882-83 was—Imports, merchandise, £25,419,831, and treasure, £4066557, total £29486388. Exports, merchandise, £24524241, and treasure, £3316125, total, £27,840,366. Total value of private imports and exports, merchandise, £49,944,072, and treasure, £7,382,682, grand total, £57,326,754. This total, however, includes £5,217,328 of re imports, and £6,035,678 of re exports, grand total, £11,253,006 representing re exports and re imports of the foreign trade given in the previous section of this chapter. The Government imports in 1882-83 comprised—stores, £459,985, and treasure, £1882411, total, £2,342,396. The exports comprised—stores, £338,026, and treasure, £2,497,265, total, £2,835,291. Grand total of Government imports and exports, by coasting vessels, £5,197,687. Comparing the figures for the two years, it will be seen that Commerce the number of vessels engaged in carrying cargoes coastwise increased by 15,676, and the tonnage by 2,850,366 tons, between the two years 1878-79 and 1882-83. The increase was principally in the steam traffic. Of the private trade, imports of merchandise in the same period increased by £3,441,820, and of treasure by £288,705, total, £3,730,525. Exports of merchandise increased by £1,351,913, and of treasure by £873,468, total, £2,225,381. Including both imports and exports, the value of the merchandise carried coastwise showed an increase of £4,793,733, and of treasure by £1,162,173; grand total increase of private merchandise and treasure, £5,955,906.

Adding the value of Government imports and exports, the total coast-borne trade of India increased from £56,659,404 in 1878-79 to £62,524,441 in 1882-83, or by £5,865,037.

Frontier trade.

FRONTIER TRADE.—Attempts have been made to register the trade which crosses the long land frontier of India on the north, stretching from Baluchistán to Independent Burma. The returns obtained for a period of five years ending 1882-83 show an annual trans-frontier landward trade averaging about $9\frac{1}{3}$ millions sterling; the yearly imports averaging about 5 millions, and the exports about $4\frac{1}{3}$ millions sterling. Of this, nearly one-half, or 44 per cent., belongs to Burma, and between one-fourth and one-third, or upwards of 28 per cent., to the Punjab and Sind. Details of this import and export trans-frontier trade for each of the five years will be found in the tables on subsequent pages. The figures, although perhaps not absolutely accurate, may be accepted as substantially correct.

Three main trade routes to Afghánistán.

Three main trade routes pierce the Suláimán Mountains, across the western frontier of the Punjab and Sind. These are—(1) the Bolan Pass, which collects the trade both of Kandahár and Khelát, and debouches upon Sind at the important mart of Shikárpur, whose merchants have direct dealings with the remote cites of Central Asia; (2) the Gomal Pass, leading from Ghazní to Dera Ismáíl Khán, which is followed by the half-military, half-trading clan of Povindahs, who bring their own caravans of camels into the heart of India; (3) the Khaibar Pass, from Kábul to Pesháwar.

Value of Afghán trade.

The aggregate value of the annual trade with Afghánistán, previous to the late war, was estimated at 1 million sterling each way, or a total of 2 millions; but it has since decreased. The figures for 1875-76, which, however, are stated to be incomplete, give the value of the imports from Afghánistán at £914,000, consisting chiefly of raw silk, dried fruits and nuts, *manjit* or madder and other dyes, *charas* (an intoxicating preparation of hemp) and other drugs, wood, and furs; the total exports in 1875-76 were valued at £816,000, chiefly cotton goods both of native and European manufacture, Indian tea, indigo, and salt. In 1882-83, the total imports from Afghánistán and the neighbouring hill tribes into Sind and the Punjab amounted to £526,560, and the exports to £863,445; total, £1,390,005.

Trade with Central Asia.

The Punjab also conducts a considerable business with Kashmír with Ladákh, Yarkand, and Kashgar, estimated at about 1 million sterling altogether. The chief marts on the side of

Indra are Amritsar and Jalandhar, from which latter place the route runs northwards past Kangra and Palampur to Leh, where a British official has been stationed since 1867, in which year also a fair was established at Palampur to attract the Yarkand merchants. Merchandise is usually conveyed across the Himalayan passes on the backs of sheep and yaks, but the British enterprise has successfully taken mules as far as Leh. In 1875-76, the total imports from Kashmir were valued at £484,000, chiefly *pashmina* or shawl wool, *charas*, raw silk, gold dust and silver ingots, and borax, the exports were valued at £342,000 chiefly cotton goods, food grains, metals, salt, tea, and indigo. In 1882-83, the imports from Kashmir into the Punjab amounted to £505,335, and the exports to £349,477, total, £854,812. The whole trans frontier landward trade of the Punjab in 1882-83 was—imports £981,167, and exports, £1,083,920, grand total, £2,065,087.

Farther east, the Independent State of Nepal cuts off direct intercourse with Tibet for a total length of nearly 700 miles, Nepal bordering the North Western Provinces, Oudh, and Behar. Little trade is allowed to filter through Nepál, to and from Tibet (amounting in value in 1882-83 to £82,519 for both imports and exports), yet a very large traffic is everywhere carried on along the frontier between the Nepális and British subjects. The Nepál Government levies transit duties in part on all commodities, but it is asserted that their fiscal tariff is not intended to be protective, and does not in fact operate as such. Markets are held at countless villages along the boundary, for the exchange of rural produce and articles of daily consumption, and many cart tracks cross the line from our side, to lose themselves in the Nepál *taras*. The principal trade route is that which starts from Patná, and proceeds nearly due north through Champáran District to the capital of Khatmandu, but even this is not passable through out for wheeled traffic. From Khatmandu, two routes branch off over the central range of the Himalayas, which both ultimately come down into the valley of the Tsanpu, or great river of Tibet.

In 1877-78, the registered trade with Nepál (which Nepal is doubtless below the truth) amounted to a total of ^{values} £1,687,000, of which more than two thirds was conducted by Bengal. The imports from Nepál were valued at £1,054,000, the principal items being food grains and oil seeds, cattle, timber, and horns. Other articles of import which do not figure prominently in the returns are musk, borax, *chireta*, madder,

- Trade with Nepál ; cardamoms, *chauris* or yak-tails, ginger, *balchar* or scented grass, furs, and hawks. The Indian exports to Nepál in 1877-78 were valued at £633,000, chiefly European and native piece-goods (of cotton, wool, and silk), salt, metals, raw cotton, sugar, and spices. To these may be added the miscellaneous articles which may be usually found in a pedlar's pack. In 1882-83, the total imports from Nepál into the North-Western Provinces, Oudh, and Bengal amounted to £1,378,175, and the exports from British India to £855,346; grand total, £2,233,521. The trade with Sikkim and Bhután is at present too insignificant to require notice, although it is possible that our future entry into Tibet may lie through these States.
- North-east frontier trade ; A certain amount of traffic is conducted with the hill tribes on the north-east frontier, who almost surround the Province of Assam from Bhután to Manipur. According to the returns for 1877-78, the total frontier trade of Assam amounts to about £100,000 a year. In 1882-83 it amounted to £115,206, £83,318 being imports, and £31,888 exports. It consists chiefly of the bartering of rice, cotton cloth, salt, and metals, for the raw cotton grown by the hill tribes, and for the caoutchouc, lac, beeswax, and other jungle produce which they collect.
- Trade with Independent Burma ; The trade with Independent Burma has a special character, and it has for some years past been subject to a fairly accurate system of registration. The main route is by the Irawadi river, which is navigable by large steamers. The trade on the Sittang (Tsit-taung) is chiefly confined to the import of timber. Registration is also attempted at six land stations. The total trade in 1877-78 was valued at £3,426,000, almost equally divided between exports and imports. The principal imports from Independent Burma into British Burma were timber (£213,000), raw cotton (£163,000), sesamum oil (£130,000), manufactured silk (£107,000), jaggery sugar (£98,000), cattle (£88,000) and ponies (£20,000), cotton goods woven from European yarn (£46,000), earth-oil (£65,000), and cutch (£41,000). Many of these articles are liable to be declared royal monopolies (although these monopolies were abolished in 1882), and consequently the figures fluctuate greatly year by year. Other imports of interest, though of smaller value, are pickled tea (£19,000) and jade (£18,000).
- Exports ; The exports from British to Independent Burma in 1877, were 1877-78. rice (£435,000), cotton piece-goods (£207,000) and cotton

twist and yarn (£188,000), manufactured silk (£173,000), Tuga pi or salted fish (£159,000), raw silk (£84,000), woollen goods (£43,000), salt (£33,000), etc. Many of these goods were formerly the subjects of royal monopoly, or they competed with the products of manufactories started by the king at Mandalay. Salt is exempted from the ordinary customs duties at Rangoon, and pays only a transit duty of 1 per cent if declared for Independent Burma.¹

Full details of the import and export trade between British Burma and Independent Burma and the Shan States for 1882-83 are not available. As regards totals, the imports amounted to £2,504,135 in value, and the exports to £1,752,299 total, £4,256,434.

The trade between British Burma and Siam was estimated in 1877-78 at the total value of £126,000, being £69,000 for imports from Siam and £57,000 for exports. In 1882-83, the trade between British Burma and Siam amounted to— imports from Siam £40,349, and exports, £141,958, total, £182,307.

The following tables exhibit the total trans frontier land trade of India (1) with the different border countries and tribes, and (2) the extent to which it is participated in by the neighbouring British Provinces —

TRANS-FRONTIER LANDWARD TRADE OF INDIA WITH EXTERNAL STATES FOR THE FIVE YEARS 1878-79 TO 1882-83

From	Land and Imports into India.				
	1878-79	1879-80	1880-81	1881-82	1882-83
Afghanistan and neighbouring tracts and hill tribes	£ 63,849	£ 611,418	£ 441,536	£ 487,852	£ 520,560
Kashmir	558,537	409,744	709,272	495,949	505,330
Ladakh	17,104	17,013	17,846	37,248	51,284
Tibet	133,969	71,349	63,393	64,206	58,322
Nepal	1,235,238	1,397,487	1,606,929	1,389,548	1,378,175
Sikkim and Bhutan	24,738	61,103	43,395	35,339	33,399
N.E. States beyond the Bengal and Assam Frontier	36,402	47,312	53,027	64,949	81,078
Independent Burma and Shan States	2,072,441	2,222,165	2,126,857	2,110,346	2,504,135
Siam	35,717	80,047	41,320	39,966	40,349
Total Imports,	4,899,995	4,917,638	5,103,580	4,725,403	5,178,607

¹ A. B. — Since these pages went to the press, Independent Burma has been incorporated into the British Empire. The above figures will therefore soon lose their value.

TRANS-FRONTIER LANDWARD TRADE OF INDIA—(continued).

To	Landward Exports from India.				
	1873-79.	1879-80.	1880-81.	1881-82.	1882-83.
Afghanistan and neighbouring tracts and hill tribes,	£ 897,715	£ 1,184,695	£ 1,312,677	£ 1,239,725	£ 863,445
Kashmir,	255,545	282,426	384,934	359,193	349,477
Ladakh,	8,817	15,729	31,177	35,860	32,228
Tibet,	14,861	20,139	18,214	21,973	24,197
Nepal,	805,361	859,358	923,724	869,720	855,346
Sikkim and Bhutan,	17,166	34,576	28,513	21,508	24,973
N.E. State, beyond the Bengal and Assam Frontier,	17,935	15,657	27,676	21,990	27,213
Independent Burma and Shan tribes,	1,868,002	1,813,666	1,818,819	1,613,981	1,752,299
Sum,	86,067	66,386	109,730	150,415	141,958
Total Exports,	3,971,559	4,292,632	4,685,464	4,334,365	4,071,136
GRAND TOTAL IMPORTS AND EXPORTS,	8,871,554	9,210,270	9,789,044	9,059,768	9,249,773

TRANS-FRONTIER LANDWARD TRADE OF INDIA FOR THE BRITISH BORDER PROVINCES FOR THE FIVE YEARS 1878-79 TO 1882-83.

To	Landward Imports into India.				
	1878-79.	1879-80.	1880-81.	1881-82.	1882-83.
Sind,	£ 249,842	£ 251,558	£ 117,475	£ 130,248	£ 119,722
Punjab,	1,218,269	820,591	1,071,329	912,813	981,167
N.W. Provinces and Oudh,	439,154	531,595	615,507	633,664	617,222
Bengal,	844,006	961,140	1,075,853	827,376	832,724
Assam,	40,566	50,542	55,234	70,990	83,318
British Burma,	2,108,158	2,302,212	2,223,977	2,150,312	2,544,484
Total Imports,	4,899,095	4,917,638	5,159,375	4,725,403	5,178,637

From	Landward Exports from India.				
	1878-79.	1879-80.	1880-81.	1881-82.	1882-83.
Sind,	£ 215,235	£ 403,212	£ 326,670	£ 236,910	£ 162,759
Punjab,	949,963	1,080,940	1,403,449	1,398,995	1,083,920
N.W. Provinces and Oudh,	203,343	296,767	339,146	280,526	279,349
Bengal,	628,587	614,146	629,246	629,224	618,963
Assam,	20,272	17,515	28,404	24,314	31,888
British Burma,	1,954,159	1,880,052	1,958,549	1,764,396	1,894,257
Total Exports,	3,971,559	4,292,632	4,685,464	4,334,365	4,071,136
GRAND TOTAL IMPORTS AND EXPORTS,	8,871,554	9,210,270	9,844,839	9,159,768	9,249,773

THE INTERNAL TRADE of India greatly exceeds her foreign commerce, but it is impossible to estimate its amount. On the one hand, there is the wholesale business, connected with the foreign commerce, in all its stages—the collection of the agricultural produce from a hundred thousand villages, its accumulation at a few great central marts, and its despatch to the seaboard. The sea imports and manufactured articles are distributed by the same channels, but in the reverse direction. On the other hand, there is the interchange of commodities of native growth and manufacture, sometimes between neighbouring Districts, but also between distant Provinces. With unimportant exceptions free trade is the rule throughout the vast peninsula of India, by land as well as by sea. The Hindus possess a natural genius for commerce, as is shown by the daring with which they have penetrated into the heart of Central Asia, and to the east coast of Africa. Among the benefits which British rule has conferred upon them, is the removal of the internal duties and other restraints which native despotism had imposed upon trading energies.

Broadly speaking, the greater part of the internal trade remains in the hands of the natives. Europeans control the shipping business and have a share in the collection of some of the more valuable staples of export, such as cotton, jute, oil seeds, and wheat. But the work of distribution, and the adaptation of the supply to the demand of the consumer, naturally fall to those who are best acquainted with native wants. Even in the Presidency towns, most of the retail shops are owned by natives.

The Vaisya, or trading caste of Manu, has now scarcely a separate existence but its place is occupied by offshoots and well marked classes. On the western coast the Parsis, by the boldness and extent of their operations, tread close upon the heels of the great English houses. In the interior of the Bombay Presidency, business is mainly divided between two classes the Banijás of Gujarát and the Márwáris from Rajputana. Each of these profess a peculiar form of religion, the former being Vishnuites of the Vallabhá charya sect, the latter Jains. In the Deccan, their place is in taken by Lingáyats from the south, who again follow their own form of Hinduism, which is a species of Siva worship. Throughout Mysore, and in the north of Madras, Lingáyats are also found, but along the eastern seaboard the predominating classes of traders are the castes named Chetties and Komatis. Many of these trading castes still claim Vaisya descent.

in
Northern
India.

In Bengal, however, many of the upper classes of Súdras have devoted themselves to wholesale trade; although here also the Jain Márwáris from Rájputána and the North-West occupy the front rank. Their head-quarters are in Murshidábád District, and Jain Márwáris are found throughout the valley of the Brahmaputra, as far up as the unexplored frontier of China. They penetrate everywhere among the wild tribes; and it is said that the natives of the Khási Hills are the only hillmen who do their own business of buying and selling. In the North-Western Provinces and Oudh, the traders are generically called Baniyás; and in the Punjab are found the Khatris (Kshattriyas), who have perhaps the best title of any to regard themselves as descendants of the original Vaisyas.

Trade
Census;
1872

and 1881.

According to the general Census of 1872, the total number of persons throughout British India connected with commerce and trade was 3,224,000, or 5·2 per cent. of the total adult males. In 1881, throughout British and Feudatory India, 3,232,120 adult males were returned as engaged in commerce and trade, or 3·87 per cent. of the total male population engaged in some specific occupation.

Local
trade of
India.

THE LOCAL TRADE of India is conducted in the permanent *bázárs* of the great towns, at weekly markets in the rural villages, at annual gatherings held for religious purposes, or by means of travelling brokers and agents. The cultivator himself, who is the chief producer and also the chief customer, knows little of large cities, and expects the dealer to come to his own door. Each village has at least one resident trader, who usually combines in his own person the functions of money-lender, grain merchant, and cloth-seller. The simple system of rural economy is entirely based upon the dealings of this man, whom it is sometimes the fashion to decry as a usurer, but who is often the one thrifty person among an improvident population. If his rate of interest is high, it is only proportionate to the risks of his business. If he sometimes makes a merciless use of his legal position, the fault rests rather with the inflexible rules of our courts, which enable him to push the cultivators to extremes not allowed under native rule. Abolish the money-lender, and the general body of cultivators would have nothing to depend upon but the harvest of the single year. The money-lender deals chiefly in grain and in specie.

The village
money-
lender.

In those Districts where the staples of export are largely

grown, the cultivators commonly sell their crops to travelling Trade brokers, who re sell to larger dealers, and so on until the commodities reach the hands of the agents of the great shipping houses. The wholesale trade thus rests ultimately with a comparatively small number of persons, who have agencies, or rather corresponding firms, at the central marts.

Buying and selling, in their aspects most characteristic of Religion, India, are to be seen not in the large cities, nor even at the weekly markets but at the fairs which are held periodically at certain spots in most Districts. Religion is always the original cause of these gatherings or *melas*, at some of which nothing is done beyond bathing in the river, or performing pious ceremonies. But in the majority of cases, religion merely supplies the opportunity for secular business. Crowds of petty traders attend bringing the medley of articles which can be packed into a pedlar's wallet and the neighbouring villagers look forward to the occasion, to satisfy alike their curiosity and their household wants.

The improvement in means of communication, by the construction of railways and metalled roads, has directly developed internal no less than foreign trade. Facilities for rapid carriage tend to equalize prices not only over large areas of country, but also over long periods of time. As wheeled carts supersede pack bullocks, and as railroads supersede carts, the whole of India will gradually become one country for the purposes of food supply. It is by this means alone that a guarantee can be provided against the ravages of famine. The vicissitudes of a tropical climate will always cause local failures of the harvest, whether by drought or by flood, which science indeed may learn to foresee, but which no practicable schemes of irrigation or embankment can altogether avert. But India, as a whole, has never yet been unable in any single year to yield sufficient food for her population. The real problem of famine is a problem of distribution. The real Influx of trade

In former times, the inhabitants of one District might be perishing of starvation, while plenty reigned in a District but 100 miles distant. In 1866, the people of Orissa were decimated, not so much by drought or by inundation, as by the impossibility of transport. In 1877, the distress in Madras was alleviated by the importation of nearly one million tons of grain, all of which was carried inland by two lines of railway in twelve months. Supplies were drawn, not only from the seaboard of Bengal and Burma, but from the most remote

Provinces. In the year 1877-78, the Central Provinces exported grain to the amount of more than 300,000 tons, and the Punjab to the amount of 400,000 tons, all of which were conveyed south by rail. Trade has never known such a stimulus as was afforded on this occasion, when the carrying power proved barely equal to the strain. If the famine had happened before the opening of the railway, it would have resulted in a loss of life without parallel even in the annals of India.

Normal
action of
internal
trade

equalizes
prices ;

introduces
more valu-
able crops.

But the utility of local trade is not to be judged of only at such a crisis. In normal seasons, it tends alike to regulate prices and to promote a higher standard of comfort. Within the last twenty-five years, the cultivators have learnt for the first time the real value of their produce. In the old days, little was grown beyond grain crops for the year's food. The slightest failure meant local distress ; while a bumper harvest so depreciated the value of grain, that part of the crops was often left uncreaped to rot in the fields. In 1780 and 1781, a suspension of revenue had to be granted to the District of Sylhet, because the harvest was so bountiful that it would not pay the cost of carriage to market, and consequently the farmers had no means of obtaining money. Even so late as 1873, the Collector of Rangpur reported that 'the yield of rice was considered too good by the *râyats*, as prices were thereby kept down.' The extended cultivation of staples for export, such as cotton, jute, and oil-seeds, together with the substitution of more valuable crops for the inferior grains, is now modifying the entire system of Indian agriculture. Land is not being withdrawn from food crops to any appreciable extent, but the *râyât* is everywhere learning to cultivate high-priced subsidiary crops which will help to pay his rent.

Statistics
of internal
trade.

It is impossible to express in figures the precise extent of the internal trade of India. But the following statistics will serve in some measure to show both its recent development and its actual amount. They are based upon the registration returns which were collected in certain Provinces. Owing to changes in the system of registration, it is not safe to institute general comparison between different years. Inter-provincial trade statistics are now chiefly confined to railway returns and the traffic passing through certain registration centres.

Central
Provinces.

In 1863-64, the external trade of the Central Provinces, both export and import, was estimated to amount to 102,000 tons, valued at £3,909,000. By 1868-69, after the opening

of the Jabalpur Railway, it had increased to 209 000 tons, valued at £6,795,000. In 1877-78, the year of the famine in Southern India, the corresponding figures were 635 000 tons, and £9 373 000, showing an increase in 14 years of more than six fold in quantity, and considerably more than two fold in value. The comparatively small increase in value is partly to be attributed to the exclusion of opium which merely passes through in transit from Málwá. In 1882-83 the total external trade of the Central Provinces imports and exports, as represented by the railway borne traffic to stations outside the Chief Commissionership, and the registered trade with adjoining Native States was returned at over 650 000 tons, valued at £8 451 047.

In 1874-75 the total external trade of the Punjab amounted to about 600 000 tons, valued (but probably overvalued) at about £16 000 000. By 1877-78 it had increased to nearly 900 000 tons valued at £17 500 000. In 1882-83 the external trade of the Punjab trans frontier railway borne, and boat traffic was returned at nearly three quarters of a million tons, of the value of 13½ millions. These figures show a decrease in 1882-83 as compared with 1877-78 of more than one sixth both in weight and value. The high figures of 1877-78 are however accounted for by the famines in Kashmír and South India in consequence of which there were abnormally large exports of wheat and other grains from the Punjab in both directions.

The total trade of Behar in 1877-78 was valued at Behar £16,000 000. In 1882-83, the registered figures show that the East Indian Railway carried a total merchandise valued at over £19 000 000, to and from the 'Behar block'. But perhaps the significance of such enormous totals will become plainer if we take the case of a single mart, Patná, which may claim to be considered one of the most important centres of inland traffic in the world. Favourably situated on the Ganges, near the confluence of the Son (Sone) and the Gogra, where the principal trade route branches off to Népál, it has become a great changing station for the transfer of goods from river to rail.

In 1876-77, the imports and exports of Patná city (excluding the Government monopoly of opium, and probably omitting a good deal besides) were officially registered to the value of 7½ millions sterling. Many articles are included in the trade of Patná, but the imports alone have been returned as exported and imported, but the imports alone amount to more than 4 millions. Among the principal

items on one side or the other may be mentioned—European piece-goods, £1,217,000; indigo, £789,000; oil-seeds, £557,000; salt, £389,000; sugar, £274,000; food grains, £258,000; hides, £185,000; saltpetre, £156,000. In 1882-83, the East Indian Railway returns alone show a total import and export trade for Patná (excluding opium) amounting to over $5\frac{1}{4}$ millions sterling, nearly $2\frac{1}{2}$ millions being imports and over $2\frac{3}{4}$ millions exports. As regards the river and road trade of Patná city, no recent statistics are available, as registration has there been abandoned for some years past.

Growth of
a mart,
Dongar-
gáon.

Another example of the growth of local trade is exhibited at Dongargáon, as described in the *Report on the Trade and Resources of the Central Provinces*,—a model of what such a report should be. Dongargáon now forms the principal market for grain on the fertile plateau of Chhatísgarh, which is perhaps destined to become a regular source of wheat supply to England. Thirty years ago, it was a petty hamlet of about 20 houses, buried in wild jungle, and only distinguished from the neighbouring villages by a weekly *bázár* held on Sunday. In 1862, the enterprising agent of a Nágpur firm of native merchants settled here, and began to make purchases of grain. The number of houses has now risen to about 2000, of which the majority are tiled. Dongargáon had a resident population in 1881 of 5543. In the busy season, the concourse daily present in the *bázár* is estimated at 100,000, with 13,000 carts and 40,000 bullocks and buffaloes. Buyers come from as far west as Bombay, while the grain of all the adjoining Districts is brought here for sale.

A yearly
fair,
Kárágolá.

A third example of the varying methods of Indian trade may be found in the annual fair held at Kárágolá in Purniah. This fair dates from the beginning of the present century, although its site has changed from time to time. It lasts for about ten days in the month of February. During that season a little town of shops, constructed of bamboos and matting, rises on the sandy plain that stretches between the village and the bank of the Ganges. The business is entirely of a retail character, the local staples of grain, jute, and tobacco being conspicuously absent. But every article of necessity or luxury for a native household is to be bought. Cloth of all kinds, from thick English woollens to fine Dacca muslins; iron-mongery and furniture from Monghyr; boots, shawls, silks, and brocades from the cities of the North-West; hand-mills,

curry stones, and lac ornaments from the hills of Chutia Nagpur, knives, yaks' tails, ponies, musk, and other drugs, brought down by the Nepális, miscellaneous ware from England, such as umbrellas, matches, soap, paper, candles, buttons, etc.,—all find a ready sale. In 1876, the attendance was estimated at 40,000, and in 1881 at 30,000 persons, and the fees upon shops levied by the landowner realized £150. Such fairs are always protected by a special body of police, and the European official in charge of the District or Sub division is usually present.

CHAPTER XX.

ARTS AND MANUFACTURES.

Manu-
factures
of India.

INDIA may be truly described as an agricultural rather than a manufacturing country, yet it must not be inferred that she is destitute of the arts of civilised life. She has no swarming hives of industry to compare with the factory centres of Lancashire; nor any large mining population. But in all manufactures requiring manual dexterity and artistic taste, India may challenge comparison with Europe in the last century; in many of them, with England at the present day. The rival kingdoms into which the country was formerly divided, gave birth to numerous arts of luxury.

Art work.

When the first European traders reached the coast of India in the 16th century, they found a civilisation both among 'Moors' and 'Gentoos' at least as highly advanced as their own. In architecture, in fabrics of cotton and silk, in goldsmith's work and jewellery, the people of India were then unsurpassed.

English
competi-
tion.

But while the East has stood still, as regards manufactures on a great scale, the West has advanced by gigantic strides without a parallel in the history of human progress. On the one hand, the downfall of the native courts deprived the skilled workman of his chief market; while on the other, the English capitalist has enlisted in his service forces of nature against which the village artisans in vain try to compete. The tide of circumstance has compelled the Indian weaver to exchange his loom for the plough, and has crushed many of the minor handicrafts.

The tide
now
turned.

Some consolation can be found in the establishment, within the past few years, of mills fitted out by English capital with English machinery. A living portion of our own industrial activity has been transplanted to Indian soil. Manchester is growing up in miniature at Bombay, and Dundee at Calcutta. The time may yet come when India shall again clothe her people with her own cotton; she already supplies sacks from her jute for the commerce of the world.

Historically the most interesting and still the most important in the aggregate, of all Indian industries are the simple crafts in every rural hamlet. The weaver, the potter, the blacksmith, the brazier, the oil presser, are members of a community, as well as inheritors of a family occupation. On the one hand, they have a secure market for their wares, and on the other, their employers have a guarantee that their trades shall be well learned. The stage of civilisation below these village industries is represented by the hill tribes where the weaving of clothes is done by the women of the family. An advanced stage may be found in those villages or towns which possess a little colony of weavers or braziers noted for some speciality. Yet one degree higher is the case of local arts of luxury, such as ivory carving or the making of gold lace.

Another form of native industry owes its origin to European interference. Many a village in Bengal and on the Coromandel coast still shows traces of the time when the East India Company and its European rivals gathered large settlements of weavers round their little forts and thus formed the only industrial towns that ever existed in India. But when the Company gave up its private trade in 1813 and 1834, such centres of industry rapidly declined, and the once celebrated muslins of India have been driven out of the market by Manchester goods.

Cotton weaving is a very ancient industry of India. In England it dates back only a couple of centuries. Wool and linen were England's historical staples, but in India cotton weaving was practised before the time of the *Mahabharata*. The Greek name for cotton fabrics, *syndon*, is etymologically the same as that of India, or *Sind* while in later days, Calicut on the Malabar coast has given us 'calico'. Cotton cloth has always been the single material of Indian clothing for both men and women except in Assam and Burma, where silk is preferred, perhaps as a survival of an extinct trade with China. The author of the *Periplus*, our earliest authority on the trade of India, enumerates a great variety of cotton fabrics among her exports. Marco Polo, the first Christian traveller, dilates on the 'cotton and buckram' of Cambay. When European adventurers found out the way to India, cotton and silk always formed part of the rich cargoes they brought home.

The English appear to have been specially careful to fix their earliest settlements amid weaving populations—at Surat at Calicut, at Masulipatam, at Hughli. In delicacy of texture in purity and fastness of colour, in grace of design, Indian

Native industries
The village craftsmen

Fort Settlements
weaving settlements

Cotton weaving in India

an Indian garment in its texture

Causes of its decline. cottons may still hold their own against the world. But in the matter of cheapness, they have been unable to face the competition of Manchester. Many circumstances conspired to injure the Indian industry. In the last century, England excluded Indian cotton fabrics, not by fiscal duties, but by absolute prohibition. A change of fashion in the West Indies, on the abolition of slavery, took away the best customer left to India. Then came cheapness of production in Lancashire, due to improvements in machinery. Lastly, the high price of raw cotton during the American War, however beneficial to the cultivators, fairly broke down the local weaving trade in the cotton-growing tracts. Above all, the necessity under which England lies to export something to India to pay for her multifarious imports, has permanently given an artificial character of inflation to this branch of business.

Still a domestic industry.

Despite all these considerations, hand-loom weaving still holds its own with varying success in different parts of the country. Regarded as a trade, it has become unremunerative. Little is made for export, and the finer fabrics generally are dying out. The far-famed muslins of Dacca and of Arní are now well-nigh lost specialities. But as a village industry, weaving is still carried on everywhere, though it cannot be said to flourish. If Manchester piece-goods are cheaper, native piece-goods are universally recognised as more durable. Comparative statistics are not available; but it may be roughly estimated that about three-fifths of the cotton cloth used is woven in the country from native thread or from imported twist.

Supplies three-fifths of Indian consumpt.

Cotton-weaving in Madras, 1870;

In 1870, the Madras Board of Revenue published a valuable report on hand-loom weaving, from which the following figures are taken. The total number of looms at work in that Presidency, with its then population of 31 millions, was returned at 279,220, of which 220,015 were in villages and 59,205 in towns, showing a considerable increase upon the corresponding number in 1861, when the *mohartarfa*, or assessed tax upon looms, was abolished. The total estimated consumption of twist in 1870 was 31,422,712 lbs., being at the rate of 112 lbs. per loom. Of this amount, about one-third was imported twist, and the remainder country-made. The total value of the cotton goods woven was returned in 1870 at $3\frac{1}{2}$ millions sterling, or £12, 10s. per loom; but this was believed to be much under the truth.

The export of country-made cotton cloth from Madras in the same year, 1870, was about £220,000. By 1882-83, the export of country-made cloth from Madras had dwindled to £45,196.

In the Central Provinces, where hand loom weaving still flourishes, and where the statistics are more trustworthy than in some other parts of India, the number of looms in 1877-78 was returned at 87,588, employing 145,896 weavers, with an annual out turn valued at £828,000. In 1882-83, there were in the Central Provinces three large cotton mills at work, besides 143,801 looms, giving employment to 164,273 workmen, with an out turn valued at £858,219. In 1878-79, the export of Indian piece goods from the Central Provinces was valued at £162,642. In 1882-83, it was valued at £147,773.

As regards Bengal, hand loom weaving is generally on the decline. The average consumption of piece goods throughout the Province is estimated at about 5s per head, and the returns of registered trade show that European piece goods are distributed from Calcutta at the rate of about 2s 5d per head. In Midnapur, Nadia, and Bardwan, the native weavers still hold their own, as appears from the large imports of European twist, but in the eastern Districts, which have to balance their large exports of jute, rice, and oil seeds, the imports of European cloth rise to 2s 7d per head.

No part of India has more cruelly felt the English competition than Bombay. But in Bombay, the introduction of steam machinery is already beginning to restore the work to native hands. Twist from the Bombay mills is now generally used by the hand loom weavers of the Presidency, and is largely exported to China. But it is in the finer fabrics produced for export that the Bombay Districts have suffered most. Taking Surat alone, the export by sea of piece goods, at the beginning of the century was valued at £360,000 a year. By 1845, the value had dropped to £67,000, rising again to £134,000 in 1859, but in 1874, it was only £6332.

It is impossible to enumerate the many special fabrics which are still produced in various parts of the country. First among these are the far famed muslins of Dacca, which can still be obtained to order, although the quality is far inferior to what it was when Dacca was the capital of a luxurious Muhammadan court. Most of the weavers are Hindus, and the high development which their industry has reached may be judged from the fact that they employ no fewer than 126 distinct implements. The finest muslins are woven plain, but patterns of coloured silk are afterwards embroidered on them by a separate class of workmen. (For the decay of the Dacca manufactures, and the transfer of the weaving communities to agricultural employments, see article Dacca in *The Imperial*

Gazetteer of India.) Fine muslin is woven in small quantities at Sarail in the adjoining District of Tipperah; and Sántipur, in Nadiyá, still retains its reputation for delicate fabrics. But with these exceptions, cotton-weaving in Bengal produces only coarse articles for common use.

Madras
muslins.

Bangalore
cloths.

Bombay
fabrics.

In Madras, the fine fabrics maintain their ground better, although the trade is nowhere flourishing. Among those deserving mention are the muslins of Arní, the cloth woven by the Nairs on the Malabar coast, the chintzes of Masulipatam, the *panjam* or '120-thread' cloth of Vizagapatam, and the blue *salampurs* of Nellore. At Bangalore, the descendants of the old court weavers still manufacture a peculiar kind of cloth, printed in red and black with mythological designs. In the Bombay Presidency, Ahmadábád, Surat, and Broach are the chief centres of the manufacture of printed *sáris*, for which Gujarát is celebrated; while Poona, Yeola, Násik, and Dhárwár produce the fabrics dyed in the thread, which are much worn by the Maráthá races. Silk is often combined with cotton on the looms, and the more expensive articles are finished off with a border of silk or gold lace. Chándá and Hoshangábád are the largest weaving towns in the Central Provinces.

Indian
silk-
weaving :

in Burma
and
Assam ;

in Bengal.

Silk-weaving is also a common industry everywhere, silk fabrics, or at least an admixture of silk with cotton, being universally affected as a mark of wealth. Throughout British Burma, and also in Assam, silk is the common material of clothing; usually woven by the women of the household. In Burma, the bulk of the silk is imported from China, generally in a raw state; but in Assam it is obtained from two or three varieties of worms, which are generally fed on jungle trees, and may be regarded as semi-domesticated. Bengal is the only part of India where sericulture, or the rearing of the silkworm proper on mulberry, can be said to flourish. The greater part of the silk is wound in European filatures, and exported in the raw state to Europe. The native supply is either locally consumed, or sent up the Ganges to the great cities of the North-West. A considerable quantity of raw silk, especially for Bombay consumption, is imported from China. *Tasar* silk, from the cocoons of semi-domesticated worms, does not contribute much to the supply. (*Vide ante*, pp. 511-514.)

Classes
of silk
fabrics.

As compared with cotton-weaving, the silk fabrics form a town rather than a village industry. Silk fabrics are of two kinds—(1) those composed of pure silk, and (2) those with a cotton warp crossed by a woof of silk. Both kinds are often embroidered with gold and silver. The mixed fabrics are

known as *mashru* or *sufi*, the latter word meaning 'permitted,' because the strict ceremonial law will not allow Muhammadans to wear clothing of pure silk. They are extensively woven in the Punjab and Sind, at Agra, at Haidarabad in the Deccan, and at Tanjore and Trichinopoly in Madras. Pure silk fabrics are either of simple texture, or highly ornamented in the form of *hinkhab* or brocades. The latter are a speciality of Benares, Brocades Murshidabad, Ahmadabad, and Trichinopoly. Their gorgeous hues and texture may be inferred from the following names — *Shihargah*, 'hunting ground,' *chand tara*, 'moon and stars,' *marchar*, 'ripples of silver,' *murgala*, 'peacock's neck.' Printed silks are woven at Surat for the wear of Parsi and Gujarathi women.

Quite recently, mills with steam machinery have been estab Steam II
lished at Bombay, which weave silk fabrics for the Burmese factories
market, chiefly *lungis*, *tamains*, and *patsoes*. The silk manu-
factures exported from India consist almost entirely of the
handkerchiefs known as *bandannas* and *corahs*, with a small
proportion of *tasar* fabrics. The trade, after a temporary
period of depression, appears now to be increasing. In
1875-76, silk manufactures to the extent of 2,468,052 yards,
valued at £238,000, were exported from India. In 1877-78,
the export of manufactured silk had decreased to 1,481,256
yards, valued at £147,000. By 1878-79, the value of the
trade had risen to £195,897, by 1880-81, to £250,256, and
by 1882-83, to £306,928.

Embroidery has already been referred to in the two pre Embroi
ceding paragraphs. The groundwork may be either silk, dery
cotton, wool, or leather. The ornament is woven in the loom,
or sewn on afterwards with the needle. The well known *choga*,
which has recently come into popular use in England for
dressing gowns, is made of *patu* or camel's hair, embroidered Camel s
in Kashmir, the Punjab, and Sind. The still better known hair
and more valuable Kashmir shawl, made either in Kashmir Kashmir
itself or at Ludhiana, and a few other towns of the Punjab, is shawls
composed of *pashmina*, or the soft wool of the so called shawl
goat, which is a native of the Himalayan plateaux. Muslim
is embroidered with silk and gold thread at Dacca, Patna, and
Delhi. Sind and Cutch (Kachchh) have special embroideries of
coloured silk and gold. Leather work is embroidered in Gujarat Leather
(Guzerat). In some of the historical capitals of the Deccan, such work
as Gulbargah and Auringabad, velvet (*makhmal*) is gorgeously Velvet
embroidered with gold, to make canopies, umbrellas, and
 housings for elephants and horses, for use on State occasions.

Not only the goldsmith, but also the jeweller lends his aid to Indian embroidery. A *chadar*, or shawl made by order of a late Gáekwár of Baroda, is thus described by Sir G. Birdwood: 'It was composed entirely of inwrought pearls and precious stones, disposed in an arabesque fashion, and is said to have cost a *krór* of rupees (say 1 million sterling). Although the richest stones were worked in it, the effect was most harmonious. When spread out in the sun, it seemed suffused with an iridescent bloom, as grateful to the eye as were the exquisite forms of its arabesques.'

Carpets and rugs may be classified into those made of cotton and those made of wool. The former, called *satranjís* of cotton; and *darís*, are made chiefly in Bengal and Northern India, and appear to be an indigenous industry. They are usually white, striped with blue, red, or chocolate, and sometimes ornamented with squares and diamonds. The woollen or pile carpets, known as *kalin* and *kalicha*, are those which have recently attained so much popularity in England, by reason of the low price at which the out-turn of the jail manufactories can be placed on the market.

The pile carpet is indigenous to Persia and Túrkestán, where the best are still made. The art came into India with the Muhammadans. 'The foundation for the carpet is a warp of strong cotton or hempen threads; and the peculiarity of the process consists in dexterously twisting short lengths of coloured wool into each of the threads of the warp, so that the two ends of the twist of wool stick out in front. The projecting ends are then clipped to a uniform level, and the lines of work are compacted together by striking them with a blunt instrument' (Birdwood). The historical Indian seats of the industry are Kashmír, the Punjab, and Sind; Agra, Mírzápur, Jabalpur, Warangal in the Deccan, Malabar and Masulipatam. Velvet carpets are also made at Benares and Murshidábád, and silk pile carpets at Tanjore and Salem.

At the London Exhibition of 1851, the finest Indian rugs came from Warangal, the ancient capital of the Andhra dynasty, about 80 miles east of Haidarábád. Their characteristic feature was the exceedingly numerous count of the stitches, about 12,000 to the square foot. 'They were also perfectly harmonious in colour, and the only examples in which silk was used with an entirely satisfactory effect' (Birdwood). The price was not less than £10 per square yard. The common rugs, produced in enormous quantities from the jails at Lahore,

Jabalpur, Mirzapur, Benares, and Bangalore, sell in England at 7s 6d each

Gold and silver, and jewels, both from their colour and their intrinsic value, have always been the favourite material of Oriental ornament. Even the hill tribes of Central India and the Himalayas show skill in hammering silver into brooches, armlets, and necklets. Imitation of knotted grass and of leaves seems to be the origin of the simplest and most common form of gold ornament, the early specimens consisting of thick gold wire twisted into bracelets, etc. A second archaic type of decoration is to be found in the chopped gold jewellery of Gujarat (Guzerát). This is made of gold lumps, either solid or hollow, in the form of cubes and octahedrons, Cube strung together on red silk. Of artistic jewellers work, the best known examples are those from Trichinopoly, Cuttack, and Kashmir.

Throughout Southern India, the favourite design is that known as *swami*, in which the ornamentation consists of figures of Hindu gods in high relief, either beaten out from the surface or fixed on to it by solder or screws. The Trichinopoly work proper, which has been to some extent corrupted to suit English taste, includes also chains of rose gold, and bracelets of the flexible serpent pattern. The silver filigree work of Cuttack, identical in character with that of ancient Greece and of Malta at the present day, is generally done by boys, whose sensitive fingers and keen sight enable them to put the fine silver threads together with the necessary rapidity and accuracy. The goldsmiths work of Kashmir is of the kind known as 'parcel gilt,' and is further distinguished by the ruddy colour of the gold used. 'Its airy shapes and exquisite tracery, graven through the gilding to the dead white silver below, softening the lustre of the gold to a pearly radiance, give a most charming effect to this refined and graceful work' (Birdwood). The hammered *repousse* silver work of Cutch (Kachchh), although now entirely naturalized is said to be of Dutch origin. Similar work is done at Lucknow and Dacca. The goldsmiths art contributes largely to embroidery, as has already been mentioned. Gold and silver thread is made by being drawn out under the application of heat. The operation is performed with such nicety, that 1 rupees worth of silver will make a thread nearly 800 yards long. Before being used on the loom, this metallic thread is generally twisted with silk or the manufacture of cloth of gold (*sonari*) or cloth of silver (*chandi*), the wire is beaten flat, so as to form the warp to a

woof of thin silk or cotton. A third kind of metallic ornamentation is practised at Jaipur in Rájputána and Haidarábád in the Deccan, by printing muslins with patterns of gold and silver leaf.

Precious
stones.

Precious stones are lavishly used by Indian jewellers, who care less for their purity and commercial value than for the general effect produced by a blaze of splendour. 'But nothing can exceed the skill, artistic feeling, and effectiveness with which gems are used in India both in jewellery proper and in the jewelled decoration of arms and jade' (Birdwood). The general character may be learned from the following description of a hair-comb in the Prince of Wales' collection, made at Jaipur: 'The setting is of emerald and ruby Jaipur enamel on gold, surmounted by a curved row of large pearls, all on a level, each tipped with a green glass bead. Below is a row of small brilliants, set among the elegantly designed green and red enamelled gold leaves which support the pearls. Then a row of small pearls, with an enamelled scroll-work set with brilliants between it and a third row of pearls; below which comes a continuous row of minute brilliants forming the lower edge of the comb, just above the gold prongs.'

Indian
iron-work.

The chief duty of the village smith is, of course, to make the agricultural implements for his fellow-villagers. But in many towns in India, chiefly the sites of former capitals, iron-work still attains a high degree of artistic excellence. The manufacture of arms, whether for offence or defence, must always be an honourable industry; and in India it attained a high pitch of excellence, which is not yet forgotten. The magnetic iron-ore, found commonly in the form of sand, yields a charcoal steel which is not surpassed by any in the world. The blade of the Indian *talwár* or sword is sometimes marvellously watered, and engraved with date and name; sometimes sculptured in half-relief with hunting scenes; sometimes shaped along the edge with teeth or notches like a saw. Matchlocks and other fire-arms are made at several towns in the Punjab and Sind, at Monghyr in Bengal, and at Vizianágaram in Madras.

Cutlery.

Chain
armour.

Chain armour, fine as lacework, and said to be of Persian derivation, is still manufactured in Kashmír, Rájputána, and Cutch (Kachchh). Ahmadnagar in Bombay is famous for its spear-heads. Both fire-arms and swords are often damascened in gold, and covered with precious stones. In fact, the characteristic of Indian arms, as opposed to those of other Oriental countries, is the elaborate goldwork hammered or cut upon

them, and the unsparing use of gems. Damascening on iron and steel, known as *kust*, is chiefly practised in Kashmir, and at Gujrát and Sialkot in the Punjab. The process consists of encrusting gold upon the surface of the harder metal. Damascening in silver, which is chiefly done upon bronze, is known as *bidari* work, from the ruined capital of Bidar in the Nizám's Dominions, where it is still chiefly carried on.

The village brazier, like the village smith, manufactures the necessary vessels for domestic use. Chief among these vessels is the *lotá*, or globular bowl, universally used in ceremonial ablutions. The form of the *lotá*, and even the style of ornamentation has been handed down unaltered from the earliest times. A *lotá* now in the India Museum, which was disinterred from a Buddhist cell in Kulu and must be at least fifteen centuries old, represents Prince Siddhartha going on a high procession. Benares enjoys the first reputation in northern India for work in brass and copper, producing not only vessels for domestic and ceremonial use, but also images and religious emblems. In the south Madurai and Tanjore have a similar fame, and in the west Ahmadábád, Poona, and Násik. At Bombay itself large quantities of imported copper are wrought up by native braziers.

The temple bells of India are well known for the depth and purity of their note. In many localities the braziers have a speciality, either for a peculiar alloy or for a particular process of ornamentation. Silver is sometimes mixed with the brass, and in rarer cases gold. *Bidari* work or the damascening of *bidari* silver upon bronze, has already been alluded to. In this case, the metal ground is said to be an amalgam of copper, lead, and tin, made black by dipping in a solution of sal ammoniac, saltpetre, salt, and blue vitriol. At Moradábád, in the North Western Provinces, and at Bhilwara in Udaipur State, Rájputána, tin is soldered upon the brass and incised through in ornate patterns, which are marked by filling in the ground with a black composition of lac. At Purneah in Bengal, a variety of *bidari* ware is made of zinc and copper, damascened with silver, the processes of which are described at length in Hunter's *Statistical Account of Bengal*. The brass or rather metal ware of Murshidabad, known as *khágrat*, has more a local reputation, owing to the large admixture of silver in the demand for enormous quantities of brass work at the Deteriorated price for the London market, is rapidly deteriorating in the designs and the workmanship of the Benares articles. ^{brass work.}

The native braziers are almost compelled to degrade their industry, when they find that the most vulgar patterns, deeply but hastily carved, command a ready sale; while their old faithful work can scarcely find an English customer, at the price necessary for production.

Indian
pottery.

Next to the loom of the weaver, the potter's wheel is the characteristic emblem of an ancient civilisation. From time immemorial, the potter has formed an essential member of the Hindu village community. Pottery is made in almost every village, from the small vessels required in cooking to the large jars for storing grain, and the earthenware floats used to ferry persons across a swollen stream. But although the industry is universal, it has in few Provinces risen to the *dignity of a fine art*. Perfection has been reached neither in the substance, as in the porcelain of China, nor in the ornamentation, as in ancient Greece. The clay in many places works up well, but the product remains mere earthenware, and rarely receives a high finish.

Its imper-
fections.

Sind
pottery.

In Sind and the Southern Punjab the potter's craft has risen to a high art; and here the industry is said to have been introduced by the Muhammadans. Sind pottery is of two kinds, encaustic tiles and vessels for domestic use. In both classes the colours are the same—turquoise blue, copper green, dark purple or golden brown, under an exquisitely transparent glaze. The usual ornament is a conventional flower pattern, sometimes pricked in from paper, but often painted with much freedom and grace. The tiles, evidently of the same origin as those of Persia and Turkey, are chiefly found in the ruined mosques and tombs of the old Musalmán dynasties; but the Sind industry still survives at the little towns of Saidpur and Bubri; and at Haidarábád, Karáchi, Tatta, and Hála.

Tiles.

Punjab
and
Bombay
pottery.

Glazed tiles and pottery are also manufactured at Lahore and Múltán in the Punjab. Efforts have been made by the Bombay School of Art to foster this indigenous industry; but, as in other cases of European patronage, the Indian artisan loses his originality when set to copying alien models. Something, however, has been done in the right direction by reproducing the old designs from the cave temples of Ajanta and Karli, in the pottery made at the Bombay School of Art. The Madura pottery also deserves mention, from the elegance of its form and the richness of its colour.

Sculpture.

The earliest Indian sculptures are found in the monasteries, *topes*, and 'rails' of ancient Buddhism. The best specimens

disclose the still fresh impulse derived from Greek or Roman artists—that impulse which has been historically treated in previous chapters, pp 112 and 170–172 With the revival of Bráhmaism, Indian sculpture degenerated Modern Hindu statuary possesses a religious rather than an æsthetic interest But exquisite flat carving and perforated arabesque windows or screens in hard sandstone and marble, are still produced at Agra and Jampur

In the cities of Gujarát (Guzerat) and in other parts of India where the houses are built of wood their fronts are ornamented with elaborate carving The favourite materials are black wood (*Dalbergia latifolia*) sandal wood and jack wood The supply of sandal wood comes from the forests of the Western Ghats in Kánara and Mysore, but some of the finest carving in it is done at Surat and Ahmadábad Examples of 17th century Indian carving indicate that the art received a powerful impulse from the Dutch along the Bombay coast But Indian wood carving is an art of very great antiquity The early stone architecture of the Buddhists is evidently based, both in regard to structure and ornaments on pre-existing wooden forms Some of the patterns of modern Indian wood carving are preserved from that earlier period in exquisite open carving in marble or open lattice work windows in hard stone The more durable material has survived and now tells its tale The Burmese are also celebrated for their luxuriant wood carving

Akin to wood carving is the inlaying of the articles known Inlaying, as ‘Bombay boxes’ This art is known to be of modern date, having been introduced from Shiraz in Persia towards the close of the last century It consists of binding together in geometrical patterns strips of tin wire, sandal wood, ebony, ivory, Ivory and stags horn At Vizagapatam in Madras similar articles carved are made of ivory and stags horn, with scroll work edged in to suit European taste At Máinpur, in the North Western Provinces, wooden boxes are inlaid with brass wire The chief seats of ivory carving are Amritsar, Benares, Murshidabad, and Travancore, where any article can be obtained in order in ivory, from a full sized palanquin to a lady’s comb Human figures in clay, dressed to the life, are principally made at Krishnagar in Bengal, at Lucknow, and at figures

For Indian architecture painting and musical instruments, see *ante*,

European
industries.

The preparation of tea, coffee, and indigo have been already described in connection with agriculture. It remains to give some account of those manufactures proper, conducted by steam machinery, and under European supervision, which have rapidly sprung up in certain parts of India during the past few years. These comprise cotton, jute, silk, and wool, and beer, paper, leather, etc.

Cotton
mills,
1854-79.

The first mill for the manufacture of cotton yarn and cloth by machinery worked by steam, was opened at Bombay in 1854. The enterprise has since expanded to vast dimensions. In 1879, the total number of mills throughout India was 58, with about a million and a half spindles, and twelve thousand looms, giving employment to upwards of 40,000 persons—men, women, and children. Of this total, 30 mills, or more than half, were in the island of Bombay, which now possesses a busy manufacturing quarter with tall chimney-stalks, recalling the aspect of a Lancashire town; 14 were in the cotton-growing Districts of Gujarát (Guzerát), also in the Bombay Presidency; 6 were in Calcutta and its neighbourhood; 3 at Madras; 2 at Cawnpur in the North-Western Provinces; 1 at Nágpur in the Central Provinces; 1 at Indore, the capital of Holkar's Dominions; and 1 at Haidarábád, the residence of the Nizám.

Their dis-
tribution
throughout
India.

Cotton
mills, 1884:
Govern-
ment
returns.

By 1884, the number of steam cotton mills for which returns had been received by Government had increased to 74, with 1,895,284 spindles, and 16,251 looms, giving employment to a total of 61,836 men, women, and children. Of these, 35 were in the town and island of Bombay; 21 were in other Districts of the Bombay Presidency, chiefly Gujarát; 6 in Bengal, in the suburbs or vicinity of Calcutta; 5 in Madras, namely, 4 in Madras town, and 1 in Bellary District; 3 at Cawnpur in the North-Western Provinces; 2 in the Central Provinces, namely, at Nágpur and at Hinghanghát; and 1 each at Indore and Haidarábád in the Deccan.

Cotton
mills, 1884:
private
returns.

Private returns of the cotton industry show a somewhat different result to that quoted above. A carefully-compiled statement gives the figures up to the 30th June 1884 as follows:—On that date there were, in the town and island of Bombay itself, 43 cotton mills, namely, 38 in work, and 5 in course of construction, with a total paid-up capital of £4,580,430; the number of spindles was 1,251,726, and of looms (in 22 mills), 11,985; giving employment to a daily average of 36,071 men, women, and children; quantity of

COTTON MILLS

611

cotton consumed (in 36 mills) in twelve months, 1,218,490 cwt. Elsewhere in the Bombay Presidency there were 18 mills, with a total paid up capital for 17 mills of £943,706. The number of spindles was 289,153, and of looms, in the only 12 mills which had them, 2314. Number of hands employed, 9293, quantity of cotton consumed, 235,935 cwt. There were thus, in June 1884, in the Bombay Presidency, 61 mills, either in active operation or in course of construction, with a total paid up capital of £5,452,136, employing 45,364 hands and consuming 1,454,475 cwt. of cotton. In the other Provinces of India there were 20 mills, namely, 6 in Bengal 3 in the North Western Provinces, 1 in the Central Provinces, 1 at Haidarabad, and 9 in Madras, of which 4 were under construction in June 1884. The total paid up capital of these mills outside the Bombay Presidency was £1,414,950, number of spindles, 79,176, and of looms, 1426, number of hands employed daily, 17,472, quantity of cotton consumed during the year, 371,591 cwt. Throughout India there were thus 81 mills in June 1884, constructed at a cost of £6,867,086, with 1,520,055 spindles, and 15,725 looms, consuming 1,826,016 cwt. of cotton during the previous twelve months, and affording employment to a daily average of 62,836 men, women, and children.

The general character of the cotton industry and its progress Nagpur may be inferred from the following returns supplied by the Cotton Mill 1882 Empress Spinning and Weaving Mills Company at Nagpur, which in 1882 had 30,000 spindles and 450 looms at work, and employed a daily average of 3137 hands. Their consumption of raw cotton up to 1880 averaged 1,707,000 lbs a year, their out turn has averaged 1,040,000 lbs of yarn valued at £45,358, and 627,700 lbs of cloth valued at £30,661. In 1882, the consumption of raw cotton at these mills was 3,796,240 lbs, with an out turn of 1,804,530 lbs of twist, and 1,494,945 lbs of manufactured cloth, of a total value of £159,386.

This rapid and widespread development sufficiently proves Sound I that the new industry, though still in its infancy, is being ^{the basis of} carried on under wholesome conditions, and meets a real ^{the market} demand. Checks have from time to time occurred at Bombay, caused partly by competition with European goods recklessly thrown upon the market regardless of profit, and partly by that mismanagement to which joint stock enterprise is peculiarly exposed. But with the revival of general commerce, the

Bombay mills have always again started upon a career of renewed activity.

Cheap material.

Their advantages over the English manufacturer are manifest.

Cheap labour.

The crop of raw material and the market for the manufactured article are both at their very doors, thus saving a double freight.

No adulteration.

Labour is cheap, abundant, docile, and not liable to strike. A certain amount of prejudice exists in favour of their products, partly because of their freedom from adulteration, and partly from the patriotic pride naturally felt for a native industry. Lastly, up to March 1882, they had the slight protection of a moderate customs duty of 5 per cent. *ad valorem* (imposed for fiscal purposes solely) upon imported goods. The cotton import duties were finally abolished, together with the general import duties upon all but a few excepted articles of merchandise, such as arms and ammunition, liquors, etc., by the Indian Tariff Act, xi. of 1882.

The drawbacks.

Cost of erection.

On the other hand, they labour under not a few countervailing disadvantages. The cost of erection, including spindles and fitting up, was said (1877) to be about three times as much in India as in England. Thus a mill containing 50,000 spindles, which in Lancashire might be set up for about £1 per spindle, or a total of £50,000, would cost at Bombay about £150,000. On this capital the initial charge for interest would be only £2500 a year in England, calculated at 5 per cent., as compared with £13,500 in India, at the rate of 9 per cent. Again,

High interest.

the cost of fuel, and all stores which require to be imported from England, tells greatly against the Bombay mills. Another important consideration which it is difficult to estimate in all its bearings, is the quality of Indian cotton, known as 'short stapled,' which does not admit of being spun into the finer kinds of yarn. Consequently the Indian mills can only turn out the lower 'counts' of yarn, and the coarser fabrics of piece-goods, leaving English imports of the higher classes without competition.

Short staple.

Only coarse qualities made.

Adopting the technical language of the trade, the great bulk of the yarn spun in Indian mills consists of numbers 6, 10, and 20 mule twist. Water twist is spun in smaller quantities, generally of number 16. The maximum of either kind is number 30. The mills are capable of spinning up to 40; but as a matter of fact, they never attempt this number, owing partly to the inferior quality of the cotton, and partly to the carelessness of the work-people. As regards piece-goods, the kinds principally woven in the mills are those known as T cloths, domestics, sheetings, drills, and jeans,

made entirely from the yarn spun in the same mills. Long cloths, *chadars* and *dhotis*, are also manufactured, and recently attempts have been made to turn out drawers, stockings, night caps, and towelling. But Manchester still possesses a practical monopoly both of the higher 'counts' of yarn which are used by the hand loom weavers, and of the superior qualities of cloth.

The Indian mills are almost without exception the property of joint stock companies, the shares in which are largely taken up by natives. The overlookers are skilled artisans brought from England, but natives are beginning to qualify themselves for the post. The operatives are all paid by the piece, and, as compared with other Indian industries, the rates of wages are high. In 1877, at Bombay, boys earned from 14s to £1 a month, women, from 16s to £1, and jobbers, from £3 to £6, 10s. Several members of one family often work together, earning between them as much as £10 a month. The hours of work are from six in the morning to six at night, with an hour allowed in the middle of the day for meals and smoking. The Indian Factories Act, xi of 1881, regulates the hours of work for children and young persons, and enforces the fencing of dangerous machinery, etc.

Besides supplying the local demand these mills are gradually beginning to find a market in foreign countries, especially for their twist and yarn. Between 1872-73 and 1882-83, the export of twist from Bombay increased from 1,802,863 lbs valued at £97,162 in 1872-73, to 21,271,059 lbs valued at £883,665 in 1878-79 and to 42,598,400 lbs valued at £1,705,978 in 1882-83, or an increase of twenty-four fold in quantity and nearly eighteen fold in value in eleven years. Within the same period, the export of grey piece goods from Bombay increased from 4,780,834 yards valued at £75,195 in 1872-73 to 14,993,336 yards valued at £198,380 in 1878-79, and to 30,730,396 yards valued at £357,320 in 1882-83. The total foreign exports of Indian twist and yarn, and of Indian manufactured grey, white, and coloured piece goods from all Indian ports amounted to £2,578,382 in value in 1882-83. The above figures refer to Indian produce and manufactures only, and are exclusive of 1½ million sterling of re-exported British cotton manufactures. Including these re-exports, the total exports of cotton twist, yarn, and manufactures amounted to just under 4 millions in 1882-83 from all Indian ports. The twist and yarn is mostly sent to China and Japan, the piece-goods to the coast of Arabia and Africa.

The figures for the coasting trade show a slower growth, the total value of twist carried from port to port in 1878-79 having been £804,996, and of piece-goods (including handloom goods), £654,553. In 1882-83, cotton twist and yarn to the value of £896,369, and piece-goods to the value of £633,316, were exported in the coasting trade, apart from exports to foreign countries.

Future of
the trade.

Mr. O'Connor, who has devoted much attention to the matter, thus summarizes his opinion regarding the future of the Indian cotton mills in his *Review of Indian Trade* for 1877-78:—'Whether we can hope to secure an export trade or not, it is certain that there is a sufficient outlet in India itself for the manufactures of twice fifty mills; and if the industry is only judiciously managed, the manufactures of our mills must inevitably, in course of time, supersede Manchester goods of the coarser kinds in the Indian market.' The correctness of this opinion is further shown by Mr. O'Connor's *Review of Indian Trade* for 1884-85, in which he states—'The importation of the coarser kinds of twist has long been unimportant, the yarn of the Indian mills having driven it out of the market. Even the medium kinds are now diminishing, an indication that the Indian mills are beginning to make them too.'

Wool
mills.

Besides cotton mills, wool-weaving by steam machinery has recently been established in India, the principal mills being the Egerton Mills in Gurdáspur District, Punjab, and the Cawnpur woollen mills in the North-Western Provinces.

Jute mills.

The jute mills of Bengal have sprung up in rivalry to Dundee, as Bombay competes with Manchester; but in Bengal the capital for jute-manufacturing is almost entirely supplied by Europeans. The jute-mills cluster round Calcutta, and on the opposite side of the river in Howrah District. The industry has also taken root at Sirájganj, far away, up the Brahmaputra, in the middle of the jute-producing country.

Number
in 1882-83.

In 1882-83, the total number of jute mills in India was 21, of which 19 were in Bengal, 1 at Kolába on Bombay island, and 1 at Chittivalása in Vizagapatam District, Madras. The weaving of jute into gunny cloth is an indigenous handloom industry in Northern Bengal, chiefly in the Districts of Purniah and Dinájpur. The gunny is made by the semi-aboriginal tribe of Koch, Rájbandsí or Páli, both for clothing and for bags; and, as with other industries practised by non-Hindu races, the weavers are the women of the family, and not a distinct caste. The mills turn out bags, and

also cloth in pieces to a limited extent. The bags vary in Jute size, according to the markets for which they are intended. The largest are the twilled wool packs sent to Australia, which measure 56 inches by 26½, and weigh about 10½ lbs each. The smallest are the Hessian wheat bags for California, measuring 36 inches by 22, and weighing only 12 ounces. The average weight may be taken to be from 2 to 2½ lbs.

The mills in Calcutta and its neighbourhood were estimated in 1878 to keep about 4000 looms at work, the total amount of raw jute worked up annually was about 1½ million cwt, which yielded about 90 million bags. The 21 steam jute mills in India in 1883 worked 6139 looms and 112,650 spindles, the total quantity of raw jute worked up in the year being returned at 2,831,778 cwt. These figures are below the mark, as certain companies and private individuals have not supplied full information. The jute manufacturing industry afforded employment to 47,868 men, women, and children in 1882-83.

The activity of the jute trade, and the general direction of the exports, will be seen by comparing the figures for 1877-78 and 1882-83 in the two following paragraphs.

In 1877-78, 3 million bags were brought into Calcutta from Pabna District, being the product of the Sirājganj mills. The total exports from Calcutta by sea and land of both power loom and hand made bags numbered 80 millions in 1877-78, of which not more than 6 millions were hand made. The East Indian Railway took 20 millions for the grain marts of Behar and the North Western Provinces (chiefly Patna and Cawnpur), and 1 million went as far as Ludhiana in the Punjab. The total exports by sea in 1877-78 exceeded 57 millions, of which 32 millions represent interportal, and 25 millions foreign trade. Bombay took as many as 16 millions, and British Burma 12 millions. In fact, Calcutta supplies bagging for the whole of India.

In 1882-83, besides the local manufactures in Calcutta, 28,972,920 bags were imported into that city from the interior Districts, of which 12,494,243 were power loom and 16,478,677 hand made. The total exports from Calcutta of power loom and hand made bags numbered 123,219,477 bags. Of the internal trade, the East Indian Railway carried 16,808,855 bags for the following marts and Districts — Patná (3,189,970), Cawnpur (2,583,210), Faizābād (959,455), Delhi (676,375), Satal Parganās (623,945), Monghyr (609,875), Birbhum (558,915), and Bardwan (544,355). The total internal

Varieties,
of gunny
bags

Out turn of
Calcutta
jute mills,
1878,

Indian and
foreign
consump-
tion

1878,

and 1883

exports by rail, boat, and road amounted to 18,877,715 bags. The exports by sea numbered 104,341,762 bags, of which 45,018,189 represented coasting, and 59,323,573 foreign exports.

The foreign jute trade may be given in greater detail, for gunny-weaving is perhaps the single Indian manufacture that has secured a great foreign market. The sea-borne export of jute manufactures (bags and cloth) in 1872-73 was valued at £188,859. By 1878-79, the value had risen to £1,098,434, and by 1882-83 to £1,487,831, or an increase of £389,397 in four years. These figures seem to justify Mr. O'Connor's statement in his *Review of Indian Trade* for 1878-79, that 'there is little room to doubt that in course of time India will be able, not only to supplant the manufactures of Dundee in the American and other foreign markets, but to supply England herself with bags more cheaply than they can be made in Dundee.' On the other hand, it must be recollected that large figures, and even growing figures, do not necessarily show that a business is remunerative. Calcutta, like Bombay, sometimes suffers from the mismanagement incidental to joint-stock enterprises. The principal countries which take Indian gunny-bags are:—Australia, £714,747 in 1882-83; Straits Settlements, £189,869; United States (California), £164,405; China, £173,295.

Brewing. Brewing has been established on a large scale at the hill stations for several years. There were in 1882-83, 22 breweries in India; 12 in the Punjab and the North-Western Provinces, at Mari (Murree), Simla, Solon, Kasauli, Dalhousie, Masuri (Mussoorie), Naini Tal, Chakrata, and Ránikhet; 2 in Bombay, at Moody Bay and at Banderá; 3 in Madras, at Utakamand and Coonoor; 4 at Bangalore in Mysore; and 1 at Rangoon. The total quantity of beer brewed was returned at 2,162,888 gallons in 1877, and 2,597,298 gallons in 1882-83. The quantity imported into India in 1878-79 was 2 million gallons by Government, and 1 million gallons on private account. In 1882-83, the Government imports were just under 1½ million gallons, and the private imports a little over 1 million gallons, total 2,656,788 gallons; so that the Indian breweries now satisfy one-half of the entire demand. Indian brewed beer is rising in public favour, and is rapidly superseding imported beer for commissariat purposes. In 1875, 349,095 gallons of Indian beer were purchased by the Bengal Commissariat Department; in 1883, the quantity thus

purchased was 1,936,221 gallons, as against 1,486,234 gallons imported by Government

At Simla, imported beer sells at over 18s per dozen quarts, ^{Pier} while that from the local breweries can be obtained for 10s per ^{prices} dozen. The hops are entirely imported. An experimental hop plantation of 100 acres established by the Mahārāja of Kashmir has not yet proved a practical success, but efforts are still being made, both in Kashmir and in India, to successfully introduce the hop plant into the country. The imports of hops show an increase from 1529 cwts in 1875-76, to 1807 cwts in 1876-77, and 2135 cwts in 1877-78. In ^{Hop} imports 1882-83, however, the import of hops had fallen to 1940 cwts valued at £47,983.

The steam paper mills established in the neighbourhood of ^{paper} Calcutta and at Bombay have almost entirely destroyed the ^{making} local manufactures of paper which once existed in many parts of the country. The hand made article, which was strong though coarse, and formed a Muhammadan speciality, is now no longer used for official purposes.

The Government possesses a large leather factory at Cawn ^{Leather} pur, which turns out accoutrements, saddlery, etc., of excellent quality. Two large European firms have also established leather factories at Cawnpur. Indeed, leather hand-manufactures have long been an important local industry in Oudh and the North Western Provinces. They are worked so cheaply as to discourage importation from England, except in the case of *articles de luxe*, and saddlery or harness for the richest classes.

Rice husking by steam machinery is largely carried on at the ^{Rice} ports of British Burma ^{husking}.

CHAPTER XXI.

MINES AND MINERALS.

Mines and minerals. THE Indian peninsula, with its wide area and diversified features, supplies a great store of mineral wealth. In utilizing this wealth, English enterprise has met with many rebuffs. Capital has been expended in many cases with no result except disappointment. But the experience has not been thrown away; and mining industry, now established on a sure basis, is gradually rising into an important position.

Indian iron.

In purity of ore, and in antiquity of working, the iron deposits of India rank among the first in the world. They are to be found in every part of the country, from the northern mountains of Assam and Kumáun to the extreme south of Madras. Wherever there are hills, iron is found and worked

Indigenous methods.

to a greater or less extent. The indigenous methods of smelting the ore, handed down unchanged through countless generations, yield a metal of the finest quality in a form well suited to native wants. But they require an extravagant supply of charcoal; and notwithstanding the cheapness of native labour, the product cannot compete in price with imported iron from England. European enterprise, attracted by the richness of the ore and the low rate of wages, has repeatedly tried to establish ironworks on a large scale. But hitherto each of these attempts has ended in failure.

Failure of English efforts, 1825;

The most promising early efforts were those undertaken in Madras by Mr. Heath of the Civil Service, the anticipator of the Bessemer process. In 1825, he founded a company which opened works at Porto Novo on the Coromandel coast, in the hills of Salem District, and at Beypur in Malabar. The iron and steel produced were of first-rate quality; and all went well so long as an unlimited supply of charcoal could be obtained in the neighbourhood of the furnaces. But when this essential condition of cheap production gradually ceased, the enterprise became unremunerative, and had to be abandoned. Within the last few years, an attempt has been made to smelt ore by means of coal, according to English

1880.

methods, in the neighbourhood of Rániganj and in Bírbbhum and Mánbhum. Coal abounds, and also limestone as a flux, but in this case, again, the company made no profit, and has been compelled to wind up. Similar experiments in the Central Provinces and in Kumaun have met with similar results.

In 1882-83, the Bengal Government took over the works of the suspended Bírakhar Iron Company at Khendua in Manbhúm District, and cast and pig iron is now manufactured on the spot. The iron works are doing a considerable amount of good, as not only do they encourage the private coal companies in the neighbourhood, but they also give employment to a large number of skilled workmen. They also promise to be remunerative, and the question of the expansion of the works is (1884) under the consideration of Government. With the exception of these works, iron in India is manufactured only by peasant families of smelters, each working on a very small scale.

The initial difficulty in India is to find the three elements of iron working, namely, the ore, the flux, and the fuel, sufficiently near to each other. The second difficulty is the choking of the furnaces from the excessive quantity of ash in the coal.

Coal has been known to exist in India since 1774, and is said to have been worked as far back as 1775. The first English coal mine was opened at Rániganj in 1820. There are now (1885) 65 working collieries in the country, with an annual out turn of about 1 million tons. In India, as elsewhere, coal and railway extension have gone hand in hand. Coal is comparatively worthless unless it can be brought to market by rail, and the price of coal is the chief element in determining the expenses of railway working. The history of coal in India is, on the whole, a record of continual progress. The first mine, as already mentioned, dates from 1820, and it has been worked regularly up to the present time. In 1878, its output was 50,000 tons. Until about 1840 no other mine was opened, but the commencement of the East Indian Railway in 1854 gave a fresh impetus to the industry, and since that date collieries have been set on foot at the rate of two or three every year. The largest number of additions was seven in 1874. From these are supplied not only the railway itself, but also the jute mills of Calcutta, and the river steamers of Lower Bengal.

In 1883, there were in all 62 working collieries in Bengal, 188, besides 15 others, principally in the Santal Parganas, which were either closed, or were not working during the year. The

Rániganj Sub-division, with its 50 working collieries, had an output of 603,591 tons in 1883, as compared with an average output of 547,930 tons in the previous three years. Four new mines were opened during the year. Hazáribagh and Mánbhúm Districts contain 6 collieries, which yielded an out-turn of 559,849 tons in 1883, against an annual average for the three previous years of 502,860 tons. The East Indian Railway Company's valuable mines at Karharbárá and Srírámpur are situated within Hazáribagh District. In 1883, these two mines yielded a total output of 308,000 tons, against an average of 274,087 in the three previous years. The total out-turn from all the working mines in Bengal in 1883 was 1,200,957 tons, against an average of 1,058,084 tons for the three previous years. In 1882-83, the imports of coal into Calcutta by sea were only 74,610 tons, so that Bengal now uses locally about 94 per cent. of Indian to about 6 per cent. of foreign coal. Bombay and Madras are entirely supplied with coal from England.

Imported
coal.

Coal-
mining in
Central
Provinces ;

The collieries in the Central Provinces, the only other Indian ones worked on a large scale, are limited to the supply of the Great Indian Peninsula Railway. They consist of—
(1) the Warorá colliery in Chándá District, under the management of the Public Works Department ; and (2) the Mohpání colliery, which has been leased to the Narbadá Coal Company.

(1) Warorá In 1878-79, the Warorá colliery put out 43,000 tons, of colliery ; which 11,000 tons consisted of slack. The gross receipts were £18,686, and the net receipts £5873, being about 8·3 per cent. on the estimated capital expenditure of £70,000. In 1883, the Government mine at Warorá yielded an out-turn of 95,738 tons, and averaged 51,376 tons in the previous three years. The profits are estimated at 4 to 6 per cent. But it is difficult to fix the sum, as the accounts are mixed up with those of the Wardhá State Railway, a branch from the Nágpur line of the Great Indian Peninsula Railway. Cost of raising coal in the Central Provinces, Rs. 2. 10. (5s. 3d.) per ton ; price paid by the Railway Company for large coal, Rs. 5 (10s.) per ton. In 1877-78, the cotton mills at Nágpur took 4872 tons.

(2) Moh-
pání
colliery.

The Mohpání colliery had an output in 1878-79 of 8900 tons, valued at £8000. In 1883, the total output from Mohpání mine was 19,281 tons, as against an average of 13,714 tons in the previous three years. Almost the whole of this was taken by the Great Indian Peninsula Railway. Extensive coal-fields have recently been discovered at Umária, within the Native State of Rewá, only 34 miles beyond the

northern boundary of the Central Provinces, which are believed to extend into the northern portion of Jabalpur

The principal drawback of Indian coal is its large proportion of ash, varying from 14 to 20 per cent, as against 3 to 6 per cent in English coal. This places Indian coal measures at a great disadvantage, alike for iron smelting and locomotive purposes. But it has been proved that, with efficient fire grates and proper manipulation, 135 lbs of Warora coal will do the work of 100 lbs of English coal.

The Ranigunj coal field has been estimated at an area of 500 square miles. In this 'black country' of India, which is dotted with tall chimney stalks, many European companies are at work, besides many native firms.¹ At first coal was raised from open workings, but regular mining is now carried on, according to the system known as 'pillar and stall'. The seams are entirely free from gas, so that the precautions usual in England against explosion are found unnecessary. The miners are all drawn from the aboriginal races, chiefly Santals and Bauris, who are noted for their endurance and docility. Bauris work with the pick, but Santals will consent to use no other instrument than the crowbar. Wages are high, and the men look well fed, although they waste their surplus earnings in drink.

The coal fields of India lie almost entirely in the broad centre of the peninsula, between the Ganges and the Godavari. South of the Godavari no carboniferous strata exist, and the whole Presidency of Madras is thus compelled to depend for its supply upon importation. North of the Ganges, the only extensive fields are to be found in the outlying Province of Assam. There, in the Khasi and Jaintia Hills, mines have been worked on a small scale for many years, but the aggregate of the deposits is insignificant, and the difficulties of carriage almost insurmountable. Still farther away, in the frontier District of Lakhimpur, a large coal field of excellent quality was discovered at Mákum, and a private company has been established with a view to open out the field, by means of a railway. The company obtained a lease of the coal beds for a period of twenty years, and a light railway has been constructed to the mines. Operations have not yet been carried sufficiently far to justify any forecast as to the profitable work.

¹ For a full account of the Ranigunj coal field, see article RANIGUNJ in *The Imperial Gazetteer*, and for its geological aspects, see a subsequent chapter.

ing of these deposits. In 1883-84, the out-turn from the Mákuṃ mines was about 450 tons a week; but the company hopes to increase the out-turn to 3000 tons a week, which it is estimated will allow the mines to be worked at a fair profit.

Dárjiling,
Punjab.

Coal is also found in the neighbourhood of Dárjiling, and in the Salt Range of the Punjab.

The four
great coal-
fields.

Apart from these outlying beds, the central coal-fields of India have been divided by Mr. Blanford, of the Geological Survey, into the four following groups:—(1) The Dámodar valley, including both Rániganj and Karharbári, which yields at least nine-tenths of all the coal as yet produced in India, and finds a ready market at Calcutta. (2) The Chutiá Nágpur group, extending over a wide area of mountainous and difficult country, as yet but imperfectly explored. (3) The Narbadá valley, south of the Sátputra range, where actual borings have hitherto proved disappointing, except in the case of the Mohpání colliery, which is connected by a short branch with the main line of the Great Indian Peninsula Railway. (4) The Godávári valley, where coal has been traced from Nágpur southwards as far as Ellore: In this coal-field the only successful works are at Warorá:

Future of
Indian
coal.

Of the future of Indian coal it is difficult to speak with certainty. On the one hand, the demand is constant, and increases with the construction of every fresh mile of railway, and every new factory. On the other hand, the quality is distinctly inferior to English coal, which comes out to India at a low freight—almost at ballast rates. Rániganj coal, which is the best of the Indian coals, can do only from one-half to two-thirds of the duty performed by the same amount of English coal. It contains a low proportion of fixed carbon, and more than three times the average percentage of ash.

Indian
salt.

Its three
sources.

Salt, an article of supreme necessity to the Indian peasant, who eats no butcher's meat, except a festival goat or kid at rare intervals, is derived from three main sources, exclusive of importation from Europe.¹ (1) By evaporation from seawater along the entire double line of seaboard from Bombay to Orissa, but especially in Gujarát and on the Coromandel coast. (2) By evaporation from inland salt lakes, of which the Sámbar Lake in Rájputána affords the chief example. The right of working this lake was leased by Government in 1870 from the Maharájas of Jaipur and Jodhpur, within whose territories it is situated, and who are paid a royalty upon the out-turn. (3)

¹ For the administrative aspects of Indian salt, see *ante*, chap. xvi.; and for its geological aspects, *post*, chap. xxii.

By quarrying solid hills of salt in the north-east of the Punjab The list is the only source in which salt in India can be said to exist as a mineral. It occurs in solid cliffs, which for extent and purity are stated to have no rival in the world. The Salt Range runs across the two Districts of Jehlam (Jhelum) and Shahpur, from the bank of the Jehlam river to Kálabagh in Binnu District. Similar deposits are found beyond the Indus in Kohat District, where the salt is of two kinds, red and green, and in the Hill State of Mandi bordering on Kangra District. The salt is found in the red marls and sandstones of the Devonian group. In some cases it can be obtained from open quarries, but more generally it is approached by regular mining by pick and blasting, through wide galleries. The principal mine is at Kheura in Jehlam (Jhelum) District, now called after Lord Mayo. The total annual outturn in the Punjab is returned at about 50 000 tons, yielding in average net revenue to Government of from £300,000 to £350,000.

In Southern India, salt made by evaporation is almost universally consumed. Lower Bengal, and especially Eastern Bengal, use salt imported from Cheshire, at low rates of freight, and paying the excise duty at Calcutta or other port of entry. In Orissa and South Western Bengal, both imported salt and salt made by solar evaporation are consumed, the solar salt being alone considered pure for religious purposes or for the priests.

India has almost a monopoly of the supply of natural saltpetre upon which Europe largely depends for the manufacture of gunpowder. It occurs with other saline substances as a white efflorescence upon the surface of the soil in many parts of the country, especially in the upper valley of the Ganges. Its preparation leaves common salt as one of the residuary products, and fiscal restraints have accordingly tended to limit the manufacture to the most remunerative region, which is found in North Behar.

The system of saltpetre manufacture is simple, and is entirely in the hands of a special caste of natives, called Nunjás, who are conspicuous for their capacity of enduring hard work. As is the case with most Indian industries, they work under a system of money advances from middle men, who are themselves sub-contractors under large central houses of business. In former times, the East India Company engaged in the manufacture on its own account, and when it gave up its private trade, the works were taken over by European firms.

But these have in their turn retired from the business, which is now in a state of decline (almost killed in Southern India), partly owing to the general fall in price, and partly to the restrictions imposed by the salt preventive department.

Process
of manu-
facture.

The manufacturing season begins with the cold season in November. The presence of saltpetre in the soil is revealed by efflorescence after a heavy fall of rain. This earth is scraped together, and first placed in a large vessel, through which water is filtered. The brine is then boiled in pots, and crude saltpetre mixed with common salt is the result. The proportion of salt to saltpetre is said to be about one-sixth. The sale of this salt is prohibited under stringent penalties. The crude saltpetre is now handed over to the refiners, who work on a larger scale than the Nuniyás. It is again subjected to a process of boiling in large iron boilers of English manufacture, and is allowed to crystallize gradually in open wooden troughs. In refining, it loses nearly one-half its weight, and is now ready for the market. In 1873, the single District of Tírhút contained 22,528 filters, and 305 refineries.

Exports of
saltpetre.

The exports of saltpetre from Calcutta are fairly constant, averaging about 450,000 cwts. a year, of which one-half goes to the United Kingdom. More than two-thirds of the total comes from Behar, chiefly from the Districts of Tírhút, Sárán, and Champáran, though Patná is the railway station for despatch to Calcutta. Cawnpur, Gházipur, Allahábád, and Benares, in the North-Western Provinces, send small quantities; while a little comes from the Punjab.

Indian
gold.

Although silver has ever been the currency of India in historical times, that metal is nowhere found in the country, nor in the adjoining States of Central Asia. Gold, on the other hand, exists in many parts of India, and probably in large quantities. The 'Ophir' of King Solomon has been identified by some scholars with the Malabar coast. However that may be, India claims to rank as a gold-producing country. Many hill streams are washed for gold, alike in the extreme south, in the central plateau, and on the north-east and north-west frontiers. Gold-washing is everywhere in India a miserable business, affording the barest livelihood; but the total amount of gold obtained cannot be insignificant.

Gold-
mining in
Madras.

In recent years, attention has been prominently drawn to the possibility of extracting gold from the quartz formation of Southern India, which bears many points of resemblance to

the auriferous quartz reefs of Australia. The principal localities are in the Wainád (Wynaad) Sub-division of the Nilgiri District, and in Kolar District of Mysore. Gold washing has always been practised here, and the remains of old workings show that at some unknown period operations have been conducted on a large scale. Since about 1870, individual pioneers have been prospecting in this region. Crushing the quartz by rude native methods, they proved that it contained a larger proportion of gold than is known to give a profit in Australia. These experiments on the southern ends of six reefs yielded an average of 7 dwts per ton of quartz, rising in one case to 11 dwts. The best assay of the gold showed a fineness of slightly over 20 carats. In 1879, Government summoned a practical mining engineer from Australia, whose report was eminently hopeful. He described the quartz reefs as of great extent and thickness and highly auriferous. One reef in Kolar, laid bare 100 feet longitudinally, had given an average of 1 oz of gold per ton. In order to attract capital, Government proposed to grant mining leases at a dead rent of Rs 5 (10s) per acre, subject to no royalty or further tax. Several English companies with large capital entered the field, and the reports of their professional advisers held forth high hopes of success. Those hopes have not, however, been yet realized. Gold mining in Southern India is in a depressed state, although some of the operations again hold out promise of success (1885).

The other Indian metals comprise copper, lead, and tin. Other metals
Copper exists in many parts of the country in considerable quantities. The richest mines are in the lower ranges of the Copper
Himálayas, from Dárljīng westward to Kumáun. The ore occurs in the form of copper pyrites, often accompanied by mundic, not in true lodes, but disseminated through the slate and schist. The miners are almost always Nepális, and the remoteness of the situation has deterred European capital. Nepáli
The extent of abandoned workings shows that these mines have been known and worked for many years. The best seams show a proportion of copper slightly above the average of Cornish ore, but the ordinary yield is not more than about 4 per cent.

The mines resemble magnified rabbit holes, meandering 'Rabbit
passages being excavated through the rock with little system hole'
The tools used are an iron hammer and chisel, with some mines
times a small pick. After extraction, the ore is pounded, washed, and smelted on the spot. The price obtained

for the metal is Rs. 2. 8. per 3 *seers*, or at the rate of about 10d. a pound. Copper-ore, of fair purity and extending over a considerable area, also occurs in Singbhúm District of Chutiá Nágpur, where there are many deserted diggings and heaps of *scoriæ*. In 1857, a company was started to reopen the workings at these mines; but although large quantities of ore were produced, the enterprise did not prove remunerative, and was finally abandoned in 1864. A similar attempt to work the copper found in Nellore District in Madras also ended in failure.

Singbhúm
copper.

Nellore.

Lead. Lead occurs, in the form of sulphuret or galena, along the Himálayas on the Punjab frontier, and has been worked at one place by an English company. Tin is confined to the Burmese peninsula. Very rich deposits, yielding about 70 per cent. of metal, occur over a large extent of country in Mergui and Tavoy Districts of the Tenasserim Division. The ore is washed and smelted, usually by Chinese, in a very rough and unscientific way. Recent experiments by a European firm tend to show that the deposits, although rich and extensive, are not sufficiently deep to repay more elaborate processes.

Tin.

Antimony. Antimony, in the form of *surmá*, largely used by the natives as a cosmetic for the eyes, is chiefly derived from the hill States of the Punjab. It is also found in Mysore and Burma. The minerals of Rájputána have not yet been thoroughly investigated; but they include an ore of cobalt, used for colouring enamel.

Cobalt.

Petroleum, Petroleum is produced chiefly in Independent Burma, but it has also been found in British Burma, in Assam, and in the Punjab. Near the village of Ye-nan-chaung in Upper in Burma; Burma, on the banks of the Irawadi, there are upwards of 100 pits or wells with a depth of about 250 feet, from which petroleum bubbles up in inexhaustible quantities. The annual yield in 1877 was estimated at 11,000 tons, of which a considerable quantity was exported. Petroleum wells are also found in the British Districts of Akyab, Kyauk-pyu (Kyauk-hpyu), Pegu, and Thayet-myo, which first attracted British capital with most promising results in 1877.

Oil-refin-
ing in
Búrma.

Two private oil-refining companies having obtained a lease from Government, under favourable conditions, of certain areas at Minbyin in Ramri island, Kyauk-pyu District, are working a number of wells by means of steam boring machinery, under the superintendence of Canadian experts, with satisfactory results. The oil when refined is of a high quality; but

Hills in Assam, known as 'Sylhet lime,' and from the Susuniá quarries in Bánkura District. Except for occasional beds of *kankar*, the lower valley of the Ganges is absolutely destitute of stone; nor does the alluvial soil afford good materials for brickmaking or fine pottery. But a European firm has recently established large pottery and cement works at Rániganj in Bardwán, which employ about 500 hands, and carry out contracts for drainage pipes and stoneware. These works are annually increasing in importance and value.

The centre of the peninsula, and the hill country generally, abounds in building-stone of excellent quality, which has been used locally from time immemorial. Among the finest stones may be mentioned—the pink marble of Rájputána, of which the historical buildings at Agra were constructed; the trap of the Deccan; the sandstone of the Godávári and the Narbadá; and the granite of Southern India. Quarries of slate are scattered through the peninsula, and sometimes worked by European capital. Mica and talc are also quarried to make ornaments. Among the hills of Orissa and Chutiá Nágpur, household vessels and ornaments are skilfully carved out of an indurated variety of potstone.

Precious stones. Despite its legendary wealth, which is really due to the accumulations of ages, India cannot be said to be naturally prolific in precious stones. Under the Muhammadan rule, Diamonds, diamonds were a distinct source of State revenue; but at the present day, the search for them, if carried on anywhere in British territory, is too insignificant an occupation to have attracted the notice of Government. The name of Golconda has passed into literature; but that city, once the Musalmán capital of the Deccan, was rather the home of the diamond-cutters than the actual source of supply. It is believed that the far-famed diamonds of Golconda actually come from the sandstone formation, which extends across the eastern borders of the Nizám's Dominions into the Madras Districts of Kistna and Godávári. A few worthless stones are still found in this region.

in Sambalpur; Sambalpur, on the upper channel of the Mahánadi river in the Central Provinces, is another spot once famous for diamonds. In the last century, a British officer was despatched to Sambalpur by Clive to arrange for remittances home by means of Sambalpur diamonds. As late as 1818, a stone is said to have been found here weighing 84 grains and valued at £500. The river valleys of Chutiá Nágpur are also known

to have yielded a tribute of diamonds to their Muhammadan conqueror

At the present day, the only place where the search for diamonds is pursued as a regular industry is the Native State of Panna (Punnah) in Bundelkhand. The stones ^{in Bun} are found by digging down through several strata of gravelly ^{dellkhand} soil, and washing the earth. Even here, however, the pursuit is understood to be unremunerative, and has failed to attract European capital.

About other gems very little information is available. The town of Cambay in Gujarât (Guzerat) is celebrated for its ^{Carne} carving of carnelian, agate, and onyx. The stones come from ^{hians} the neighbourhood of Ratanpur, in the State of Rajpipla. They are dug up by Bhil miners, and subjected to a process of burning before being carved. The most valued colour for carnelians is red, but they are also found white and yellow. Lapis lazuli is found in the mountains of the north, and is freely used in the decoration of temples and tombs.

Inferior pearl fisheries are worked off the coast of Madura ^{Pearl} District in the extreme south, and in the Gulf of Cambay, ^{fisheries} but the great majority of Indian pearls come either from Ceylon (which is also rich in other gems) or from the Persian Gulf. In the year 1700, the Dutch obtained a lease of all the pearl fisheries along the Madura coast, and sublet the right of fishing to native boatmen, of whom 700 are said to have taken licences annually at the rate of 60 *cus* per boat.

We have now sketched the physical aspects of India, its ^{Scientific} past history, and its present administration and condition ^{branches} under British rule. It remains to briefly deal with the topics ^{of the} of scientific interest connected with the country ^{subject} its material framework or geology, its climatic conditions, or meteorology, its animal and vegetable products, and the health statistics of its population. Each of these subjects forms the subject of many elaborate volumes, and the adequate treatment of any one of them would demand a body of scientific condutors not available to the author of this work. But some account of them may be useful for administrative purposes.

The following pages are offered, not for the instruction of ^{Scope} specialists, but to the general reader who wishes to study ^{of the} India in all its various aspects. In previous sections, the ^{following} author has not hesitated to repeat himself when dealing with ^{chapters.} Indian products, such as opium, cotton, and salt, first from

the administrative and then from the economic point of view. For he believes that such repetitions are convenient to many who desire a view of the subject under each head. In like manner, the following sections will not shrink from repetitions, in referring to certain productions, such as coal, iron, or forests, in their scientific aspects.

CHAPTER XXII.

GEOLOGY OF INDIA

FOR geological purposes British India may be mapped out into the four geographical divisions of—the Himálayan region, the Indo Gangetic plain, Peninsular India, and Burma¹

THE HIMALAYAN REGION —The geology of this tract is more complex and less fully known than that of the Peninsular area. Until the ground has been carefully gone over by the Geological Survey many points must remain doubtful, and large areas of the Himálayas (Nepál and Bhután) are still inaccessible to Europeans. The oldest rock of the Himálayas is a gneiss, differing in character from the gneiss of the Peninsula, and from that of Assam and Burma. The Himalayan gneiss is usually white and grey, its felspar orthoclase and albite, it contains much mica and mica schist, and is more uniform in character than the gneiss of the Peninsula. The latter is usually pink, its felspar being orthoclase and oligoclase, it contains little mica schist, but often has quartzite and hornblendic rock. Hornblende occurs in the syenitic gneiss of the Northern Himalayan (or Ladakh) range.

The Central Himálayan region may be described as consisting of two gneissic axes, with a trough or synclinal valley between them, in which fossiliferous beds have been deposited and are now preserved. The gneiss of the southern or main axis (the 'central gneiss' of Dr Stoliczka) is the oldest, that of the northern or Ladakh axis comes next in age. The gneiss of the Ladakh axis is generally syenitic, or is that variety of the Himalayan gneiss already described as containing hornblende. It is probably an extremely altered condition of ordinary marine sediment. The gneiss of the central axis is the ordinary kind, it is penetrated by granite, which ranges along some of the highest peaks. Between these two gneissic

¹ This section is based upon the official *Manual of the Geology of India*, by Messrs H B Medlicott and W T Blanford, 2 vols, Government Press, Calcutta, 1879. Mr W Topley, of the English Geological Survey, conducted the preliminary condensation.

axes occurs the basin-shaped valley, or the Hundes and Zanskar synclinal. In this valley, fossiliferous rocks are preserved, giving representatives of the Silurian, Carboniferous, Triassic, Jurassic, and Cretaceous formations. All these seem there to have followed each other without important breaks or unconformities; but after the deposition of the Cretaceous rocks of the Himálayan region, important changes appear to have taken place in its physical geography. The Nummulitic (Eocene) strata were laid down on the eroded edges of some of the older beds, and in a long trough within the Silurian gneiss of the Ladákh axis.

Lower
Himá-
layas.

On the south of this true Himálayan region there is a band of country known as the Lower Himálaya, in which the beds are often greatly disturbed, and even completely inverted, over great areas; the old gneiss apparently overlying the sedimentary rocks. This Lower Himálayan region is about 50 miles wide, and consists of irregular ridges, varying from 5000 to 8000 feet in height, and sometimes reaching 12,000 feet. Resting upon the gneiss, but often through inversion apparently underlying it, in the neighbourhood of Simla, is a series of unfossiliferous beds (schists, quartzites, sandstones, shales, limestones, etc.) known in descending order as the Krol, Infra-Krol, Blaini, and Infra-Blaini beds. In the Krol beds is a massive limestone (Krol limestone) probably representing the limestone of the Pir Panjál range, which is most likely of Carboniferous age. The Blaini and Infra-Blaini beds are probably Silurian.

Krol
limestone.

Sub-
Himá-
layas.

The Lower Himálayan range ends at the Sutlej valley, west of which the continuation of the central range is followed immediately by the third or sub-Himálayan range. This occurs almost always on the south of the Lower Himálayas, and is composed of later Tertiary rocks (Siwálíks, etc.), which stretch parallel with the main chain. Generally, the sub-Himálayas consist of two ranges, separated by a broad, flat valley (*dún* or 'doon'); the southern slope, overlooking the great Indo-Gangetic plain, is usually the steepest. Below Náini Tál and Dárjiling (Darjeeling), the sub-Himálayan range is wanting; on the Bhután frontier the whole range is occasionally absent, and the great alluvial plain slopes up to the base of the Lower Himálayan region.

Siwálík
beds.

It is within the sub-Himálayan range that the famous Siwálík beds occur, long known for their vast stores of extinct mammalia. Of about the same age are the Manchhar beds of Sind, which also contain a rich mammalian fauna. The Lower Manchhars

probably correspond to the Náhan beds, the lowest of the Siwálíks, they rest upon the Gaj beds, which are probably Upper Miocene. From this it would seem that the lowest Siwálíks are not older than Upper Miocene. The higher Siwálík beds are considered by Mr W. T. Blanford to be Pliocene, and to this later period he also refers the mammalian beds of Pikermi in Greece. These have a large number of fossils in common with the Siwálíks, but they contain, at their base, a marine band with Pliocene shells. The Manchhar and Siwálík beds are chiefly of fresh water origin.

The Salt Range in the north west of the Punjab has, in addition to its economic value, a special geological importance. Representatives of most of the great European formations of Silurian and later epochs are found in it, and throughout the vast length of time represented by these formations there is here no direct evidence of any important break in succession, or unconformity. The lowest beds (salt marl, probably Silurian) and the highest (Siwálíks) are found through the range. But the others cannot be traced continuously throughout, some occur well developed in one place, some in another. All the principal fossiliferous beds of the Jurassic, Triassic, and Carboniferous formations are confined to the western part of the range.

THE INDO-GANGETIC PLAIN covers an area of about 300,000 square miles, and varies in width from 90 to nearly 300 miles. It rises very gradually from the sea at either end. The lowest point of the watershed between the Punjab rivers and the Ganges is about 924 feet above sea level. This point, by a line measured down the valley, but not following the winding of the river, is about 1050 miles from the mouth of the Ganges and 850 miles from the mouth of the Indus, so that the average inclination of the plain, from the central watershed to the sea, averages only about 1 foot per mile. It generally exceeds this near the watershed, but there is here no ridge of high ground between the Indus and the Ganges, and a very trifling change of level would often turn the upper waters of one river into the other. It is not unlikely that such changes have in past time occurred. Towards the sea, the slope becomes almost imperceptible.

There is no evidence that the Indo Gangetic plain existed as such in pre-Tertiary times. The alluvial deposits made known by the boring at Calcutta, have already been described in

Its alluvial deposits. sufficient detail.¹ They prove a gradual depression of the area through the later Tertiary times. There are peat and forest beds, which must have grown quietly at the surface, alternating with deposits of gravel, sand, and clay. The thickness of the delta deposit is unknown; 481 feet was proved at the bore hole, but probably this represents only a very small part of the deposit. Outside the delta, in the Bay of Bengal, is a deep depression known as the 'swatch of no ground'; all around it the soundings give only 5 to 10 fathoms, but they very rapidly deepen to over 300 fathoms. The sediment seems to be carried away from this hole by the set of the currents; so that it has remained free from silt whilst the neighbouring sea-bottom has gradually been filled up. If so, the thickness of the alluvium is at least 1800 feet, and may be much more.

Its geological history.

The Indo-Gangetic plain dates back to Eocene times; the origin of the *Himālayas* may be referred to the same period. Numerous minor disturbances occurred in the area which is now Northern India during Palæozoic and Secondary times, but the great disturbance which has resulted in the formation of the existing chain of the *Himālayas* took place after the deposition of the Eocene beds. Disturbances even greater in amount occurred after the deposition of the Pliocene beds. The Eocenes of the sub-*Himālayan* range were deposited upon uncontorted Palæozoic rocks, but the whole has since been violently contorted and disturbed. There are some indications that the disturbing forces were more severe to the eastward during middle Tertiary times, and that the main action to the westward was of later date. It seems highly probable that the elevation of the mountain ranges and the depression of the Indo-Gangetic plain were closely related. This view gains some support from a glance at the map, where we see that the curves of the great mountain chains are strictly followed by those of the great alluvial plain. Probably both are due to almost contemporary movements of the earth's crust; these movements, though now of greatly diminished intensity, have not wholly ceased. The alluvial deposits prove depressions to have occurred in quite recent geological times; and within the *Himālayan* region earthquakes are still common, whilst in Peninsular India they are rare.

Peninsular India.

PENINSULAR INDIA.—The oldest rocks here consist of gneiss, in three tracts:—throughout a very large part of Bengal and

¹ *Vide ante*, chap. i. p. 26.

Madras, extending to Ceylon, among the Aravalli ranges, and in Bundelkhand. Of these formations, the gneiss of Bundelkhand is known to be the oldest, because the oldest Transition rocks rest upon it, whereas the same Transition rocks are altered and intersected by granitic dykes which proceed from the gneiss of the other tracts. The Transition rocks are of great but unknown age. The Vindhyan rocks which succeed them are of very old Palæozoic age, perhaps pre-Silurian. Yet long before the earliest Vindhyan rocks were laid down, the Transition rocks had been altered and contorted. In more recent times there have been local disturbances, and large faults have in places been found, but the greater part of the Peninsular rocks are only slightly disturbed, and the most recent of the great and widespread earth movements of this region date back to pre-Vindhyan times.

The Vindhyan series are generally sharply marked off from older rocks, although in the Godavari valley there is no well defined line between these and the Transition rocks. The Vindhyan beds are divided into two groups. The Lower, with an estimated thickness of only 2000 feet, or slightly more, cover a large area,—extending with but little change of character, from the Son (Soane) valley in one direction to Cuddapah, and in a diverging line to near Bijapur—in each case a distance of over 700 miles. The Upper Vindhyans cover a much smaller area, but attain a thickness of about 12,000 feet. The Vindhyans are well stratified beds of sand stone and shale, with some limestones. As yet they have yielded no trace of fossils, and their exact age is consequently unknown. So far as the evidence goes, it appears probable that they are of very ancient Palæozoic age, perhaps pre-Silurian. The total absence of fossils is a remarkable fact, and one for which it is difficult to account, as the beds are for the most part quite unaltered. Even if they are entirely of fresh water origin, we should expect that some traces of life from the waters or neighbouring land would be found.

The Gondwana series is in many respects the most interesting and important of the Indian Peninsula. The beds are almost entirely of fresh water origin. Many sub-divisions have been made, but here we need only note the main division into two great groups—Lower Gondwanas, 13,000 feet thick, Upper Gondwanas, 11,000 feet thick. The series is mainly confined to the area of country between the Narbadá and the Son (Soane) on the north, and the Kistna (Krishna) on

the south ; but the western part of this region is in great part covered by newer beds. The lowest Gondwánas are very constant in character, wherever they are found ; the upper numbers of the lower division show more variation, and this divergence of character in different Districts becomes more marked in the Upper Gondwána series. Disturbances have occurred in the lower series before the formation of the upper.

Gondwána
fossils.

The Gondwána beds contain fossils which are of very great interest. In large part these consist of plants which grew near the margins of the old rivers, were carried down by floods, and deposited in the alluvial plains, deltas, and estuarine areas of the old Gondwána period. So vast was the time occupied by the deposition of the Gondwána beds, that great changes in physical geography and in the vegetation repeatedly occurred. The plants of the Lower Gondwánas consist chiefly of acrogens (*Equisetaceæ* and ferns) and gymnogens (cycads and conifers), the former being the more abundant. The same classes of plants occur in the Upper Gondwánas ; but there the proportions are reversed, the conifers, and still more the cycads, being more numerous than the ferns, whilst the *Equisetaceæ* are but sparingly found. But even within the limits of the Lower Gondwána series there are great diversities of vegetation, three distinct floras occurring in the three great divisions of that formation. In many respects the flora of the highest of these three divisions (the Páñchet group) is more nearly related to that of the Upper Gondwánas than it is to the other Lower Gondwána floras.

Páñchet
group.

Tálcher
group.

One of the most interesting facts in the history of the Gondwána series is the occurrence near the base (in the Tálcher group) of large striated boulders in a fine mud or silt, the boulders in one place resting upon rock (of Vindhyan age) which is also striated. There seems good reason for believing that these beds are the result of ice-action. They probably nearly coincide in age with the Permian beds of Western Europe, in which Professor Ramsay long since discovered evidence of glaciation. But the remarkable fact is that this old ice-action occurred within the tropics, and probably at no very great height above the sea.

Dámodar
series and
coal-fields.

The Dámodar series, the middle division of the Lower Gondwánas, is the chief source of coal in Peninsular India, yielding more of that mineral than all other formations taken together. The Karharbári group is the only other coal-bearing formation of any value. The Dámodars are 8400 feet thick in the Rání-

ganj coal field, and about 10,000 feet thick in the Sâtpura basin. They consist of three divisions, coal occurs in the upper and lower, ironstone (without coal) in the middle division. The Rânigany coal field is the most important in India. So far as yet known, it covers an area of about 500 square miles, running about 18 miles from north to south, and about 39 miles from east to west, but it extends farther to the east under the laterite and alluvium. It is traversed by the Damodar river and also the road from Calcutta to Benares and by the East Indian Railway. From its situation and importance, this coal field is better known than any other in India. Much has been learnt concerning it since the last examination by the Geological Survey, especially from the recent reports by Mr H. Bauermann.

The upper or Rânigany series has eleven seams, with a total thickness of 120 feet, in the eastern district and thirteen seams, 100 feet thick, in the western district. The average thickness of the seams worked is from 12 to 18 feet, but occasionally a seam reaches a great thickness—20 to 80 feet. The lower or Barâkhar series (2000 feet thick) contains four seams, of a total thickness of 69 feet. Compared with English coals, those of this coal field are of a poor quality, they contain much ash, and are generally non-coking. The seams of the lower series are the best, and some of these at Sânktonia, near the Barâkhar river, are fairly good for coke and gas.

The best coal in India is in the small coal field at Karharbari. The beds here are lower in the series than those of the Rânigany field, they belong to the upper part of the Tâlcher group, the lowest of the Gondwâna series. The Karharbari coal beds cover an area of about 11 square miles, and have three seams, varying from 9 to 33 feet thick. The lowest seam is the best, and it is nearly as good as English steam coal. This coal field, now largely worked, is the property of the East Indian Railway, which is thus supplied with fuel at a cheaper rate than any other railway in the world. Indian coal usually contains phosphoric acid, which greatly lessens its value for iron smelting.¹

The Dâmodar series, which, as we have seen, is the chief source of coal in India, is also one of the most important

¹ The economic aspects of Indian coal have been dealt with in the chapter on Mines and Minerals. For full accounts of the Indian coal fields see articles RÂNIGANY, KARHARBARI, etc., in *The Imperial Gazetteer of India*.

sources of iron. The ore occurs in the middle division, coal in the highest and lowest. The ore is partly a clay ironstone, like that occurring in the coal-measures of England, partly an oxide of iron or hæmatite. It generally contains phosphorus, which prevents its use in the preparation of the finer qualities of steel. A similar difficulty attends the use of the Cleveland ore of North Yorkshire. Experiments have been in progress for years in search of a process which shall, in an economical manner, obtain iron from Cleveland ore free from phosphorus, latterly, it is hoped, with some success. If this be so, India will be a great gainer. Excellent iron-ore occurs in the metamorphic rocks south of the Dámodar river. Laterite (see below) is sometimes used as ore. It is very earthy, with a low percentage of metal; but it contains only a comparatively small proportion of phosphorus.¹

The want of limestone for flux, within easy reach, is generally a great drawback as regards iron-smelting in India. *Kāṅkar*. *Kāṅkar* or *ghutīn* (concretionary carbonate of lime) is collected for this purpose from the river beds and alluvial deposits. It sometimes contains as much as 70 per cent. of carbonate of lime; but generally the proportion is much less, and the fluxing value proportionally diminished. The real difficulty in India is to find the ore, the fuel, and the flux, in sufficiently close proximity to yield a profit.

Deccan trap. The enormous mass of basaltic rock known as the Deccan trap, is of great importance in the geological structure of the Indian Peninsula. It now covers an area of about 200,000 square miles, and probably extended in former times over a much wider area. Where thickest, the traps are at least 6000 feet in depth. They form the most striking physical features of the country, many of the most prominent hill ranges being the denuded edges of the basaltic flows. The great volcanic outbursts which produced this trap commenced in the Cretaceous period, and lasted into the Eocene period.

Laterite; Laterite is a ferruginous and argillaceous rock, varying from 30 to 200 feet thick, which often occurs over the trap area, but is also found in other tracts. As a rule, it makes rather barren land; it is highly porous, and the rain rapidly sinks into it. Laterite may be roughly divided into two kinds, high-level; high-level and low-level laterite. The former, which covers a large area of the high basaltic plains, is believed by Mr. R. B.

¹ For the economic aspects of Indian iron, see chapter on Mines and Minerals.

Foot to be very frequently the product of decomposition of the trap, and to have been thus formed in the place where it is now found. Sometimes the high level laterite overlies gneiss or other rocks, and in these cases it has probably been transported. The low level laterite is generally more low level sandy in character, and is often associated with gravels. In most cases this has clearly been carried down to its present position, probably largely by sub aerial action, aided by rains and streams. Possibly in some cases it has been spread out along the coasts by marine action. The low level laterite fringes the coast of the Peninsula, from near Bombay on the west and Orissa on the east, to Cape Comorin. It is not continuous throughout these regions, and it is of very varying width and elevation. The age of the high level laterite is unknown. Its formation probably extended throughout a long period of time, much of which must be of very ancient date, for the laterite, together with the underlying basalt, has suffered extensive denudation.

As regards gems, the geologist comes to the same conclusion as the economist, viz that the precious stones of ancient India were the product of forced labour, and that the search for them in our days can scarcely repay the working expenses. Precious stones

BRITISH BURMA.—The geological structure of Burma comprises three sections—western, middle, and eastern, nearly corresponding to the Divisions of Arakan, Pegu, and Tenasserim. Burma its three sections

The geological groups met with in Arakan and Pegu are, in the ascending order, as follow. The crystalline rocks of Taungngu, age undetermined, comprising beds of different ages. Axial or Arakan group, occupying the northern part of Arakan range, age probably Triassic. Nummulitic group, including the entire range of Arakan, age Eocene or early Tertiary. Pegu group, occupying the whole of the country east of the Irawadi to the Sittaung river, age Miocene or middle Tertiary. Fossil wood group, most largely developed in eastern Pegu, in which fossil wood, in the form of silicified trunks of trees, some of them 30 to 40 feet long is plentifully present, age probably Pliocene or newer Tertiary. Lastly, the Alluvium group, comprising older alluvial deposits in places where the river channels are excavated, and newer alluvial

deposits thrown down on the surface by the Irawadi and other rivers.

Tenasserim.

In geological structure, Tenasserim is entirely distinct from Pegu and Arakan; the groups in ascending order are as follow. The crystalline rocks; age uncertain. Mergui group, largely developed in Mergui District; age perhaps Silurian. Maulmain group, well seen near Maulmain and Amherst; age lower Carboniferous. Tenasserim group, embracing the various coal-fields in the southern part of the Tenasserim Division; age doubtful, but probably Tertiary.

CHAPTER XVIII

METEOROLOGY OF INDIA

THE great peninsula of India, with its lofty mountain ranges and its extensive seaboard, exposed to the first violence of the winds of two oceans, forms an exceptionally valuable and interesting field for the study of meteorological phenomena. But the Department of Government which deals with these phenomena has had to contend with many obstacles, and it is only within the last few years that trustworthy statistics have been obtained from a complete system of registration stations. Every year, however, is now adding to our knowledge of the meteorology of the country, and supplying authentic materials for purposes of comparison and induction.

METEOROLOGICAL GEOGRAPHY — After the general description of the country given at the beginning of this volume, it is only necessary to sketch very briefly the meteorological geography of India. The following paragraphs are condensed from an interesting account in the official *Report on the Meteorology of India* (for 1883), by Mr H F Blanford. Mr Blanford's volume on the *Meteorology of India*, being the second part of *The Indian Meteorologist's Vade Mecum* (Government Press, Calcutta, 1877), should be in the hands of every student.

The great mountain ranges of the HIMALAYAS and the SULAIMANS, which form the northern and north western boundaries of India, have been fully described¹. From the gorge of the Indus to that of the Dihong (Bráhmáputra), a distance of 1400 miles, the Himálayas form an unbroken watershed, the northern flank of which is drained by the upper valleys of these two rivers, while the Sutlej (Sutlaj), starting from the southern foot of the Kailás peak, breaks through the watershed, dividing it into two very unequal portions, that to the north west being the smaller. The average elevation of the higher Himálayas may be taken at not less than 19,000 feet, and therefore equal to

¹ *Vide ante*, chap. I, pp. 3-10, also articles HIMALAYAS and SULAIMAN MOUNTAINS, *The Imperial Gazetteer of India*

Himá-
layan air-
currents.

the height of the lower half of the atmosphere ; indeed, few of the passes are under 16,000 or 17,000 feet. Across this mountain barrier there appears to be a constant flow of air, more active in the day-time than at night, northwards to the arid plateau of Tibet. There is no reason to believe that any transfer of air takes place across the Himálayas in a southerly direction ; unless, indeed, in those elevated regions of the atmosphere which lie beyond the sphere of observation. But a nocturnal flow of cooled air, from the southern slopes, is felt as a strong wind where the rivers debouch on the plains, more especially in the early morning hours. This current probably contributes to lower the mean temperature of the belt of plain country which fringes the mountain zone.

Eastern
Himá-
layas.

The Eastern Himálayas present many points of contrast with the western parts of the range. The slopes of the Sikkim and Bhután Hills, where not denuded for the purposes of cultivation, are clothed with an almost impenetrable forest, which at the lower levels abounds in figs, rattans, and representatives of a tropical humid climate. At higher levels they are covered with oaks, chestnuts, magnolias, pines, etc., of the most luxuriant growth.

Western
Himá-
layas.

In the Western Himálayas, on the other hand, the spurs of the outer ranges are more sparsely clad with forest, especially on their western faces ; and naked precipitous crags are of constant occurrence. The vegetation of the lower and warmer valleys, and of the fringing belt (the Tarái), is comparatively thin, and such as characterizes a warm but dry region. Pines of several species form a conspicuous feature of the landscape at lower levels. It is chiefly the outer ranges that exhibit these contrasted features ; and they depend partly on the difference of latitude, but mainly on that of rainfall. In Sikkim and Bhután this is abnormally copious, and is discharged full on the face of the range. As the chain recedes to the north-west, the greater is the distance to be traversed by the vapour-bearing winds in reaching it, and the more easterly is their direction. For such winds, whether coming from the Bay of Bengal (apparently their principal source) or from the Arabian Sea, turn on reaching the Gangetic valley, and blow more or less parallel to its axis and that of the mountain range.

Vapour-
bearing
winds.

Punjab
frontier.

The country on either side of the Suláimán range is characteristically arid. Dry winds from the desert tracts of Persia and Baluchistán predominate throughout the year. The scanty cultivation on the hills is dependent on the

winter snows, or the rare showers which reach them from the eastward, or the supply of the larger local streams. The lower plains would be uninhabitable but for the fertilizing irrigation furnished by the great river that traverses them.

At the foot of the great Himálayan barrier, and separating it from the more ancient land which now forms the highlands of the peninsula, a broad plain, for the most part alluvial, stretches from sea to sea. On the west, in the dry region, this is occupied partly by the alluvial deposits of the Indus and its tributaries, partly by the saline swamps of Kachchh (Cutch), and the rolling sands and rocky surface of the desert of Jaisalmer (Jeysulmere) and Bikaner, and partly by the more fertile tracts to the eastward. Over the greater part of this region rain is of rare occurrence, and not infrequently more than a year passes by without a drop falling on the parched surface. On its eastern margin, however, in the neighbourhood of the Aravalli Hills, and again in the Northern Punjab, rain is more frequent, occurring both in the south west monsoon, and also at the opposite season in the cold weather. As far north as Sirsa and Multán, the average rainfall does not much exceed 7 inches.

The alluvial plain of the Punjab passes into that of the Gangetic valley without visible interruption. Up or down this plain, at opposite seasons, sweep the monsoon winds, in a direction at right angles to that of their nominal course, and in this way the vapour brought by winds from the Bay of Bengal, is discharged as snow and rain on the peaks and hill sides of the Western Himálayas. Nearly the whole surface is under cultivation, and it ranks among the most productive as well as the most densely populated regions of the world. The rainfall diminishes from 100 inches at the south east corner of the Gangetic delta to less than 30 inches at Agra and Delhi, and there is an average difference of from 15 to 25 inches between the northern and southern borders of the plain.

Eastward from the Bengal delta, two alluvial plains stretch up between the hills that connect the Himálayan system with that of the Burmese peninsula. The first is that of Assam and the Bráhma-putra, long and narrow, bordered on the north by the Himalayas, on the south by the lower plateau of the Gáro, Khási, and Nagá Hills. The second, or Sylhet and Cachar valley, is chiefly occupied by swamps and *jhils*, and separates the Gáro, Khási, and Nagá Hills from those of Tipperah and the Lushái country. The climate of both these plains is

damp and equable, and the rainfall is prolonged and generally heavy, especially on the southern slopes of the hills. A meteorological peculiarity of some interest has been noticed, more especially at the stations of Sibságar and Silchár, viz. the great range of the diurnal variation of barometric pressure, particularly during the cool months of the year. It is the more striking, since at Rúrki, Lahore, and other stations near the foot of the Himálayas, this range is less than on the open plains.

Central
table-land.

Sátpura
range.

The highlands of the peninsula are cut off from the Himálayan ranges by the Indo-Gangetic plain. They are divided into two unequal parts, by an almost continuous chain of hills, loosely known as the Sátpura range, running across the country from west-by-south to east-by-north, just south of the Tropic of Cancer. This chain may be regarded as a single feature, forming the principal watershed of the peninsula. The waters to the north of it drain chiefly into the Narbadá (Nerbudda) and the Ganges; those to the south, into the Tápti, the Godávári, the Mahánadi, and smaller streams. In a meteorological point of view, this central chain of hills is of much importance. Acting together with the two parallel valleys of the Narbadá and Tápti, which drain the flanks of its western half, it gives a more decided easterly and westerly direction to the winds of this part of India, and condenses a tolerably copious rainfall during the south-west moonsoon.

Málwá
plateau.

Aravalli
range.

Separated from this chain by the valley of the Narbadá on the west, and that of the Son (Soane) on the east, the plateau of Málwá and Baghelkhand occupies the space intervening between these valleys and the Gangetic plain. On the western edge of the plateau are the ARAVALLI HILLS, which run from near Ahmadábád up to the neighbourhood of Delhi, and include one hill, Mount Abú, over 5000 feet in height. This range exerts an important influence on the direction of the wind, and also on the rainfall. At Ajmere, an old-established meteorological station at the eastern foot of the range, the wind is predominantly south-west. Both here and at Mount Abú the south-west monsoon rains are a regular phenomenon; which can hardly be said of the region of scanty and uncertain rainfall which extends from the western foot of the range and merges in the Bikáner desert.

Southern
plateau.

The peninsula south of the Sátpura range consists chiefly of the triangular plateau of the Deccan, terminating abruptly on the west in the Sahyádrí range. (Western Gháts), and

shelving to the east (Eastern Ghats) This plateau is swept by the south west monsoon after it has surmounted the western barrier of the Gháts The rainfall is consequently light at Poona and places similarly situated under the lee of the range, and but moderate over the more easterly parts of the plateau The rains however, are prolonged to the north of the Sâtpuras three or four weeks later than in Southern India, since they are brought there by the easterly winds which blow from the Bay of Bengal in October and the early part of November, when the re curved southerly wind ceases to blow up the Gangetic valley, and sets towards the Karnatik This was formerly thought to be the north east monsoon and is still so spoken of by some writers but the rainy wind is really a diversion of the south west monsoon

At the junction of the Eastern and Western Ghats rises the Anamalai bold triangular plateau of the Nilgiris, and to the south of ^{II 11s} them come the Anamalais, Palnis (Pulneys), and Travancore Hills These ranges are separated from the Nilgiris by a broad depression or pass known as the Palghat gap, some 25 miles wide, the highest point of which is about 1500 feet above the sea This gap affords a passage to the winds, which elsewhere are barred by the chain of the Western Gháts The country to the east of the gap receives the rainfall of the south west monsoon, and during the north east monsoon, ships passing Bepur meet with a stronger wind from the land than is felt elsewhere on the Malabar coast According to Captain Newbold, the Palghát gap 'affords an outlet to those furious storms from the eastward which sweep the Bay of Bengal, and, after traversing the peninsula, burst forth through it to the neighbouring sea.'

In the coast strip of low country which fringes the peninsula below the Western Gháts, the rainfall is heavy, the climate warm and damp, the vegetation dense and tropical The steep slopes of the Gháts, where they have not been artificially cleared, are also thickly clothed with forest Southern coast strips

Ceylon should, for meteorological purposes, be included in this survey The country both south and west of the hills which occupy the south centre of the island is very rugged down to the coast The rainfall is here frequent and heavy, and the temperature being high and equable, the vegetation is dense and very luxuriant, such as is characteristic of islands in tropical seas, and also of the coast of Travancore The plains on the east coast are drier, and both in climate and vegetation bear much resemblance to those of the Karnatik Meteorology of Ceylon
Rainy south west region
Drier east coast

The contrast.

When the south-west monsoon is blowing in May and June, and discharging torrents of rain on the forest-clad spurs and slopes that face to windward, the contrast presented by the eastward face of the same hills is very striking, and the two phases of climate are sharply demarcated. Newara Eliya (7000 feet), day after day, and even week after week, lies under a dense canopy of cloud, which shrouds all the higher peaks, and pours down in almost incessant rain. But let the traveller leave the station by the Badulla road, and cross over the main range at a distance of two or three miles from Newara Eliya. As he begins the descent towards Wilson's bungalow, he emerges on a panorama of the grassy downs of the lower hills, bathed in dazzling sunshine; while on the ridge above he sees the cloud-masses ever rolling across from the west, and dissolving away in the drier air to leeward. Hence the east and west coasts of Ceylon are as strongly contrasted in climate as those of the southern extremity of the Indian peninsula.

British Burma.

In British Burma, the western face of the Arakan Yoma hills, like that of the Indian Western Gháts, is exposed to the full force of the south-west monsoon, and receives a very heavy rainfall. At Sandoway, this amounts to an annual mean of 212 inches. It diminishes to the northwards; but even at Chittagong, it amounts to 104½ inches annually.

Upper Burma.

The country around Ava, as well as the hill country of North Burma, is the seat of occasional severe earthquakes, one of which destroyed Ava city in 1839. The general meridional direction of the ranges and valleys determines the direction of the prevailing surface winds; subject, however, to many local modifications. But it would appear, from Dr. Anderson's observations of the movement of the upper clouds; that throughout the year there is, with but slight interruption, a steady upper current from the south-west, such as has been already noticed over the Himalayas. The rainfall in the lower part of the Irawadi valley, viz. the delta and the neighbouring part of the Province of Pegu, is very heavy, about 190 inches; the climate is warm and equable at all seasons. But higher up the valley, and especially north of the Pegu frontier, the country is drier, and is characterized by a less luxuriant vegetation, and by a retarded and more scanty rainfall of about 56 inches.

Observatories.

OBSERVATORIES.—Up to the year 1883, meteorological observatories had been established at 125 stations in India (including British Burma, the Andamans, and Nepal). These

observatories are situated at all elevations, from the highest, LEH (11,502 feet above mean sea level) and CHAKRATA (7051 feet) to SAGAR ISLAND, 25 feet and NEGAPATAM, only 15 feet above mean sea level

OBSERVATIONS — The observations taken at Indian meteorological stations record — (1) temperature of solar and of nocturnal radiation, (2) air temperature, (3) atmospheric pressure, (4) direction and velocity of the wind, (5) humidity, (6) cloud proportion, and (7) rainfall. For full information on each of these subjects, the reader is referred to the valuable and deeply interesting reports of Mr F. Blanford and Mr Elliot printed at the Government Press, Calcutta, and available to all inquirers at the India Office, London.

SOLAR RADIATION — Although, theoretically, differences in the height above ground of the registering thermometer produce little difference in the amount of radiation from the ground, yet the nature of the surface forms an important feature, the action of which differs very considerably in different parts of India, and interferes with an exact comparison of results obtained from different stations. Thus the radiation from the parched, heated, and bare surface of the soil in the North Western Provinces in May, must be considerably greater than from the moist grass covered surface of the soil at the coast stations of Bengal and Western India in the same month.

The following figures are obtained from Bengal stations where the instruments are believed to be accurate and comparable. The yearly average maximum equilibrium temperatures of compared sun thermometers *in vacuo*, varied in these stations from $121\ 5^{\circ}$ F at Dárjiling (much the lowest average) and $131\ 3^{\circ}$ at Goalpára (the next lowest), to $145\ 6^{\circ}$ at Bardwán and $147\ 4^{\circ}$ at Cuttack. The excess of the above over the corresponding maximum shade temperatures was — at Dárjiling, $59\ 1^{\circ}$, at Goalpára, $48\ 4^{\circ}$, at Bardwán, 57° , and at Cuttack, $55\ 8^{\circ}$.

TEMPERATURE OF THE AIR — From the average annual mean temperatures of 117 stations (derived from the means of three or more years), the following figures are taken. In the two following stations in this list, the average mean yearly temperature was over 82° F — Trichinopoly, $82\ 1^{\circ}$, Vizagapatam, $82\ 8^{\circ}$. Both of these stations are in the Madras Presidency. The

80°4'; Port Blair, 80°3'; Bikáner, 80°; False Point, 79°3'; Goa, 79°9'; Cochin, 79°6'; Ságar Island, 78°6'; Deesa, 79°9'; and Calcutta, 77°8'. The mean annual temperature of Bombay is 79°7'. The lowest means are obtained at the hill stations of Dárjiling, 51°8'; Simla, 55°; Murree, 56°1'; and Chakráta, 56°3'. Between these and the next coolest stations is a gap, Masuri (Mussoorie) following with 59°2', Ráníkhét with 60°2', Pachmarhi with 68°7', and Ráwal Pindi with a yearly mean of 69°3'. The highest mean monthly temperatures given are:—94°7' at Jhánsí, in May; 94°4' at Múltán, in June; 93°7' at Lahore, Delhi, and Agra, in June. The lowest monthly means are returned by the four coldest hill stations mentioned above, the figures being:—Murree—January 39°, February 39°4'; Simla—January 40°4', February 41°4'; Chakráta—January 42°3', February 43°4'; Dárjiling—January 39°4', February 41°2'. The mean temperature at Leh in January is 17°1', and in December 23°1' F.

Atmo-spheric pressure. ATMOSPHERIC PRESSURE.—The Meteorological Report for 1883 contains a table showing the annual mean pressure at 111 stations, corrected (except in the case of Madras) to the Calcutta standard, which reads 0·011 inch higher than that of Kew. From that table the following figures are obtained. The mean yearly pressure in inches at the highest stations is:—22·944 at Dárjiling, 23·224 at Chakráta, 23·275 at Simla, 24·059 at Ráníkhét, 26·392 at Pachmarhi, and 26·924 at Bangalore. The greatest annual mean pressures returned are:—29·889 at Cochin, 29·845 at Negapatam, 29·840 at Madras, and 29·821 at Bombay. These pressures are not reduced to the level of the sea.

Wind. WIND.—The general directions of the wind in different parts of the peninsula have already been noticed in the introductory portion of this chapter describing the meteorological geography of the country.

Humidity. HUMIDITY.—The humidity figures given in the Report for 1877 are, according to Mr. Eliot, the Officiating Meteorological Reporter to the Government of India, not generally inter-comparable, as the mean relative humidity is deduced from a varying number of daily observations.

Cloud proportion. CLOUD PROPORTION.—The Report for 1883 gives the averages of estimated cloud proportion for 113 stations in India, an overcast sky being represented by 10 and a clear sky by 0. Some of the extreme figures follow. The average annual proportion of clouded sky is represented at Sibságar by 7·19; at Merkára by 6·68; at Dárjiling by 6·44; at Trichinopoli by

6 04, at Coimbatore by 5 19, at Salem by 4 66 The lowest proportions recorded are — for Jhansi, 1 20, Hyderabad (Sind), 1 69, Multan, 1 66, Dera Ismáíl Khan, 2 04, Sagar (Saugor), in the Central Provinces, 2 43

RAINFALL —The average annual rainfall at 435 stations is Rainfall recorded in the Meteorological Report for 1883, from which the following figures were derived

In the Punjab, the highest average fall (124 91 inches) is at The Dharmsálá, which is situated on the face of the hills, and ^{Punjab} exposed to the full force of the monsoon, the next highest recorded is little more than half that amount, or 71 24 inches, at Sunla The lowest average falls in the Punjab are —5 88 inches at Muzaffargarh, 7 07 at Multan, 7 03 at Dera Ghází Khan, and 8 46 at Dera Ismail Khan All these stations are protected by the Sulámán range from the monsoon

In Rájputana and Central India the minimum is 12 07 ^{Rajputana and Cen} inches at Pachbadra, and the maximum, 63 21, at Mount Abu, ^{tral India} the highest point in this part of India

In the North Western Provinces the heaviest rainfalls are ^{North Western Provinces} at Masurí (94 72 inches), Nainí Tal (91 17), and Dehra (74 91), all of which lie high, the minimum average fall is 25 28 at Muttra, the next lowest figures being 26 06 at Aligarh, 25 66 at Agra, and 25 70 at Bulandshahr—all stations on the plains

In Oudh, the maximum rainfall is at Bahraich, 43 48 inches, Oudh and the minimum at Rai Bareli, 32 18 inches

The following stations of Bengal have an average rainfall of Bengal more than 100 inches —Baxa, 220 91, Jalpáiguri, 129 21, Mongpu, 128 43, Dárlíng, 120 85, and Kuch Behar, 130 89—all at the base of the hills, Noakhálí, 111 75, Dema giri, 112 97, Cox's Bazaar, 141 60, and Chittagong, 104 58, all near the north east corner of the Bay of Bengal The lowest averages are returned by Keunghar, 32 61 inches, Buxar, 39 04, Chhapra, 39 15, and Gayá, 40 29 The average rainfall throughout Bengal is 67 inches

Assam possesses in Cherra Poonjee (Chára Punji) the ^{Assam} station with the largest rainfall in the world Former returns gave the fall at 368 inches, later and fuller returns at 481 80 inches A total fall of 805 inches was reported in 1861, of which 366 were assigned to the single month of July In 1850, Dr Hooker registered 30 inches in twenty four hours, and returned the fall from June to November of that year at 530 inches In the four days 9th to 12th September 1877, 56 19 inches were registered The cause of this extraordinary rainfall is

noticed in the chapter on Physical Geography. The following stations in Assam have also a very high average rainfall:—Silchár, 118·85; Sylhet, 156·12; Dibrugarh, 113·53; and Turá, 123·80. The lowest recorded averages in Assam are at Samaguting (52·58 inches) and Gauhati (69·26 inches), both on the northern side of the hills separating Cachar from Assam.

Central Provinces. In the Central Provinces, the highest average falls are at Pachmarhi, 77·85 inches, and Bálághát, 65·92; lowest averages, Khandwá, 33·29 inches, and Arvi, 35·09 inches.

Bombay. In Bombay, two stations on the Gháts are recorded as having an average rainfall of over 250 inches, viz.:—Malcolm-pet (Mahábleswar), 258·49; and Baura (Fort), 255·28. Next in order come Matherán, with 245·24 inches; Lonauli, with 165·13; Honawár, 138·08; and Igatpuri, Kárwár, Vingúrla, and Ratnágiri, with 124·19, 116·03, 110·89, and 104·55 inches respectively. The lowest average rainfalls recorded in Bombay are:—18·82 inches at Mandargi; 20·97 at Dhulia; and 21·41 at Gokak. The average rainfall in Bombay is 67 inches.

Sind. In Sind, the average rainfall is very low, varying from 16·17 inches at Nagar, and 11·09 at Umárkot, to 4·65 at Shikárpur, and 4·33 at Jacobábád.

Madras. In Madras, the highest local averages recorded are:—132·87 inches at Mangalore; 129·68 at Cannanore; 128·21 at Merkára; 125·66 at Tellicherri; 115·04 at Calicut; and 115·02 at Cochin—all on the west coast. The lightest falls recorded are:—at Bellary, 17·64; Tuticorin (sheltered by the Gháts), 19·44; Gutí (Goody), 21·79; and Coimbatore, 21·34. All these stations lie low. The average fall at the stations on the east coast is about 41 inches. A fair average rainfall for Madras Presidency is 44 inches.

British Burma. The rainfall along the coast of British Burma is heavy, as might be expected, the following averages being recorded:—Sandoway, 212·03 inches; Tavoy, 197·02; Akyab, 197·61; Maulmain, 189·37; Kyauk-pyu, 174·79. The smallest rainfall is at Thayet-myo (47·37) and Prome (53·00), sheltered by the Yoma range.

Port Blair. The rainfall at Port Blair and Nancowry is also heavy, the averages being returned as 118·38 and 108·91 inches respectively.

Sun-spot cycles. **SUN-SPOT CYCLES.**—These alleged cycles have formed the subject of several separate papers, and the results were popularly summed up in a joint article by Mr. Norman

Lockyer and the present author in the *Nineteenth Century* for November 1877. It will therefore suffice here to state the views of the Indian Meteorological Department on the intricate questions involved. The following are the inferences which the meteorology of India appears to suggest, if not to establish. There is a tendency at the minimum sun spot periods to prolonged excessive pressure over India, and at the maximum sun spot periods to an unusual development of the winter rains, and to the occurrence of abnormally heavy snowfall over the Himalayan region (to a greater extent probably in the Western than the Eastern Himalayas). This appears also to be usually followed by a weak south west monsoon. The characteristics of a weak monsoon are, great irregularity in the distribution of the rainfall over the whole of India, and the occurrence of heavy local rainfalls, which tend, by a law of rainfall and of air motion, to recur over the same limited areas. The irregularity of rainfall distribution is often shown by the persistence of dry land winds and the prolonged absence of rain over considerable areas. These areas of drought and famine are partly marked off by nature, depending to a certain extent on the geographical features and position of the district. Thus, the rains are more likely to fall below the amount necessary for cultivation in the dry region of the Deccan or in Upper India, than over the Malabar coast area or the Province of Bengal.

CHAPTER XXIV.

ZOOLOGY AND BOTANY OF INDIA.

Mammals. WILD ANIMALS.—First among the wild animals of India must be mentioned the lion (*Felis leo*), which is recorded to have been not uncommon within historical times in Hindustán

Lion. Proper and the Punjab. The lion is now confined to the *Gir*, or rocky hill-desert and forest of Káthiáwár. A peculiar variety is there found, marked by the almost total absence of a mane; but whether this variety deserves to be classed as a distinct species, naturalists have not yet determined. The lion has now almost entirely disappeared; and the official Gazetteer of Káthiáwár states that there are now (1884) probably not more than ten or a dozen lions and lionesses left in the whole *Gir* forest tract. They are strictly preserved. The former extent of the lion's range, or the degree to which its presence impressed the imagination, may be inferred from the common personal names, Sinh or Singh, Sher, and Haidar, which all signify 'lion.' Sher, however, is also applied to the tiger.

Tiger. The characteristic beast of prey in India is the tiger (*Felis tigris*), which is found in every part of the country from the slopes of the Himálayas to the Sundarban swamps. Sir Joseph Fayrer, the highest living authority on this subject, believes that 12 feet is the maximum length of the tiger, when measured from nose to tip of tail immediately after death. The advance of cultivation, even more than the incessant attacks of sportsmen, has gradually caused the tiger to become a rare animal in large tracts of country; but it is scarcely probable that he ever will be exterminated from India. The malarious *taráí* fringing the Himálayas, the uninhabitable swamps of the Gangetic delta, and the wide jungles of the central plateau, are at present the chief home of the tiger. His favourite food appears to be deer, antelope, and wild hog. When these abound, he does not attack domestic cattle. Indeed, the natives of certain Districts consider the tiger as in some sort their protector, for he saves their crops from destruction by the wild animals on which he feeds. But when

once he develops a taste for human blood, then the slaughter which he works becomes truly formidable

The confirmed man eater, generally an old beast, disabled from overtaking his usual prey, seems to accumulate his tale of victims in sheer cruelty rather than for food. A single tiger is known to have killed 108 people in three years. Another killed an average of about 80 persons per annum. A third caused 13 villages to be abandoned, and 250 square miles of land to be thrown out of cultivation. A fourth, so lately as 1869, killed 127 people, and stopped a public road for many weeks, until the opportune arrival of an English sportsman, who killed him. Such cases are, of course, exceptional, and generally refer to a past period, but they explain the superstitious awe with which the tiger is regarded by the natives.

The favourite mode of shooting the tiger is from the back of elephants, or from elevated platforms (*machans*) of boughs in the jungle. In Central India and Bombay, tigers are shot on foot. In Assam, they are sometimes speared from boats, and in the Himalayas they are said to be ensnared by bird lime. Rewards are given by Government to native *shikaris* for the heads of tigers varying in time and place according to the need. In 1877, 819 persons and 16,137 cattle were reported to have been killed by tigers. On the other side of the account, 1579 tigers were destroyed by native hunters, and £3777 paid in rewards, besides the slaughter by English sportsmen. In 1882, no fewer than 895 persons and 16,517 cattle were returned as killed by tigers. The sum of £4800 was paid during the year to native *shikaris* for the destruction of 1726 tigers.

The leopard or panther (*Felis pardus*) is far more common than the tiger in all parts of India, and at least equally destructive to life. The greatest length of the Indian leopard is about 7 feet 6 inches. A black variety, as beautiful as it is rare, is sometimes found in the extreme south of the Indian peninsula, and also in Java. The cheetah or hunting leopard (*Felis jubata*) must be carefully distinguished from the leopard proper. This animal appears to be a native only of the Deccan, where it is trained for hunting the antelope. In some respects it approaches the dog more nearly than the cat tribe. Its limbs are long, its hair rough, and its claws blunt and only partially retractile. The speed with which it bounds upon its prey, when loosed from the cart, exceeds the swiftness of any other wild mammal. If it misses its first attack, it scarcely ever attempts to follow, but returns to its master. Among

Other
species.

other species of the family Felidæ found in India may be mentioned the ounce or snow leopard (*F. unica*), the clouded tiger (*F. macroscelis*), the marbled tiger cat (*F. marmorata*), the jungle cat (*F. chaus*), and the common viverrine cat (*F. viverrina*).

Wolf.

Wolves (*Canis lupus*) abound throughout the open country, but are rare in the wooded districts. Their favourite prey is sheep, but they are also said to run down antelopes and hares, or rather catch them by lying in ambush. Instances of their attacking man are not uncommon; and in 1882, 278 persons, principally children, besides 8661 cattle, were reported to have been killed by wolves. In 1827, upwards of 30 children were carried off by wolves in a single *parganá* or fiscal division; and the story of Romulus and Remus has had its counterpart in India within recent times. The Indian wolf has a dingy reddish-white fur, some of the hairs being tipped with black. By some naturalists it is regarded as a distinct species, under the name of *Canis pallipes*. Three distinct varieties, the white, the red, and the black wolf, are found in the Tibetan Himalayas.

Fox.

The Indian fox (*Vulpes bengalensis*) is comparatively rare; but the jackal (*Canis aureus*) abounds everywhere, making night hideous by its never-to-be-forgotten yells. The jackal, and not the fox, is usually the animal hunted by the packs of hounds kept by Europeans.

Jackal.

Dog.

The wild dog or *dhole* is found in very many of the wilder jungles of India, including Assam and British Burma. Its characteristic is that it hunts in packs, sometimes containing 30 dogs, and does not give tongue. When once a pack of wild dogs has put up any animal, whether deer or tiger, that animal's doom is sealed. They do not leave it for days, and finally bring it to bay, or run it down exhausted. These wild dogs have sometimes been half domesticated, and trained to hunt for the use of man. A peculiar variety of wild dog exists in the Karen Hills of Burma, thus described from a specimen in confinement. It was black and white, as hairy as a Skye-terrier, and as large as a medium-sized spaniel. It had an invariable habit of digging a hole in the ground, into which it crawled backwards, remaining there all day with only its nose and ferrety eyes visible. Among other dogs of India are the pariah, which is merely a mongrel, run wild and half-starved; the poligar dog, an immense creature peculiar to the south; the greyhound, used for coursing; and the mastiff of Tibet and Bhután.

The striped hyæna (*Hyæna striata*) is common, being found *Hyæna* wherever the wolf is absent. Like the wolf, it is very destructive both to the flocks and to children.

Of bears, the common black or sloth bear (*Ursus labiatus*) *Bear* is common throughout India wherever rocky hills and forests occur. It is distinguished by a white horse shoe mark on its breast. Its food consists of ants, honey, and fruit. When disturbed it will attack man, and it is a dangerous antagonist, for it always strikes at the face. The Himalayan or Tibetan sun bear (*Ursus tibetanus*) is found along the north, from the Punjab to Assam. During the summer it remains high up in the mountains near the limit of snow, but in the winter it descends to 5000 feet, and even lower. Its congener, the Malayan sun bear (*Helarctos malayanus*), is found in British Burma, where also there is a smaller species (*Helarctos eury spilus*), and a very large animal reported to be as big as the American grizzly. There were 114 persons returned as killed by bears in 1882.

The elephant (*Elephas indicus*) is found in many parts of *The Ele India*, though not in the north west. Contrary to what might *phant* be anticipated from its size and from the habits of its African cousin, the Indian elephant is now, at any rate, an inhabitant, not of the plains, but of the hills, and even on the hills it is usually found among the higher ridges and plateaux, and not in the valleys. From the peninsula of India the elephant has been gradually exterminated, being only found now in the primæval forests of Coorg, Mysore, and Travancore, and in the Tributary States of Orissa. It still exists in considerable numbers along the *tardû* or submontane fringe of the Himalayas. The main source of supply at the present time is the confused mass of hills which forms the north east boundary of British India, from Assam to Burma. Two varieties are there distinguished, the *gunda* or tuskier, and the *makna* or *hine*, which has no tusks.

The reports of the height of the elephant, like those of its intelligence, seem to be exaggerated. The maximum is probably 12 feet. If hunted, the elephant must be attacked on foot, and the sport is therefore dangerous, especially as the animal has but few parts vulnerable to a bullet. The regular mode of catching elephants is by means of a *kheda* or gigantic *I let hunt stockade*, into which a wild herd is driven then starved into *catching* submission, and tamed by animals already domesticated. The practice of capturing them in pitfalls is discouraged as cruel and wasteful. Elephants now form a Government monopoly.

throughout India. The shooting of them is prohibited, except when they become dangerous to man or destructive to the crops; and the right of capturing them is only leased out upon conditions.

Elephant
Preserva-
tion Act.

A special law, under the title of 'The Elephants Preservation Act' (No. VI. of 1879), regulates this licensing system. Whoever kills, captures, or injures an elephant, or attempts to do so, without a licence, is punishable by a fine of 500 rupees for the first offence; and by a similar fine, together with six months' imprisonment, for a second offence. In the year 1877-78, a total of 264 elephants were captured in the Province of Assam, yielding to Government a revenue of £3600. In 1882-83, 475 elephants were captured in Assam, yielding a revenue to Government of £8573. In the season of 1873-74, no less than 53 elephants were captured at one time by Mr. Sanderson, formerly the superintendent of the Kheda Department in Mysore, who has made a special study of the Indian elephant, as Sir S. Baker has of the same animal in Ceylon. Although the supply is decreasing, elephants continue to be in great demand. Their chief use is in the timber trade, and for Government transport. They are also bought up by native chiefs at high prices for ostentation. Sixty persons were reported as killed by elephants in 1882.

The Rhin-
oceros.

Of the rhinoceros, four distinct varieties are enumerated, two with a single, and two with a double horn. The most familiar is the *Rhinoceros unicornis*, commonly found in the Brahmaputra valley and its wide swamps. It has but one horn, and is covered with massive folds of naked skin. It sometimes attains a height of 6 feet; its horn, which is much prized by the natives for medicinal purposes, seldom exceeds 14 inches in length. It frequents swampy, shady spots, and wallows in mud like a pig. The traditional antipathy of the rhinoceros to the elephant seems to be mythical. The Javan rhinoceros (*R. sondaicus*) is found in the Sundarbans. It also has but one horn, and mainly differs from the foregoing in being smaller, and having less prominent 'shields.' The Sumatran rhinoceros (*R. sumatrensis*) is found from Chittagong southwards through Burma. It has two horns and a bristly coat. The hairy-eared rhinoceros (*R. lasiotis*) is known from a specimen captured at Chittagong, and sent to the Zoological Gardens, London. Two are at Calcutta.

The wild
Hog.

The wild hog (*Sus scrofa*, *var. indica*) is well known as affording the most exciting sport in the world—'pig-sticking.' It frequents cultivated localities, and is the most mischievous

enemy which the husbandman has to guard against, doing more damage than elephants, tigers, leopards deer, and antelope, all put together. A rare animal, called the pigmy hog (*Porcula salvania*), exists in the *taru* of Nepal and Sikkim, and has been shot in Assam. Its height is only 10 inches, and its weight does not exceed 12 lbs.

The wild ass (*Equus onager*) is confined to the sandy deserts of Sind and Kachchh (Cutch), where, from its speed and timidity, it is almost unapproachable. The wild Ass

Many wild species of the sheep and goat tribe are to be found in the Himálayan ranges. The *Ovis* common and *O. poli* are Tibetan rather than Indian species. The *urial* and the *shapu* are kindred species of wild sheep found respectively in Ladakh and the Suláiman range. The former comes down to 2000 feet above the sea; the latter is never seen at altitudes lower than 12 000 feet. The *barhal*, or blue wild sheep, and the *markhor* and *tahr* (both wild goats) also inhabit the Himálayas. A variety of the ibex is also found there, as well as in the highest ranges of Southern India. The *sarau* (*Nemorædus rubidus*), allied to the chamois, has a wide range in the mountains of the north, from the Himálayas to Assam and Burma. Sheep and Goats

The antelope tribe is represented by comparatively few species, as compared with the great number found in Africa. The antelope proper (*Antelope cervicapra*), the 'black buck' of sportsmen, is very generally distributed. Its special habitat is salt plains, as on the coast line of Gujarát (Guzerat) and Orissa, where herds of 50 does may be seen, accompanied by a single buck. The doe is of a light fawn colour, and has no horns. The colour of the buck is a deep brown black above, sharply marked off from the white of the belly. His spiral horns, twisted for three or four or more turns like a corkscrew, often reach the length of 30 inches. The flesh is dry and unsavoury, but is permitted meat for Hindus, even of the Brahman caste. The four-horned antelope (*Tetraceros quadricornis*) and the gazelle (*Gazella bennettii*) are also found in India. The *chiru* (*Pantholops hodgsoni*) is confined to the Himálayan plateaux. Antelopes

The *nilgai* or blue cow (*Panthus pictus*) is also widely distributed, but specially abounds in Hindustán Proper and Gujarát. As with the antelope, the male alone has the dark blue colour. The *nilgai* is held peculiarly sacred by Hindus, from its fancied kinship to the cow, and on this account its destructive inroads upon the crops are tolerated. Nilgai

The king of the deer tribe is the *sámbhar* or *gerau* (*Cervus*). Deer

aristotelis), erroneously called 'elk' by sportsmen. It is found on the forest-clad hills in all parts of the country. It is of a deep-brown colour, with hair on its neck almost like a mane; and it stands nearly 5 feet high, with spreading antlers nearly 3 feet in length. Next in size is the swamp deer or *bâra-singha*, signifying 'twelve points' (*Cervus duvaucelli*), which is common in Lower Bengal and Assam. The *chital* or spotted deer (*Cervus axis*) is generally admitted to be the most beautiful inhabitant of the Indian jungles. Other species include the hog deer (*Cervus porcinus*), the barking deer or muntjac (*Cervulus muntiac*), and the so-called mouse deer (*Tragulus meminna*). The musk deer (*Moschus moschiferus*) is confined to Tibet.

The Bison. The ox tribe is represented in India by some of its noblest species. The *gaur* (*Bos gaurus*), the 'bison' of sportsmen, is found in all the hill jungles of the country, in the Western Ghâts, in Central India, in Assam, and in British Burma. This animal sometimes attains the height of 20 hands (close on 7 feet), measuring from the hump above the shoulder. Its short curved horns and skull are enormously massive. Its colour is dark chestnut, or coffee-brown. From the difficult nature of its habitat, and from the ferocity with which it charges an enemy, the pursuit of the bison is no less dangerous and no less exciting than that of the tiger or the elephant. Akin to the *gaur*, though not identical, are the *gayâl* or *mithûn* (*Bos frontalis*), confined to the hills of the north-east frontier, where it is domesticated for sacrificial purposes by the aboriginal tribes; and the *tsine* or *banting* (*Bos sondaicus*), found in Burma.

The Buffalo. The wild buffalo (*Bubalus arni*) differs from the tame buffalo only in being larger and more fierce. The finest specimens come from Assam and Burma. The horns of the bull are thicker than those of the cow, but the horns of the cow are larger. A head has been known to measure 13 feet 6 inches in circumference, and 6 feet 6 inches between the tips. The greatest height is 6 feet. The colour is a slaty black; the hide is immensely thick, with scanty hairs. Alone perhaps of all wild animals in India, the buffalo will charge unprovoked. Even tame buffaloes seem to have an inveterate dislike to Europeans.

Rat tribe. The rat and mouse family is only too numerous. Conspicuous in it is the loathsome bandicoot (*Mus bandicota*), which sometimes measures 2 feet in length, including its tail, and weighs 3 lbs. It burrows under houses, and is very

destructive to plants, fruit, and even poultry. More interesting is the tree rat (*Mus arboreus*), a native of Bengal, about 7 inches long, which makes its nest in cocoa nut palms and bamboos. The voles or field mice (genus *Arvicola*) occasionally multiply so exceedingly, as to seriously diminish the output of the local harvest, and to require special measures for their destruction.

The ornithology of India, although it is not considered so rich in specimens of gorgeous and variegated plumage as that of other tropical regions, contains many splendid and curious varieties. Some are clothed in nature's gay attire, others distinguished by strength, size and fierceness. The parrot tribe is the most remarkable for beauty. So various are the species, that no attempt is made here even to enumerate them, but the reader is referred for details to the scientific works on the subject.¹

Among birds of prey four vultures are found, including the common scavengers (*Gyps indicus* and *G. bengalensis*). The eagles comprise many species, but none to surpass the golden eagle of Europe. Of falcons, there are the peregrine (*Falco peregrinus*), the *sham* (*Falco peregrinator*), and the *lagar* (*Falco jugger*), which are all trained by the natives for hawking, of hawks, the *shukara* (*Astur badius*), the sparrow hawk (*Accipiter nisus*), and the crested goshawk (*Astur trivirgatus*). Kingfishers of various kinds, and herons are sought for their plumage. No bird is more popular with natives than the *maina* (*Acridotheres tristis*), a member of the starling family, which lives contentedly in a cage, and can be taught to pronounce words, especially the name of the god Krishna.

Waterfowl are especially numerous. Of game birds, the floriken (*Sypheotides auritus*) is valued as much for its rarity as for the delicacy of its flesh. Snipe (*Gallinago scolopacina*, etc.) abound at certain seasons, in such numbers that one gun has been known to make a bag of 100 brace in a day. Pigeons, partridges, quail, plover, duck, teal, sheldrake, widgeon—all of many varieties—complete the list of small game. The red jungle fowl (*Gallus ferrugineus*), supposed to be the ancestor of our own poultry, is not good eating, and the same may be said of the peacock (*Pavo cristatus*), except when young. The pheasant does not occur in India Proper, but a white variety is found in Burma, and several beautiful species (conspicuously the *manaul*) abound in the Himalayas.

¹ Especially those of Jerdon, Gould, Hume, and Marshall.

Reptiles.

The
'cobra.'

The serpent tribe in India is numerous; they swarm in the gardens, and intrude into the dwellings of the inhabitants, especially during the rainy season. Most are comparatively harmless, but the bite of others is speedily fatal.¹ The cobra di capello—the name given to it by the Portuguese, from the appearance of a hood which it produces by the expanded skin about the neck—is the most dreaded (*Naja tripudians*). It seldom exceeds 3 or 4 feet in length, and is about an inch and a quarter thick, with a small head, covered on the forepart with large smooth scales; it is of a pale brown colour above, and the belly is of a bluish-white tinged with pale brown or yellow. The Russellian snake (*Daboia Russellii*), about 4 feet in length, is of a pale yellowish-brown, beautifully variegated with large oval spots of deep brown, with a white edging. Its bite is extremely fatal. Itinerant showmen carry about these serpents, and cause them to assume a dancing motion for the amusement of the spectators. They give out that they render snakes harmless by the use of charms or music—in reality, by extracting the venomous fangs. But, judging from the frequent accidents, they sometimes seem to dispense with this precaution. All the salt-water snakes in India are poisonous, while the fresh-water forms are innocuous.

Deaths
from
snake-bite.

Sir Joseph Fayrer has demonstrated that none of the reputed antidotes will cure the bite of the cobra, if the snake is full-grown, and if its poison fang is full and be not interfered with by clothing. The most hopeful remedy in all cases of snake-bite is the injection of ammonia. The loss of life from this cause in India is painful to contemplate. But the extermination of snakes is attended with great difficulty, from the great number of the species, the character of the country, the rapid undergrowth of jungle, and the scruples of the people. Something, however, is being effected by the offer of rewards. In 1877, a total of 16,777 persons are reported to have been killed by snakes, as compared with only 819 by tigers. In the same year, rewards to the amount of £811 were given for the destruction of 127,295 snakes. In 1882, a total of 19,519 persons are reported to have been killed by snakes, as compared with 2606 by tigers, leopards, and all other wild beasts. A sum of £1487 was paid in 1882 for the destruction of 322,421 venomous reptiles.

Statistics,
1877;

and 1882.

Crocodile.

The other reptiles include two varieties of crocodile (C.
¹ Sir Joseph Fayrer's *Thanatophidia* is the standard work on Indian snakes. Vincent Richards' *Landmarks of Snake Poison Literature* is an excellent compendium.

porosus and *C. biporcatus*) and the gharial (*Gavialis gangeticus*)
Scorpions also abound

All the waters of India—the sea, the rivers, and the tanks—Fishes swarm with a great variety of fishes,¹ which are caught in every conceivable way, and furnish a considerable proportion of the food of the poorer classes. They are eaten fresh, or as nearly fresh as may be, for the art of curing them is not generally practised, owing to the exigencies of the salt monopoly. In Burma, the favourite relish of *nga pi* is prepared from fish. At Goālandā, at the junction of the Brahmaputra with the Ganges, and along the Madras coast, establishments have been established for salting fish in bond. The indiscriminate slaughter of fry, and the obstacles opposed by irrigation dams to breeding fish, are said to be causing a sensible diminution in the supply in certain rivers. Measures of conservancy have been suggested, but their execution is attended with great difficulty, owing to the habits and the necessities of the poorer population.

Among Indian fishes, the Cyprinidæ or carp family and the Siluridæ or cat fishes are best represented. From the angler's point of view, by far the finest fish is the *mahsir*, found in all hill streams, whether in Assam, the Punjab, or the south. One has been caught weighing 60 lbs., which gave play for more than seven hours. Though called the salmon of India, the *mahsir* is really a species of barbel. One of the richest and most delicious of Indian fishes is the *hilsa*, which tastes and looks like a sort of fat white salmon. It is caught in immense quantities in the rivers of the Bengal delta, and forms a staple article of food in Calcutta. The Bombay and Madras markets are still better supplied by a variety of delicate fishes. But the enhanced price of this important article of native diet throughout the country, the decreased supply, and the ever increasing fineness of the meshes of the nets employed in catching the fry, are matters of grave concern alike to the Government and to the poorer classes of the population.

In this connection may be mentioned the *susu* or Gangetic Dolphin (*Platanista gangetica*), a mammal often erroneously called a porpoise. Both the structure and habits of this animal are very singular. It measures from 6 to 12 feet in

¹ The latest standard works on Indian fishes and their economic aspects are the Reports and official volume by Dr. Francis Day, late Inspector General of Fisheries to the Government of India, available to all inquirers, at the India Office, London.

length, and in colour is sooty-black. Its head is globular, with a long, narrow, spoon-shaped snout. Its eyes are rudimentary, like those of the mole; and its ear-orifices are no bigger than pin-holes. Its dentition, also, is altogether abnormal. It frequents the Ganges and Indus from their mouths right up to their tributaries within the hills. A specimen has been taken at least 1000 miles above Calcutta. Ordinarily its movements are slow, for it wallows in the muddy bed of the river, and only at intervals comes to the surface to blow. The *susu* belongs to the order *Cetacea*; and inquiries have recently been directed to the point whether its blubber might not be utilized in commerce.

Insects.

The insect tribes in India may be truly said to be innumerable; nor has anything like a complete classification been given of them in the most scientific treatises. The heat and the rains give incredible activity to noxious or troublesome insects, and to others of a more showy class, whose large wings surpass in brilliancy the most splendid colours of art. Stinging mosquitoes are innumerable, with moths and ants of the most destructive habits, and other insects equally noxious and disagreeable. Amongst those which are useful are the bee, the silkworm, and the insect that produces lac. Clouds of locusts occasionally appear, which leave no trace of green behind them, and give the country over which they pass the appearance of a desert. Dr. Buchanan saw a mass of these insects in his journey from Madras to the Mysore territory, about 3 miles in length, like a long narrow red cloud near the horizon, and making a noise somewhat resembling that of a cataract. Their size was about that of a man's finger, and their colour reddish. They are swept north by the wind till they strike upon the outer ranges of the Himálayas.

Locusts.

Indian
flora.

FLORA.¹—Unlike other large geographical areas, India is remarkable for having no distinctive botanical features peculiar to itself. It differs conspicuously in this respect

¹ For a general sketch of the flora of India, recourse must still be had to the introductory essay to the *Flora Indica*, published by Hooker & Thomson in 1855. The *Flora of British India*, the preparation of which is in progress at Kew, will comprise descriptions of all the species known to science up to the date of publication. It will form a great national work on the botany of India. For the following paragraphs on the flora, written by Mr. W. T. T. Dyer of Kew, the author is indebted to the courtesy of Messrs. A. & C. Black, publishers of the *Encyclopædia Britannica*.

from such countries as Australia or South Africa. Its vegetation is in point of fact of a composite character, and is constituted by the meeting and blending of the various floras adjoining,—of those of Persia and the south-eastern Mediterranean area to the north west, of Siberia to the north, of China to the east, and of Malaya to the south east. Space does not admit of a minute discussion of the local features peculiar to separate districts, but regarded broadly, four tolerably distinct types present themselves namely, the Himalayan, the North Western, the Assamese or Malayan, and the Western India type.

The upper levels of the Himalayas slope northwards gradually to the Tibetan uplands, over which the Siberian temperate vegetation ranges. This is part of the great temperate flora which, with locally individualized species but often with identical genera, extends over the whole of the temperate zone of the northern hemisphere. In the Western Himalayas, this upland flora is marked by a strong admixture of European species, such as the columbine (*Aquilegia*) and hawthorn (*Crataegus oxyacantha*). These disappear rapidly eastward, and are scarcely found beyond Kumaon.

The base of the Himalayas is occupied by a narrow belt forming an extreme north western extension of the Malayan type described below. Above that, there is a rich temperate flora which in the eastern chain may be regarded as forming an extension of that of Northern China, gradually assuming westwards more and more of a European type. *Magnolia*, *Aucuba*, *Abelia* and *Skimmia* may be mentioned as examples of Chinese genera found in the Eastern Himalayas, and the tea tree grows wild in Assam. The same coniferous trees are common to both parts of the range. *Pinus longifolia* extends to the Hindu Kush, *P. excelsa* is found universally except in Sikkim, and has its European analogue in *P. Peuce*, found in the mountains of Greece. *Abies Smithiana* extends into Afghanistan, *Abies Webbiana* forms dense forests at altitudes of 8000 to 12,000 feet, and ranges from Bhutan to Kashmir, several junipers and the common yew (*Taxus braccata*) also occur. The deodar (*Cedrus Deodara*), which is indigenous to the mountains of Afghanistan and the north west Himalayas is nearly allied to the Atlantic cedar and to the cedar of Lebanon, a variety of which has recently been found in Cyprus. Another instance of the connection of the Western Himalayan flora with that of Europe is the holm oak (*Quercus Ilex*), so characteristic of the Mediterranean region.

North-
west.

The north-western area is best marked in Sind and the Punjab, where the climate is very dry (rainfall under 15 inches), and where the soil, though fertile, is wholly dependent on irrigation for its cultivation. The low-scattered jungle contains such characteristic species as *Capparis aphylla*, *Acacia arabica* (*babul*), *Populus euphratica* (the 'willows' of Ps. cxxxvii. 2), *Salvadora persica* (erroneously identified by Royle with the mustard of Matt. xiii. 31), tamarisk, *Zizyphus*, *Lotus*, etc. The dry flora extends somewhat in a south-east direction, and then blends insensibly with that of the western peninsula; some species representing it are found in the upper Gangetic plain, and a few are widely distributed in dry parts of the country.

Assam and
Malayan
peninsula.

This area is described by Sir Joseph Hooker as comprising 'the flora of the perennially humid regions of India, as of the whole Malayan peninsula, the upper Assam valley, the Khási mountains, the forests of the base of the Himálayas from the Brahmaputra to Nepál, of the Malabar coast, and of Ceylon.'

Western
India.

The Western India type is difficult to characterize, and is intermediate between the two just preceding. It occupies a comparatively dry area, with a rainfall under 75 inches. In respect to positive affinities, Sir Joseph Hooker has pointed out some relations with the flora of tropical Africa as evidenced by the prevalence of such genera as *Grewia* and *Impatiens*, and the absence, common to both countries, of oaks and pines which abound in the Malayan archipelago. The annual vegetation which springs up in the rainy season includes numerous genera, such as *Sida* and *Indigofera*, which are largely represented both in Africa and Hindustán. Palms also in both countries are scanty, the most notable in Southern India being the wild date (*Phoenix sylvestris*); *Borassus* and the cocoa-nut are cultivated. The forests, although occasionally very dense, as in the Western Gháts, are usually drier and more open than those of the Malayan type, and are often scrubby. The most important timber-trees are the *tín* (*Cedrela Toona*), *sál* (*Shorea robusta*), the present area of which forms two belts separated by the Gangetic plain; satin-wood (*Chloroxylon Swietenia*), common in the drier parts of the peninsula; sandal-wood, especially characteristic of Mysore; iron-wood (*Mesua ferrea*), and teak (*Tectona grandis*).

CHAPTER XXV

VITAL STATISTICS OF INDIA

THE vital statistics of India¹ are derived from five chief ^{Five} sources. Of these, the first or European army consists of ^{sources of} foreigners under special medical conditions, and subject to ^{health} the disturbing influence of 'invaliding'. The second, or native ^{returns} army, the third, or jail population, and the fourth, or police, are all composed of natives, but of natives under special conditions as regards food, discipline, or labour. It is dangerous to generalize from returns thus obtained, with regard to the health statistics of the ordinary population of India. For that

¹ The literature of Indian health statistics and medical aid may be divided into eight chief classes — (1) Separate treatises by a series of medical observers, dating from the latter part of the 18th century and continuing up to the present time. (2) Official special Reports of the Medical Boards of Bengal, Madras, and Bombay on the great outbreak of cholera in 1817, the Medico Topographical Reports (1825-40) of the chief stations of the Madras Presidency, by the Medical Board of that Presidency. (3) The Transactions of the Medical Physical Society of Calcutta (1823-39), and of Bombay (1837-76), the Indian Annals of Medical Science (Calcutta) from 1853-80, other medical journals at different periods in the three Presidencies. (4) Reports on the Medical Education of the Natives of India, commencing with vernacular medical schools in Calcutta and Bombay (1820-30), developing (1835-57) into the Medical Colleges of Bengal, Madras, and Bombay, and extending into medical schools at Hyderabad (Deccan), Nagpur, Agra, Lahore, Balrampur (Oudh), Patná, Dacca, Poona, Ahmadabad. (5) Reports on Vital Statistics by the various Medical Boards, Medical Departments, and Inspectors General of Hospitals, since 1827 these assume a prominent place. (6) The Annual Reports of the Sanitary Commissioner with the Government of India, since 1874, and of the Sanitary Commissioners to the local Governments, the Annual Reports of the Inspectors General of Jails, of the Inspectors General of Police, and of the health officers to municipal bodies in the various Presidencies and Provinces. (7) Reports by special Committees or Commissions, such as those on the Fardjan fever, on the cattle plague in Bengal, the Orissa famine of 1866, the Madras famine of 1878, etc. (8) Annual Reports of the public hospitals, dispensaries and other medical charities. The author has been unable to test all the dates in this footnote, but he reproduces some of them, unverified, from a memorandum supplied to him by Dr. Morhead, formerly of Bombay.

population, however, a system of registration exists, and this system forms the fifth source of our data on the subject.

Registration of general population. Why untrustworthy.

In certain Provinces, registration is carried out with some degree of efficiency. But the natives shrink from publicity touching the details of their life. They could only be forced to give uniform and absolutely trustworthy returns of births, deaths, marriages, sex, and age by a stringent legislation, and a costly administrative mechanism, from which the Government wisely abstains. In municipalities, however, registration furnishes a fairly accurate account of the vital statistics of the urban population. For the rural Districts, special areas in some Provinces were selected for statistical supervision; and this has been now gradually extended, with the exception of certain exceptionally situated tracts, to practically the whole population. But the results obtained are still necessarily imperfect.

The Census.

The Census operations, conducted under special legislation, will furnish a general picture of the Indian people every ten years. But the complete details have, up to the present time of writing, been obtained only for the two Censuses of 1871 and 1881. The chief results of the Census of 1881 are given in chapter ii., and in Appendices I. to X. at the end of this volume.

Sources of error.

In treating of the public health of India, therefore, three points must always be borne in mind. The data are obtained either, first, from limited classes under special medical conditions; or second, from limited areas under special statistical supervision; or third, from a general system of registration spread over the whole country, but which has hitherto failed to yield trustworthy results. General averages from such sources, struck for the entire population, can only be accepted as estimates based upon the best information at present available.

Death-rate in India.

Subject to the above remarks, it may be stated that the evidence goes to show an annual death-rate of 32·57 per thousand in India. During the famine of 1877-78, the death-rate in Madras was ascertained to be equal to an annual rate of 53·2 per thousand. In 1877, the death-rate among the European troops in India was 12·71 per thousand, being the lowest recorded up to that year; in the native army, 13·38 per thousand; in the public jails, 61·95 per thousand, rising to 176 per thousand in the Madras prisons, which were flooded by the famine-stricken population. In 1883, the death-rate returns of European troops in India showed a mortality of

1088 per thousand, the lowest recorded in any year for which full returns have been compiled. In the native army in 1883 the mortality on the total strength was 1176 per thousand, or including men absent from their regiments, 1431 per thousand, being about one half the average rates for 1877-81. The jail mortality also showed a satisfactory reduction, the death rate having fallen to 3364 per cent.

The returns of births, as given hereafter for each Province, are too untrustworthy to allow of an attempt to calculate the birth rate for the whole country. The average duration of life in India is on slender foundation, estimated at 30½ years. Average duration of life. Instead of attempting generalizations which, although interesting to the speculative statistic, might mislead the actuary and be perverted into an unsound basis for induction, the following paragraphs are confined to the returns as furnished for the separate Provinces, together with the health statistics of the European troops, the native army, and the jail population. The following paragraphs are condensed from the Reports of the Sanitary Commissioner with the Government of India, for 1877 and 1883.

In Bengal, the system of collecting statistics over specially selected areas has been abolished and an attempt is being made to obtain returns equally from the whole Province. Vital statistics of Bengal in 1877 The registration of deaths in 1877 showed a ratio of 1796 per thousand (varying in different Districts from 36 down to 8), which, according to the Sanitary Commissioner, 'must be very much under the truth'. The mortality in towns (where the registration is less incomplete) was returned at 3249 per thousand, compared with 1739 in the rural circles. Of the total death rate, 2024 per thousand was among males, and only 1569 among females, 'a discrepancy which must be due in the main to defective registration'. The birth rate, which averaged 1020 per thousand for the whole Province, varied, according to the returns, from 35 in Patná to only 6 per thousand in Bardwán and Bâkarganj Districts. The male births were returned in 1877 as exceeding the female births in the proportion of 118 to 100.

Registration of vital statistics in Bengal is still very imperfect, and it is only with regard to deaths that any attempt is made at a general registration. Vital statistics of Bengal in 1883 The total number of deaths returned in 1883 as occurring among a population under registration of 66,163,884, was 1,245,676, or at the rate of 18½ per thousand (varying in different Districts from a maximum of 36 down to a minimum of 10 per thousand). The defective character of the registration is shown by the fact that the

death-rate among the males was 20·59 per thousand, and among the females 17·08 per thousand, showing an apparent increase of over 18 per cent. of male over female deaths. It is also exhibited in a comparison of the mortality in towns and rural circles. In 96 towns in Bengal where registration is necessarily under closer control, the death-rate amounted to 27·28 per thousand, while in 552 rural registration circles it was only 18·49. Compulsory birth registration in Bengal is only enforced in 46 towns and municipalities, with a population of 1,685,159. These returned a total birth-rate of 22·08 per thousand in 1883; but that this is below the truth is exhibited by the fact that the deaths exceeded the births in the ratio of 7·87 per thousand, as well as by the fact that the registered male births in towns exceeded the female births by 14 per cent. The following figures show the causes of the registered deaths in 1883, and the ratio they bear to the general mortality:—Fevers, 13·81 per thousand; cholera, 1·36; small-pox, 0·14; bowel complaints, 0·83; injuries, 0·35; all other causes, 2·30 per thousand.

Vital
statistics
of Madras
in 1877.

In the Madras Presidency, both births and deaths were much affected in 1877 by the famine which desolated that part of the country, and registration was conducted under special difficulties. Though many defects are consequently apparent, the Sanitary Commissioner is of opinion 'that the relative intensity of the famine in different circles is fairly represented by the mortuary registration.' The general registered death-rate was 53·2 per thousand; and in Madras city, 116·7 per thousand (*see* article MADRAS PRESIDENCY, *The Imperial Gazetteer of India*). Among males, the rate is given as 58·4, and among females 48·06 per thousand, 'which points to imperfections in the record of female deaths.' The following figures show the causes under which the deaths of 1877 in Madras were classified:—Cholera, 12·2 per thousand; small-pox, 3·02; fevers, 16·06; bowel complaints, 4·5; injuries, 0·5; all other causes, 16·8 per thousand. The number of registered deaths in 1876 was 23·34, and in 1875, 21·1 per thousand. The famine resulted in a marked reduction in the birth-rate, the ratio for 1877 being only 16·3, or less than that of 1876 by more than 5 per thousand. For every 100 female births, 107 male births were registered. In the nine Districts where the famine was most severe, the birth-rate was only 12 per thousand, whereas in the eight where the people suffered less, the rate was 20 per thousand. Excess of deaths over births in Madras Presidency in 1877, according to the above figures, 36·9 per thousand of the

population The registration of births and deaths was not compulsory in Madras in 1877

Registration of vital statistics is still very imperfect in Madras, although better than in the Bengal Districts The total number of deaths returned in 1883 as occurring among a population under registration of 28,503,100, was 541,930, or at the rate of 19.0 per thousand (varying in the several Districts from a maximum of 38.6 to a minimum of 11.8 per thousand), the rate of male deaths being 19.7, and of female deaths 18.3 per thousand The urban death rate in 76 towns, with a population of 1,696,075, was 24.9 per thousand, as against 18.6 per thousand in 153 rural registration circles, with a total population of 26,839,745 The total number of births registered in 1883 was 791,774, or 27.7 per thousand, a larger number and ratio than in any year since 1869, when registration was first commenced The excess of male over female births is less in proportion in Madras than in any other Province of India, the ratio being 104.6 males to 100 females The death rate from different causes in 1883 was returned as follows—Fever, 7.1 per thousand, cholera, 1.2, small pox, 1.3, bowel complaints, 0.7, injuries, 0.4, all other causes, 8.0 per thousand Excess of births over deaths registered in 1883, 8.7 per thousand of population

In the Bombay Presidency, famine affected the death rate in 1877, and the year was also more than usually unhealthy, cholera and small pox being both epidemic The mortality, according to the returns, was at the rate of 38.76 per thousand In the famine stricken Districts the mortality was 55.09, compared with 25.71 per thousand in 1876 The following figures show the causes of the deaths registered in 1877—Cholera, 2.53, small pox, 1.69, fever, 20.79, bowel complaints, 3.72, injuries, 0.46, all other causes, 8.55 per thousand The birth rate in 1877 was 19.26 per thousand (varying from 29 to 6), or 2.09 per thousand less than the rate for 1876—'a result which is for the most part ascribed to the effects of famine, but also, in great measure, to neglect in registration' For every 100 female births, 111 male births were registered Excess of deaths over births in Bombay Presidency in 1877, 19.54 per thousand of the population

Registration shows better results in the Bombay Presidency than in Madras or Bengal, but in the Sind Districts it is still very imperfect, and the returns from these lower the average for the entire Presidency The total number of deaths returned in 1883 was 420,198, or 25.53 per thousand of the

total population (varying from 41·97 per thousand in Khândesh to 9·19 in the Upper Sind Frontier District), the ratio of male deaths being 26·02, and of female deaths 25·02 per thousand. The male deaths registered were 111·06, for every 100 female deaths. The urban death-rate in 62 towns and municipalities, with a total population of 2,105,756, was 29·61 per thousand, as against 24·94 per thousand in 223 rural registration circles, with a population of 14,348,658. The ratio of mortality due to different causes was returned as follows:—Fevers, 16·21 per thousand; cholera, 2·31; small-pox, 0·81; bowel complaints, 2·14; injuries, 0·36; all other causes, 3·70. The number of births registered during the year was 501,801, giving a rate of 30·50 per thousand of the population, which would be considerably higher but for defective returns from Sind. Throughout the entire Presidency, 109·22 male births were registered for every 100 female. The excess of the registered births over the deaths was at the rate of 4·97 per thousand of the population.

Vital statistics of North-Western Provinces and Oudh in 1877. The North-Western Provinces and Oudh together returned a death-rate in 1877 of 19·67 per thousand, varying from 29 to 12 per thousand. For Oudh alone, the rate was 17·1; and for the North-Western Provinces alone, 20·6. The mortality in the towns of the amalgamated Province was 29·43, compared with 18·99 in the rural circles; and of the total death-rate, 21·06 was among males, and 18·12 among females. The registration of births, which in 1877 was confined to the municipalities, showed an average rate of 39·22 per thousand, varying from 70 at Urai to 14 at Dehra. Excess of births over deaths, 10·27 per thousand of the population.

Vital statistics of North-Western Provinces and Oudh in 1883. Considerable improvement in registration of vital statistics in the North-Western Provinces and Oudh has been effected since 1877, and birth as well as death registration is now carried on throughout the entire Lieutenant-Governorship. The statistics, however, still bear internal evidence that at the best they are only approximately accurate. The total number of deaths returned in 1883 (a year of improved health, accompanied by plenty and cheapness of food) was 1,216,297, or at the rate of 27·57 per thousand of the population, the lowest for any year since 1877 (varying from 48·33 to 17·49 per thousand), the rate of male deaths being 28·49, and of female deaths 26·58 per thousand, the excess of male over female deaths being on an average 15·88 per cent. The urban death-rate in 103 towns and municipalities, with a total population of 2,756,493, was 35·32 per thousand, as against 27·05 per

thousand in 1044 rural registration circles, with a population of 41,351,376. The ratio of mortality due to different causes was returned as follows — Fevers, 18.82 per thousand, cholera, 0.41, small pox, 3.14, bowel complaints, 1.51, injuries, 0.48, all other causes, 3.21 per thousand. The mortality from small pox was unusually high during the year. The average birth rate in 1883 was 40.84 per thousand, the highest on record since 1879, when the general registration of births was first introduced into these Provinces, and the highest in any of the Provinces of India in 1883. The birth rates in the various Districts ranged from 58.24 per thousand in Lahitpur to 20.39 per thousand in Dehra Dun. Throughout the Lieutenant Governorship as a whole, 111.81 boys were born for every 100 girls. Except in the malaria infested Tarai, the registered births exceeded the deaths in every District, the total excess of births over deaths being at the ratio of 13.27 per thousand of the population.

In the Punjab, the death rate for 1877 was recorded as 20 per thousand, and the same rate applies to both males and females taken separately. The District average varies from 27 per thousand in Lahore to 8 in Kohát on the frontier. In the towns, the mean mortality was 33 per thousand, varying between a maximum of 52 (in the town of Delhi) and a minimum of 12 (in Kohát). In 1877, births were registered only in the municipal towns of the Punjab, and the results showed a birth rate of 31.86 per thousand. Excess of births over deaths, 5 per thousand of the population.

In 1883, the total number of deaths returned in the Punjab was 475,741, or at the rate of 25.25 per thousand of the population (varying in the several Districts from 35 to 16 per thousand), the rate of male deaths being 25.13, and of female deaths 25.39 per thousand. The urban mortality in 1883, in 49 towns and municipalities, with a population (excluding that of four hill sanitarium) of 1,310,383, was at the rate of 30 per thousand, as against 25 per thousand in 397 rural registration circles, with a population of 17,512,378. The ratio of mortality due to different causes was returned as follows — Fevers, 16.25 per thousand, cholera, 0.01, small pox, 0.64, bowel complaints, 0.77, injuries, 0.28, all other causes, 7.29 per thousand. The average birth rate during the year was 39 per thousand throughout the Punjab as compared with an average of 41 in municipal towns. Throughout the Punjab as a whole, 115.14 boys were born for every 100 girls, or an excess of 15.14 per cent of male over female births. The excess of

births over deaths was at the rate of 14 per thousand of the general population. The year, however, was an exceptionally healthy one, and the mortality from the chief diseases was less than in any year since 1877.

Vital
statistics
of the
Central
Provinces
in 1877.

In the Central Provinces and in Berar, the registration of births and deaths is more general, and the results obtained approach nearer to accuracy than in any of the other Provinces of India. The recorded death-rate in the Central Provinces in 1877 was 23·91 per thousand, varying from 38 in Mandlā to only 18 in Nágpur District. Among males the death-rate was 25·66, and among females 22·11 per thousand. In the towns, the rate was 35·86 per thousand. In 1877, the total number of births registered in the Central Provinces show a rate of 39·26 per thousand; varying from a maximum of 45 per thousand in Biláspur to a minimum of 31 in Nágpur. The proportion of male births recorded was 111 for every 100 female births. Excess of registered births over deaths in the Central Provinces in 1877, 15·35 per thousand of the population.

Vital
statistics
of the
Central
Provinces
in 1883.

In 1883, the total number of deaths returned in the Central Provinces, among a population of 8,817,185 under registration, was 304,763, or an average rate of 34·56 per thousand (varying in the several Districts from 48·84 to 26·13), the rate of male deaths being 35·83, and of female deaths 33·28 per thousand, the excess of male over female deaths being 9 per cent. The urban mortality in 1883, in 74 towns and municipalities, with a total population of 757,092, was at the rate of 35·56 per thousand, as compared with 34·48 per thousand in 94 rural registration centres, with a population of 8,060,093. The ratio of mortality due to different causes was as follows:—Fevers, 19·86 per thousand; cholera, 1·84; small-pox, 0·53; bowel complaints, 3·02; injuries, 0·52; all other causes, 8·79 per thousand. Total number of births registered, 357,864, or at the average rate of 40·59 per thousand, varying in the several Districts from 54·29 to 34·15. Male births preponderated over female births by 7·61 per cent. The excess of registered births over deaths was at the rate of 6·03 per thousand of the population.

Vital
statistics
of Berar
in 1877.

In Berar, the general registered death-rate was returned in 1877 at 28·1 per thousand. In the towns alone the mortality was 31·4 per thousand. The birth-rate shown by the returns of 1877 was 39·5 per thousand, varying from 47 in Akola to 35 in Wún District. The number of male births recorded was 109 for every 100 female births. Excess of

births over deaths in Berar in 1877, 11 40 per thousand of the population

The year 1883 was a particularly unhealthy one in Berar, owing, it is supposed, to abnormally heavy rainfall, and a severe epidemic of cholera largely raised the mortality returns. The total number of deaths returned during the year was 135 081, or at the rate of 51 3 per thousand of the population (varying in the several Districts from 65 7 to 39 3 per thousand), the rate of male deaths was 51 4, and of female deaths 51 3 per thousand, the excess of male over female deaths being 7 per cent. The urban death rate in 11 towns and municipalities, with a population of 138,378, was 53 2 per thousand, as against 51 3 per thousand in 134 rural registration circles, with a population of 2,491,640. The ratio of mortality due to different causes was as follows—Fever, 20 3 per thousand, cholera, 10 6, small pox, 1 5, bowel complaints, 7 2, injuries, 0 4, all other causes, 11 3 per thousand. The average birth rate in 1883 was 40 3 per thousand varying from 43 2 to 37 8 per thousand, the male births exceeding the female by 6 5 per cent. Owing to the cholera epidemic, and general unhealthiness of Berar in 1883, the registered deaths exceeded the births in that year in the ratio of 11 per thousand of the population.

In Assam, the system of registration in 1877 was that formerly in vogue in Bengal, of which this Province until recently formed part. The returns were taken over certain selected areas, and the results were quite untrustworthy. The death rate, as ascertained from these returns, was only 10 9 per thousand, varying in the several Districts from 29 to 5 per thousand. The births recorded in the selected areas were at the rate of 20 per thousand, ranging from 34 to 10 per thousand. The figures show an excess of deaths over births in Assam in 1877 of 4 9 per thousand of the population.

Compulsory registration throughout the whole of Assam, with the exception of certain hill tracts was not introduced till the latter half of 1882, and the results, as might be expected, do not even approximate to accuracy. In 1883, the total number of deaths registered was returned at 122,932, or an average of 27 14 per thousand of the population (varying in the several Districts from 41 89 to 16 27 per thousand), the rate of male deaths being 28 34, and of female deaths 25 89 per thousand. Excess of male over female registered deaths, 16 per cent. In 21 towns and municipalities, with a total population of 99 202, the average death rate was

30·07 per thousand, as against 27·08 per thousand in 657 rural registration circles, with a population numbering 4,428,732. The ratio of mortality due to different causes was as follows:—Fevers, 14·90 per thousand; cholera, 3·29; small-pox, 1·36; bowel complaints, 3·19; injuries, 0·27; other causes, 4·12 per thousand. The average birth-rate in 1883 was 23·91 per thousand, those of the males exceeding the females by nearly 10 per cent. Excess of registered deaths over births, 3·23 per thousand of the population.

Vital
statistics
of British
Burma
in 1877.

In British Burma, registration is shown to be even more defective than in the worst Provinces of India. The average death-rate, according to the returns in 1877, was 17·44 per thousand, the rate for males being 18, and for females 16 per thousand. In Myanaung the deaths were returned at 119, and at Maulmain at less than 13 per thousand. In the towns the mortality was 34 per thousand, compared with 15 in the rural circles. The birth returns showed a rate of only 21 per thousand; 'and this general average,' to use the words of the Report in 1877, 'is made up of such extremes that no reliance can be placed on the figures.' In one place the birth-rate was no less than 115 per thousand, in another it was as low as 5. Excess of registered births over deaths in British Burma in 1877, 4 per thousand of the population.

Vital
statistics
of British
Burma in
1883.

No improvement in registration in British Burma seems to have been effected up to 1883. Indeed, in that year the death-rate had fallen below the figures returned for 1877. In 1883, the total registered deaths numbered 53,583, or a rate of 14·67 per thousand of the population under registration (varying in the several Districts from 21·42 to 9·22), the male deaths being returned at 15·37, and the female deaths at 13·86 per thousand. The excess of registered male deaths over female deaths was 27 per cent. In 20 towns and municipalities, with a total population of 425,775, the registered death-rate was 25·50 per thousand, against 13·24 per thousand in 823 rural registration circles, with a population numbering 3,227,854. The ratio of mortality due to different causes was as follows:—Fevers, 7·19 per thousand; cholera, 0·60; small-pox, 0·19; bowel complaints, 0·76; injuries, 0·17; other causes, 5·76. The birth-rate of the Province was returned at 23 per thousand, ranging in the several Districts from 31·65 to 16·60. The registered male births exceeded those of the females by 6 per cent. The registered births exceeded the deaths in the ratio of 8·0 per thousand of the population. A revised scheme of

registration for British Burma is now (1884) under consideration, the adoption of which it is hoped will result in more accurate statistics

After what has been stated in the introductory paragraph of this section, it is manifest that the figures quoted from the Reports of the Sanitary Commissioner with the Government of India are of little or no value for the purpose of establishing the comparative healthiness or unhealthiness of the different portions of the country. To construct a comparative table out of the provincial returns would be misleading, if any attempt were made to use it for actuarial purposes. But the tables on the four following pages may be interesting as showing the defects and uncertainties of Vital Statistics in India, as well as the progress towards accuracy which has been effected between 1877 and 1883 in registering births and deaths among the general population. The wide variations in both the birth and death rates for various Districts usually arise from different degrees of imperfection in the registration

Danger of
using these
statistics

HEALTH OF THE EUROPEAN ARMY.—The sanitary statistics of the army in India are, in every way, more trustworthy than those obtained for the general population, and as they have been regularly collected on a uniform system for a number of years, it is possible to draw valuable inferences

Health
of the
European
Army,

The sanitary history of the European Army during 1877 was more favourable than in any previous year for which the statistics are on record. The total strength of the European Army in India in 1877 was returned at 57,260 men, the admissions into hospital numbered 71,992 (1257 per thousand of average strength), daily sick, 3196 (56 per thousand), deaths, 728 (12.71 per thousand). The averages for the five years 1871-1875 were as follows—admissions into hospital, 1394 per thousand, daily sick, 57, deaths, 17.62 per thousand. 'Not only,' writes the Sanitary Commissioner, 'do the results compare favourably with the averages of the five years 1871 to 1875, but, what is deserving of special notice, the admission rate and death rate are the lowest which have yet (1877) been attained'

its general
statistics
in 1877,

In 1883 the total strength of the European Army in India was 55,525, the average admission into hospital being at the rate of 1336 per thousand, daily sick, 63 per thousand, while the deaths were 10.88 per thousand, the lowest on

[Sentence continued on page 680]

BIRTH-RATE AMONG GENERAL POPULATION IN INDIAN PROVINCES IN 1877.

PROVINCE.	Population under Registration.	RATIO OF BIRTHS PER 1000 OF POPULATION.			Number of Males born to every 100 Females born.	Excess of Births over Deaths per 1000 of Population.	Excess of Deaths over Births per 1000 of Population.
		Maximum for any one District.	Minimum for any one District.	Mean for the Province.			
Bengal,	58,281,453	35	6	18'20	118	07	...
North-Western Provinces, ¹	2,231,534	70	14	39'22	117	10'27	...
Punjab,	3,022,071	51	12	31'86	111	5'00	...
Central Provinces,	7,408,074	45	31	39'26	111	15'35	...
Berar,	2,184,945	47	35	39'50	109	11'40	...
British Burma,	2,934,981	115	5	21'07	105	4'00	...
Assam,	120,821	34	10	20'90	123	...	4'9
Madras Presidency, ²	29,209,542	36	5	16'30	107	...	36'9
Bombay Presidency, ²	16,181,741	29	6	19'26	111	...	19'54

¹ Births were not registered in Oudh in 1877.

² It should be remembered, as already stated, that the averages in Madras, and to a less degree in Bombay, were powerfully influenced by the Famine (1877). The average death-rate in 1876 was 23'34 per thousand in Madras, and 21'81 per thousand in Bombay. The birth-rate in 1876 in Madras was 21'6 per thousand; and in Bombay, 21'35.

DEATH RATE AMONG GENERAL POPULATION IN INDIAN PROVINCES IN 1877.

GENERAL DEATH STATISTICS, 1877. 677

Province.	Population under Registration	Area in Square Miles	Average Population per Square Mile	Ratio of Deaths per 1000 of Population in Districts			Death Rate per 1000	
				Maximum	Minimum	Mean	Male	Female.
Bengal,	59,993,332	144,614	415	36	8	17 96	20 24	15 69
North Western Provinces and Oudh,	42,724,741	104,402	409	29	12	19 67	21 06	18 12
Punjab,	17,487,125	104,975	166	27	8	20 00	20 00	20 00
Central Provinces,	7,408,074	65,162	113	38	18	23 91	25 66	22 11
Bihar,	2,184,945	16,227	134	34	20	28 10	1	1
British Burma,	2,934,981	88,283	33	119	11	17 44	18 47	16 33
Assam,	3,805,364	27,319	131	29	5	10 90	6 30	4 60
Madras Presidency,	29,209,542	138,318	222	119	217	53 20	58 40	48 06
Bombay Presidency,	16,181,741	124,196	130	101	28	38 76	41 32	36 01

¹ Not given by Sanitary Commissioner.

² It should be remembered, as already stated, that the averages in Madras, and in a lesser degree in Bombay, were powerfully influenced by the Famine (1877). The average death rate in 1876 was 23 34 per thousand in Madras, and 21 81 per thousand in Bombay. The birth rate in 1876 in Madras was 21 6 per thousand; and in Bombay, 21 35

BIRTH-RATE AMONG GENERAL POPULATION IN INDIAN PROVINCES IN 1883.

Province.	Population under Registration.	RATIO OF BIRTHS PER 1000 OF POPULATION.			Number of Males born to every 100 Females born.	Excess of Births over Deaths per 1000 of Population.	Excess of Deaths over Births per 1000 of Population.
		Maximum for any one District.	Minimum for any one District.	Mean for the Province.			
BENGAL PRESIDENCY.	Bengal (46 Municipalities and Towns),	49'17	6'40	22'08	114'00	...	- 7'87
	North-Western Provinces and Oudh,	58'24	20'39	40'84	111'81	13'27	...
	Punjab,	53'32	10'04	39'00	115'14	14'00	...
	Central Provinces,	54'29	34'15	40'59	107'61	6'03	...
	Berar,	43'20	37'80	40'30	106'50	...	11'00
	British Burma,	31'65	16'60	22'92	106'00	8'00	...
	Assam,	59'13	13'28	23'91	109'73	...	3'23
Madras Presidency,	28,503,100	40'90	13'70	27'70	104'60	8'70	...
Bombay Presidency,	16,454,414	44'09	15'92	30'50	109'22	4'97	...

DEATH RATE AMONG GENERAL POPULATION IN INDIAN PROVINCES IN 1883

Province	Population in 1881	Area in square miles	Average population per square mile	Ratio of Deaths per 1000 of Population in Districts			Death Rate per 1000	
				Maximum	Minimum	Mean	Male	Female
Bihar	6,163,884	311,863	197	3607	993	1882	2059	1708
North Western Provinces and Oudh	16,107,863	106,401	116	4833	1749	2757	2849	2658
Punjab	18,812,274	107,055	175	3500	1600	2525	2513	2539
Central Provinces	8,023,155	71,215	124	4584	2613	3456	3583	3328
Bengal	26,801,878	16,052	164	6570	3950	5130	5140	5150
British Burma	1,685,629	78,087	13	2142	922	1467	1537	1356
Assam	4,527,074	127,006	1162	4159	1627	2714	2834	2589
Madras Provinces	28,604,400	133,800	221	5500	1150	1900	1070	1830
North Eastern Provinces	16,484,114	128,860	133	4107	919	2553	2002	2502

Notes: The above figures are for the year 1883, and are for the General Population.

Sentence continued from page 675.]

record since 1870. The loss from invaliding was 33 per thousand, making a total loss from all causes of 44 per thousand of average strength, or about 12 per thousand below the average of thirteen previous years. The ratio of loss due to invaliding in 1883 was about 4 per cent. below the average. In 1883, the death-rate in the Bengal Army was as low as 11·21 per thousand. In Madras, the death-rate in 1883 was as low as 10·19 per thousand, the lowest in the three Presidencies. Rate of mortality in the Bombay Army in 1883, 10·50 per thousand of average strength.

Nine chief causes of sickness.

In all three Presidencies, the same diseases form the nine chief causes of sickness, with slight variations in the order in which they occur. These nine were:—malarial fevers, venereal diseases, wounds and accidents, abscess and ulcer, respiratory diseases, rheumatism, diarrhoea, hepatitis, and dysentery. They are here given in the order of their frequency (1883) in Bengal. Malarial fevers, which stood first in both Bengal and Bombay (486 and 436 admissions per 1000 respectively), were replaced at the top of the list in Madras by venereal diseases (289 admissions per 1000); respiratory diseases and rheumatism, which took the fifth and sixth places in Bengal, were seventh and ninth in Madras, and fourth and sixth in Bombay; whereas dysentery and hepatitis, which came fifth and eighth in Madras, came ninth and eighth in Bengal, and occupied the same position in Bombay. The arrangement of the diseases in all three Presidencies accorded generally, to a remarkable extent, with the experience of previous years; and the year 1883 may be taken as a typical one. Total admissions into hospital from all causes, 1336 per 1000 in all India. In the Bengal Army, the average admissions were 1463 per 1000; in Madras, 1013; and in Bombay, 1249 per 1000.

The chief causes of mortality.

The six principal causes of deaths in Bengal in 1877 were in the order of their frequency: enteric fever, apoplexy, hepatitis, cholera, remittent and continued fevers, and dysentery. In all three Presidencies, the six forms of disease which contributed most to the death-rate were the same. The total death-rate from these six diseases were—in Bengal, 6·60 out of a total mortality of 11·21 per 1000; in Madras, 6·47 out of a total mortality of 10·19 per 1000; and in Bombay, 5·39 out of a total of 10·50 per 1000. Enteric fever headed the list of the chief causes of death in all three Presidencies; Madras having the highest ratio (2·86 per 1000

followed by Bengal (2.52 per 1000), and Bombay (1.55 per 1000)

Cholera was not prevalent during 1883, and added but little to the army mortality throughout India. The experience of a number of years goes to show that enteric fever is in the main a disease of young soldiers new to India, the majority of sufferers being men in their first or second year. With reference to the great prevalence of venereal diseases in the European Army, it is stated that 'the working of the lock hospitals in all three Presidencies during 1877 must be pronounced to have been more or less a failure,' and in 1883 the admission rate into military hospitals for venereal diseases was reported to be only a fraction lower in protected than in unprotected stations.

Out of a total, in 1883 of 604 deaths in the European British Army in India, 133 were due to enteric fever, 26 to other fevers, 51 to cholera, 63 to hepatitis, 61 to apoplexy, 38 to phthisis, 37 to diseases of the respiratory organs, 17 to heart disease, and 23 to dysentery and diarrhoea.

The following tables show—(1) the health statistics of the European troops throughout all India, for a series of years ending 1883 and (2) the sickness, mortality, and invaliding among those troops in 1883, arranged separately under the three Presidencies —

DEATH RATE AMONG EUROPEAN TROOPS IN INDIA, 1871-1883

PERIOD	Strength	RATIO PER 1000 OF AVERAGE STRENGTH				
		Admissions into Hospital	Daily Sick	Deaths	Invaliding	TOTAL
1871 to 1875 (average),	58,432	1,594	57	17.62	43.09	61
1876,	57,858	1361	56	15.32	38.90	54
1877,	57,260	1257	55	12.71	42.25	55
1878,	56,475	1651	68	21.46	45	66
1879	49,582	1977	78	24.28	49	73
1880	51,796	1789	74	24.85	26	51
1881,	58,728	1605	70	16.86	38	55
1882,	57,269	1445	65	12.07	33	45
1883,	55,525	1336	63	10.88	33	44
Average,	56,666	1492	63	17.43	40	57

Causes of invaliding

SICKNESS, MORTALITY, AND INVALIDING AMONG EUROPEAN TROOPS IN THE THREE PRESIDENCIES DURING 1883.

PRESIDENCY.	Average Strength.	RATIO PER 1000 OF AVERAGE STRENGTH.				
		Admissions into Hospital.	Daily Sick.	Deaths.	Invaliding.	Total Loss.
Bengal, . .	34,079	1463	66	11·21	31	42·21
Madras, . .	10,498	1013	59	10·19	33	43·19
Bombay, . .	10,948	1249	57	10·50	38	48·50

Health
of the
Native
Army,
in 1877
and 1883,

HEALTH OF THE NATIVE ARMY.—The sickness and mortality in 1877 in the regular Native Armies of Bengal, Madras, and Bombay, the Central India Regiments, Punjab Frontier Field Force, and Haidarábád Contingent, are shown by the following figures:—average strength of troops (present with regiments), 113,966; admissions into hospital, 1030 per thousand; daily sick, 32; deaths from cholera, 1·53; deaths from all causes, 10·90, or, including men dying while absent from their regiments, 13·38 per thousand. In 1883, the total average strength of the Native Army of India (present with regiments) was 114,830; admissions into hospital, 923 per thousand; average daily sick, 31; deaths from cholera, 1·15 per thousand; deaths from all causes, 11·76 per thousand of actual regimental strength, or 14·31 per thousand, including deaths among absentees. Malarial fevers are the chief cause of admission into hospital; wounds and accidents come next; followed by dysentery, diarrhoea, and enteric fever. The mortality amounted to 27·28 per cent. of the total treated, the lowest since 1877. Respiratory diseases were the cause of the largest mortality, namely, 3·91 per thousand, followed by fevers, 1·41; and by cholera, 1·15 per thousand.

of Bengal; In the Bengal Native Army, the death-rate in 1883 was 10·55 per thousand, a lower ratio than for any one year since 1877, when it was 10·32 per thousand. In the Central India Regiments, the mortality was as low as 7·89 per thousand in 1883, compared with 9·71 in 1877, and with 11·10, the average of the ten years preceding 1877. In the Punjab Frontier Force, the death-rate, including deaths among absentees, was 23·35 per thousand in 1883, and excluding absentees, 21·46; while in 1877 the rate was 12·26 per thousand. Altogether, the Sanitary Commissioner reports that the health of the

HEALTH OF THE NATIVE ARMY. 683

Native Army in Bengal is very satisfactory, and that there is still a tendency towards diminishing mortality in normal years.

In the Madras Native Army, the regimental mortality, including deaths among absentees, was 14.36 per thousand in 1877, and 12.51 per thousand in 1883. Besides garrisoning its own Province, the Madras Army supplies troops for British Burma and the Andaman and Nicobar islands, as also to certain Districts in the Central Provinces, and to Cuttack District in Orissa.

In the Bombay Native Army, the death-rate, including deaths among absentees, in 1877 was 12.96 per thousand, varying from 11.65 for regiments in the northern Division of Bombay, to 18.81 for those in the Konkan. In 1883, the rate of mortality, including deaths among absentees, was 14.96 per thousand; excluding absentees, the rate among those actually serving with their regiments was 12.81 per thousand.

The returns for the Hardwar Cantonment, both for 1877 and 1883, are more favourable than those for any other portion of the Native Army. The admissions into hospital in 1877 were only 806 per thousand; daily sick, 25; and mortality (including deaths among absentees), 9.61 per thousand. The number of deaths from cholera, however, 443 per thousand, was much above that recorded in any other part of the Native Army. In 1883, the admissions into hospital had fallen to an average of 572 per thousand, the daily sickness to 22 per thousand, and the mortality to 7.53 per thousand.

The sickness and mortality in the Regular Native Army, and other forces in 1877 and 1883, are compared in the following tables:—

SICKNESS AND MORTALITY AMONG NATIVE FORCES IN 1877.

PRESENCE, &c.	1877	1883	1877	1883	1877	1883	1877	1883
Bengal Native Army	13.53	11.65	25.00	22.00	10.00	8.00	10.00	8.00
Madras " "	14.36	12.51	25.00	22.00	10.00	8.00	10.00	8.00
Bombay " "	12.96	14.96	25.00	22.00	10.00	8.00	10.00	8.00
Central India & Rangoon	18.81	12.81	25.00	22.00	10.00	8.00	10.00	8.00
Punjab Frontier Field Force	18.81	12.81	25.00	22.00	10.00	8.00	10.00	8.00
Hardwar Cantonment	9.61	7.53	25.00	22.00	10.00	8.00	10.00	8.00

SICKNESS, MORTALITY, AND INVALIDING AMONG EUROPEAN
TROOPS IN THE THREE PRESIDENCIES DURING 1883.

PRESIDENCY.	Average Strength.	RATIO PER 1000 OF AVERAGE STRENGTH.				
		Admissions into Hospital.	Daily Sick.	Deaths.	Invaliding.	TOTAL Loss.
Bengal, . . .	34,079	1463	66	11'21	31	42'21
Madras, . . .	10,498	1013	59	10'19	33	43'19
Bombay, . . .	10,948	1249	57	10'50	38	48'50

Health
of the
Native
Army,
in 1877
and 1883,

HEALTH OF THE NATIVE ARMY.—The sickness and mortality in 1877 in the regular Native Armies of Bengal, Madras, and Bombay, the Central India Regiments, Punjab Frontier Field Force, and Haidarábád Contingent, are shown by the following figures:—average strength of troops (present with regiments), 113,966; admissions into hospital, 1030 per thousand; daily sick, 32; deaths from cholera, 1'53; deaths from all causes, 10'90, or, including men dying while absent from their regiments, 13'38 per thousand. In 1883, the total average strength of the Native Army of India (present with regiments) was 114,830; admissions into hospital, 923 per thousand; average daily sick, 31; deaths from cholera, 1'15 per thousand; deaths from all causes, 11'76 per thousand of actual regimental strength, or 14'31 per thousand, including deaths among absentees. Malarial fevers are the chief cause of admission into hospital; wounds and accidents come next; followed by dysentery, diarrhoea, and enteric fever. The mortality amounted to 27'28 per cent. of the total treated, the lowest since 1877. Respiratory diseases were the cause of the largest mortality, namely, 3'91 per thousand, followed by fevers, 1'41; and by cholera, 1'15 per thousand.

of Bengal; In the Bengal Native Army, the death-rate in 1883 was 10'55 per thousand, a lower ratio than for any one year since 1877, when it was 10'32 per thousand. In the Central India Regiments, the mortality was as low as 7'89 per thousand in 1883, compared with 9'71 in 1877, and with 11'10, the average of the ten years preceding 1877. In the Punjab Frontier Force, the death-rate, including deaths among absentees, was 23'35 per thousand in 1883, and excluding absentees, 21'46; while in 1877 the rate was 12'26 per thousand. Altogether, the Sanitary Commissioner reports that the health of the

Native Army in Bengal is very satisfactory, and that there is still a tendency towards diminishing mortality in normal years

In the Madras Native Army, the regimental mortality, in of Madras, including deaths among absentees, was 14 36 per thousand in 1877, and 12 51 per thousand in 1883. Excluding deaths of absentees, the ratio was 11 80 per thousand in 1877, and 10 76 per thousand in 1883. Besides garrisoning its own Province, the Madras Army supplies troops for British Burma and the Andaman and Nicobar islands, as also to certain Districts in the Central Provinces, and to Cuttack District in Orissa.

In the Bombay Native Army, the death rate, including of Bombay, deaths among absentees, in 1877 was 12 96 per thousand, varying from 11 65 for regiments in the northern Division of Bombay, to 18 81 for those in the Konkan. In 1883, the rate of mortality, including deaths among absentees, was 14 96 per thousand, excluding absentees, the rate among those actually serving with their regiments was 12 81 per thousand.

The returns for the Haidarabad Contingent both for 1877 and 1883, are more favourable than those for any other portion of the Native Army. The admissions into hospital in 1877 were only 806 per thousand, daily sick, 26, and mortality (including deaths among absentees), 9 61 per thousand. The number of deaths from cholera, however (4 43 per thousand), was much above that recorded in any other part of the Native Army. In 1883, the admissions into hospital had fallen to an average of 572 per thousand, the daily sick rate to 20 per thousand, and the mortality to 7 59 per thousand.

The sickness and mortality in the Regular Native Army and other forces in 1877 and 1883 are compared in the following tables —

SICKNESS AND MORTALITY AMONG NATIVE TROOPS IN 1877.

PRESIDENCY ETC	Deaths per 1000, including Deaths among Absentees	Average Strength (present with regiments)	RATIO PER 1000			
			Admissions into Hospital	Daily Sick	Deaths from Cholera	Deaths from all Causes
Bengal Native Army,	13 63	37 649	1076	33	35	10 32
Madras " "	14 36	28 304	870	28	27	11 27
Bombay " "	12 96	23 355	1074	33	1 93	10 90
Central India Regiments,	10 59	5 246	810	25	7	9 71
Punjab Frontier Field Force,	14 55	10 359	1493	41	—	12 26
Haidarabad Contingent,	9 61	7 229	806	26	4 43	9 42
In India,	13 28	113 666	6 10	—	—	—

Haidarabad Contingent

Results in the three Presidencies compared

SICKNESS AND MORTALITY AMONG NATIVE TROOPS IN 1883.

PRESIDENCY, ETC.	Deaths per 1000, including Deaths among Absentees.	Average Strength (present with Regiments).	RATIO PER 1000.			
			Admissions into Hospital.	Daily Sick.	Deaths from Cholera.	Deaths from all Causes.
Bengal Native Army, . . .	13·98	40,932	985	32	0·56	10·55
Madras " " . . .	12·51	27,703	737	27	2·92	10·76
Bombay " " . . .	14·96	23,576	994	35	0·47	12·81
Central India Regiments, . .	10·16	5,197	595	19	0·39	7·89
Punjab Frontier Field Force, .	23·35	10,438	1,419	45	0·00	21·46
Hyderabad Contingent, . . .	9·31	6,983	572	20	2·15	7·59
India, . . .	14·31	114,830	923	31	1·15	11·76

Health of
the jail
popula-
tion.

HEALTH OF THE JAIL POPULATION.—The Report of the Sanitary Commissioner with the Government of India for 1877, was the first which included the vital statistics of the jails of all three Presidencies. 'The year 1877, to which it refers,' says the Sanitary Commissioner, 'is particularly unfortunate for commencing this change, as, owing to famine and distress over great portion of both Madras and Bombay, the number of prisoners in those parts was suddenly increased far beyond all precedent; the new prisoners were, in large proportion, received in a low state of health, consequent on continued privation; the jails having such large and unexpected calls for accommodation on them, were, as a rule, greatly overcrowded, and the sickness and mortality, as was to be expected, have been lamentably in excess of former years.'

General
statistics,
1877.

The average number of prisoners throughout India in 1877 was returned at 110,147; admissions into hospital numbered 1017 per thousand; daily sick, 36 per thousand; average death-rate, 61·95 per thousand. The months of October and November gave the highest admission rate, 97; and the month of November the highest death-rate, 9·18. Dysentery, diarrhœa, and cholera were the main causes of mortality, the three together accounting for 33·61 out of the total of 61·95 per thousand. 'There are no previous figures with which these general results of 1877 can be compared; they deserve attention as the first collection of statistics regarding the sickness and mortality among the prisoners of all India, a collection which cannot fail in a few years to contribute very valuable

information' The returns for the Bengal Presidency were very favourable, the mortality being 31.88 per thousand, as compared with 37.51 in 1876, 33.65 in 1875, and 46.09, the average for the ten year period, 1864-73. In the Madras Presidency, the returns showed a mortality of 176.01, while the ratio for the Bombay Presidency was 54.37 per thousand. The causes of these high figures have already been indicated. In only 17 of the 34 jails in the Madras Presidency was the death rate under 100 per thousand, in the others it varied much, rising to 200, 300, 500, and in one (Coimbatore District Jail) to 657 per thousand. And in Bombay Presidency, where similar causes were at work, though in a minor degree, the mortality, 54.37 per thousand, was double what it had been for years.

Although 1877 was an abnormal year, especially in Madras and Bombay, owing to the causes stated above, the returns for 1883 show a great improvement in the vital statistics of Indian jails over those of the previous five years. The average prison population in India in 1883 was 88,174 as against 112,670 in the previous five years. The admissions into hospital were 996 per thousand, as compared with an average of 1189 in 1877-81, average daily sick, 36 per thousand in 1883, as compared with 44.9 per thousand in 1877-81. The cholera mortality was in the ratio of 2.28 per thousand in 1883, against an annual average of 4.48 for the previous five years, deaths from dysentery and diarrhoea showed a ratio of 10.64 per thousand in 1883 against 24.97 per thousand in the years 1877-81, while the deaths from all causes were 31.37 per thousand in 1883, as against 63.01 per thousand in the five years 1877-81. The heaviest jail mortality in 1883 was in the Central Provinces (70.97 per thousand), Bengal (52.21 per thousand) and Assam (43.12 per thousand), while the lowest ratio was reached in Berar, with only 8.49 deaths per thousand.

The following tables condense the health statistics of the Indian jails in 1877 and in 1883 —

SICKNESS AND MORTALITY IN INDIAN JAILS, 1877.

PROVINCE.	Average Strength.	RATIO PER 1000 OF AVERAGE STRENGTH.					
		Admissions into Hospital.	Daily Sick.	Deaths.			
				Cholera.	Bowel Complaints.	Atrophy and Anæmia.	All Causes.
Bengal Proper,	17,862	1276	39	8'29	18'98	3'42	49'66
North-Western Provinces, ¹	21,668	535	21	1'43	5'45	1'89	19'71
Oudh, ¹	6,726	504	16	...	2'08	1'19	10'56
Punjab,	12,129	1504	37	'08	10'64	1'07	33'80
Central Provinces,	3,484	907	37	'29	12'92	12'92	45'06
Berar,	963	937	26	...	1'04	5'19	15'58
Assam,	1,261	1382	40	11'10	23'00	2'38	56'30
British Burma,	4,686	844	38	19'63	18'56	4'27	56'76
Madras, ²	20,328	967	40	26'12	85'15	24'50	176'01
Bombay, ²	11,531	935	27	3'64	26'19	8'67	54'37
Andamans,	9,039	1687	76	...	5'20	7'19	34'30

¹ These, although now under one Local Government, are shown separately for comparison with former years. The favourable results in Oudh are worthy of attention.

² It should be remembered that the mortality in the Madras and Bombay Jails in 1877 was greatly increased by the reception of starving prisoners during the famine.

SICKNESS AND MORTALITY IN INDIAN JAILS, 1883.

PROVINCE.	Average Strength.	RATIO PER 1000 OF AVERAGE STRENGTH.					
		Admissions into Hospital.	Daily Sick.	Deaths.			
				Cholera.	Bowel Complaints.	Atrophy and Anæmia.	All Causes.
Bengal Proper,	14,288	1498	50	4'27	23'44	2'94	52'21
North-Western Provinces and Oudh,	22,924	563	23	2'18	4'32	1'48	19'76
Punjab,	12,128	951	27	...	6'18	1'24	29'11
Central Provinces,	3,875	919	36	2'84	46'71	4'13	70'97
Berar,	1,060	558	14	...	1'89	...	8'49
Assam,	1,206	2125	56	5'80	16'58	3'32	43'12
British Burma,	5,149	1159	39	7'96	7'96	1'55	28'94
Madras,	7,666	861	32	1'96	12'78	2'61	29'87
Bombay,	7,806	734	27	2'05	6'79	1'67	34'33
Andamans,	11,511	1454	67	...	2'87	'69	19'63

APPENDIX II.—TOWNS AND VILLAGES IN BRITISH INDIA, CLASSIFIED ACCORDING TO POPULATION, IN 1881.

(Compiled from the Imperial Census Report.)

PROVINCES.	With less than 200 Inhabitants	From 200 to 500 Inhabitants	From 500 to 1,000 Inhabitants	From 1,000 to 2,000 Inhabitants	From 2,000 to 3,000 Inhabitants	From 3,000 to 5,000 Inhabitants	From 5,000 to 10,000 Inhabitants	From 10,000 to 15,000 Inhabitants	From 15,000 to 20,000 Inhabitants	From 20,000 to 50,000 Inhabitants	Upwards of 50,000 Inhabitants	Total Number of Villages and Towns.
Government of Madras,	21,559	14,067	9,379	5,042	1,291	813	404	48	15	21	9	52,648
" of Bombay and Sind,	7,067	8,534	5,471	2,464	545	319	132	39	8	13	6	24,598
Lieutenant-Governorship of Bengal,	165,263	67,307	23,561	6,994	1,958	340	146	49	14	22	11	264,795
" of the Punjab,	11,937	11,879	6,348	2,954	693	349	115	20	8	13	8	34,324
" of the North-Western Provinces,	46,096	34,817	16,690	5,941	1,999	483	192	51	20	18	14	105,421
Chief-Commissionership of Oudh,												
" of the Central Provinces,	19,077	11,233	3,379	693	121	61	32	7	3	3	3	34,612
Chief-Commissionership of Assam, ¹	14,469	5,285	1,290	326	35	7	4	3	22,408
Commissionership of Berar,	2,225	1,883	962	356	72	53	24	6	2	2	...	5,585
" of Ajmere, ²	271	244	125	51	16	11	4	...	1	2	...	739
" of Coorg,	234	149	99	16	3	1	1	503
Chief-Commissionership of British Burma,	9,963	4,886	819	142	19	8	10	2	4	2	2	15,857
TOTAL FOR BRITISH INDIA,	298,161	160,284	68,123	24,979	4,952	2,445	1,064	225	75	96	53	561,460

¹ The details and the total of villages in Assam differ by 989 villages in the Gáro and Nágá Hills, which were not classified according to population.

² Details available for only 725 villages.

1881.

APPENDIX III.—CULTIVATED, CULTIVABLE, AND UNCULTIVABLE AREA, LAND REVENUE, ETC., IN 1881.
IN PROVINCES FOR WHICH RETURNS EXIST.
(Compiled from the *Provincial Census Reports*)

PROVINCE	Total Area Assessed and Unassessed in square miles	GOVERNMENT ASSESSED AREA IN SQUARE MILES			Total Govern-ment Land Revenue, includ- ing Cesses and Local Rates levied on Land	Total Rental paid by Cultivators, including Cesses and Rates	Average incidence of Government Revenue per Cultivated Acre		Average incidence of Rent per Cultivated Acre	
		Total	Cultivated	Cultivable	Un- cultivable		Rs.	d.	Rs.	d.
Government of Madras, . .	140,821	59,094	38,753	13,223	7,118	£ 6,716,181	Rs. 4 1½	5 0½	Rs. 4 1½	5 0½
Government of Bombay, . .	117,757	63,692	51,015	12,677	No returns	No returns	1 10½	No returns	No returns	No returns
Lieutenant Governorship of Bengal, .	150,588	No returns	No returns	No returns	No returns	13,489,196	2 0	4 4½	2 0	4 4½
Lieutenant Governorship of the Punjab, .	107,010	97,662	32,467	34,261	30,934	4,879,054	3 11½	6 8½	3 11½	6 8½
Lieutenant Governorship of Oudh, .	106,111	95,981	52,056	19,266	24,659	11,647,767	0 9½	1 8½	0 9½	1 8½
N. Western Provinces and Oudh, .	84,445	64,121	24,462	20,163	19,496	1,326,024	1 9½	..	1 9½	..
Chief-Commissionership of the Central Provinces, . .	27,666	6,714	6,714	No returns	No returns	No returns	2 1½	6 0½	2 1½	6 0½
Chief-Commissionership of Assam (exclusive of hill tracts), . .	17,714	12,702	10,069	1,773	860	No returns	2 0	No returns	2 0	No returns
Commissionership of Berar, . .	1,583	285	186	99	820	36,058	4 0½	..	4 0½	..
Commissionership of Coorg, . .	2,711	1,766	910	36	No returns	No returns	4 0½	..	4 0½	..
Commissionership of Ajmere, . .	87,220	5,443	5,400	43	No returns	703,237	2 9½	..	2 9½	..
Chief-Commissionership of British Burma, . .	843,626¹	407,460	222,032	101,541	83,887	38,094,280	2 9½	..	2 9½	..
TOTAL, . .										

1 The areas in this column are in some cases only approximate to those given in the general table of area and population of British India.

2 This average is exclusive of Bengal, for which Province no details of cultivated, cultivable, and uncultivable area are available.

APPENDIX IV.—POPULATION OF BRITISH INDIA, CLASSIFIED ACCORDING TO SEX AND AGE, IN 1881.

(Compiled from the Tables of the Imperial Census Report.)

PROVINCES.	MALES.				FEMALES.				BOTH SEXES.			
	Boys under 15.	Male Adults 15 and upwards.	Age unspecified.	Total Males.	Girls under 15.	Female Adults 15 and upwards.	Age unspecified.	Total Females.	Children under 15	Adults 15 and upwards.	Age unspecified.	Grand Total.
Government of Madras, . .	5,886,087	9,040,879	494,077	15,421,043	5,761,831	9,527,603	460,154	15,749,588	11,647,918	18,568,482	954,231	31,170,631
Government of Bombay, . .	3,371,089	5,126,629	..	8,497,718	3,065,956	4,890,740	..	7,956,696	6,437,045	10,017,369	..	16,454,414
Lieut.-Governorship of Bengal, ¹	14,229,149	20,271,425	125,017	34,625,591	13,420,629	21,382,277	108,364	34,911,270	27,649,778	41,653,702	233,381	69,536,861
Lt.-Governorship of the Punjab,	3,928,578	6,274,254	7,221	10,210,053	3,314,052	5,326,176	156	8,640,384	7,242,630	11,600,430	7,377	18,850,437
Lt.-Governorship of the North-Western Provinces and Oudh,	8,735,283	14,177,273	..	22,912,556	7,651,764	13,543,549	..	21,195,313	16,387,047	27,720,822	..	44,107,869
Chief-Commissionership of the Central Provinces, . .	2,053,909	2,905,326	200	4,959,435	1,949,987	2,929,182	187	4,879,356	4,003,896	5,834,508	387	9,838,791
Chief-Commissionership of Assam	1,011,010	1,401,303	91,390	2,593,703	938,905	1,349,172	89,646	2,377,723	1,949,915	2,750,475	181,036	4,881,426
Commissionership of Berar, .	513,382	867,110	..	1,380,492	497,496	794,685	..	1,292,181	1,010,878	1,661,795	..	2,672,673
Commissionership of Ajmere, .	89,033	159,811	..	248,844	75,472	136,466	..	211,878	164,505	296,217	..	460,722
Commissionership of Coorg, .	30,986	69,453	..	100,439	28,911	48,952	..	77,863	59,897	118,405	..	178,302
Chief-Com. of British Burma, .	776,890	1,214,115	..	1,991,005	734,526	1,011,240	..	1,745,766	1,511,416	2,225,355	..	3,736,771
Total, . .	40,625,396	61,507,578	717,905	102,850,879	37,439,529	60,939,982	658,507	99,038,018	78,064,925	122,447,560	1,376,412	201,888,897

¹ Including Native States superintended directly by the Bengal Provincial Government.

ANNEX V—POPULATION OF BRITISH INDIA CLASSIFIED ACCORDING TO RELIGION, IN 1881
(Compiled from the Tables of the *Imperial Census Report*)

Provinces	Hindus	Muhammadans	Aborigines and Tribes	Buddhists	Christians	Sikhs	Jains	Satviks	Kabirpanths	Natural worshippers	Parsees	Jews	Bráhmans	Kumbh pathás	Unspecified and Others	TOTAL OF ALL RELIGIONS
Government of Madras,	28,497,678	1,933,561		153	711,080		24,973				143	30	132		1459	31,170,631
Government of Bombay	12,308,582	3,022,131	562,678		138,317	127,100	216,224				72,065	7,932			365	16,454,414
Leutenant Governor of Bengal	45,458,626	21,704,724	1,055,821	155,801	128,135	549	1,609				156	1,059	788		5,404	69,536,861
Leutenant Governor of the Punjab	7,130,528	10,535,150		286	33,420	1,21,004	35,826				462	10	6		183	18,850,437
Leutenant Governor of the North-Western Provinces	38,053,394	5,922,886		10	47,664	3,644	79,957				399	63			12	9,838,791
Chief Commissioner of Oudh	7,317,830	275,773	1,533,599	17	11,949		97	45,783	358,161	294,474			177		692	4,281,426
Chief Commissioner of the Central Provinces	3,062,148	1,370,222	488,751	656	7,093		14	158			242	3				2,672,673
Chief Commissioner of Assam	2,425,754	167,551	37,338		1,335	525	20,020				75	94				460,722
Commissioner of Peshawar	316,029	57,854			2,725	182	24,368				21					178,302
Commissioner of Ajmere	162,489	12,541			3,521		99									3,736,771
Commissioner of Coorg	83,777	169,881		3,751	84,219		5				143,581	83	204	37	692	38,463,201
Chief Commissioner of India	144,875,315	45,127,033	4,677,688	3,418,476	1,068,589	1,253,115	448,897	358,161	294,474	143,581	73,760	9,506	1,147			888,897
TOTAL FOR BRITISH INDIA																

Statistics intended directly by the Bengal Provincial Government.

APPENDIX VI.—ASIATIC NON-INDIAN POPULATION OF BRITISH INDIA, CLASSIFIED ACCORDING TO BIRTH-PLACE, IN 1881.
(Compiled from the Tables in the Imperial Census Report.)

PROVINCES.	Afghanistan.	Arabia.	Baluchistan.	China.	Nepal.	Upper Burma.	Armenia.	Bhutan.	Ceylon.	Japan.	Java.	Persia.	Siam.	Straits Settlements.	Tibet.	Turkey in Asia.	Other Asiatic Countries, and unspecified.
Government of Madras, . . .	127	498	114	81	330	4	2332	9	4	31	15	390	3	72	...
Government of Bombay, . . .	7,265	4,626	57,312	285	105	70	...	15	2,672	12	130	1	215	...
Lieutenant-Governorship of Bengal, . . .	834	354	...	825	85,011	98	11	3,549	77	8	...	313	3	175	1,090
Lieutenant - Governorship of the Punjab, . . .	112,712	196	1,478	97	2,660	30	18	5	...	63	2	10	706
Lieut.-Governorship of the North-Western Provinces and Oudh, . . .	1,140	223	1	28	39,490	...	4	17	71	3	1	65	956
Chief - Commissionership of the Central Provinces, . . .	225	20	17	27	66	12	7	...	7	...	16	...
Chief-Commissionership of Assam, . . .	58	1	...	13	6,395	1,367	1	1	...	4
Commissionership of Berar, . . .	90	14	2	1	5	1	3	2	...
Commissionership of Ajmere, . . .	106	24	17	1	5	...
Commissionership of Coorg, . . .	17	4	1	14	...	1
Chief-Commissionership of British Burma, . . .	24	77	...	11,314	60	334,737	2	...	82	11	...	69	2,509	1,140
TOTAL, . . .	122,598	6,033	58,924	12,675	134,140	334,839	17	4,964	2678	36	21	3,224	2,541	1,856	2,756	310	...

Grand total of Asiatic non-Indians residing in British India, 688,828.

APPENDIX VIII.—LIST OF THE 149 TOWNS IN BRITISH INDIA OF WHICH THE POPULATION
EXCEEDS 20,000, IN 1881.

(Compiled from the Table in the Imperial Census Report.)

NAME OF TOWN.	PROVINCE.	DISTRICT.	POPULATION.
1. Bombay City and Island, . . .	Bombay,	773,196
2. Calcutta City, . . .	Bengal,	433,219
3. Calcutta Suburbs, . . .	Bengal,	251,439
Total,	684,658
4. South Suburban, . . .	Bengal, . . .	24 Parganás, . . .	51,658
5. North Suburban, . . .	Bengal, . . .	24 Parganás, . . .	29,982
Grand total of Calcutta and suburbs,	766,298
6. Madras City, . . .	Madras,	405,848
7. Lucknow, . . .	Oudh, . . .	Lucknow, . . .	261,303
8. Benares, . . .	N.-W. Provinces, . . .	Benares, . . .	199,700
9. Delhi, . . .	Punjab, . . .	Delhi, . . .	173,393
10. Patná, . . .	Bengal, . . .	Patná, . . .	170,654
11. Agra, . . .	N.-W. Provinces, . . .	Agra, . . .	160,203
12. Bangalore, . . .	Mysore, . . .	Bangalore, . . .	155,857
13. Amritsar, . . .	Punjab, . . .	Amritsar, . . .	151,896
14. Cawnpur, . . .	N.-W. Provinces, . . .	Cawnpur, . . .	151,444
15. Lahore, . . .	Punjab, . . .	Lahore, . . .	149,369
16. Allahábád, . . .	N.-W. Provinces, . . .	Allahábád, . . .	148,547
17. Rangoon, . . .	British Burma, . . .	Rangoon, . . .	134,176
18. Poona, . . .	Bombay, . . .	Poona, . . .	129,751
19. Ahmadábád, . . .	Bombay, . . .	Ahmadábád, . . .	127,651
20. Bareilly (Bareli), . . .	N.-W. Provinces, . . .	Bareilly, . . .	113,417
21. Surat, . . .	Bombay, . . .	Surat, . . .	109,844
22. Howrah, . . .	Bengal, . . .	Howrah, . . .	105,206
23. Meerut, . . .	N.-W. Provinces, . . .	Meerut, . . .	99,565
24. Nágpur, . . .	Central Provinces, . . .	Nágpur, . . .	98,299
25. Trichinopoli, . . .	Madras, . . .	Trichinopoli, . . .	84,449
26. Pesháwar, . . .	Punjab, . . .	Pesháwar, . . .	79,982
27. Dacca, . . .	Bengal, . . .	Dacca, . . .	79,076
28. Gayá, . . .	Bengal, . . .	Gayá, . . .	76,415
29. Jabalpur, . . .	Central Provinces, . . .	Jabalpur, . . .	75,705
30. Sháhjahánpur, . . .	N.-W. Provinces, . . .	Sháhjahánpur, . . .	74,830
31. Madura, . . .	Madras, . . .	Madura, . . .	73,807
32. Karáchi, . . .	Sind, . . .	Karáchi, . . .	73,560
33. Múltán, . . .	Punjab, . . .	Múltán, . . .	68,674
34. Bhágalpur, . . .	Bengal, . . .	Bhágalpur, . . .	68,238
35. Ambála, . . .	Punjab, . . .	Ambála, . . .	67,403
36. Moradábád, . . .	N.-W. Provinces, . . .	Moradábád, . . .	67,387
37. Darbhanga, . . .	Bengal, . . .	Darbhanga, . . .	65,955
38. Farukhábád, . . .	N.-W. Provinces, . . .	Farukhábád, . . .	62,437
39. Koil (Aligarh), . . .	N.-W. Provinces, . . .	Aligarh, . . .	61,730
40. Sholápur, . . .	Bombay, . . .	Sholápur, . . .	61,281
41. Saháranpur, . . .	N.-W. Provinces, . . .	Saháranpur, . . .	59,194
42. Gorakhpur, . . .	N.-W. Provinces, . . .	Gorakhpur, . . .	57,922
43. Calicut, . . .	Madras, . . .	Malabar, . . .	57,385
44. Mirzapur, . . .	N.-W. Provinces, . . .	Mirzapur, . . .	56,318
45. Faizábád, . . .	Oudh, . . .	Faizábád, . . .	55,570
46. Monghyr, . . .	Bengal, . . .	Monghyr, . . .	55,372
47. Tanjore, . . .	Madras, . . .	Tanjore, . . .	54,745
48. Negapatam, . . .	Madras, . . .	Tanjore, . . .	53,855
49. Bellary, . . .	Madras, . . .	Bellary, . . .	53,460
50. Maulmain, . . .	British Burma, . . .	Maulmain, . . .	53,107
51. Ráwal Pindi, . . .	Punjab, . . .	Ráwal Pindi, . . .	52,975
52. Jálándhar, . . .	Punjab, . . .	Jálándhar, . . .	52,119
53. Chaprá, . . .	Bengal, . . .	Sáran, . . .	51,570
54. Khampati, . . .	Central Provinces, . . .	Nágpur, . . .	50,987
55. Salem, . . .	Madras, . . .	Salem, . . .	50,667
56. Combaconum, . . .	Madras, . . .	Tanjore, . . .	50,098
57. Behar, . . .	Bengal, . . .	Patná, . . .	48,968
58. Ajmere, . . .	Rájputána, . . .	Ajmere, . . .	48,735
59. Haiderábád, . . .	Sind, . . .	Haiderábád, . . .	48,153
60. Muttra, . . .	N.-W. Provinces, . . .	Muttra, . . .	47,483
61. Siálkot, . . .	Punjab, . . .	Siálkot, . . .	45,762
62. Sagar (Saugor) . . .	Central Provinces, . . .	Ságar, . . .	44,416
63. Ludhiána, . . .	Punjab, . . .	Ludhiána, . . .	44,163
64. Cuddalore, . . .	Madras, . . .	South Arcot, . . .	43,545
65. Arrah, . . .	Bengal, . . .	Shahábád, . . .	42,998
66. Jaunpur, . . .	N.-W. Provinces, . . .	Jaunpur, . . .	42,845
67. Cuttack, . . .	Bengal, . . .	Cuttack, . . .	42,656
68. Shikárpur, . . .	Sind, . . .	Shikárpur, . . .	42,496
69. Muzaffarpur, . . .	Bengal, . . .	Muzaffarpur, . . .	42,460
70. Murshidábád, . . .	Bengal, . . .	Murshidábád, . . .	39,231
71. Firozpur, . . .	Punjab, . . .	Firozpur, . . .	39,570
72. Coimbatore, . . .	Madras, . . .	Coimbatore, . . .	38,967
73. Dinapur, . . .	Bengal, . . .	Patná, . . .	37,593

APPENDICES.

697

LIST OF 149 TOWNS IN BRITISH INDIA OF WHICH THE POPULATION EXCEEDS 20,000—cont n ed

NAME OF TOWN	PROVINCE	DISTRICT	POPULATION
74 Ahmadnagar	Bombay	Ahmadnagar	37,492
75 Vellore	Madras	North Arcot	37,491
76 Broach	Bombay	Broach	37,281
77 Conjevaram	Madras	Chengalpat	37,275
78 Hubli	Bombay	Dhárwar	36,677
79 Pálghát	Madras	Malabar	36,339
80 Amroha	Madras	Moradábád	36,143
81 Bandar (Masulipatam)	N W Provinces	Kistna	35,056
82 Etawah	Madras	Etawah	34,721
83 Bardwán	N W Provinces	Bardwán	34,080
84 Akyab	Bengal	Akyab	33,989
85 Bháráli	Brit sh Burma	Husar	33,762
86 Budaun	Punjab	Budaun	33,680
87 Mdnapur	N W Provinces	Mdnapur	33,560
88 Ghazipur	Bengal	Ghazipur	32,885
89 Belgáum	N W Provinces	Belgáum	32,697
90 Mangalore	Bombay	S Kanara	32,099
91 Hugli and Chnsura	Madras	Hugli	30,317
92 Agarpárá,	Bengal	24 Pargana	30,291
93 Vagapatam	Bengal	Vagapatam	30,017
94 Burhanpur	Madras	Nmár	29,721
95 Párá	Central Provinces	Párá	29,687
96 Sánpur	N W Provinces	Nad yá	29,028
97 Satára	Bombay	Satára	28,974
98 Bandá	Madras	Bandá	28,856
99 Coconada,	Brit sh Burma	Godávári	28,843
100 Prome	Bombay	Prome	28,304
101 Nadiad	N W Provinces	Kára	28,147
102 Basse n	Madras	Basse n	27,521
103 Chandaus	Brit sh Burma	Moradábád	27,505
104 Nellore	N W Provinces	Nellore	27,477
105 Krishnagar	Madras	Nad yá	27,389
106 Sukkur	Bengal	Sh kápur	27,191
107 Dhárwar	S nd	Dhárwar	27,190
108 Khurjá	Bombay	Bulandshahr	27,070
109 Násk	N W Provinces	Násk	26,728
110 Ellchpur	Bombay	Ellchpur	26,410
111 Tellcherr	Berar	Malabar	26,386
112 Cannanore	Madras	Malabar	25,656
113 Hathrá	Madras	Algarh	25,559
114 Serampur	N W Provinces	Hugli	25,092
115 Ellore	Bengal	Godávári	25,078
116 Hájpur	Madras	Muzaffarpur	25,022
117 Panpat	Bengal	Karnál	24,941
118 Rájahmadr (Rajahmundry)	Madras	Rápur	24,511
119 Batála	Central Provinces	Godávári	24,281
120 Rewári	Madras	Gurdaspur	23,971
121 Berhampur	Punjab	Gurgáon	23,601
122 Perhampur	Punjab	Murshdábád	23,511
123 Amráoti	Bengal	Ganjám	23,511
124 Tinneveli	Madras	Amráoti	23,211
125 Karnál	Madras	Tinneveli	23,111
126 Mayavaram	Madras	Karnál	23,011
127 Gujránwála,	Punjab	Tanjore	22,911
128 V zánagaram	Madras	Gojránwála	22,811
129 Adoni	Punjab	V zágapatam	22,711
130 Dera Gházi Khán	Punjab	Bellary	22,611
131 Dera Ismáíl Khán	N W Provinces	D G Khán	22,511
132 Deoband	Bengal	Saharanpur	22,411
133 Párá	Bengal	Puri	22,311
134 Na háli	Lengal	24 Parganas	22,211
135 Ir ndában	N W Provinces	Muttra	22,111
136 Sambháli	N W Provinces	Moradábád	22,011
137 Hoshiarpur	Punjab	Hosharpur	21,911
138 Fatehpur	N W Provinces	Fatehpur	21,811
139 Nas ríúd	Ajmere	Ajmere	21,711
140 Bettah	Bengal	Champáran	21,611
141 Jehlam (Jhelum)	Bengal	Jehlam	21,511
142 S rájganj	N W Provinces	Labná	21,411
143 Ch itagong	Madras	Ch itagong	21,311
144 Nagina	Bengal	I gnour	21,211
145 Karnul (Kurnool),	N W Provinces	Ka núl	21,111
146 Bázor	Madras	I alavor	21,011
147 Mainpurí	Madras	Ma npu f	20,911
148 Pánroti	Madras	S. Arcot	20,811

6 towns with above 50,000 inhabitants
2,000 and 30,000,

PROVINCES	MUHAMMADANS						CHRISTIANS			
	Male			Female			Male		Female	
	Under Instruction.	Able to Read and Write but not under Instruction.	Total Male Muhammadans	Under Instruction.	Able to Read and Write but not under Instruction.	Total Female Muhammadans	Under Instruction.	Able to Read and Write but not under Instruction.	Under Instruction.	Total Female Christians
Government of Madras	42 656	110 897	952 388	4 353	8 121	981 173	27 020	57 176	12 592	361 998
of Bombay	36 477	71 889	1 612 154	3 566	4 586	1 403 977	7 723	23 943	3 909	57 127
Leut. Governorship of Bengal	244 158	415 666	10 855 771	8 241	11 747	10 848 953	7 498	20 149	5 295	60 400
Leut. Governorship of the Punjab	68 551	95 816	5 639 845	3 224	2 399	4 885 305	2 234	17 874	1 609	8 376
Western Provinces and Oudh	57 850	116 763	3 022 445	2 428	3 474	2 900 441	5 632	19 988	3 958	16 456
Chief Commissionership of the Central Provinces	6 752	12 720	140 611	451	667	135 162	972	4 213	645	4 779
Chief Commissionership of Assam	7 614	14 307	673 189	89	205	643 833	441	1 549	306	3 005
Commissionership of Berar	2 760	3 859	97 230	85	117	90 325	78	424	38	563
of Ajmere	777	1 853	31 999	41	55	25 810	154	1 110	106	674
Chief Commissionership of Coorg	305	1 112	7 880	35	30	4 661	144	716	62	1 377
Chief Commissionership of British Burma	5 711	22 121	110 731	1 161	1 094	58 150	6 260	17 024	2 951	37 800
	473 611	867 003	23 144 243	23 634	32 495	21 982 790	58 176	164 166	31 491	552 375

APPENDIX IX.—POPULATION OF BRITISH INDIA, CLASSIFIED ACCORDING TO EDUCATION, IN 1881—continued.

PROVINCES.	BUDDHISTS.						SIKHS.			
	Male.			Female.			Male.		Female.	
	Under Instruction.	Able to Read and Write, but not under Instruction.	Total Male Buddhists.	Under Instruction.	Able to Read and Write, but not under Instruction.	Total Female Buddhists.	Under Instruction.	Able to Read and Write, but not under Instruction.	Under Instruction.	Total Male Sikhs.
Government of Madras, . . .	38	239	864	671
" of Bombay,	6,093	21,396	...	67,613
Lieut.-Governorship of Bengal, . . .	1,696	5,172	78,555	96	193	77,254	20	90	206	304
Lieut.-Governorship of the Punjab, . . .	33	196	1,359	1,505	9,458	35,976	1	639,460
Chief - Commissionership of the Western Provinces and Oudh, . . .	9	17	61	42	293	818	305	2,776
Central Provinces, . . .	1	3	10	7	4	20	3	59
Chief-Commissionership of Assam, . . .	247	535	3,863	...	54	2,700	1	2	...	5
Commissionership of Berar,	1	1	5	53	...	305
" of Ajmere,	15	39	...	115
" of Coorg,
Chief-Commissionership of British Burma, . . .	199,836	644,742	1,686,263	26,094	24,816	1,565,321
	201,860	650,905	1,770,976	26,190	25,063	1,647,500	15,879	58,394
							710,637	515	798	542,478

APPENDIX IX.—POPULATION OF BRITISH INDIA, CLASSIFIED ACCORDING TO EDUCATION, IN 1881—*continued*.

PROVINCES.	ALL OTHERS, including Kabirpanthis, Satnámis, Kumbhipathis, Jews, Nat-worshippers, Bráhmós, Aboriginal Tribes, and unspecified.					
	Male.			Female.		
	Under Instruction.	Able to Read and Write, but not under Instruction.	Total Male 'Others.'	Under Instruction.	Able to Read and Write, but not under Instruction.	Total Female 'Others.'
Government of Madras, . . .	33	73	910	11	17	751
" of Bombay, . . .	1,268	2,178	290,069	277	421	280,926
Lieut.-Governorship of Bengal, . . .	3,200	3,575	1,043,411	815	693	1,049,662
" of the Punjab, . . .	3	16	1,071	...	7	112
Lieut.-Governorship of the North-Western Provinces and Oudh, . . .	14	38	61	7	16	46
Chief-Commissionership of the Central Provinces, . . .	3,603	2,810	1,087,283	81	101	1,099,725
Chief-Commissionership of Assam, . . .	731	492	241,955	191	53	246,473
Commissionership of Berar, . . .	2	26	18,734	...	1	18,607
" of Ajmere, . . .	10	30	56	1	8	38
" of Coorg,
Chief-Commissionership of British Burma, . . .	2,054	2,604	73,604	620	243	70,218
	10,918	11,842	2,757,154	2,003	1,560	2,766,558

MILINDIN AND POPULATION OF BRITISH INDIA CLASSIFIED ACCORDING TO CASTE
(Continued from the Table in the Previous Census Report)

PROCESSES	HINDUS		MUSLIM ADAMS			CHRISTIANS			AUXILIARY CENSUS RESULTS	MISCELLANEOUS	GRAND TOTAL
	Brahmins	Rajputs	Other Castes	Sunnis	Shi'as	Wahabis	Unspecified	Christians	Born here and abroad		
Males	1,122,000	97,465	27,169,143	1,759,375	41,378	1,102,200,706	Unspecified	564,004	21,802	8,312	31,170,631
Females	664,411	106,966	11,447,655	2,040,764	78,531	1,631,278	Unspecified	111,803	23,601	4,370	16,154,414
Population	2,786,411	204,431	38,616,798	3,800,139	120,909	2,733,478	Unspecified	675,807	45,403	12,682	47,325,045
Population	800,081	65,181	5,669,266	1,030,022	95,655	2,114,475,630	Unspecified	86,366	14,705	12,682	69,536,861
Population	4,655,204	3,027,400	30,370,790	5,752,056	170,547	4,748,754	Unspecified	3,803	1,821	1,161	18,520,437
Population	332,207	221,819	6,763,771	259,608	6,772	186,907	Unspecified	5,558	1,301	699	44,107,869
Population	319,075	10,541	2,932,532	1,308,712	6,377	1,340,593	Unspecified	5,462	1,631	6,912	9,838,791
Population	65,754	46,148	2,313,752	185,686	1,360	39,470	Unspecified	579	54	37	4,881,426
Population	22,388	15,876	337,765	57,621	547	1	Unspecified	799	196	20	2,672,693
Population	2,445	480	1,59,564	12,540	1	1	Unspecified	2,637	87	2	4,607,217
Population			88,177	150,811	11,297	1,249,524	Unspecified	71,325	4,998	3,395	3,756,771
TOTAL FOR BRITISH INDIA	10,516,735	5,788,000	128,540,380	13,710,503	1,077,748	8,680,730,102	Unspecified	865,601	57,921	16,040	101,889,867

Includes Buddhists, Jains, Parsis, and others in the above figures. It will be observed that in regard to the Christians the difference probably arises from the Imperial Census Report. The total of Christians agrees with the special

INDEX.

—0—

A

- bars, an aboriginal tribe in Assam, 57
 aboriginal criminal tribes, 71, 72
 aboriginal tribes, non Aryan population,
 chap iii pp 53 74 Kistvaen builders,
 flint and bronze periods, 53, non
 Aryans of Vedic India, 53 54. Anda
 man islands, 55, Anamalu hillmen,
 55, Gonds and aboriginal tribes of the
 Central Provinces, 55, 56, the Juangs
 or leaf wearers of Orissa, 56 tribes of
 the Himalayas, 56, of Assam, 57,
 Santals their tribal government, his
 tory, religion, 57 60, the Kandhs of
 Orissa, their tribal government, blood
 revenge, marriage by capture, and
 human sacrifice, 60 63, origin of the
 non Aryan tribes, 63, the three non
 Aryan stocks—Tibeto Burman, Dra
 vidian, Kolanian, — their languages,
 63 68; statistics of non Aryan races in
 1872 and 1881, 69 71, Hinduizing
 tendency among aboriginal tribes, 70,
 71; crushed aboriginal tribes, 71,
 Eipsy clans, 71, aboriginal criminal
 tribes, 71, 72; the non Aryan hill
 tribes as soldiers, 72; Colonel Dixon's
 work among the Mhairs of Rájputana,
 73; Sir James Outram's work among
 the Bhils, 73; fidelity of the hill
 races, 73
Alorignes of India, by Mr B H Hodg
 son, quoted, 340 (footnote 1)
 Abu, Mount, in Rájputana, held sacred
 by the Jains, 35; 159
 Abul Fazl, Akbar's finance minister and
 historian, and the author of the *Ain i-*
Akbari, 300
Acta Sanctorum, The, of the Hindus,
 208
 Adams, Major, defeat of Mir Kásim by,
 at Gheriah and Udhanaia, 386
 Adams, Mr., acting Governor General
 (1823), 403
 Adam's Peak in Ceylon, Shrine common
 to Buddhism, Siva worship, and Mu
 hammadanism, 203
 Adil Shahi, Muhammadan dynasty in
 Southern India (1490 1636 A D), 288
 Administration of British India — See
 BRITISH ADMINISTRATION
 Adoption, Hindu practice of, 414, 415
 Afghan dynasty of Delhi (1540 56 A D),
 291
 Afghanistan, History of, under the
 Duranis (1747 1826), 406, early
 British dealings with (1800 37)
 407. Afghan dynastic quarrels, 407,
 Russian intrigues, 407, installation of
 Shah Shuja, and occupation of Kabul
 by a British force (1839), 407, 408
 rising of the Afghan people, murder of
 the British envoy, and massacre of the
 British army on its retreat through
 the passes to India (1841 42), 408, the
 British army of retribution, 408, 409
 Lord Ellenborough's proclamation,
 409, second Afghan war (1878 81),
 426 427, murder of Sir L. Cavignani,
 the British Resident, 427, retributive
 occupation of Kabul, 427; Sir F.
 Roberts' march from Kabul to Kan
 dahar, and defeat of Ayub Khan, 424,
 recognition of Abdurrahman Khán as
 Amir, 427, the Ráwal Pindi *dirtir*,
 427, trade routes to Afghanistan, 586,
 value of Afghan trade, 586
 Agastya, the Brahman Saint of Southern
 India, Legend of, 329
 Aghori, a carnion eating sect of Sivaite
 devotees, 214.
 Agni, the Vedic God of Fire, 80
 Agra, capital of Akbar the Great, who
 built the fort, 294; Akbar's tomb at
 Sikandra near, 295; embassy of Sir
 Thomas Roe to the Emperor Jahángir,
 301; 367; Shah Jahan's great architec
 tural works at the Taj Mahál and Moti
 Masjid, 304, deposition of Shah Jahan
 and imprisonment within Agra Fort
 (where he died), by his usurping son
 2 1

- Aurangzeb, 305; establishment of English factory at (1620 A.D.), 367.
- Agra Canal, 29; 532, 533.
- Agricultural Relief Acts for Southern India, 449, 450.
- Agricultural school at Sáidapet in Madras, 516.
- Agricultural stock in India, 519-523; famous breeds of cattle and horses, 520, 521.
- Agriculture and products, chap. xvii. pp. 482-544. Agriculture in India, the occupation of almost the entire population, 482, 483; various systems of agriculture, 483; rotation of crops, *petite culture*, 483, 484; statistics of rice cultivation in different Provinces, 484-486; hill cultivation, 486; wheat, 486; area under principal food-grains, 487; millets and minor cereals, 488, 489; pulses, 489; oil-seeds, 489; vegetables, fruits, and spices, 490; palms and sugar-cane, 491; cotton, 491-494; jute, 494, 495; indigo, 495-498; opium, 498, 499; tobacco, 499, 500; uncertainty of Indian crop statistics, 500; approximate area under certain principal crops, 501; special crops, coffee, 502-504; tea, 504-509; cinchona, 509-511; silk, 511-514; lac and lac-dye, 515; model farms, their small success, 515, 516; the problem of improved husbandry, 517; the impediments to better husbandry, namely, want of cattle, want of manure, and want of water, 517-519; agricultural stock, 519-523; forest conservancy and growth of the Indian Forest Department, 522; 524-527; nomadic cultivation, 527, 528; irrigation and its function in India during famine, 528, 529; irrigation areas in the different Provinces, 529-538; irrigation statistics for British India, 538, 539; famines and their causes, 539, 540; summary of Indian famines, 541, 542; the great famine in Southern India (1876-78), 542-544.
- Agriculture in India, small holdings, 62; absence of large commercial towns, 62.
- Ahams, tribe in Assam, formerly the ruling race in that Province, now a crushed tribe, 71; present descendants of, 188.
- Ahi, the Vedic Demon of Drought, 81 and footnote.
- Ahmadnagar, Muhammadan Kingdom of Southern India (1490-1636 A.D.), 288.
- Ahmad Sháh, Duráni (1747-61 A.D.), 314, 315.
- Ain-i-Akbari*, or chronicles of Akbar, translated by Professor H. Blochmann, 272 (footnote); 291 (footnote 1); 295 (footnotes).
- Aix-la-Chapelle, Madras restored to the English by the treaty of (1748), 379.
- Ajmere, establishment of an English factory at (1614 A.D.), 366.
- Akás, an aboriginal hill tribe in Assam, 57.
- Akbar the Great, founder of the Mughal Empire (1556-1605 A.D.), 291-300; chief events of his reign, 291 (footnote); his work in India, 292, 293; conciliatory policy towards the Hindus, 293; conquest of Rájput chiefs, and extension and consolidation of the Mughal Empire, 293, 294; change of capital from Delhi to Agra, 294; his religious faith, 295; army, judicial, and police reforms, 296; his revenue survey and land settlement of India, 297, 298; revenues of the Mughal Empire under Akbar, 297-300.
- Alabaster, Mr., *The Wheel of the Law*, quoted, 137 (footnote).
- Alá-ud-din, the second King of the Khilji dynasty (1295-1315 A.D.), 281; his invasion and conquest of Southern India, 281, 282; massacre of Mughal settlers, 282; Hindu revolts, 282.
- Albuquerque, second Viceroy of Portuguese India (1509 A.D.), 359; his capture of Goa, and death there, 359; his policy towards the natives, 359, 360.
- Albuquerque, John de, first Bishop of Goa (1539-53 A.D.), 244.
- Alexander the Great, his expedition to India, and campaigns in the Punjab and Sind (327-325 B.C.), 163-166.
- Alexandria, the modern Uchh in the Punjab, founded by Alexander, 166.
- Alfred the Great's Mission to India (883 A.D.), 239.
- Alí Vardi Khán, Nawáb of Bengal (1740-56); construction of the Maráthá ditch around Calcutta as a protection against the Maráthás, 381.
- Aligarh, Defeat of the Maráthás at, by Lord Lake (1803), 398.
- Alíwál, Battle of, in the first Sikh war, 411.
- Allahábád and Kora made over to the Mughal Emperor by Clive, 387 and footnote; their resumption by Hastings and sale to the Wazir of Oudh, 389, 390.
- Almeida, Francisco de, first Viceroy of Portuguese India (1505 A.D.), 359.
- Alphabets of ancient India, 102, 103.
- Altamsh, the third monarch of the Slave dynasty (1211-36 A.D.), invasion by Mughals, 279.
- Ambála *darbár*, The, 425.

- Amboyna, massacre of, 362, 368, 561
 Amherst, Lord, Governor General of India (1823 28), first Burmese war (1824 26), capture of Bhartpur, 403, 404
 Amir Khan, the Pindari leader (1817), 404
 An or Aeng, Pass over the Arakan Yoma Mountains in Burma 6
Analysis of the Constitution of the East India Company, by P. Auber, quoted, 364, 365 (footnotes)
 Analysis of Indian foreign import and export trade, principal staples, 565 581
Ancient India as described by Megasthenes and Arrian, by Mr J. McCrindle, quoted, 168 (footnote 1), 356 (footnote)
 Ancient land system of India, 438
 Ancient mingling of castes, 195, 196
 Andaman Islanders, The, 55, assassination of Lord Mayo at Port Blair, 425
Anecdota Oxoniensia, Aryan series, 102 and footnote
Annals and Antiquities of Rajasthan, by Colonel Tod, quoted, 180 (footnotes 1 and 3), 184 (footnote 2), 185 (footnotes 1 and 3)
 Antelope and deer, Varieties of, 657, 658
 Antimony, 626
 Arab expeditions to Bombay and Sind (636 828 A.D.), 268.
 Arakan Oil Company, 626, 627
 Arakan Yomas, range of hills in Burma, 3
Archaeological Survey of Western India Mr E. Thomas' Papers in, quoted, 147 (footnote), 172 (footnotes), 175 (footnote 3), 182 (footnotes 1 and 4), 185 (footnote 4)
 Architecture, ancient Indian, 112, 170, under the Mughal Emperors, 294, 304
 Arcot, capture and defence of, by Clive (1751), 379, rival French and English nominees for the throne of, 379
 Area, towns, villages, houses, population, etc., of British India, Appendix I, 689
 Argáum, Battle of, 323, 398
 Armagaon, East India Company's factory established at (1625 26 A.D.), 368
 Army of India, its constitution, 470, 471, the armies of the three Presidencies, 471, strength, 471; health and vital statistics, 675 684
 Art and architecture in ancient India, 112; 170, 171
 Arts and manufactures, 112, 113, also chap. xv pp 595 617 English competition with native art work, 598; native rural industries, 599; fortified weaving settlements of the East India Company, 599, cotton weaving an indigenous industry in India, 599, its decline, but still a domestic industry supplying three fifths of the Indian consumption, 600, cotton weaving in different Provinces, 600, 601, special Indian cotton fabrics, 601 603, Indian silk weaving in Burma, Assam, and Bengal, 602, classes of silk fabrics, 602, 603; steam silk factories, 603, embroidery, 603, Kashmir shawls, 603, leather work, 603, velvet work, 603, jewelled embroidery, 604, carpets and rugs, 604, 605, goldsmith's work and jewellery, 605, 606; precious stones, 606, iron work and cutlery, 606, chain armour and damascene work, 606, 607, brass, copper, and bell metal work, 607, 608, pottery and tile work, 608, sculpture, 608, 609, wood carving, 609, inlaying and ivory carving, 609, European industries, cotton mills, 610 615, jute mills, 614 616, breweries, 616, 617, paper mills, 617, leather factories, 617
 Aryan and Turanian migrations from Central Asia, 174 175, 130, 131
 Aryan races of India, number in 1881, 51 Also chap. iv pp 75 131 The Aryan stock, its European and Eastern branches, 75, the Aryans in their primitive home, 75, 76, European and Indian languages merely varieties of Aryan speech, 76, Indo European words, 76, common origin of European and Indian religions, 76, the Indo Aryans on the march, and in their new settlements 76, 77, the Rig Veda, its supposed dates, 77, Vedic hymns, 78; caste and widow burning unknown to the Rig Veda, 78, Aryan civilisation in the Veda, 79; eastern spread of the Aryans, 79, the gods of the Veda, 79, Indra, the Cloud Compeller or rain bringer, and Agni, the God of Fire, 80, 81; other Vedic gods, 81; the Brahmanical triad 81, Flood loving deities of Hinduism scarcely known in the Veda, 82, the Horse Sacrifice a substitution for Human Sacrifice, 82, Vedic conception of the Deity, 82, a Vedic hymn, 82, 83, primitive Aryan funeral, 84, burning of the dead, 84, 85, Vedic legend of Yama, the King of Death 85, Vedic farewell to the dead, 85, Vedic conception of immortality, 86, Aryan advance towards the Jumra and Upper Ganges, 86, Aryan tribes organized into kingdoms, 87; origin of princely

- families, 87; growth of the priesthood, 87, 88; the four Vedas, 88; the Bráhmaṇas, 88, 89; the Sūtras or sacred traditions, 89; formation of the Bráhmaṇ caste, 89; growth of the warrior or Kshattriya caste, 89, 90; the cultivating caste (Vaisya), 90; the four Hindu castes, 90, 91; increase of Bráhmaṇ, Kshattriya, and Śūdra castes, 91; decrease of Vaisyas, 91, 92; struggle between the priestly and warrior castes, 92; rising pretension of the Bráhmaṇs, 92; well-known prehistoric legends of Kshattriyas attaining Bráhmaṇhood, 92, 93; the Middleland, the focus of Bráhmaṇism, 93; Aryan tribes outside the Bráhmaṇical pale, 93; establishment of Bráhmaṇ supremacy, 94; four stages of a Bráhmaṇ's life, 95; the Bráhmaṇ rule of life and its hereditary results on the caste, 96; work done by Bráhmaṇs for India, 97; Bráhmaṇ theology, 97; the post-Vedic gods, 97, 98; the Hindu triad, 98; Bráhmaṇ philosophy, its six *darsanas* or schools, 98, 99; summary of Bráhmaṇ religion, 100; Bráhmaṇ science, 100; Sanskrit grammar, 100, 101; Sanskrit and Prakrit speech, 101; Sanskrit manuscripts, 102; the Indian alphabets, 102, 103; Sanskrit writings almost entirely in verse, 103; prose, a forgotten art, 103, 104; Sanskrit dictionaries, 104; Bráhmaṇ astronomy, 104-106; Bráhmaṇ mathematics, 106; Bráhmaṇ medicine, 106-110; Indian surgery, 107, 108; Buddhist public hospitals, 108, 109; decline of Hindu medicine, 109; English Medical Colleges, 108, 109; vernacular medical publications, 110; Hindu art of war, 110; Indian music, 110-112; Indian architecture, 112; Indian decorative art and painting, 112, 113; Bráhmaṇ law, 113-118; code of Manu, 113, 114; code of Yajñavalkya, 114, 115; scope of Indian law, its rigid caste system, 115, 116; growth of Hindu law, 116; its incorporation of local customs, 117; perils of modern codification, 117, 118; secular literature of the Hindus, 118-129; the Mahābhārata, 118-122; the Rāmāyana, 122-125; age of the Sanskrit drama, 125, 126; Śakuntala and other Hindu dramas, 126, 127; the Hindu novel, 127; Beast stories, 127; Sanskrit lyric poetry, 128; the Purānas, 128, 129; Indian modern vernacular literature, 129; intellectual and religious development of the early Aryans, 129, 130; the Bráhmaṇs in Indian history, and attacks on Bráhmaṇism from the 6th to the 19th century, 130, 131.
- Aryan influences on the Dravidian races, 329, 330; the modern Aryan vernaculars of India, 334-355.
- Asiatic non-Indian population of British India, Appendix VI., 694.
- Asoka, Buddhist King of Magadha or Behar (257 B.C.), 144-147; his Great Council (244 B.C.), 144; his Rock and Cave Edicts, 145 and footnote; his Department of Public Worship, 145; his missionary efforts and doctrinal code, 145; character of the Rock Edicts, 146, 147 and footnote.
- Assam, unsuccessful invasion of, by Aurangzeb's general, Mir Jumlá, 309; expulsion of the Burmese from, and annexation of Assam to British territories (1826), 404; yearly settlement of the land revenue, 445; frontier trade of, 588-590.
- Assaye, Battle of, 323; 398.
- "Assisted" railways in India, 548.
- Astronomy, Bráhmaṇical system of, 104-106; astronomy of the Vedas, 104; Greek influences on Indian astronomy, 105; decay of astronomical science under Muhammadan rule, 105; Rājā Jai Singh's observatories in the 18th century, 105, 106.
- Aswamedha or Great Horse Sacrifice of ancient India, 82; connection of the Horse Sacrifice with the Human Sacrifice of pre-Buddhistic times, 175, 176.
- Atharva-Veda, The, 88.
- Atrai, river of Bengal; its changes of course, 30.
- Auber's *Analysis of the Constitution of the East India Company*, quoted, 364, 365 (footnotes).
- Auckland, Lord, Governor-General of India (1836-42), 406-409; Afghán affairs and our early dealings with Kábul, 406, 407; Dost Muhammad, Afghán dynastic wars, 407; Russian influences in Afghánistán and the installation of Sháh Shujá and occupation of Kábul by a British force, 407, 408; rising of the Afghán people, and massacre of the British army on its retreat to India, 408.
- Aurangzeb, sixth Mughal Emperor of India (1658-1707 A.D.), 305-312; his rebellion and usurpation of the throne, 305, 306; chief events of his reign, 306, 307 and footnote; murder of his brothers, 307; conquests in Southern India, 307; rise of the Maráthá power, 307, 308; Aurangzeb's Grand Army and twenty years' guerilla war with the Maráthás, 308, 309; his despair and death, 309; unsuccessful expedi-

INDEX

- tion to Assam 309, his bigotry and persecution of the Hindus, 309, revolt of the Raptus, 309, 310, revenues of the Empire, 310, 311; Aurangzeb's character, 312
Australia, India's trade with 578, 579
Avatars or Incarnations of Vishnu, 215, 216 (footnote 3)
- B**
- Babar, first Mughal Emperor of Delhi, (1526 30 A.D.), early life, defeat and overthrow of Ibrahim Lodi at Panipat, conquest of Northern India, 290, 291
Bahmani, Muhammadan dynasty in Southern India (1347 1525 A.D.), 287
Bairam Khan, regent of the Mughal Empire during the early years of Akbar's reign, 291, 292
Baji Rao, second Maratha Peshwa (1721 40 A.D.), his conquest of the Deccan and Malwa from the Mughals, and capture of Bassein from the Portuguese, 320
Baji Rao II, seventh and last Maratha Peshwa (1795 1818), 323, second and third Maratha wars, and annexation of the Peshwa's territories, 323, 324
Balaji Baji Rao, third Maratha Peshwa (1740 61), his expeditions to Bengal and to the Punjab, defeat of, by Ahmad Shah Durrani at the third battle of Panipat, 320, 321
Balaji Viswanath, first Maratha Peshwa (1718 20), extorts *chauth* from the Delhi Emperor for the Deccan, 320
Balance sheet of British India, 465 466
Balance of trade (India's), 558, 559, Sir R. Temple's Minute on, 581 583
Palasor, Last India Company's factory founded at (1642 A.D.) 369
Balban, the last king but one of the Slave dynasty (1265 87 A.D.), his cruelties to the Hindus, Rajput revolts and Mughal inroads, his fifteen royal pensioners, 280.
Pallantyne, Dr., *The Sankhya Aphorisms of Kapila*, quoted, 154 (footnote 1)
Bankipur, old settlement of the Ostend Last India Company on the Hugli
between Calcutta and Chinsurah, its destruction by the Muhammadans (1753), 374
Bantam, a Presidency of the East India Company in Java, 368, 369
Baptist Mission of Carey, Marshman, and Ward at Serampur, 260
Barak river, Steam Navigation on, 552
Barakhar coal seams, 637
Bari Doib Canal, 29, 532, 533
Barid Shahi, Muhammadan dynasty of Southern India (1492 1657 A.D.), 288
Barlaam and Josaphat (Saints) Legend of, and its analogies with that of Buddha, 151, 152
Barlow, Sir George, *ad interim* Governor General (1805 07), Mutiny of Vellore, 399
Baroda, Maratha State of Western India, 322, 323, deposition of the late Gaekwar for an attempt to poison the British Resident at his Court, 323, 426
Bartholomew the Apostle, his preachings in India certified by Pantænus the Alexandrian (2nd century A.D.), 235, conversion of India proper ascribed to St Bartholomew, and of Persia and Central Asia to St Thomas, according to Hippolytus (220 A.D.), 235
Barth's *Religions of India*, quoted, 161 (footnote 2), and his *Aczue de l'Histoire des Religions*, quoted, 161 (footnote 2)
Bassein, capture of, from the Portuguese by the Marathas, 320, treaty of, at the conclusion of the second Maratha war, 323
Baxar, defeat of the Mughal and Oudh armies at, by Major Munro, 386
Beal, Samuel, *Sa ju ki, or Buddhist Record of the Western World*, translated from the Chinese of Huen Tsiang, quoted, 2 (footnote), 137 (footnote 2), 154, 155 (footnote 3), 155 (footnote 2), 175 (footnote 1), *Catena of Buddhist Scriptures from the Chinese*, 142 (footnote), 147 (footnote 2), 151 (footnote 1), 157 (footnote 2), 204 (footnote 2)
Beames, Mr John, *Comparative Grammar of the Modern Aryan Languages of India*, 67 (footnote), 103 (footnote), 335 and footnote, 337 (footnote 2), 339 and footnote
Bears, Species in India of, 655
Beast stories and fables, 127, beast hospitals, 201
Lediya's, a semi Hinduized gipsy clan of Lower Bengal, 71
Bells, manufacture of, 607
Benfey, Professor, article 'Indien' (published in Ersch and Gruber's *Encyclopædie*), quoted, 110 (footnote 2)
Bengal, early English settlements in 368 385, first permission to trade (1634 A.D.), 368, factories at Hugli, Balasore, and Kasimbazar, 369, 370
Bengal separated from Madras, 370
English in Bengal and their early factories, 380, native rulers of Perga (1707 56), Murshid Kuli Khan, Vardi Khan, and Siraj ul daula 381, capture of Calcutta, the '12

- [illegible]

supremacy of the Brahmins 92 94 1
 Viswamitra the Kshatriya 11 1
 Vasishtha the Brahmin 92 93 11
 four stages of a Brahmin's life 95
 Brahmin rule of life at its best 97
 results of caste 92 93 11
 theology the post-Vedic 11 11
 the Hindu mind 11 11 11
 or Brahmin philosophy 11 11 11
 92 93 11 11 11
 100 101 11 11 11
 110 111 11 11 11
 112 113 11 11 11

111 112 113 114 115 116 117 118 119 120
 121 122 123 124 125 126 127 128 129 130
 131 132 133 134 135 136 137 138 139 140
 141 142 143 144 145 146 147 148 149 150
 151 152 153 154 155 156 157 158 159 160
 161 162 163 164 165 166 167 168 169 170
 171 172 173 174 175 176 177 178 179 180
 181 182 183 184 185 186 187 188 189 190
 191 192 193 194 195 196 197 198 199 200
 201 202 203 204 205 206 207 208 209 210
 211 212 213 214 215 216 217 218 219 220
 221 222 223 224 225 226 227 228 229 230
 231 232 233 234 235 236 237 238 239 240
 241 242 243 244 245 246 247 248 249 250
 251 252 253 254 255 256 257 258 259 260
 261 262 263 264 265 266 267 268 269 270
 271 272 273 274 275 276 277 278 279 280
 281 282 283 284 285 286 287 288 289 290
 291 292 293 294 295 296 297 298 299 300
 301 302 303 304 305 306 307 308 309 310
 311 312 313 314 315 316 317 318 319 320
 321 322 323 324 325 326 327 328 329 330
 331 332 333 334 335 336 337 338 339 340
 341 342 343 344 345 346 347 348 349 350
 351 352 353 354 355 356 357 358 359 360
 361 362 363 364 365 366 367 368 369 370
 371 372 373 374 375 376 377 378 379 380
 381 382 383 384 385 386 387 388 389 390
 391 392 393 394 395 396 397 398 399 400
 401 402 403 404 405 406 407 408 409 410
 411 412 413 414 415 416 417 418 419 420
 421 422 423 424 425 426 427 428 429 430
 431 432 433 434 435 436 437 438 439 440
 441 442 443 444 445 446 447 448 449 450
 451 452 453 454 455 456 457 458 459 460
 461 462 463 464 465 466 467 468 469 470
 471 472 473 474 475 476 477 478 479 480
 481 482 483 484 485 486 487 488 489 490
 491 492 493 494 495 496 497 498 499 500
 501 502 503 504 505 506 507 508 509 510
 511 512 513 514 515 516 517 518 519 520
 521 522 523 524 525 526 527 528 529 530
 531 532 533 534 535 536 537 538 539 540
 541 542 543 544 545 546 547 548 549 550
 551 552 553 554 555 556 557 558 559 560
 561 562 563 564 565 566 567 568 569 570
 571 572 573 574 575 576 577 578 579 580
 581 582 583 584 585 586 587 588 589 590
 591 592 593 594 595 596 597 598 599 600
 601 602 603 604 605 606 607 608 609 610
 611 612 613 614 615 616 617 618 619 620
 621 622 623 624 625 626 627 628 629 630
 631 632 633 634 635 636 637 638 639 640
 641 642 643 644 645 646 647 648 649 650
 651 652 653 654 655 656 657 658 659 660
 661 662 663 664 665 666 667 668 669 670
 671 672 673 674 675 676 677 678 679 680
 681 682 683 684 685 686 687 688 689 690
 691 692 693 694 695 696 697 698 699 700
 701 702 703 704 705 706 707 708 709 710
 711 712 713 714 715 716 717 718 719 720
 721 722 723 724 725 726 727 728 729 730
 731 732 733 734 735 736 737 738 739 740
 741 742 743 744 745 746 747 748 749 750
 751 752 753 754 755 756 757 758 759 760
 761 762 763 764 765 766 767 768 769 770
 771 772 773 774 775 776 777 778 779 780
 781 782 783 784 785 786 787 788 789 790
 791 792 793 794 795 796 797 798 799 800
 801 802 803 804 805 806 807 808 809 810
 811 812 813 814 815 816 817 818 819 820
 821 822 823 824 825 826 827 828 829 830
 831 832 833 834 835 836 837 838 839 840
 841 842 843 844 845 846 847 848 849 850
 851 852 853 854 855 856 857 858 859 860
 861 862 863 864 865 866 867 868 869 870
 871 872 873 874 875 876 877 878 879 880
 881 882 883 884 885 886 887 888 889 890
 891 892 893 894 895 896 897 898 899 900
 901 902 903 904 905 906 907 908 909 910
 911 912 913 914 915 916 917 918 919 920
 921 922 923 924 925 926 927 928 929 930
 931 932 933 934 935 936 937 938 939 940
 941 942 943 944 945 946 947 948 949 950
 951 952 953 954 955 956 957 958 959 960
 961 962 963 964 965 966 967 968 969 970
 971 972 973 974 975 976 977 978 979 980
 981 982 983 984 985 986 987 988 989 990
 991 992 993 994 995 996 997 998 999 1000

- revenues, 465, 466; nature of the land-tax, 467; items of taxation summarized, 460, 461; 467, 468; Indian expenditure,—the army, public debt, loss by exchange, public works, railways, etc., 468-470; local and municipal finance, 470; constitution and strength of the three Presidency armies, 471; police and jail statistics, 472; education, 472-479; education in ancient India, village schools and Sanskrit *lots*, 472, 473; the Company's first efforts at education, the Calcutta *Madrasa* and other colleges, 473; mission schools, 473; State system of education, 474, 475; the Education Commission of 1882-83, and its recommendation, 474; educational statistics of British India, 474, 475; the Indian Universities and their constitution, 475, 476; colleges, middle schools, and primary schools, in the various Provinces, 476-478; girls' schools, 478, 479; normal and other special schools, 479; the vernacular press and native journalism, 480; registered publications in India, 480, 481.—For historical details, see *ENGLISH IN INDIA*, and *HISTORY OF BRITISH RULE*.
- British Burma, its physical geography, products, etc., 41, 42.—See also *BURMA*.
- British conquest of India, not from the Mughals but from the Hindus, 317.
- British India, its twelve Provinces, area and population in 1881, 43-45; also Appendices I. to X., 689-703.
- Britto, John de, Jesuit priest in Southern India, murdered (1693 A.D.), 245.
- Brocades, 603.
- Brydon, Dr., the solitary survivor of the Kábul garrison in its retreat from Afghánistán, 408.
- Bucephala, memorial city on the west bank of the Jehlam, founded by Alexander, and named after his favourite charger, Bucephalus, near the modern Jalálpur, 165.
- Buchanan - Hamilton, Dr. Francis, his MS. Survey of the North - Eastern Districts of Bengal, quoted, 205, 206 (footnote 4); 207 (footnote 1).
- Buckingham Canal in Madras, navigation on, 553.
- Buddha, the Sakya, 176, 177.
- Buddha, his Life, his Doctrine, his Order*, by Professor Oldenberg, quoted, 161 (footnote 3).
- Buddhism, and life of Gautama Buddha, chap. v. pp. 132-162. The story of Buddha modelled on the pre-existing Indian epic type, 132-135; Buddha and Ráma compared, 132; parentage of Buddha, his youth and early married life, 133; his Great Renunciation, 133, 134; his Temptation in the forest, 134; his 'Enlightenment,' 134, 135; his public teachings and disciples, 135; his conversions in the Gangetic valley, and of his own family, 135, 136; his last words and death, 136; different versions of the legend of Buddha, 136, 137; biographies of Buddha, 137, 138; the southern and northern versions, 138; political life of Buddha, 139; defeat of his opponents by magical arts, 139, 140; overthrow of the schismatic Devadatta, 140; Buddha as a Sakya prince, 140; Chinese text of Buddha's dying discourse, 141; his doctrines, 141; law of *Karma*, 141, 142; law of *Nirvana* or 'liberation,' 142; moral code of Buddhism, 143; missionary aspects of Buddhism, 143; the four great Buddhist Councils, 143-147; the work of Asoka, his great Council, 144-146; his Rock Edicts, 144, 145; Asoka's missionary efforts, 146, 147; his reformed canon of the Buddhist scriptures, 146, 147; Kanishka's Council and his three commentaries on the Buddhist faith, 147; the northern and southern canons, 147, 148; Buddhism as a national religion, 148; its religious orders and practical morality, 148, 149; spread of Buddhism in the south to Ceylon, and in the north to China, 149, 150; Buddhist influence on Christianity, 150, 151; Buddha as a Christian saint, 151; legend of saints Barlaam and Josaphat, 151, 152; a Japanese temple, its analogies to Hinduism and Christianity, 152; Buddha as an incarnation of Vishnu, 153; Buddha's personality denied, 153, 154; continuous co-existence of Buddhism and Bráhmanism, 154; modern Hinduism, the joint product of both religions, 154, 155; Buddhism in India in the 7th century A.D., 156; Council of Siláditya, 156; Siláditya's charity, 156, 157; monastery of Nalanda, 157; mingling of Buddhism and Bráhmanism, 157; victory of Bráhmanism, 157, 158; Buddhism an exiled religion from India, 158; its foreign conquests, 158; Buddhist survivals in India, 158-162; the Jains, 158-162; Jain doctrines, 159; Jain temple cities, 159; relation of Jainism to Buddhism, 159, 160; antiquity of the Jains, 160, 161; date of the Jain scriptures, 161, 162; the Jains an independent sect, 162; modern Jainism, 162.
- Buddhist population in India, 136 (and footnote); see also Appendix V., 693;

- Buddhist influences on later religions,
 of a Japanese temple to
 Buddhism and Christianity, 152, 202
 oes, 520; 658
 r, Dr G., *Tour in Search of Sanskrit*
 S., published in the *Journal of the*
Library Branch of the Asiatic Society,
 2 (footnotes 1 and 3), 1877, quoted,
 2 (footnote 2)
Indu Law of Inheritance, Partition,
Adoption, 117 (footnote 2)
 lding stone, 627, 628
 ndelas, a Rajput tribe, formerly
 the ruling race in Bundelkhand,
 ousted by the Marathas, 71 and foot
 note
 urma, in ancient times and in the 15th
 century A D., 403, encroachments on
 India and first Burmese war (1824-26),
 403-404, annexation of Assam,
 Arakan, and Tenasserim, 404, second
 Burmese war (1852) and annexation of
 Pegu, 413, 414, prosperity of Burma
 under British rule, 414; annexation of
 Upper Burma (1st January 1886),
 430, export of rice from, 572, trans
 frontier trade with, 588-590, geology
 of, 639, 640 — See also BRITISH
 BURMA
 Burnell, Dr., *Palaeography of Southern*
India, quoted, 103 (footnote), *The*
Ordinances of Manu, 114 (footnotes),
Daya vibhagha, 117 (footnote), 195
 (footnote 2)
 Burnes, Sir Alexander, assassination of,
 in Kabul (1841), 408
 Cabot's attempt to reach India by way of
 the north west passage, 363
 Cabral's expedition to India (1500 A D.),
 and establishment of Portuguese fac
 tories at Calicut and Cochin, 358
 Cacharls, a semi-Hinduized aboriginal
 tribe of Assam and North Eastern
 Bengal, 71 (footnote)
 Calcutta founded (1686 A D.), 371, cap
 ture of, by Siraj ud Daula, and the
 Black Hole, 381, re capture of Calcutta
 by Clive, 381, 382, Calcutta Canals,
 553, Calcutta as a seaport and its share
 of trade, 559, 560
 Caldwell, Bishop, *Comparative Grammar*
of the Dravidian Languages, quoted,
 65-68, and footnotes, 173 (footnote 2),
 240 (footnote 1), 327 (footnotes 2 and
 3), 328 (footnote), 330 (footnote 1); 369
 332 (footnote); 340 (footnote 1); 369
 (footnote)
 Calicut, visits of Vasco da Gama to, and
 establishment of a Portuguese factory,
 357, 358, attempt of the English to
 establish a factory at, 367
 Camels, 520, camel hair embroidered
 shawls, 603
 Campbell, Sir Colin (Lord Clyde) relief
 of Lucknow by, 421, campaign in
 Oudh, 421, 422
 Campbell, Sir George, *Specimens of the*
Languages of India, quoted, 67 (foot
 note)
 Canals (irrigation) in Sind and Bombay
 530, 531, the three great Punjab canals,
 531, 532 the Doab canals in the North
 Western Provinces 532, 533. Orissa
 canal system, 534, the Son canal
 and irrigation in Bengal, 534, 535
 irrigation works in the Madras delta,
 536, 537
 Canning Earl Governor General of
 India (1856-62) 417-424 The Mu
 tiny of 1857-58, 417-424, downfall
 of the Company, 422, India trans
 ferred to the Crown, and the Queen's
 Proclamation 423, 424, Lord Canning
 the first Viceroy, 424, financial and
 legal reforms 424
 Car Festival of Jagannath 224-226, self
 immolation not practised, 224, blood
 less worship and gentle doctrines of,
 225, 226
 Carnelians 629
 Carpet weaving, 604
 Caste, formation of the four castes,
 87-91
 Caste rewards and punishments, 199
 200
 Caste system, its religious and social
 aspects, 192-200
 Catena of Buddhist Scriptures from the
Chinese, by Mr S. Beal, quoted, 142
 (footnote 1), 147 (footnote 2), 150
 (footnote 3), 157 (footnote 2)
 (footnote 2), 204 (footnote 2)
 Cathay and the Way Thither, by Colonel
 Yule, quoted, 233 (footnote 2), 235
 (footnote 3)
 Catholic Missions in India, 229-259
 Origin of Christianity in India, 229,
 230, the three legends of St Thomas,
 the Apostle, Thomas the Manichean,
 and Thomas the Armenian and their
 respective claims as the founder of
 Indian Christianity, 231-235, Nesto
 rian Church in Asia side by side
 with Buddhism for 1000 years, its
 wide diffusion, 235, 236, the forcible
 conversion of the Nestorians or St
 Thomas Christians, to the Church of
 Rome, by the Portuguese, 241-243
 Syrian and Jacobite Catholics in
 Malabar, 243, 244: labours of St
 Francis Xavier, 2
 priests, their con

- labours, agricultural settlements, and collegiate city of Cochin, 245-253; Portuguese inquisition established at Goa, *auto da fé*, and abolition of the inquisition, 253, 254; suppression of the Jesuits (1759-73), and their re-establishment (1814), 254, 255; organization of modern Roman Catholic Missions, 255; jurisdiction of the Archbishop of Goa, 255, 256; distribution of Roman Catholics, 257; Syrian and Roman Catholic Christians, 257; Roman Catholic population of India, 258; progress of Roman Catholicism, its missions, colleges, and schools, 259.
- Cattle, Breeds of, 520.
- Cave inscriptions of Asoka, 145, 146.
- Cawnpur, the Mutiny at, massacre of the garrison and the women and children, 420.
- Central Asia, trans-Himalayan trade with, 586-592.
- Ceylon, India's trade with, 578, 579.
- Chain armour, manufacture of, 606, 607.
- Chaitanya, Hindu religious reformer (1485-1527 A.D.), his life and teachings, 219-221.
- Chait Singh, Rājā of Benares, exactions of Warren Hastings from (1780), 390.
- Chandarnagar, French Settlement in Bengal, 381; bombardment and capture of, by Admiral Watson (1757), 382.
- Chand Bardāi, Hindi poet (12th century), 345.
- Chandelas, formerly a ruling race in Bundelkhand, North-Western Provinces, 71.
- Chandi Dās, religious poet of the 15th century, 348; hymn to Krishna, 348, 349.
- Chandra Gupta, King of Magadha (326 B.C.), 166-170; cession of the Greek possessions in the Punjab to, by Seleukos, Alexander's successor (306 B.C.); the Embassy of Megasthenes, 167-170.
- Changes of caste occupation by the Shāhas, Telis, and Tambulis of Bengal, 196, 197.
- Changes of river-beds and deserted river capitals, 30.
- Character of the non-Aryan tribes, their fidelity as soldiers, 72.
- Charak-pūjā or hook-swinging festival, 213.
- Charas, Excise duty on, 455.
- Charities of Indian trade guilds, 198.
- Chauth, or 'quarter-revenues' exacted by the Marāthās in the Deccan and in Bengal, 320, 321.
- Cheetah or hunting leopard, 653, 654.
- Chera, ancient Hindu dynasty in Southern India, 286.
- Cherra-Pūnjī, rainfall at, 7; 649, 650.
- Child, Sir John, 'Captain-General and Admiral of India' (1684), also Governor-General, 370, 371.
- Child-worship of Krishna, 222.
- Childers, Mr., *Dictionary of the Pa'i Language*; quoted, 132; 134, 137, 138; 142 (footnotes).
- Chilianwāla, Battle of, 412, 413.
- China, India's trade with, 577; 582, 583.
- Chinsurah, defeat of the Dutch at, by Clive, 362, 363; head-quarters of the Dutch settlement in Bengal, 381.
- Chips from a German Workshop, by Professor Max Müller, quoted, 83 (footnote 1); 127 (footnote 3); 142 (footnote 2); 151 (footnote 1).
- Chola, Ancient Hindu dynasty in Southern India, 286.
- Christianity in India (100 to 1881 A.D.), chap. ix. pp. 229-267. Christianity coeval with Buddhism in India for 900 years, 229; origin of Christianity in India, 229; Syrian Christians in India, 230; the three legends of St. Thomas, 230-233; wide meaning of India in the writings of the Christian Fathers, 233, 234; first glimpse of Indian Christians (190 A.D.), 234; ancient Roman trade with India, 234; Jew Settlements in ancient Malabar, 234, 235; Indian Christians (190-547 A.D.), as described by Pantænus, Hippolytus, and Cosmos Indicopleustes, 235; Nestorian Church in Asia, 235, 236; Nestorianism and Buddhism side by side for 1000 years, 236; wide diffusion of the Nestorian Church, 236, 237; the 'Thomas Christians' of Persia and of India, 237; localization of the legend of St. Thomas, 237-239; embassy of Alfred the Great to India (833 A.D.), 239; troubles of the ancient Indian Church, 240; the Nestorian St. Thomas Christians of Malabar, a powerful and respected military caste, 240, 241; Portuguese efforts at their conversion to Rome, 241; Synod of Diamper (1599 A.D.), 241, 242; Malabar Christians freed from Portuguese oppression by the Dutch, 242, 243; Jacobite and Syrian Christians in Malabar, 243; extinction of Nestorianism in Malabar, 243, 244; early Portuguese missionaries identified with Portuguese aggressions, 244; Xavier and the Jesuits (1542 A.D.), 244, 245; work done by the Madras Jesuits, 245, 246; early Jesuit stations in India, 246; conquest and con-

- on the basis of Portuguese India 246, 247, parochial organization of Portuguese India, 247; Jesuit mission of Thana (1550 A.D.), its Christian craftsmen and cultivators, 248, Jesuit rural organization, 248, Cochin, a Jesuit collegiate city, 248, 249, Jesuit itineraries and conversions, 250, 251; the Malabar mission in the 17th and 18th centuries, 251, caste questions among Malabar Christians, 251, 252, Christian martyrdoms, 252, 253, establishment of the inquisition at Goa, 253, 254, *antes da fe*, 254, persecutions and aggressions by Portuguese, 254, Goa inquisition abolished (1812), 254; suppression of the Jesuits (1759), 254, 255; their re-establishment (1814), 255, organization of Roman Catholic Missions in India, 255, separate jurisdiction of the Archbishop of Goa, 255, 256, distribution of Roman Catholics, 257, the Verapoli vicariate in Travancore, 257; Syrian and Roman Catholic Christians, 257, statistics of Roman Catholic population of India, 258, Roman Catholic progress, 259, Pondicherry Mission, 259, Catholic colleges and schools, 259, first Protestant Missions in India (1703), 259, 260, vernacular translation of the Bible (1725 A.D.), 260, Protestant missionaries in Tanjore, Calcutta, and Serampur, 260, opposition of the East India Company to Missions, 260, Bishopric of Calcutta, 261, other Indian sees, 261, Presbyterian and other Protestant Missions, 261, statistics of Protestant Missions, 261, 262, increase of native Protestants, 262, 263, extended use of native agency, 263, rapid development of school work of Protestant Missions, 262, 263, general statistics of Christian population in India, 263, 264, Protestant denominational statistics, 264, 265, Indian Ecclesiastical establishment, 266, 267
- Chronicle of the Pathán Kings of Delhi*, by Mr E. Thomas, quoted, 271 (footnote), 280, 281 (footnote); 283 (footnote 1), 284 (footnote 1), 285 (footnote 3), 287 (footnote 2), 291 (footnote), 298 (footnote 1)
- Chronological table of Governors, Governors General and Viceroys of India (1758-1885), 384
- Chronological table of Muhammadan conquerors and dynasties (1001-1857 A.D.), 271
- Chronology of early European travellers, 256, 257 (footnote)
- Cinchona cultivation, 503-511; introduction of plant, 509; the plant in Southern India and at Durg, 509, 510; cultivation of cinchona and financial results, 510, 511
- Clive, struggle with Durrani in the Karnatak, 373, 379; defence of Arcot, 379; re-capture of Calcutta, 381, 382; loss of Plassey and its results, 382, Clive's *ajir*, 383, 384, appointed Governor of Bengal, 384; Clive's second Governorship, 386; his partition of the Ganges valley, 387; grant of the diwani of Bengal, 387; reorganization of the Company's service, 387
- Clive Lord, relief of Lucknow, 420, campaign in Oudh, and suppression of the Mutiny, 421
- Coal and coal mining, 41; 619; history of Bengal coal mining, 610, 620, coal in the Central Provinces, 620, 621, Raniganj coal fields, 621; outlying coal beds, 621, 622, future of Indian coal, 622, geology of Indian coal fields, 636, 637
- Coalition of Vishnuism with Islam in Kabir's teaching, 219
- Coasting trade of India and coast shipping, 583, 586
- Cobalt in Rajputana, 626
- Cobra di capello, The, 660
- Cochin, the Jesuit Collegiate city of the 16th century, 248-250, first establishment of Portuguese factory at (1500 A.D.), 358
- Coffee cultivation, 502-504, its introduction into India, 502, area under cultivation, 502, 503, suitable sites for gardens, 503, processes of preparation, 503, 504, exports of, 575
- Colebrooke's *Essays*, quoted, 191 (footnote 2)
- Colleges and high schools, 476, 477
- Commerce and Navigation of the Ancients in the Indian Ocean*, by Dean Vincent, quoted, 164 (footnote 1), 356 (footnote)
- Commerce and Navigation of the Erythraean Sea*, by Mr J. McCrindle, quoted, 166 (footnotes 1 and 2), 356 (footnote)
- Commerce and trade, chap. xix pp. 555-597. Ancient and medieval trade of India, 555, function of modern Indian trade, 555, 556; sea borne trade impossible under the Mughals, 556, growth of trading and industrial cities under British rule, 556, 557, summary of Indian exports (1700-1885), 558, India's balance of trade, 558, 559, the Home charges, 559, India's yearly trade savings, 559, the chief Indian ports of export trade, 559, 560, early Portuguese trade, 560, Dutch mon-

- 27; amount of silt deposited at Gházipur and in the delta, 27, 28; age of the Bengal delta, 28.
- Deltaic channel of the Ganges, Section of, 23.
- Density of the Indian population, 46; overcrowded and under-peopled Provinces, 46, 47; population entirely rural, 46; immobility of the rural population, 47; relation of labour to land, 48, 49; unequal pressure of the population on the land, 49, 50; increase of population since 1872, 50.
- Deserted river-marts and capitals, 30.
- Devadatta, the Buddhist schismatic, 140.
- Dhangars, a semi-Hinduized tribe of Bengal and Chutia Nágpur, their numbers in 1872, 71 (footnote 1).
- Diamonds, 41; 628, 629.
- Dictionary of Hindu Mythology*, by Professor Dowson, quoted, 180 (footnote 4); 184 (footnote 1).
- Dig, Battle of, and defeat of Holkar, 323.
- Diminution of population in Madras and Mysore, 50.
- Dina Bandu Mitra, dramatic poet and author of the *Nil Darpan*, 354.
- Dina Krishna Dás, Uriyá poet of the 16th century, 343.
- Distillation of country spirits, 454.
- Distribution of Indian trade with foreign countries, 565-580.
- District officers, Duties of, 436.
- Districts, Number of, in India, their varying size and population, 436, 437.
- Diwání, or financial administration of Bengal, granted to the East India Company (1765), 387.
- Dnyánoba, Maráthi poet of the 13th century, 346.
- Doctrines of Buddha, 141, 142; moral code and missionary aspects of Buddhism, 143.
- Dog, Different varieties of, 654.
- Dongargáon, mart in the Central Provinces, 596.
- Dowson, Professor, *Dictionary of Hindu Mythology*, quoted, 180 (footnote 4); 184 (footnote 1).
- Drama, The Indian, 125-127; 354.
- Draupadi, the wife of the five Pándava brethren in the epic of the Mahábhárata, 195.
- Dravidians, The, aboriginal races of Southern India, their languages, 64-68; place of Dravidian languages in philology, 327, 328; the Dravidians in Sanskrit literature, 328; pre-Aryan Dravidian civilisation, 328; Dravidian art, 328, 329; Bráhmanical influence on the Dravidians, 329, 330; development of Dravidian speech into vernacular literatures, 330; Tamil, the oldest and the most influential vernacular of Southern India, 330; Jain cycle of Tamil literature, earliest Tamil poets, 331; Tamil hymnology, 332; modern Tamil writers, Beschi, the Italian Jesuit and Tamil scholar, 333; recent statistics of Tamil literature, 333.
- Droughts.—See FAMINES.
- Drugs and medicines, 34.
- Dual system of administration in Bengal (1767-72), 387, 388.
- Duarte Nunez, first Portuguese bishop in India (1514-17 A.D.), 244.
- Duff, Rev. Alexander, first Presbyterian missionary to India, 261.
- Dufferin, Earl of, Viceroy (1884), 430.
- Duka, Dr. Theodore, *Life and Works of Alexander Csoma de Korös*, quoted, 153 (footnote 1).
- Duncker, Professor Max, *Ancient History of India*, quoted, 81 (footnote 2); 84 (footnotes 2 and 4); 115 (footnote); 163 (footnote 4).
- Dupleix, French administrator, his ambition of founding a French Empire in India, and his struggles in the Karnátik with Clive, 378, 379.
- Duráni rule in Afghánistán (1747-1826), 406, 407.
- Duration of life (average) in India, 667.
- Durgá, one of the forms of the wife of Siva, 211, 212.
- Dutch, The, in India (1602-1824 A.D.), 361-363; Dutch East India Companies, 361, 362; supremacy of the, in the Eastern Seas, brilliant progress, and decline, 362; Dutch relics in India, 363; English 'Treaty of Defence' with the Dutch (1619), 367; massacre of Amboyna, and expulsion of the English from the Eastern Archipelago (1624), 368; Dutch conquests in India, 371, 372; Dutch defeated by Clive at Chinsurah, 385; Dutch monopoly of Eastern trade (1600), 560.
- Dyes, export of, 574, 575.

E

- Early Greek historians of India, 163; 164.
- Early History of Tibet and Khoten*, in Mr. Rockhill's *Life of the Buddha*, from the Tibetan classics, 176 and 177 (footnotes).
- Early Muhammadan rulers (711-1526 A.D.), chap. x. pp. 268-289.
- Early Arab expeditions to Bombay (636-711 A.D.), 268; Muhammadan

settlement in Sind (711 A D), 268, expulsion of the Muhammadans from Sind (828 A D), 268, India on the eve of the Muhammadan conquest (1000 A D), 268, 269, the Hindu kingdoms and Hindu power of resistance, 269, slow progress of Muhammadan conquest, 269, 270, Muhammadan conquest only partial and temporary, 270, recapture of India from the Muhammadans by the Hindus (1707 61 A D), 270, chronology of Muhammadan conquerors and dynasties of India (1001 1857 A D), 271, first Turki invasions, Subuktigin (977 997 A D), 272, the seventeen invasions of Mahmud of Ghazni (1001 24 A D), 272 274, the Somnath expedition, 273, 274, Mahmud's conquest of the Punjab, 274, the Ghor dynasty (1152 1206 A D), 275 278, Muhammad of Ghor's invasions (1191 1206 A D), 275, 276, his conquest of Bengal (1203 A D), 277, 278, Muhammad's work in India and subjugation of Northern India, 278, Kutab ud din (1206 10 A D), 278, the Slave dynasty, 278 280, Altamsh (1211 36 A D), 279, the Empress Razia (1236 39 A D), 279, Mughal irruptions and Rajput revolts (1244 88), 279, 280, Balban (1265 87 A D), his cruelties, 280, his Royal pensioners, 280, end of the Slave kings, 280, the house of Khilji (1290 1320 A D), 280-283, Ala ud din's raids into Southern India (1294), 281, conquest of Northern India (1295 1303), 281, 282, Muhammadan power and population in India (1306) 282, Mughal mercenaries and Hindu revolts, 281, Khusru, the renegade Hindu Emperor (1316 20 A D), 282, 283, the house of Tughlak (1320 1414 A D), 283 286, Muhammad Tughlak (1324 51 A D), his expeditions, cruelties, forced currency, 283 284, revolts, 284, Muhammad Tughlak's revenue exactions, 284, 285, Firoz Shah Tughlak (1351 88 A D), his canals, 285, Timur's

Dutch, 361 363; English, 363 371, other India Companies, 371, French, 372; Danish, Scotch, and Spanish, 372; German or Ostend, 372 374, 376, Prussian, 374 376, Swedish, 376, causes of failure, 376, 377.
East India Company (English), 363 365, first Charter, 364; amalgamated Companies, 365, early voyages, 365, 366, defeat of the Portuguese at

Company embarks on territorial sway (1689 A D), 371; downfall of the Company, and transfer of India to the Crown (1858 A D), 422

Eastern branches of the early Aryans, 75

Eastern Ghats, mountain range along the Eastern coast of India, 36, 38, forests of, 39

Eastern Jumna canal, 29, 532

Ecclesiastical Department, The Indian, 266, 267

Education Commission appointed by Lord Ripon, 429, its recommendations, 429, 474

Education in India, 472 479, education in ancient India, 472, Sanskrit *tois*, 472; Calcutta *Madrasa* and other colleges, 473; Mission schools, 473, State system of education, 473, 474; educational finance, 475, Indian universities, 475, 476; colleges, 476; upper, middle, and primary schools, 476, 477, girls' schools, 478, 479; normal and other special schools, 479; educational classification of the population, Appendix IX, 698 702

Elephants, domestic and wild, 521; 655; elephant catching a Government monopoly, 655, 656, *Elephant Preservation Act*, 656

Elgin, Lord, Viceroy of India (1862-63), 424.

409; conquest and annexation of Sind, 409, Gwalior outbreak, and the battles of Maharajpur and Panniali, 409

Ellichpur, Muhammadan bin, *born of* Southern India (1484 1572 A D), 284

Elliot, Sir Henry, *Tribes of the North-Western Provinces*, 195 (*Series 2*); *History of India as told by its own Historians*, 271 (*Series 1*), 272 (*Series 2*), 273 (*Series 3*), 274 (*Series 4*), 275 (*Series 5*), 276

States of the Deccan, 288, the Hindu kingdom of Vijayanagar, 286, 288, independent Nayaks and Palegars of Southern India, 288, independent Muhammadan kingdoms of Bengal, Gujarat, and Jaunpur, 289

1st India Companies, and early European Settlements, Portuguese, 356 361;

- 1498 A.D., 356; state of India on arrival of Portuguese, 358; Portuguese territorial expedition (1500 A.D.), 358; Portuguese supremacy in the Eastern Seas (1500-1600 A.D.), 358, 359; capture of Goa by Albuquerque (1510 A.D.), 359; Portuguese cruelties, 359; Albuquerque's policy of conciliation, 359, 360; later Portuguese Viceroys, their oppressions and conquests, 360; downfall of the Portuguese in India (1630-1739), 360, 361; Portuguese possessions in 1881, 361; mixed dominions, 361. The Dutch in India (1602-1824), 359-362; Dutch East India Company, 361; Dutch supremacy in the Eastern Seas (1600-1700 A.D.), 362; their brilliant progress, but shortsighted policy and ultimate downfall, 362; Dutch relics in India, 363. The early English in India, 363-371; attempts to reach India by the North-West passage, 363; Thomas Stephens, the first authentic English traveller in India (1579 A.D.), 363, 364; later travellers, Dutch, Newberry, and L. St. (1583 A.D.), 364; first Charter of the East India Company (1600 A.D.), 364; later East India Companies, (1635, 1655, and 1698 A.D.), 365; the amalgamated Company (1709 A.D.), 365; early English voyages (1600-12 A.D.), 365; defeat of the Portuguese fleet at Swally, off Surat (1615), 366; Sir Thomas Roe, first English Ambassador to India (1615 A.D.), 367; treaty with the Dutch (1619 A.D.), 367; English expelled from the Spice islands and Java by the Dutch (1620-21 A.D.), 367; establishment of English factories at Agra and Patna (1620 A.D.), 367; Masumpatam factory established (1622 A.D.), 368; English expelled from Eastern Archipelago, and retire to India, 368; Emperor's *Farman* granting English liberty to trade in Bengal, 368, 369; Madras founded (1639 A.D.), 369; Hugli factory established (1640 A.D.), 369; Kásimbázár factory (1658 A.D.), 369, 370; Bombay ceded to the British Crown (1661 A.D.), 370; Presidency removed from Surat to Bombay (1684-87 A.D.), 370; separation of Bengal from Madras (1681), 370; Sir John Child, first 'Governor-General' (1686 A.D.), 370, 371; Calcutta founded (1686), 371; the Company embarks on territorial sway (1689 A.D.), 371; French East India Companies and possessions in 1881, 372; Danish, Scotch, and Spanish Companies, 372; the German or Ostend Company, 372; its Indian settlements (1772 A.D.), 373; its successful experimental voyages and political objects, 373, 374; Ostend Company bankrupt and destroyed (1783-84 A.D.), and extinguished (1793 A.D.), 374; the Prussian and Embden (1510 A.D.), 359; Portuguese cruelties, 359; Albuquerque's policy of conciliation, 359, 360; later Portuguese Viceroys, their oppressions and conquests, 360; downfall of the Portuguese in India (1630-1739), 360, 361; Portuguese possessions in 1881, 361; mixed dominions, 361. The Dutch in India (1602-1824), 359-362; Dutch East India Company, 361; Dutch supremacy in the Eastern Seas (1600-1700 A.D.), 362; their brilliant progress, but shortsighted policy and ultimate downfall, 362; Dutch relics in India, 363. The early English in India, 363-371; attempts to reach India by the North-West passage, 363; Thomas Stephens, the first authentic English traveller in India (1579 A.D.), 363, 364; later travellers, Dutch, Newberry, and L. St. (1583 A.D.), 364; first Charter of the East India Company (1600 A.D.), 364; later East India Companies, (1635, 1655, and 1698 A.D.), 365; the amalgamated Company (1709 A.D.), 365; early English voyages (1600-12 A.D.), 365; defeat of the Portuguese fleet at Swally, off Surat (1615), 366; Sir Thomas Roe, first English Ambassador to India (1615 A.D.), 367; treaty with the Dutch (1619 A.D.), 367; English expelled from the Spice islands and Java by the Dutch (1620-21 A.D.), 367; establishment of English factories at Agra and Patna (1620 A.D.), 367; Masumpatam factory established (1622 A.D.), 368; English expelled from Eastern Archipelago, and retire to India, 368; Emperor's *Farman* granting English liberty to trade in Bengal, 368, 369; Madras founded (1639 A.D.), 369; Hugli factory established (1640 A.D.), 369; Kásimbázár factory (1658 A.D.), 369, 370; Bombay ceded to the British Crown (1661 A.D.), 370; Presidency removed from Surat to Bombay (1684-87 A.D.), 370; separation of Bengal from Madras (1681), 370; Sir John Child, first 'Governor-General' (1686 A.D.), 370, 371; Calcutta founded (1686), 371; the Company embarks on territorial sway (1689 A.D.), 371; French East India Companies and possessions in 1881, 372; Danish, Scotch, and Spanish Companies, 372; the German or Ostend Company, 372; its Indian settlements (1772 A.D.), 373; its successful experimental voyages and political objects, 373, 374; Ostend Company bankrupt and destroyed (1783-84 A.D.), and extinguished (1793 A.D.), 374; the Prussian and Embden
- Ethnic division of the population, 51, 52; 73, 74.
- European and Indian languages merely variants of Aryan speech, 70.
- European Settlements (1498 to 18th century A.D.), chap. xiv. pp. 356-377. The Portuguese in India, 356-361; early Portuguese voyages, Covilham (1487 A.D.), and Va-co da Gama (1498 A.D.), 357, 358; state of India on arrival of Portuguese, 358; Portuguese territorial expedition (1500 A.D.), 358; Portuguese supremacy in the Eastern Seas (1500-1600 A.D.), 358, 359; capture of Goa by Albuquerque

- Companie, 374 376, Swedish Company (1731 A D), 376, causes of failure of foreign European Companies, and of English success in India, 376, 377, European traders in India in 1872 and 1881, 377
- Livest, Mount, peak of the Himalayas, and highest measured mountain in the world, 5
- Livest, Rev. Mr., calculations regarding silt discharge of Ganges, 27
- Exchange, Loss by, 469
- Excise administration, distilleries, rice beer, opium, *ginja*, *charas*, 454 455, 467, expenditure and income of British India, 465 470
- Excommunication from caste privileges 199, 200
- Executive Council of the Governor General, 432
- Export trade of India, its origin and growth, analysis and principal staples of, 567, 569 580 distribution of exports to different countries, 569, 580, coasting trade, 584 586
- External sources of the ancient history of India, 163

F

- Fa Hian, Chinese Buddhist pilgrim of the 5th century A D, 155
- Famine relief expenditure, 469
- Famines, 539 544, causes of scarcity and of real famine, 539, means of husbanding the water supply, 540, irrigation area, 540, 541, summary of Indian famines, 541, 542, the great famine of 1876 78, its causes, 542, 543, famine expenditure, 543, mortality from disease and starvation, 543 544, famine a weak check on population, 544
- Faulmann, *Buch der Schrift*, quoted 103 (footnote)
- Fauna of India, 10 —See also ZOOLOGY, 652 662
- Female education, 478, 479
- Fertile Nature of India —See ZOOLOGY AND BOTANY
- Ferdousi, Persian poet and historian in the days of Mahmud of Ghazni, 275
- Fergusson, Mr James, Paper in the *Journal of the Royal Asiatic Society for April 1880*, quoted, 147 (footnote), *Tree and Serpent Worship*, quoted, 185 (footnote 4), 204 (footnote 1), 205 (footnote 2)

- Final Struggles of the French in India*, by Colonel Malleson, 379 (footnote)
- Finances and taxation of India, obscurities and changes in system of account, 457 465, taxation of British India, 459 461, taxation under the Mughals and under the British, 462, 463, taxation in Native States, 464; incidence of taxation in British India, 464, 465
- Firishta's *Rise of the Muhammadan Power in India*, Colonel Briggs' translation, quoted, 271 (footnote), 287 (footnote 2), 291 (footnotes)
- Firozshahr, Battle of, 411
- 1 3
1 the
his
- Fitch, Newberry, and Leedes, the first English traders in India (1583 A D), 364
- Flint weapons of ancient India, 53
- Flora of India, 662 664
- Flora of India, 662 664
- Flora of India, 662 664

- growth, 561 581, returns of foreign trade (1840 84), 562 564, staples of import and export sea-borne trade (1882 83), 565 581
- Forest Department, Growth of, and its administration, 522 528, Forest Conservancy statistics, 526, 527, 'open' and 'reserved' forests, 526
- Forests of the Himalayas, 8, in Southern and South Western India, 38 40, in Sind and Punjab, 524, 525, North Western Provinces, 525, Sundarbans, 525, Assam and Burma, 525, 526 —See also FOREST DEPARTMENT, *ut supra*
- Fortified weaving settlements of the East
- ..
- Fox, The Indian, 654
- France, India's foreign trade with, 578, 579
- French East India Companies, and the present French possessions in India, 372, French and English in the Karatik, the first French war (1746 48), 378, capture of Madras by the French

of

Frobisher's, Davis', Hudson's, and Baffin's

attempts to reach India by way of the North-West passage, 363.
 Frontier trade of India, 585-590.
 Fruits, Varieties of, 490.
 Funeral mounds and ceremonies of the Sakyas and Buddhists in ancient India, 178.

G

Gáekwár, family name of the chief of the Maráthá State of Baroda, rise of the family, deposition of the late Gáekwár, 322, 323; 426.
 Game birds of India, 659, 660.
 Gandamak, Treaty of, 426.
 Ganges, The, 11; 16-32; its river system and course, 16, 17; discharge, 17; sanctity, 17, 18; the fertilizer and highway of Bengal, 19, 20; traffic, 20, 21; great cities, 20, 21; different stages in the life of the Ganges or any great Indian river, 21-25; as a silt collector, 21, 22; as a land-maker, 22, 23; section of a deltaic channel of the Ganges, 23; combined delta of the Ganges, the Brahmaputra, and the Meghná, 24, 25; subterranean structure of the Gangetic delta, 26 and footnote; silt brought down by Ganges at Gházipur, 27 and footnote; estimated silt of united river system, 28; age of the Bengal delta, 28; river irrigation, 28; the Ganges and Jumna Canals, 28, 29; Ganges floods, 29; saline deposits, 29; changes of Ganges channel, 30; deserted river capitals, 30; the 'bore' of the Ganges and Meghná, 30, 31; the Goalánda railway station washed away by the Ganges, 31, 32; fluvial changes, alluvion and diluvion, 30-32; navigation on the Ganges, 552.
 Ganges Canals, 28, 29; 532, 533.
 Gangetic historical and commercial cities, 20; deserted cities, 30.
 Gánjá, Excise duty on, 455.
 Gaulis, an ancient ruling race in the Central Provinces, now a crushed tribe, 71.
 Gautama Buddha, the founder of the Buddhist religion, his life and doctrine. —See BUDDHISM.
 Geography of India. —See PHYSICAL ASPECTS.
 Geology of India, chap. xxii. pp. 631-640. Geology of the Himálayas, 631; the central gneissic axis, 631, 632; lower Himálayas, 633; the sub-Himálayas and Sivaliks, 632, 633; the Salt Range, 633; Indo-Gangetic plain, its age, history, and geological deposits,

633, 634; peninsular India, 634-639; the Vindhya system, 635; Gondwána series, 635, 636; Páñchet and Tálcher group, 636; Dámodar series and coal-fields, 636-638; Deccan trap and laterite, 638, 639; precious stones, 639; geological structure of Burma, 639, 640.
 Ghakkars, a tribe in Ráwal Pindi District, their invasions of India, and their present descendants, 185.
 Gháts, Eastern, mountain range along the Eastern coast of India, 36; 38; forests of, 39.
 Gháts, Western, mountain range along the Western coast of India, 36; the Bhor Ghát pass, 36; Thal Ghát pass, 37; Pálghát pass, 37; rivers of the Western Gháts, 37, 38; rainfall, 38; forests, 39.
 Gheriah, defeat of Mír Kásim at, by Major Adams, 386.
 Ghiyás-ud-dín Tughlak, founder of the Tughlak dynasty (1320-1324 A.D.), 283.
 Ghor, Dynasty of (1152-1206 A.D.), Muhammad of Ghor's invasions, his first defeats and ultimate conquest of Northern India and Bengal, 275-278.
 Gibbon's *Decline and Fall of the Roman Empire*, quoted, 230 (footnote 1); 239 (footnote 2).
 Gingi, Surrender of, by the French to Sir Eyre Coote, 380.
 Gipsy clans, 71.
 Girls' schools, 478, 479.
 Gíta Govinda, The, or 'Divine Herdsman,' the song of Krishna; 128.
 Goa, Supposed relics of St. Thomas at, 238; John de Albuquerque, first bishop of (1539-53 A.D.), 244; establishment of Archbishopric of, 245; Archbishop Menezes (1596-99), 245; jurisdiction of the Goa Archbishopric, 255, 256; capture of Goa by Albuquerque (1510 A.D.), 359.
 Goalánda railway station washed away by the Ganges, 31.
 Godávári river, 37; irrigation works, improvement of navigation on, 551, 552.
 Goddard, General, his march across India during the first Maráthá war, 391.
 Golconda, Diamonds of, 41; 628.
 Golconda, Muhammadan kingdom of Southern India (1512-1688 A.D.), 288.
 Gold and gold-mining in Southern India, 624, 625.
 Gold and silver, imports of, 562, 568, 569.
 Goldsmith caste in Madras, 196.

High Courts of Justice in India, 433.

Hijili navigable canal in Midnapur District, 553.

Hill cultivation, 9; 486.

Hill forts (Maráthá) in the Deccan, 318.

Himálaya mountains, The, 4-10; the double wall and trough, 5, 6; passes and offshoots, 6; water-supply and rainfall, 7; scenery, vegetation, irrigation and products, 7-10; animals and tribes, 10; geology, 631-633; meteorology, 641, 642. — See also TRANS-HIMALAYAN TRADE.

Hindi literature and authors, 345, 346.

Hinduism, Rise of (750 to 1520 A.D.), chap. viii. pp. 192-228. Disintegration of Buddhism, 191; preaching of Kumáila, 191; persecution of Buddhism, 191, 192; caste and religion the twofold basis of Hinduism, 192; race origin of caste, 192; modified by 'occupation' and 'locality,' 192; complexity of caste, 192, 193; the Bráhma caste analyzed, 193, 194; building of the caste system, 194; Hindu marriage law, 195; ancient mingling of castes, 195; 'occupation' basis of caste, 196-199; the Vaisyas or ancient cultivating caste, 196; the 'right-hand' and 'left-hand' castes of Madras, 196, 197; the Dattas of Bengal, 197; Sháhas, Telis, and Tambulis forcing their way to higher castes, 197; caste, a system of trade-guilds, 197, 198; working of the Indian trade-guild, its funds, charities, rewards, and punishments, 198, 199; excommunication a penalty for a breach of caste rules, 199, 200; the religious basis of Hinduism, its stages of evolution, and how far influenced by Buddhism, 200, 201; Beast hospitals, 201; monastic religious life, 201, 202; analogies of Japanese worship to Hinduism and Christianity, 202; serpent ornamentation in Buddhist, Hindu, and Christian art, 202, 203; coalition of Buddhism with earlier religions, 203; shrines common to various faiths, 203, 204; non-Aryan elements in Hinduism, 204; phallic emblems in Hinduism, 204, 205; fetish-worship in Hinduism, 205, 206; the *Sálgrám* or village deity, 206; jungle rites, 206, 207; non-Aryan religious rites merging into Hinduism, 207; Bráhma founders of Hinduism, 207; low caste apostles, 207, 208; mediæval Hindu saints, their miracles, 208; Kabír's death, 208; Bráhma religious reformers, 209, 210; growth of Siva-worship, 210-215; Siva-worship in its philosophical and terrible aspects,

211; twofold aspects of Siva and of Durgá his queen, and their twofold sets of names, 211, 212; human sacrifices as late as 1866, 212, 213; animals substituted for human sacrifice, 213; the *Charak puja* or swinging festival, 213; the thirteen Sivaite sects, 213, 214; gradations of Siva-worship, 214, 215; secret orgies of Sivaism, 215; the 'right-hand' and 'left-hand' forms of Siva-worship, 214, 215; Siva and Vishnu compared, 215; Vishnu the Preserver always a friendly god, 215; his incarnations or *avatars*, 215 (and footnote); 216; the Vishnu Puránas, 216, 217; Bráhmaical and popular Vishnuism, 217; Vishnuite religious reformers, 217-222; Rámánuja, 217; Rámánand, 218; Kabír, 218, 219; Chaitanya, 219-221; Vallabha-Swámí, 221, 222; Krishna-worship, 222, 223; the twenty chief Vishnuite sects, 223; theistic movements in Hinduism, 223; the Sikhs, and Nának Sháh, their spiritual founder, 223; Jagannáth, the coalition of Bráhma and Buddhist doctrines forming the basis of Vishnu-worship, 223, 224; Car festival of Jagannáth, 224; bloodless worship of Jagannáth, self-immolation a calumny, 224-226; gentle doctrines of Jagannáth, 226; religious *nexus* of Hinduism, 226; practical faith of the Hindus, its tolerance, 226, 227; the modern Hindu triad, 227; recapitulation, 228.

Hindu architecture, 112.

Hindu kingdoms of the Deccan, 286.

Hindu population of India, 51. — See also Appendix V., 693.

Hindu Tribes and Castes, by the Rev. M. A. Sherring, quoted, 193 (footnote 1); 194 (footnotes 2, 3, and 4); 195 (footnote 2); 221 (footnote 4).

Histoire du Christianisme des Indes, by La Croze, 232 (footnote 1); 240 (footnote 4); 241 (footnote 1); 242 (footnotes).

Histoire de la Littérature Hindoue et Hindoustanie, by Garcin de Tassy, 343 and footnote.

History of Architecture, by Mr. J. Ferguson, quoted, 304 (footnotes).

History of British Rule (1757-1885 A.D.), chap. xv. pp. 378-430. Madras, the first British territorial possession in India (1639), 378; Southern India after the death of Aurangzeb (1707), 378; French and English in the Karnátik, 378; first French war and capture of Madras by the French (1746), 379; second French war (1750-61), 379; Clive's defence of Arcot

(1751), 379, Sir Eyre Coe's victory of Wandewash (1760) 379, capitation of Pondicherry and Gingi, 380, the English in Bengal (1634-96), 380, native rulers of Bengal (1707-26), Murshid Kuli Khan, Ali Vardi Khan and Siraj ud-daula 380, 381, capture of Calcutta by Siraj ud-daula (1756), 381, recapture of Calcutta and battle of Plassey, 382, Mir Jafar (1757)

(1761), 383, Mir Kasim's quarrel with the English, and massacre of Latna, 385, 386, first Sepoy Mutiny (1764), 386, battle of Laxar (1764), 386, Clive's second Governorship (1765-67), partition of the Gangetic valley, the Diwani grant of Bengal, and reorganization of the Company's service, 386, 387, dual system of administration (1767-72), abolished by Warren Hastings 387, 388, Warren Hastings' administration (1772-85), 388-392 his administrative reforms, and policy with native powers 388, Warren Hastings, the first Governor General of India (1774), 388, his financial administration, and sale of Allahabad and Kora to the War of Oudh, 389, 390, withholds the Emperor's tribute, 390, the Rohilla war (1773-74), 390, plunder of Chait Singh and of the Oudh Begums, 390, charges against Hastings and his impeachment, 392, the first Maratha and Mysore wars, 392, 393, Lord Cornwallis' administration (1786-93), his revenue reforms, the Permanent Settlement of Bengal and second Mysore war, 393, 394, Sir John Shore (1793-98), 394, Lord Wellesley's administration (1798-1803), 394-399, French influence in India, 394, sale of India before Lord Wellesley, 395, Lord Wellesley's scheme for crushing French influence in India, 395, 396, treaties of Lucknow and with the Nizam, 396, third Mysore war and fall of Seringapatam, 396, 397, Wellesley's dealings with the Marathas, and the second Maratha war, 397, 398, British victories and annexations (1803), British disasters, Colonel Monson's retreat, and General Lake's repulse before Bharatpur (1804-05), 398, India on Lord Wellesley's departure (1805), 398, 399, Lord Cornwallis' second administration as Governor General (1803), 399, Sir George Barlow (1805), 399, Earl of

Minto's administration (1807-13), his embassies to the Punjab, Afghanistan, and Persia, 399, 400; Marquis of Hastings' administration (1814-23) the Nepal war and treaty of Segauli, the Pindar campaign the third and last Maratha war, and annexation of the Peshwa's territories, 400-402, Mr. Adam, first territorial Governor-General (1823), 403; Lord Amherst (1823-28), French encroachments on India, first Chinese war and annexation of Assam, Arakan, and Tenasserim, 403, 404, capture of Bharatpur, 404, Lord William Bentinck (1828-35), his financial reforms, abolition of *Sati*, suppression of *Thug* and criminalities, renewal of Company's Charter, Mysore taken under British administration, and Ceylon annexed, 404-406, Sir Charles Metcalfe (1835-36), the grant of liberty to the Press, 406, Lord Auckland (1836-42), our early dealings with Kabul, and the disastrous Afghan campaign, and annihilation of our army, 406-408, Earl of Ellenborough (1842-44), the Kabul army of retribution, the 'Gates of Somnath' travesty, annexation of Sind, and Gwalior on breach, 408, 409, Lord Hardinge (1844-48), the first Sikh war and annexation of the Cis-Satlej tract, 410, 411, Earl of Dalhousie (1848-56), 411-417; his administrative reforms and public works, 412, second Sikh war and annexation and partition of the Punjab, 412, 413; second Burmese war and annexation of Pegu, 413, 414, Lord Dalhousie's dealings with the Nave Sates, the doctrine of 'Lapse' in the case of Satara, Jharkhand, and Nagpur Sates, 414, 415, 1848 handed over by the Nizam of Hyderabad, as a territorial guarantee for safety of subsoil and for the payment of the Hyderabad contingent, 415, annexation of Oudh and Lord Dalhousie's grounds for the measure, 415-417; Earl Carnarvon (1856-62), 417-424; the Sepoy Mutiny and its cause, 417-419, the trial and execution of Akbar, and spread of the Mutiny, 419, loyalty of the British, 419, 420, the terms of Carnarvon's and the terms of the Mutiny, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000

sála, 424; Lord Lawrence (1864-69), the Bhután war and Orissa famine, 424, 425; Lord Mayo (1869-72), the Ambála *Darbár*; internal and financial reforms, and abolition of inland customs lines, his assassination, 425; Lord Northbrook (1872-76), the Bengal famine of 1874, dethronement of the Gáekwár of Baroda, and visit of the Prince of Wales to India, 425, 426; Lord Lytton (1876-80), Proclamation of the Queen as Empress of India, famine of 1877-78; the second Afghán campaign, 426, 427; Lord Ripon (1880-84); end of the second Afghán campaign, rendition of Mysore to its hereditary Hindu dynasty, internal administration reforms, local Government Acts, amendment of Criminal Procedure, reconstitution of the Agricultural Department, revenue reforms, the Education Commission, abolition of customs duties, Bengal Tenancy Bill, 427-429; Earl of Dufferin (1884), 430; annexation of Upper Burma (1886), 430.

History of British India, by J. Mill, quoted, 314 (footnote 3); 365 (footnote 2).

History of India, by the Hon. Mountstuart Elphinstone, quoted, 270 (footnote); 291 (footnote); 300 (footnote); 302 (footnotes); 306 (footnote 1).

History of India as told by its own Historians, by Sir Henry Elliot, quoted, 271; 287 (footnote 2); 291 (footnotes); 295 (footnote 2); 300 (footnote); 302 (footnote 2); 306 (footnote 1); 313 (footnote).

History of the Settlements and Trade of the Europeans in the East and West Indies, by Abbé Raynal, quoted, 374 (footnote).

History of the French in India, by Colonel Malleson, 379 (footnote).

History of the Maráthás, by James Grant Duff, quoted, chap. xii. pp. 317-324, footnotes, *passim*.

History of the Maráthás, by E. Scott Waring, quoted, 317 (footnote 1).

Hüen Tsiang, Chinese Buddhist pilgrim, 2; 155 and footnote; 156, 157; 178, 179; 182.

Hog, wild, The, 656, 657.

Holkar, family name of the Chief of the Maráthá State of Indore; rise of the family to power, 322; war with the British, 323.

Horses, Breeds of, 520; Government studs, 520; horse fairs, 521.

Húglí, East India Company's factory established at (1640), 369; oppressed by the Mughal governor, 370.

Human sacrifice among the Kandhs, 62; in Siva-worship, 212; substitute of animals for human offerings, 213.

Humáyún, second Mughal Emperor of Delhi (1530-56 A.D.), 290, 291; expulsion from India by his Afghán governor of Bengal (1540), 291; subsequent recovery of the throne by the second battle of Pánipat, 291.

I

Ibráhím Lodí, Defeat and overthrow of, by Bábar at the first battle of Pánipat (1526 A.D.), 290.

Imad Sháhí, Muhammadan dynasty of Southern India (1484-1572), 288.

Immobility of the Indian peasant, 47.

Impediments to improved husbandry, namely, want of cattle, want of manure, and want of water, 517-519.

Import trade of India, analysis and principal staples of, 565-568; coasting imports and exports, 584-586.

Incarnations of Vishnu, 215, 216 and footnote.

Income and expenditure of British India, 465-470.

Increase of population between 1872 and 1881, 47; 49, 50.

Independent Náyks and Pálegárs of Southern India, 288.

India on the eve of the Mughal conquest (1526 A.D.), 290.

India, origin of the name, 1-3.

Indian Caste, by Dr. J. Wilson, quoted, 194 (footnote 1); 195 (footnote 2); 196 (footnote 1).

Indian products mentioned in the Bible, 163.

Indian Society as described by Megasthenes (300 B.C.), 168, 169.

Indian vernaculars and their literature, chap. xiii. pp. 325-355.

Asiatic civilisation of India as found by the early European powers, 325, 326; India in the 1st and the 16th centuries A.D., 326, 327; the Dravidians or non-Aryans, their language and its place in philology, 326-328; the Dravidians in Sanskrit literature, 328; pre-Aryan Dravidian civilisation, 328; Bráhmanic influence on the Dravidians, 329, 330; development of Dravidian speech into vernacular literatures, 330; the Tamil language, 330, 331; Jain cycle of Tamil literature, 331; the Tamil Rámáyana, 331, 332; Sivaite and Vishnuite Tamil hymnology, 332, 333; modern Tamil writers, 333; Beschi, the Jesuit Tamil scholar, 333; recent statistics of Tamil literature,

- 333, Aryan languages of North India, Sanskrit, 334 335, evidence as to whether Sanskrit was ever a spoken language, 334 336, Panini and Vararuchi, ancient Sanskrit grammarians, 336, the Prakrits or ancient spoken dialects of India, their divergence from Sanskrit 336, routes of Prakrit speech, 337, Prakrits developed by Buddhists for their Scriptures, 338, evolution of modern vernaculars from Prakrits, 338, 339, their Prakrit framework and Sanskrit enrichments, 339, non Aryan element in the vernaculars, proportion of non Aryan words, 340, 341, the fourfold composition of the vernaculars, namely the Prakrit and aboriginal elements, Sanskrit borrowings and Persian terms 342, the seven vernaculars of India, 342 343, vernacular literature and vernacular writers, 343, 344, Rajputana religious literature, 344, Hindi authors from the 12th to the 19th centuries, 345, 346, Marathi literature and authors, 346, Bengali literature its three periods, 343 348, Bengali religious poetry, 349 351; Bengali poets from the 16th to the 18th centuries, 349 352, the court of Nadiya, the chief seat of learning in Bengal in the last century, 352, Bengali prose literature in the 19th century, 354, the Bengali drama, 354
- In ligo, Cultivation of, in different localities, 495, 496, systems of indigo planting, and out turn in Bengal and Behar, 497, export of, 497, 574.
- In fusche Alterthumskunde*, by Professor Lassen quoted, 161 (footnote 1), 191 (footnote 2), 340 (footnote 2)
- Indo Aryan stock, its European and Eastern branches, 75 76, their march towards and into India, religion, etc., 76 78
- Indo Gangetic plain, Geology of, 633, 634, meteorology of, 643 644
- Indo Greek treaties (306 and 256 B.C.), 167, 170
- Indra, the Vedic God of Rain, 80 81, influence of the rainy season on Aryan mythology, 80, Indra displaced by the modern Brahmanical Triad, 81
- Indus great river of Northern India and Sind, 11 13, its upper waters, 11, its feeder the Sutlej, 11, 12, its inundations, 11, lower course 12, irrigation facilities, 13, 529, silt deposits, 13, Its steam flotilla recently broken up on completion of the railway system, 552
- Inlaying work, 609
- Inquisition established by the Portuguese at Goa (1560), 241, 253, *autos da fe*, 254, abolished (1812), 254
- Inscribed pillars of Asoka, 145, 146
- Insects, Indian, 662
- Internal and local trade of India, 591
- in mine, 593, normal action of internal trade, 594, provincial statistics of internal trade, 594 595, trade statistics of a large town, village mart, and annual fair, 594 596
- Introduction to the Urdu Language*, by the Rev E. Droege, quoted, 327 (footnote 1)
- In tu, the Buddhist derivation of the word India, 2
- Invaliding, Causes of, in the European army, 681
- Iron mining and smelting, difficulties of Indian ironworks, 41, 619, indigenous methods of iron smelting 618, failure of English efforts, 618, 619, Government efforts 619
- Ironwork, 606
- Irrigated area in different tracts with statistics, 528 538
- Irrigation from hill streams in the Himalayas, 9, river irrigation in the plains 28, 29
- Iswar Chandra Vidyasagar, famous modern Hindu social reformer, 353
- Italy, India's trade with, 578 579
- Itinerary Jesuit missionaries in the 15th and 16th centuries, their labours and conversions 250, 251.
- Ivory carving, 609

J

- Jachal, The, 654
- Jackson, Lewis D.A., *Hydraulic Manual*, quoted 17 (footnote)
- Jacobi, Hermann *The Jaina Sutras*, forming vol. xxii of Prof. Max Muller's *Sacred Books of the East*, 161 (footnotes 4 and 5), 167 (footnote 1)
- Jacobite branch of the Syrian Church in India, 242 243 257
- Jagannath, Worship of, 223 226, his Brahmanical and Buddhist origin 224, the Car festival, 225, English calumnies against Jagannath, self immolation seldom practised, 224, 225, his bloodless worship and gentle doctrines, 225, 226
- Jahangir, fourth Mughal Emperor of India (1605-27 A.D.), 300-302, chief events of his reign, 300 (footnote 2), rebellion of his son Shah Jahan, 301, his Empress Nur Jahan, 301, personal

- character, justice and religious toleration, 301, 302.
- Jai Singh, Rájá of Jaipur, his astronomical observatories at Jaipur, Delhi, Benares, Muttra, and Ujjain in the 18th century, 105, 106.
- Jail statistics, 472; vital statistics of Indian prisons, 684, 685.
- Jains, the modern representatives of the Buddhists in India, 158; Jain population in India, 158 (footnote); Jain doctrines, 159; temple cities, 159; relation of Jainism to Buddhism, 159, 160; antiquity of the Jains, 160; date of the Jain scriptures, 161; the Jains, an independent sect, 162; modern Jainism, 162.
- Jaipál, Hindu chief of Lahore, his defeats by Subuktigin and Mahmúd of Gházni, 272.
- Jalál-ud-dín, the first king of the Khilji dynasty (1290-95 A.D.), 280.
- Jamá Masjid, Sháh Jahán's great mosque at Delhi, 304.
- Jamuná, the name of the Brahmaputra from its entering the Bengal delta to its junction with the Ganges, 14.
- Jang Bahádur, assistance rendered by, during the suppression of the Mutiny, 421.
- Játs, The, their Scythian origin, 179, 180.
- Java, Conquest of, by Lord Minto, 399.
- Jayadeva, a celebrated Sanskrit poet of the 12th century, 128.
- Jazīrá, or Mughal poll-tax on non-Musalmáns, 309.
- Jesuits in India, 244-255; first Portuguese missionaries (1500 A.D.), 244; St. Francis Xavier, 244, 245; the Madras Jesuits, 245; letters of the early Jesuit missionaries, 246; Thána, a Jesuit station (1550 A.D.), with its colony of Christian artisans and cultivators, 247, 248; rural organization of the Jesuits, 248; the Jesuit college at Cochin, 248-250; Jesuit itinerant missionaries, and their conversions, 250, 251; Jesuit missions in Malabar in the 17th and 18th centuries, 251, 252; Jesuit martyrdoms, 252, 253; literary labours of the Jesuits, 253; establishment of the Portuguese inquisition at Goa (1560), 251-253; *autos da fé*, 253, 254; abolition of the inquisition (1812), 254; the Jesuits suppressed (1759-73), 254, 255; re-established (1814), 255.
- Jewellery and goldsmiths' work, 605, 606.
- Jewish settlements in ancient Malabar, 234, 235.
- Jhānsí, Native State, lapsed to the British for want of heirs, 415; revolt of the ex-princess in 1857, 421, 422.
- Jones, Sir William, 114; 126.
- Josaphat, a saint of the Christian Church, analogies between him and Buddha, and asserted identity of the two, 151, 152.
- Journal Asiatique*, Paper by M. Senart, quoted, 175 (footnote 3).
- Journalism and newspapers, 480.
- Juánga, a leaf-wearing tribe in Orissa, 56.
- Jumna, great river in Northern India, and chief tributary of the Ganges, 17.
- Jumna Canal, Eastern, Statistics of, 29; 532, 533.
- Jumna Canal, Western, Statistics of, 29; 531.
- Jungle products, *tasar* silkworm, lac, etc., 34; 513-515.
- Jungle rites in Hinduism, 206, 207.
- Jute, Cultivation of, 494, 495; export of raw and of manufactured jute, 495; 570, 571; 576; 615; steam jute mills, 614-616.

K

- Kabír, Vishnuite religious reformer (1380-1420), claimed as a saint by both Hindus and Muhammadans, 208; his doctrines, 218, 219; coalition of Vishnuism with Islám, 219; Kabír's religious poetry, 345.
- Kaders, aboriginal tribe of the Anamalai Hills, Madras, 55.
- Kailás, sacred mountain in Tibet, and the watershed from which the Indus, Sutlej, and Brahmaputra take their rise, 11, 13.
- Káimur, range of mountains in Central India and Bengal, an offshoot of the Vindhya, 35.
- Kalanos, the Bráhmaṇ at Alexander's court, 169.
- Kálí, the non-Aryan form of the wife of Siva, 211, 212.
- Kálidása, famous Hindu poet and dramatist (56 B.C.), 125; his drama of *Sakuntalá*, 126.
- Kanauj, ancient city, now deserted by the Ganges, 30; court pageant at, in the 12th century A.D., 276.
- Kanchanjanga, mountain in the Himalayas, 5.
- Kandahár, wrested from the Mughal Empire during the reign of Sháh Jahán, 303; occupation of, during the first Afghán campaign (1839), 408; defeat of Ayúb Khán at, in the second campaign (1880), 427.
- Kandhs, aboriginal hill tribe of Orissa and northern Madras, 60-63; their patriarchal government, 60; wais and

punishments, and blood revenge, 60, 61, agriculture, 61, marriages by capture, 61, serfs attached to their villages, 61, 62, human sacrifices, 62, the Kandhs under British rule, 62, 63
 amishka, Buddhist king in North Western India (40 A D), his great Council, 147, 148; 175, 176, 178
 ankār, or nodular limestone, 628, 638
 aragola, large trading fair, 596, 597
 arakoram, pass over the Himalayas on the trading route from the Punjab into eastern Turkistan 6
 arengs, an aboriginal tribe of Burma and Siam, 71
 arharbari coal field, 637
 arma, Buddhist doctrine of, 141, 142
 arnatik, The, English and French wars in, rival English and French candidates for the throne of Arcot (1746-61), 379, 390
 armul canal purchased by Government from the Madras Irrigation Company, 536, 537
 Kartabhajas, a reformed Vishnuite sect in the Districts around Calcutta, 223
 Kashmir shawls, Weaving of, 603
 Asimbāzār, East India Company's factory established at (1658), 369, the chief emporium of the Gangetic trade in the middle of the 18th century 380
 Āsim's expedition and temporary conquest of Sind (711-714 A D), 268
 Asī Ram Das, Bengali poet of Bardwan District, and translator of the Mahābhārata (17th century), 351
 Āuravās, their quarrel and struggle with the five Pandavas, as related in the Mahābhārata, 119, 120
 Āveri (Cauvery) river, 37, irrigation works, 536, 537
 Bennett, Reverend Dr., *St. Thomas the Apostle of India*, quoted, 233 (footnote 3), 235 (footnote), 237 (footnote 4), 239 (footnote 1)
 Beshava Das, Hindi poet of the 16th century, and composer of the Kamachandrika, 345

(footnote)

Khilji dynasty, The (1290-1320 A D), 280, 283, Jalal ud din (1290-95), 280, Ala ud din (1295-1315), 281, 282, Mughal mercenaries and Hindu revolts, 282, 283, Khusrū, renegade Hindu Emperor (1316-20), 282, 283
 Khusrū Khan, renegade Hindu emperor of the Khilji dynasty (1316-20 A D), 282, 283

Kiernander, Danish Protestant missionary, 260
 Kinki, attack on by, and repulse of, the Marathas (1817), 402
 Kirtibās Ojha, Sivaite religious poet of Bengal, 187, 188
 Kolarians, aboriginal races of Bengal and Central India, 64-68, their convergence in Central India, 64, their dispersion, 64, 65, scattered Kolarian fragments, 65, Kolarian languages, 65-68
 Koros, Alexander Csoma de, *Life and Works of*, by Dr. Theodore Dal, quoted, 153 (footnote 2), *Journal Asiatic Society of Bengal* (1833), quoted, 175 (footnote 1)
 Krishna worship, 222, a religion of pleasure, 222, 223, love songs, 223, hymn to, 345, 349
 Kshattriya or warrior caste of ancient India 89, 94, growth of the caste, 89-91, struggle between the priestly and warrior castes, 92-94, castes of Kshattriyas attaining Brahmanhood, 92, 93, legendary extermination of the Kshattriyas by Parasurama, the sixth incarnation of Vishnu, 94
 Kumarila, a Brahmanical religious reformer (750 A D), 191, 209, 329, 330
 Kuram, mountain pass into Afghanistan from the Punjab, 6
 Kustia, river station of the Eastern Bengal Railway terminus removed owing to silting of Ganges 30
 Kutub ud din, the first of the Slave dynasty, and the first resident Muhammadan sovereign in India (1206-10 A D), 278
 Kutub Shahi, Muhammadan dynasty in Southern India (1512-1688 A D), 288

L

La Bourdonnais, capture of Madras by a French squadron under the command of (1746) 379
 Labour and land, Relation between, in former times and at the present day in India, 48, 49
 La Croze's *Histoire du Christianisme des Indes*, 232 (footnote 1), 240 (footnote 4); 241 (footnotes 1 and 3), 242 (footnotes)
 Lac industry, 513, 515; export of lac and lac dye, 575
 Lake, Lord, victories over the Marathas at Laswari and D'g, 323; 398

- Lakshman Sen, last independent Hindu king of Bengal, his overthrow by Muhammad of Ghor (1203 A.D.), 277.
- Lāl Kavi, Hindi poet of Bundelkhand in the 17th century, and author of the *Chhatra Prakās*, 345.
- Lally, Defeat of, at Wandewash by Coote (1761), 379, 380; siege and surrender of Pondicherri and Gingi, 380.
- Land-making powers of deltaic rivers, 22-25; 27.
- Land revenue of India under the Mughals, 297-299; 304; land revenue of British India, 452.
- Land Settlement, 438-452; ancient land settlement of India, 438; Musalman land-tax, 439; the Company's efforts at land settlement, 439; growth of private rights, 439; the Permanent Settlement of Bengal (1793), 441; rights of the cultivators and intermediate tenure-holders, 442, 443; oppression of the cultivators, 543; land reform of 1859, 443, 444; the Kent Commission (1879), and further schemes for reform, 444, 445; temporary Settlement in Orissa, 445; yearly Settlement in Assam, 445; Madras *riyatwari* Settlement, 445-447; 'survey' tenure of Bombay, 448, 449; Southern India Agriculturists' Relief Acts (1879 and 1881), 449, 450; land system of the N.-W. Provinces and the Punjab, 451; *tālukdars* of Oudh, 451; land system of the Central Provinces, 452; the land revenue of India, 452; nature of the land-tax, 469.
- Languages (Aryan) of Northern India, Sanskrit, 334; the evidence for and against Sanskrit ever having been a spoken language, 334-336; divergence of Sanskrit and Prākṛit, 336; spread of the Prākṛits, 336, 337; classification of Prākṛits—Māhārāshtri or Marāṭhī, the Sauraseni or the Braj of the North-Western Provinces, the Magādhī or modern Bihārī, and the Paisachi or non-Aryan dialects, 337; evolution of modern vernaculars from the Prākṛits, 338, 339; the Sanskrit, Prākṛit, and non-Aryan elements in modern vernaculars, 339-342; the seven modern vernaculars, 342, 343; vernacular literature and writers, 343-354.
- Languages of non-Aryan tribes, 63-68; the Dravidian languages of Southern India; Tamil, its principal development, 330-333.
- Lassen, *Indische Alterthumskunde*, quoted, 161 (footnote 1); 191 (footnote 2); 340 (footnote 1).
- Laswāri, Defeat of Holkar at, 323; 398.
- Laterite, 628; 638, 639.
- Law and Custom of Hindu Castes*, by Mr. Arthur Steele, quoted, 195 (footnote 2).
- Law, Brāhmanical codes of, 113-118; the Grihyā Sūtras, an outgrowth from the Vedas, 113; code of Manu and its date, 113, 114; code of Yajñavalkya, 114, 115; scope of Hindu law, 115; its rigid caste system, 115, 116; growth of the law, 116; its incorporation of local customs, 117; perils of modern codification, 117, 118; modern legal literature, 118.
- Law, The, of British India, 433, 434.
- Lawrence, Lord, Viceroy of India (1864-69); famine in Orissa; Bhutān war; inquiry into the status of the Oudh peasantry; the commercial crisis of 1866, 424, 425.
- Lawrence, Major, his ineffectual siege of Pondicherri in 1748 in co-operation with the English fleet under Admiral Boscawen, 379.
- Lawrence, Sir Henry, Resident at Lahore (1845), 410; Chief Commissioner of Oudh, 415; killed at Lucknow (1857), 420.
- Lead, 626.
- Leaf-wearing tribe of Orissa, 56.
- Leather work, 603; leather factories at Cawnpur, 417.
- Left-hand and Right-hand castes of Madras, 196, 197.
- Legislative Council of the Governor-General, 432; of Madras, Bombay, and Bengal, 433.
- Leopard, The Indian, 653, 654.
- Limestone, 41, 42; 627, 628.
- Lion, The Indian, or maneless, of Gujarāt, 652.
- Literature of Bengal, The*, by Mr. Arce Dae, quoted, 347 and footnote; 348, 349, and footnote; 352 (footnote).
- Literature of India, 118-129; 343-354; and 480, 481; the Mahābhārata, 118-122; the Rāmāyana, 122-124; later Sanskrit epics, 124, 125; Vālmiki, the author of the Rāmāyana, 123; the poet Kālidasa, 125; the Sanskrit drama, 125, 126; the Hindu novel, 127; Beast stories and fables, 127; Sanskrit lyric poetry, 128; the Purānas or Brāhmanical mediæval theological writings, 128, 129; modern Indian literature, 129; Uriyā literature and authors, 343, 344; Rājputāna sacred literature, 344; Hindi literature and authors, 345, 346; Bengālī literature and authors, 346-354; 480, 481.
- Local finance, 470.
- Local and internal trade, statistics of, 592-597.

Locusts, 662

Lodi dynasty, The (1450-1526 A.D.),
286

Loss by exchange, 469

Love poems in Krishna worship, 223

Low caste apostles in religious reformations in Siva and Vishnu worship, 207, 208

Lower Ganges Canal, Statistics of, 29,
532, 533

Lucknow, Siege and relief of, 420, 421.

Lucknow, Withdrawal of English factory
at, 369

Lutheran Missions, 259, 260

Lyell, Sir Charles, *Principles of Geology*,
quoted, 27

Lytton, Lord, Viceroy of India (1876-80)

Proclamation of the Queen as Empress
of India, great famine of 1877 78
second Afghan war, 426, 427

second Afghan war, 426, 427

M

Macaulay, Lord, first Law Member of
the Council of India, 406

Macnaghten, Sir William, Assassination
of, at Kabul (1839), 408

Madhava Acharya, a Sanskrit religious writer of the 14th century, 191

Madhu Rao, fourth Maratha Peshwa
(1761-72), 321

Madhu Rao Narayan, sixth Maratha
Peshwa (1774-95), 6, 25

Madhu Sudan Datta, Bengal epic poet of the 19th century, 354

Madras, founded in 1639, the first territorial British possession in India, 369, 378, capture of, by the French, in effectual siege of, by the English, restoration to the British, 379

Madras, Muhamminadan College of Calcutta, 473

Maahabharata, the epic poem of the heroic age in Northern India, 118
122, the struggle between the Kauravas and Pandavas, 119, 120, the polyandry of Draupadi, 121
Mahmud, 62

272 275; his seventeen invasions of India, 272, 273, patriotic resistance of the Hindus, 273, sack of Somnath, 273, 274, conquest of the Punjab, 274, Mahmud's justice and thrift, 274, 275

ahmud Tughlak, last king of the Tughlak dynasty (1398-1414 A.D.), invasion of Timur (Tamerlane), 285

Thiruvannamalai (St Thomas' Mount), legend
of the martyrdom of St Thomas the
Apostle at, near Madras city, 231.

lignite coal beds in Assam, 621.

Makunda Ram, famous poet of Bardwan in the 16th century, story of Kalketu the hunter, 350, 351, the Srimanti Sadagar, 351

Malabar Christians, legendary preaching of St Thomas the Apostle on the Malabar and Coromandel coasts (68 A D), 229, Thomas the Manichean and Thomas the Armenian merchant, their rival claims as founders of Christianity in Southern India, 231, 232, troubles of the ancient Indian Church, 240, the St Thomas Nestorian Christians of Malabar, a powerful and respected military caste, 240, 241, Portuguese efforts at their conversion to Rome, 241, incorporation of the St Thomas Christians into the Roman Catholic Church, and downfall of the Nestorian Church, 241, Synod of Diamper (1599 A D), 241, Malabar Christians under Jesuit prelates (1601 to 1653 A D), 241, 242, Malabar Christians freed from Jesuit supremacy by the Dutch conquest of Cochin (1563) 242 first Jacobite Bishop to Malabar (1665), 242, 243, Malabar Christians since 1665, their division into Syrians and Jacobites, and present numbers, 243 tenets of the Jacobites of Malabar, 243 Nestorianism extinct in Malabar, 243, 244, the Jesuit Malabar Mission in the 17th and 18th centuries, 251, caste among Malabar Christians, 251, 252, letters of the Jesuit missionaries of Malabar

Malabar navigable back waters or lagoons, 553

Malik Kafur, slave general of Ala ud
dīn (1303-15 A.D.), his conquest of
Southern India, 282

Malleon, Colonel, *History of the French in India, and Final Struggles of the French in India*, by, quoted, 379 (foot note)

Mammalia of India, 652-659

Manchester cotton imports, 565, 568

Man hunts' of Muhammad Tughlak,
284, 285

lan Singh, Akbar's Hindu general and
governor of Bengal, 293

fanu, the legendary founder of Sanskrit law, 113, 114

Manufactures and Arts.—See ARTS AND MANUFACTURES

Manure, Use of, 483, want of, a draw

[illegible]

$\frac{d}{dt} \left(\frac{\partial L}{\partial \dot{x}} \right) = \frac{\partial L}{\partial x}$

but

the

1371

- the consolidator of the Maráthá power, 317; state of parties in the Deccan, (1650), 318; the Maráthás courted by the two rival Muhammadan powers, 318; Sivaji's hill forts, army of cavalry, tactics, etc., 319; his murder of the Bijápur general Akbar Khán, 319; coins money in his own name, 319; visits Delhi (1666), 319; enthrones himself as an independent prince at Raigah (1674), 319; death (1680), 319; Aurangzeb's mistaken policy in the Deccan, 319; Sambhaji and Sahu, successors of Sivaji, 319; the Sátára and Kolhápúr families, the last of Sivaji's line, 320; rise and progress of the Peshwás, 320; second Peshwá (1721-40), conquers the Deccan, 320; third Peshwá (1740-61), conquests in the Deccan, and raids from Bengal to the Punjab, 320, 321; defeat of the Maráthás by Ahmad Sháh the Afghán (1761), 321; fourth Peshwá (1761-72), 321; the five great Maráthá branches, 321; fifth Peshwá (1772), his assassination, 321; decline of the Peshwás (1772-78), 321, 322; the northern Maráthás, Sindhia and Holkar (1761-1803), 322; the Bhonslas of Berar (1751-53), 322; the Gáekwárs of Baroda, 322, 323; the sixth and seventh Peshwás (1774-1818), and the three Maráthá wars, 323, 324; end of the Peshwás (1849), 324.
- 'Maráthá Ditch,' The, moat constructed partly around Calcutta as a protection against the Maráthás, 320, 321.
- Maráthá wars, the first (1778-81), 323; 391; the second (1802-04), 398; third and last, annexation of the Peshwá's dominions (1818), 323; 402.
- Maráthí literature and authors, 346.
- Marble carving, 112; marble building stone, 628.
- Marco Polo*, by Colonel Yule, quoted, 152 (footnote 1); 231 (footnote 1); 233 (footnotes 1 and 2); 237 (footnote 4); 239 (footnote 3); 356 (footnote).
- Mar Gregory, first Jacobite Bishop to the Syrian Church in India, 242, 243.
- Máriás, aboriginal tribe in the Central Provinces, 55.
- Máris, aboriginal tribe in the Central Provinces, 55.
- Marriage law of the Hindus, 195, 196.
- Martyrdoms of Jesuit missionaries, 252, 253.
- Masulipatam, East India Company's factory established at (1622), 368; temporarily abandoned (1628), but re-established under a *farman* from the King of Golconda (1632), 368; murder of the Company's factors at (1689), 371; recapture of, from the French, 385.
- Mathematics, Bráhmanical system of, 106.
- Mauritius, India's trade with, 578, 579.
- Mausoleums, 112.
- Mayo, Earl of, Viceroy of India (1869-72), 425, 426; the Ambála *darbár*; visit of the Duke of Edinburgh, administrative reforms, abolition of customs lines, assassination at the Andaman Islands, 425; his scheme for Indian feeder lines of railway, 445, 446.
- Mayúr Pandit, Maráthí religious poet of the 18th century, 346.
- McCrindle, Mr. J. W. M., *Commerce and Navigation of the Erythrean Sea*, quoted, 166 (footnotes 1 and 2); 356 (footnote); *Ancient India as described by Megasthenes and Arrian*, quoted, 168 (footnote 1); 356 (footnote).
- Means of communication, chap. xviii. pp. 545-554. History of Indian railways, 545; Lord Dalhousie's trunk railway lines, 545; Lord Mayo's branch or feeder lines, 545, 546; the four classes of Indian railways, 'Guaranteed,' 'State,' 'Assisted,' and 'Native State,' 546-549; statistics of Indian railways, 549, 550; roads, the Grand Trunk Road, extension of minor roads, 550, 551; road metal, 551; bridges of boats, 551; navigable rivers, 551-553; navigable canals, 553, 554.
- Mediæval trade of India, 555.
- Medical colleges in India, 109.
- Medicine and drugs, 34; Bráhmanical system of medicine, 106-110; its independent development, 4th to 8th century, 107; scope of Indian medicine, 107; Indian surgery, 107, 108; Buddhist public hospitals, 108, 109; decline of Hindu medicine, 109; English Medical Colleges, 109; vernacular medical literature, 109, 110.
- Medlicott and Blanford, *Geology of India*, quoted, 27 (footnote); 631-640.
- Meerut, outbreak of the mutiny at, 419.
- Megasthenes, Seleukos' ambassador to the court of Chandragupta, 154; 163; his description of India and of Indian society (300 B.C.), 167-170; division of India into petty kingdoms, 170.
- Meghná, the eastern estuary of the united waters of the Brahmaputra and Ganges, 15; 21; 28; its 'bore' or tidal-wave, 31; the Meghná delta, 25.

- Thorne, quoted, 317 (footnote 1)
- Metcalf, Lord, Governor General of India (1835 36), 406
- Meteorology of India, chap xxiii pp 641 655 Meteorological geography of the Himalayas and Punjab frontier, 641 643, the Indus plain, and great Indian desert, 643, Gangetic plain and Eastern Bengal, 643 644, the Central Indian and Southern plateaux, 644, 645, Anamalai Hills 645, southern coast strip and Ceylon 645 646, Burma 646 solar radiation 647, air temperature, atmospheric pressure, wind, humidity, 647, 648, rainfall statistics, 649 650, sun spot cycles, 650, 651
- Mhairs aboriginal tribe in Rajputana 72, 73
- Miani, Defeat of the Sind Mirs at, by Sir C Napier (1843), 409
- Mica 628
- Middleton, first Bishop of Calcutta (1814), 261
- Middleton Sir Henry, his naval defeat of the Portuguese at Cambay (1611) 366
- Migration of the people, 47
- Military caste of St Thomas Nestorian Christians, 240, Portuguese efforts at their conversion to Rome, 241
- Military Transactions in Indostan*, by Orme, quoted, 379 (footnote), 380 (footnote 2)
- Mill, James, *History of British India*, quoted, 314 (footnote 3), 365 (footnote 2), 379 (footnote), 383 (footnote)
- Millet-, Statistics of cultivation of, and chief varieties, 487, 488, 489
- Mills by water power in the Himalayas, 9
- Mineral oils 42, petroleum wells and oil refining companies in Burma, 626, 627, petroleum in Assam and the Punjab, 627
- Minerals and Mines — See MINES AND MINERALS
- Mines and Minerals chap xxi pp 618 650. Indian iron indigenous methods of working, 618, failure of English efforts, 618, 619, Government efforts, 619, Indian coal and history of Bengal coal mining (1820 83), 619 620, the Central Provinces and Bengal coal fields, 620 621, coal beds in Assam, 621, future of Indian coal, 622, sal mining and manufacture, 622 623, sal petre, 623 624, gold washing, 624, gold mining in Madras and Mysore, 624 625, copper mining 626, lead, tin, antimony, and cobalt, 625, 626, petroleum in Burma, Assam, and the Punjab, 626 627, lime and building stone, 627, 628, marble, 628, slate, 628, diamonds and precious stones, 628, 629, pearl fisheries, 629 — See also GEOLOGY OF INDIA
- Miniature painting 113
- Minto, Earl of Governor General of India (1807 13), expeditions to Java and Mauritius, embassies to the Punjab, Afghanistan, and Persia, 399 400
- Mir Jafar, Nawab of Bengal (1757 60) compensation for losses at Calcutta 385
- Mir Jumla's unsuccessful expedition to Assam in the reign of Aurangzeb (1662), 309
- Mir Kasim Nawab of Bengal (1760 63) grant of Bardwan, Midnapur, and Chittagong to the Company, his quarrel with the English, massacre of Patna and defeat at Gherrah and Udhianala, 385 386
- Miracles of Buddhist and Hindu religions founders, 139 140, 208, miracles of the early Jesuits, 252
- Miscellaneous Essays*, by Mr B H Hodgson, 340 (footnote 1)
- Missionary efforts of Asoka, 146
- Missions, Christian, in India — See CATHOLIC MISSIONS, CHRISTIANITY IN INDIA, PROTESTANT MISSIONS
- Mixed population, 51
- Model farms, the small success hitherto attained, 515 516
- Mohpuri colliery in the Central Provinces, 620, 621
- Moura, Earl of — See HASTINGS, MARQUIS OF
- Monasteries (Hindu), 201, 202
- Monopoly, Salt, 453, opium 455
- Monson, Colonel, his retreat before Holkar, 398
- Monze, Cape, and promontory in Sind marking the extreme western boundary of British India, 3
- Mornington, Lord — See WILESLEY, MARQUIS OF
- Mot Masjid or Pearl Mosque at Agra Fort, 304
- Mukhl, Battle of, 411
- Mughal Empire, the (1526 1761 A.D.) chap xi pp 290 316. State of India in 1526, 290, early life of Babar (1482 1526), 290, invasion of India and defeat of Ibrahim Lodi at Panipat 290, Babar's conquest of Northern India,

- (1526-30), 290; Humáyún (1530-56), his expulsion from India (1540), and reconquest by the second battle of Páñipat (1556), 290, 291, and footnote; Akbar the Great (1556-1605), 291-300; Akbar's work in India, 292 and footnote; conciliation of the Hindus, 293; extension of the Mughal Empire, and reduction of the Rájputs (1561-68), 293; Akbar's Hindu officers, Rájás Mán Singh and Todar Mall, 293; Akbar's reform of Hindu customs, 293; reconquest of Bengal and subjugation of Muhammadan States, 294; change of capital from Delhi to Agra, 294; annexation of Khándesh in the Deccan, 294; Akbar's death, 295; his religious principles and new faith, 295; Akbar's reorganization of the army, police, and judicial administration of the Empire, 296; his revenue system and land revenue, 296, 297, and footnote; large totals of Mughal taxation, 298, 299; Jahángír (1605-27), 300 and footnote; Rájput revolts, 301; the Empress Nur Jahán, 301; Jahángír's personal character, justice, and religion, 301, 302; Sháh Jahán (1628-58), 302-305; loss of Kandahár, 303; Mughal conquests in the Deccan, 303, 304; Sháh Jahán's buildings, the Táñ Mahál, the Jamá and Moti Masjids, and palace at Delhi, 304, 305; rebellion of Prince Aurangzeb, and deposition of Sháh Jahán (1657-58), 305; revenues of Sháh Jahán, 305; Aurangzeb's usurpation and reign (1658-1707), 306-312; murder of his brothers, 307; rise of the Maráthá power, 307, 308; Aurangzeb's southern campaign and twenty years' war with the Maráthás, 308; Aurangzeb's 'Grand Army' worn out in the struggle (1705), his despair and death (1707), 308, 309; Mír Jumlá's disastrous expedition to Assam, 306; Aurangzeb's bigoted policy, and oppression of the Hindus, 309; revolt of the Rájputs, 309, 310; Aurangzeb's revenues and land-tax, 310, 311; character of Aurangzeb, 312; decline and fall of the Mughal Empire, the six puppet kings (1707-20), 312, 313; independence of the Deccan, of Oudh, and of the Rájput States, 314; oppressions of the Sikhs, 314; the Maráthá *chauth*, 314; Persian and Afghán invasions from the north, 314, 315; third battle of Páñipat (1761), and fall of the Mughal Empire, 315; the last of the Mughals (1862), 316.
- Muhammad of Ghor, the first king of the Ghor dynasty in India (1186-1206), 275-278; his conquests in Northern India and overthrow of the Rájput clans, 275, 276; subjugation of Bengal and defeat of its last independent Hindu king (1203 A.D.), 277, 278.
- Muhammad Tughlak, second king of the Tughlak dynasty (1324-51 A.D.), 283-285; expeditions to the south, 283; his cruelties, enforced change of capital, revolts, revenue exactions, 284, 285; 'man-hunts,' 284, 285.
- Muhammadan architecture, 112; 304.
- Muhammadan conquest of India only partial and temporary, 270.
- Muhammadan population of India, 51; also Appendix V., 693.
- Muhammadan States of the Deccan (1489-1683 A.D.), 288.
- Muir, Dr. John, *Sanskrit Texts*, quoted, 81 (footnote 2); 84 (footnote 3); 94 (footnote); 212 (footnote 4); 334 (footnotes 1 and 2).
- Mulberry cultivation in Bengal, 513.
- Mules, 521.
- Müller, Professor Max, *History of Sanskrit Literature*, translation of Rig - Veda, 83 (footnotes 1 and 2); 84 (footnotes); 85 (footnote); *Chips from a German Workshop*, 83 (footnote 1); 127 (footnote 3); 142 (footnote 2); 151 (footnote 2); *Contemporary Review* for July 1870, 151 (footnote 3); *Sacred Books of the East*, vol. xxii., the Jaina Sūtras, by Hermann Jacobi, 161 (footnotes 4, 5, 6, 7, and 8).
- Mundas, an aboriginal tribe of Kols in Chutiá Nágpur, 71 (footnote).
- Mundavers, a wandering pastoral tribe in the Anamalai Hills, 55.
- Municipal administration and statistics, 455-457; 470.
- Munro, Major (afterwards Sir Hector), Suppression of the first Sepoy Mutiny by, 386; defeat of the Imperial and Oudh armies at the battle of Baxar, 386.
- Munro, Sir Thomas, introducer of the *ráyatwári* system of land settlement in Madras, 446.
- Murshid Kúli Khán, Nawáb of Bengal, his transfer of the capital from Dacca to Murshidábád, 380, 381.
- Music, Hindu, 110-112; peculiarities of Indian music, 111; its modern revival, 111, 112.
- Muslin manufactures of Dacca and Madras, decline of industry, 602, 603.
- Mustagh, pass over the Himálayas on the trade route from the Punjab into Eastern Túrkiistán, 6.
- Mutiny, The, of 1857-58, 417-421; its causes, 417, 418; outbreaks at Meerut and Delhi, 419; spread of the revolt, 419; loyalty of the Sikhs, 419; massacre at Cawnpur, 420; siege and

re- of Lucknow, 420, 421, siege of
Delhi, 421, reduction of Oudh 421,
campaigns of Sir Colin Campbell (Lord
Clyde) and Sir Hugh Kene (Lord
Strathnairn) 421, 422

Metobalam, Export of, 574, 575

Mysore, First war with, against Haidar
Ali (1780-84), 392, second Mysore
war (1790-92), 394, Tipu's intrigues
with France, and the third Mysore
war (1799), 396 fall of Seringapatam,
and death of Tipu in the breach, 397
Mysore taken under British administration
and protection, 406, rendition of,
to its ancient hereditary Hindu rulers,
427, 435

N

Nal-haji Das Hindi poet of the 16th
century, and author of the Bhaktian shi,
345

Nadir Shah's invasion of India and sack
of Delhi, 314.

Nadiya rivers, Engineering works to
keep open the navigation of, during
the dry season, 552, 553.

Naga Hills, the mountainous district of
the Himalayas, 3.

Nagas or serpent worshippers, Ancient
dynasties of, 182, 183, 204.

Nagpur, the territory of the Marathas
Maratha family is said to have been
the seat of the Marathas (1823, 417)

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

Naga, the name of the Marathas is said to have
been the name of the Marathas, 55

- Opium, Excise duty on, 455; cultivation of, in Bengal and Málwa, 498, 499; export of, 499; Bengal opium system, 499.
- Origin of Christianity in India, its connection with St. Thomas the Apostle, 229.
- Orissa, by W. W. Hunter, quoted, 91 (footnote); 173 (footnote 1); 193 (footnote 1); 194 (footnote 5); 215 (footnote 1); 224 (footnote 4); 225 (footnotes 2, 4, and 6); 343 (footnote 2).
- Orissa Province, annexed to the Mughal Empire by Akbar's Hindu General, Rájá Todar Mall (1574), 294; ceded to the British (1803) by the Nágpur Bhonsla on the termination of the second Maráthá war, 398; the famine of 1866, 424; 542; settlement of the land revenue, 445; canal system, 534.
- Orme's *Military Transactions in Indostan*, quoted, 379 (footnote); 380 (footnote 2).
- Ostend East India Company established 1722; its factories at Covelong on the Madras coast, and at Bámkipur on the Húglí, 372-374; political objects of the Ostend Company, 373, 374; destruction of the Bámkipur settlement by the Muhammadans (1733), 374; bankruptcy and downfall of the Ostend Company (1784-93), 374.
- Oudh, Sale of Allahábád and Kora to the Wazir of, by Warren Hastings (1773), 389; the Rohillá war, 390; plunder of the Oudh Begams, 390, 391.
- Oudh, Annexation of, 415; Lord Dalhousie's justification of the measure, 416; the mutiny in, 421; inquiry into the status of the peasantry in, 424.
- Outram, Sir James, his works among the Bhíls of Khándesh, 72, 73; annexation of Oudh, 416; relief of Lucknow, 420.
- Overcrowded and under-peopled districts, 46, 47.
- Owen, Sidney J., *Selections from the Despatches of the Marquis of Wellesley*, quoted, 317 (footnote 1); *Selections from the Indian Despatches of the Duke of Wellington*, quoted, 317 (footnote 1).
- P**
- Pab hills, a southern offshoot of the North-Western Himálayas, forming a portion of the boundary between India and Baluchistán, 7.
- Paikashí ráyats, or temporary cultivators, 48.
- Painting, Indian art of, 113.
- Pálegár and Náyak chieftains of Southern India, 288.
- Pálghát Pass, a remarkable break or gap in the Western Gháts, 37.
- Pálitána, sacred temple city of the Jains, 159.
- Palm-leaf writings, 102.
- Palms, Varieties of, 491.
- Pándavas, the five brethren of the Mahábhárata; their quarrel and struggle with the Kauravas, 119-121.
- Pándya, ancient Hindu dynasty in Southern India, 286.
- Pánini, the compiler of the Sanskrit grammar (350 B.C.), 100; 336.
- Pánipat, celebrated battlefield in Northern India; defeat of Ibráhim Lodi by Bábar (1526 A.D.), 290; defeat of Afgháns by Akbar and restoration of Humáyún to the throne (1556 A.D.), 291; overthrow of the Maráthás by the Afgháns under Ahmad Sháh Duráni (1761 A.D.), 315; 321.
- Panna, Diamond mines of, 629.
- Pantænus, the Alexandrian stoic, his evidence as to Christianity in India at the end of the 2nd century A.D., 235.
- Paper-making, 617.
- Parameswara, the one First Cause, or Supreme Deity of Hinduism, 227.
- Parásnáth, hill in Bengal, held sacred by the Jains, 35; 159.
- Parasuráma, the sixth incarnation of Vishnu, his legendary war of extermination with the Kshattriyas, 94.
- Parochial organization of Portuguese India, 247.
- Partition of the Gangetic Valley by Clive (1765), 387.
- Passes of the Himálayas, the Khaibar, Kuram, Gwalari, Tál, and Bolán passes, 29; of the Western Gháts, the Bhor, Thal, and Pálghát passes, 36, 37.
- Patala, town founded by Alexander the Great, and identified with the modern city of Haidarábád, the historic capital of Sind, 166.
- Pathán Kings of Delhi, by Mr. E. Thomas, quoted, 271 (footnote); 279, 280, 281 (footnotes); 283 (footnotes 1 and 2); 284 (footnote 1); 285 (footnote 3); 287 (footnote 2); 291 (footnote).
- Patná, East India Company's Agency at (1620), 367; massacre of, 386; trade of, 595, 596.
- Pearl fisheries, 629.
- Pegu, Annexation of, as the result of the second Burmese war, 413, 414.
- Peninsular India, Geology of, 634-639.
- Permanent Settlement, The, of Lord Cornwallis and Sir John Shore, 393, 394.

- Popular Vishnuism, 217.
- Population of India, chap. ii. pp. 43-52.
 General survey of the people, 43; the feudatory chiefs and their powers, 43; the twelve British Provinces, 44; Census of 1872 and of 1881, 44, 45; population tables of British, Feudatory, and Foreign India, 44, 45; density of the population, 46; absence of large towns, 46; overcrowded districts, 46, 47; under-peopled tracts, 47; immobility of the Indian peasant, 47; nomadic system of tillage, 47, 48; relation of labour to land in the last century, and at the present day, 48, 49; serfdom, 49; unequal division of the people, 49, 50; increase of population since 1872, 50; ethnical history of India, 51; fourfold division of the people, into Aryans, non-Aryans, mixed Hindus, and Muhammadans, 51, 52; population tables for 1881, 51 (footnote), and Appendices I.-X., 689-703.
- Portuguese in India, 356-361; Covilham, 357; Vasco da Gama, 357, 358; Cabral, 358; Francisco de Almeida, 359; Albuquerque, 359, 360; oppressions of the Portuguese, 359, 360; downfall of the Portuguese power, 360; Portuguese Indian possessions in 1871, 361; mixed descendants, 361; defeat of the Portuguese fleet at Swally off Surat (1615), 366; temporary expulsion of the Portuguese from Bengal, 368, 369; early Portuguese trade with India, 560.
- Porus, Defeat of, by Alexander the Great, 164.
- Post-Vedic Gods, Rise of, 97, 98; the Hindu triad, 98.
- Potato cultivation in the Himálayas, 9.
- Pottery manufactures, 608; 628.
- Practical faith of the Hindus, its tolerance and fairness to Christianity, 226, 227.
- Pre-Aryan kingdoms in Northern India, 184; pre-Aryan civilisation, 328, 329.
- Pre-Buddhistic Scythian influences in India, connection of the Horse Sacrifice with the Human Sacrifice of pre-Buddhistic India, 175, 176; 183, 184; Scythic and Nága influences on Hinduism, and on the religions and domestic life of modern India, 189, 199.
- Precious metals in India, imports of treasure, 562, 568, 569; gold-mining, 624, 625.
- Precious stones, 9; 606; 628, 629; 639.
- Predatory hill races; their conversion from marauding tribes into peaceful cultivators and good soldiers, 71-73.
- Presbyterian Missions, 261.
- Primary education, 477, 478.
- Primitive Aryan burial, 85-87.
- Prince of Wales' visit to India (1875-76), 426.
- Prinsep, Henry T., *Narrative of Political and Military Transactions of British India under the Marquiss of Hastings*, quoted, 317 (footnote).
- Proclamation of the Queen as Empress of India, 426.
- Products and agriculture.—See AGRICULTURE AND PRODUCTS.
- Protestant Missions in India, 259-269; first translation of the Bible into the vernacular, 260; Schwartz, Kiernander, Marshman, Carey, and Ward, 260, 261; opposition of the Company to Christian missionaries, 260; withdrawal of the Company's opposition, 260, 261; Bishopric of Calcutta, 261; statistics of Protestant Missions, 261-264.
- Provincial Administration, 'Regulation' and 'Non-Regulation' territory, District officers and their duties, 434-437.
- Prussian and Embden East India Companies (1750 and 1753), Dutch and English jealousy of, and their downfall, 374-376.
- Public Works expenditure, 469, 470.—See also MEANS OF COMMUNICATION, RAILWAY SYSTEM, ROADS, CANALS, etc.
- Puliars, a wild aboriginal tribe in the Anamalai Hills, Madras, 55.
- Pulses, Cultivation of, 489.
- Puránas, The, their place in Indian literature, 216, 217.

R

- Race origin of caste modified by 'occupation' and 'locality,' 192, 193.
- Ráigarh, enthronement of Sivaji as an independent monarch at, in the Deccan (1674), 319.
- Railway system of India, inaugurated by Lord Dalhousie, 545; extended by Lord Mayo, 545, 546; the eight guaranteed trunk lines, 546, 547; State and 'Assisted' railways, 547, 548; railways in Native States, 548, 549; statistics of traffic and capital invested, 549, 550.
- Rainfall, Himálayan, 7; Western Gháts, 38; statistics of rainfall for 435 Indian stations, 649, 650.
- Rájputána literature and sacred poetry, 344.
- Rájputs, their reputed Scythian origin, 180; number of Rájput castes in modern India, 194; distribution of Rájputs in the 12th century A.D., 276, 277; Rájput revolts against the Slave kings, 280; against the Khilji dynasty, 282;

- against the Tughlak dynasty, 284, conciliation of Rājputs by Akbar, 293, revolt against Jahāngir, 301, against Aurangzeb, 309, 310
- Rāma the hero of the Sanskrit epic Rāmāyana, 123, 124
- Ramanand, Vishnuite religious reformer (1300-1400 A D), his low-caste disciples, 218
- Ramanuja, Vishnuite religious reformer (1150 A D), 217
- Rāmāyana, the Sanskrit epic relating to the Aryan advance into Southern India, 121, 122, the story of Rama, his exile together with his wife Sita; the war with the aboriginal king of Ceylon, and triumphant return, 123, 124
- Ram Mohan Kai, theistic religious reformer and prose religious writer, 353
- Ram Prasad Sen, court poet of Nadiya in the 18th century, 352
- Ranjit Singh, the founder of the Sikh kingdom, 410, 411
- Rājat carl settlement of the land in Madras, 445, 446 growth of the Madras cultivator into a proprietor, 447, extension of tillage, 447, reduction of average land tax, 448
- Raynal, Abbe, *History of the Settlements and Trade of the Europeans in the East and West Indies*, quoted, 374 (footnote)
- Raziya, Empress of Delhi (1236-39), the only lady who ever occupied that throne, 279
- Reconquest of India from the Muhammadans by the Hindus (1707-61 A D),
- Regions, 499
- Religion of the Hindus*, by Dr Wilson, quoted, 201 (footnote 2), 205 (footnote 1); 206 (footnote 2), 208 (footnote 2); 210 (footnote 2), 213 (footnote 1), 221 (footnote 2), 223 (footnotes 3 and 4), 225 (footnote 5)
- Religions of India*, by Dr Barth, quoted, 161 (footnote 2)
- Revenue Resources of the Mughal Empire, by Mr E Thomas, quoted, 271 (footnote); 297 (footnote 2), 299, 301 (footnote 1), 304, 305 (footnote); 311 (footnotes)
- Revenue system of British India, the land tax, 438-441, 452, salt-duty, 453, 454, excise and opium, 453-455, municipal revenues, 455-457, revenue and expenditure of British India, 455-470
- Revenue of the Mughal Empire under Akbar, 297, growth of the Mughal revenues (1593-1761 A D), 269
- Revue de l'Histoire des Religions* by Dr Barth, quoted, 161 (footnote 2)
- Rhinoceros The Indian, 656
- Rice cultivation in Bengal 32, 33, in other Provinces of India its numerous varieties, 485, out turn, 485, 486, export of, 572, export duty on, 573
- 'Right hand' and 'left hand' castes of Madras, 196, 197
- Rig Veda, the earliest Sanskrit hymn, 77, 88, its antiquity, 77, 78, caste and widow burning unknown, 78, the story of the Aryan advance into India, 79, Aryan civilisation in the Veda, 79, the gods of the Veda, 79-81, Vedic conceptions of the Deity, the modern blood loving gods unknown, 82, Vedic hymns and prayers, 84-86, primitive Aryan form of burial, 84, cremation substituted for burial, 84, 85 Vedic legend of Yama, the king of death, 85, the Vedic farewell to the dead, 85, 86
- Ripon Marquis of (Viceroy of India 1880-84), conclusion of the Afghan war, amendment of criminal procedure, revenue reforms, Education Commission, abolition of customs duties, Bengal Tenancy Bill, 427-429
- Rise of the Marathi power, 307, 308—See also chap. xii, 'The Maratha Power, 317-324
- River communications, 15, 16, 19, 20; 551-553
- River plains of India, 10-34; the great rivers, Ganges, Jumna, Indus (with Sutley), and Brahmaputra, 11-20, the different stages in the life of an Indian river, 21-23, the Bengal delta and process of land making, 23-25; rivers as irrigators and highways, 24, 29, destructive floods, 29-32; poetry of Indian river names, 32, crops and scenery of the river plains and the Bengal delta, 32-34
- River systems of Northern India, 10, 11; of Southern India, 37, 38
- River traffic on the Ganges and Gangetic channels, and of the port of Calcutta, 20
- Roads, old miles, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000

- against the Tughlak dynasty, 284 ;
conciliation of Rājputs by Akbar, 293,
revolt against Jahāngir, 301, against
Aurangzeb, 309, 310
- Rāma, the hero of the Sanskrit epic
Kāmayāna, 123, 124
- Ramanand, Vishnuite religious reformer
(1300 1400 A D), his low caste dis-
ciples, 218
- Ramanuja, Vishnuite religious reformer
(1150 A D), 217
- Rāmāyana, the Sanskrit epic relating to
the Aryan advance into Southern India,
121, 122, the story of Rama, his exile
together with his wife Sita; the war
with the aboriginal King of Ceylon, and
triumphant return, 123, 124
- Ram Mohan Kai, theistic religious re-
former and prose religious writer, 353
- Ram Prasad Sen, court poet of Nadiya
in the 18th century, 352
- Ranjit Singh, the founder of the Sikh
kingdom, 410, 411
- Rājasthān settlement of the land in
Madras, 445, 446 growth of the
Madras cultivator into a proprietor,
447, extension of tillage, 447, reduc-
tion of average land tax, 448
- Raynal, Abbe, *History of the Settlements
and Trade of the Europeans in the East
and West Indies*, quoted, 374 (footnote)
- Raziya, Empress of Delhi (1236 39), the
only lady who ever occupied that
throne, 279
- Reconquest of India from the Muham-
madans by the Hindus (1707 61 A D),
270
- Reform of Hindu customs by Akbar, 293
'Regulation' and 'Non Regulation
Provinces, 435
- Religion of the Hindus*, by Dr H H
Wilson, quoted, 201 (footnote 2), 205
(footnote 1), 206 (footnote 2), 208
(footnote 2), 210 (footnote 2), 213
(footnote 1), 221 (footnote 2), 223
(footnotes 3 and 4), 225 (footnote 5)
- Religions of India*, by Dr Barth, quoted,
161 (footnote 2)
- Religious classification of the population
in India, Appendix V, 693
- its reform
right and compensation for disturbance,
444, 445
- Report on the Miscellaneous Old Records
in the India Office*, by Sir George Bird-
wood, 358 (footnote 2), 360 (footnote
1); 364 (footnotes 1 and 2); 368
(footnote); 370 (footnote)
- Reptiles, 660, poisonous serpents and
deaths from snake bite, 660
- Revenue Resources of the Mughal Empire*,
by Mr E. Thomas, quoted, 271 (foot-
note); 297 (footnote 2), 299, 301
(footnote 1), 304, 305 (footnote); 311
(footnotes)
- Revenue system of British India, the
land tax, 438 441, 452, salt duty, 453,
454; excise and opium, 453 455, muni-
cipal revenues, 455 457, revenue and
expenditure of British India, 455 470
- Revenue of the Mughal Empire under
Akbar, 297, growth of the Mughal
revenues (1593 1761 A D), 269
- Revue de l'Histoire des Religions*, by Dr
Barth, quoted, 161 (footnote 2)
- Rhinoceros, The Indian, 656
- Rice cultivation in Bengal, 32, 33, in
other Provinces of India its numerous
varieties, 485, out turn, 485, 486,
export of, 572, export duty on, 573
- 'Right hand' and 'left hand' castes of
Madras, 196, 197.
- Rig Veda, the earliest Sanskrit hymn,
77, 88, its antiquity, 77, 78, caste and
widow-burning unknown, 78, the story
of the Aryan advance into India, 79,
Aryan civilisation in the Veda, 79, the
gods of the Veda, 79 81, Vedic con-
ceptions of the Deity, the modern blood-
loving gods unknown, 82, Vedic
hymns and prayers, 84 86, primitive
Aryan form of burial, 84, cremation
substituted for burial, 84, 85, Vedic
legend of Yama, the king of death,
85, the Vedic farewell to the dead,
85, 86
- Ripon, Marquis of (Viceroy of India,
1880 84), conclusion of the Afghan
war, amendment of criminal procedure,
revenue reforms, Education Commis-
sion, abolition of customs duties, Gen-
eral Tenancy Bill, 427 429
- Rise of the Maratha power, 307, 308
—See also chap xii, 'The Maratha
Power, 317 324
- River communications, 15, 16; 19, 20;
551 553
- River plains of India, 10 34; the great
rivers, Ganges, Jumna, 11 25 (x 1/2
Suley), and Brahmaputra, 11 20; the
different stages in the life of an Indian
river, 21 23, the Bengal delta and
process of land making, 22 23; the
as irrigators and 11 23, 24, 25;
destructive floods, 25 26; the
Indian river system, 22. See also
summary of the rivers; 21, 22, 23
Bengal delta, 22 24
- River system of India, 10 34; the great
rivers, Ganges, Jumna, 11 25 (x 1/2
Suley), and Brahmaputra, 11 20; the
different stages in the life of an Indian
river, 21 23, the Bengal delta and
process of land making, 22 23; the
as irrigators and 11 23, 24, 25;
destructive floods, 25 26; the
Indian river system, 22. See also
summary of the rivers; 21, 22, 23
Bengal delta, 22 24
- River system of India, 10 34; the great
rivers, Ganges, Jumna, 11 25 (x 1/2
Suley), and Brahmaputra, 11 20; the
different stages in the life of an Indian
river, 21 23, the Bengal delta and
process of land making, 22 23; the
as irrigators and 11 23, 24, 25;
destructive floods, 25 26; the
Indian river system, 22. See also
summary of the rivers; 21, 22, 23
Bengal delta, 22 24

- Trunk Road, inland route from Bombay, extension of minor roads, 550, 551.
- Roberts, Sir Frederick, his march from Kábul to Kandahár and defeat of Ayúb Khán, 427.
- Rock Edicts of Asoka, 144, 145 (footnote); 146 and footnote.
- Rockhill, Mr. W. Woodville, *Life of the Buddha, and the early History of his Order*, derived from Tibetan works, and translated by, quoted, 137 (footnote 2); 138 (footnote 2); 154 (footnote 2); 160 (footnote 2); 176 (footnote 1); 177 (footnotes).
- Roe, Sir Thomas, first British Ambassador to India, in the reign of Jahángir (1615 A.D.), 301; 367.
- Rohilkhand and Bijnaur canal, 533.
- Rohillá war, 390.
- Roman Catholics, Distribution of, in India, 257; the Verapoli vicariate, 257; Roman and Syrian Catholic population of India, 257-259: Catholic progress, colleges and schools, 257-259. — See also CATHOLIC MISSIONS.
- Roman trade with India (190 A.D.), 234.
- Rose, Sir Hugh (Lord Strathnairn), campaign in Central India, 421, 422.
- Rotation of crops, 483.
- Roth, Professor, 'Indische Medicin, Karaka,' published in the *Zeitschrift der Deutschen Morgenländischen Gesellschaft* for 1872, quoted, 110 (footnote).
- Rural population, 46; proportion of town to rural population, 46; number and population of villages and towns, Appendix II., 690.
- S**
- Sacred Books of the East*, by Professor Max Müller, quoted, 161 (footnotes 4, 5, 6, 7, and 8).
- Safed Koh, mountain range forming a portion of the western boundary between British India and Afghánistán, 3; 6.
- Safflower, Export of, 574.
- Ságar Island at the mouth of the Ganges, a celebrated place of pilgrimage, 17, 18.
- Sahu, son and nominal successor of Sambhájí, 319, 320.
- Saidapet, Government model farm at, in Madras, recently closed, 516; agricultural school at, 516.
- Saka or Scythian era (78 A.D.), 181.
- Sakhi Sarwar, place of pilgrimage in the Punjab, sacred both to Hindus and Muhammadans, 203, 204.
- Sakta or Tantuik sect of Siva-worshippers, 214.
- Sakuntalá, famous Sanskrit drama, 126.
- Sakya race customs, 178.
- Salbái, Treaty of, 323; 392.
- Salím, Prince, Akbar's favourite son and successor as the Emperor Jahángir, 300-302.
- Saline deposits from canal irrigation, 29.
- Saliváhaná, King of Southern India, his wars with the Scythians, 181.
- Salt administration, 452; sources of supply and systems of manufacture, 453, 454; the Madras monopoly, 453; equalization of duty, 453, 454; yield of salt duty, 468; the Rájputána salt lakes, and Punjab salt mines, 622, 623.
- Saltpetre, Manufacture of, 623, 624.
- Salt range, Geology of, 633.
- Sáma-Veda, The, 88.
- Sambalpur, Diamonds of, 628.
- Sambhájí, son and successor of Sivají, put to death by Aurangzeb, 319.
- Samvat and Saka eras (57 and 78 A.D.), 181.
- Sanctity of the Ganges, 17, 18.
- Sandwip island, Slavery in, 49.
- Sankara Achárya, a Sivaite religious reformer (9th century A.D.), 209, 210.
- Sámkhya, one of the six *darśanas* or Bráhmanical schools of philosophy, 99.
- Sanskrit Grammar*, by Professor Whitney, 334 (footnote 1).
- Sanskrit grammar and literature, 100-104; 334-336; Pánini's grammar, 100, 101; Sanskrit and Prákrit speech, 101; Sanskrit manuscripts, 101, 102; the Indian Alphabet, 102, 103; Sanskrit writings almost entirely verse, 103; prose a forgotten art, 103, 104; Sanskrit dictionaries, 104; evidence as to whether Sanskrit was ever a spoken vernacular, 334-336.
- Sanskrit Texts*, by Dr. John Muir, quoted, 81 (footnote 2); 84 (footnote 3); 94 (footnote); 212 (footnote 4); 334 (footnotes 2 and 3).
- Santáls, an aboriginal tribe of Bengal, 57; their village government, 57; social ceremonies, 58; religion, 58, 59; the Santáls under British rule, 59; Santál rising (1855), 59, 60.
- Satára, Native State, lapsed to the British for want of heirs (1849), 415.
- Sati*, or widow-burning, unknown in the Rig-Veda, 78; abolition of the rite by Lord W. Bentinck, 405.
- Satnámís, a reformed Vishnuite sect in the Central Provinces, 223.
- Sátapura, range of mountains in Bombay and Central India, 35.
- Sayyid dynasty, The (1414-50 A.D.), 286.
- Scarcities. — See FAMINES.
- Schools. — See EDUCATION.
- Schwartz, Protestant missionary in Tanjore, 260.

- 'Strikes' among Indian castes, 198
 Su, a Tartar tribe, their overthrow of the Greek settlements in Bactria, 175
 Subuktigin, first Turki invader of India (977 A.D.), 272
 Sudhanwan's alleged persecution of the Buddhists, 191 and footnotes
 Sudras, the servile caste of ancient India, 90, 91
 Suez Canal, Trade with India *vide*, 564, 565, 581
 Sufed Koh range in Afghanistan, an offshoot of the Himalayas, 3
 Sugar cane, Cultivation of, 491
 Sugar duties, Abolition of Inland (1836), 562
 Sulaiman range of hills marking a portion of the western boundary between British territory and Afghanistan 3, 6
 Sun spot cycles, 650, 651
 Sun worship, traces of, among the Santals, 58
 Surat, English obtain leave to trade at (1612 A.D.), 366, defeat of the Portuguese fleet at Swally, the port of Surat, by Captain Best (1615 A.D.), 366, Surat, the chief seat of the Company's government in Western India till 1684-87, when it was transferred to Bombay, 370, Surat pillaged by Sivaji (1664), 370, treaty of Surat between Raghunath Rao and the British, 391
 Sur Das, poet of Mathura in the 16th century, and author of the Sursagar, 345
 'Survey' land tenure in Bombay, its simplicity, advantages, and disadvantages, 448, 449
 Sutlej, great river of the Punjab and chief tributary of the Indus, 11
 Sutras or sacred Sanskrit traditions, 89
 Swally, Defeat of the Portuguese fleet at (1615), 366
 Swedish East India Company, 376
 Synod of Diamper (1599 A.D.), 241.
 Syrian Christians in India, their numbers and antiquity, 230, Syrian Catholics in Malabar, 243, 244; Syrian rite reformed, 245; Syrian and Roman Catholic Christians at the present day, 257, 258.

T

- Taj Mahal, The, 112; 304.
 Takht-i-Sulaiman, mountain in the Sulaiman range, 6
 Takshas, a Turanian race, and the earliest inhabitants of Kāwal Pindi District, 164 (footnote 2), their present descendants, 184.

- Takshaks, an early Scythian tribe in the Punjab, 184, 185
 ————, main pass over the Prahari hills, 6
 ————, of the, 288
 Tālukdars or great landowners, Judh, 451, 452.
 Tamil, the oldest and most influential of the vernacular literatures of Southern India, 330, first cultivation of Tamil by the sage Agastya, 330, 331, Jain cycle of Tamil literature from the 9th to the 13th century, 331, its great Pariah poet and poetess (900 A.D.), 331, the Tamil Rāmāyana, 331
 Saivite and Vishnuite Tamil hynologies, 332, the Sittar or anti-Brahmanical Tamil poets of the 17th century, 332, modern Tamil writers, 333, Beschi the Jesuit priest, 333, recent statistics of Tamil literature 333
 Tantrik sect of Shiva worshippers, 214
 Tartar overthrow of Greek conquests in Bactria, 175 — See also SCYTHIAN INVASIONS
 Tasar, or jungle silk worm, 34, 513, 514
 Tassy, Garcin de, *Histoire de la littérature Hindoue et l'Indoustanie*, quoted 343 and footnote 1
 Taxation of India under the Mughal Emperors (1593-1761 A.D.), 299, tax on under the Mughals and the British 463, 464, taxation in Native States 464, incidence of taxation in British India, 464, 465 — See also FINANCES and REVENUE SYSTEM
 Taxila, ancient town in Rawal Pindi District, Punjab, the home of the Takshas, identified with the ruins of Dera Shahān, 164 (footnote 2), 184.
 Tea cultivation and manufacture, 504, 509, indigenous to Assam, 504, early experiments and failures, 504, 505, rapid progress of the industry, 505, statistics of out-turn, 505-507, varieties of the plant, 508; the work of a tea garden, 508, 509, export of tea, 575
 Terk forests, 39; 42
 Tegnapatam (Fort St. David), East India Company's factory established at (1686-92), 371.
 Temperature of various meteorological stations in India, 647-649. — See also METEOROLOGY OF INDIA.
 Temple's, Sir R., Minute on the balance of Indian trade, 551-553
 Tenancy (Bengal) Bill, 429
 Tenant right in Bengal, compensation for disturbance, 444, 445.
 Tha, or professional stringing, Suppression of, by Lord W. Bentinck, 405

Vital statistics of India, chap. xiv. pp. 665-686. The principal sources of health returns, 665; untrustworthy registration statistics, 666, 667; death-rate and average duration of life in India, 666, 667; birth and death rates for different Provinces, 667-679; health and mortality in the European army, 675; 680-682; in the native army, 682-684; jail vital statistics, 684-686.

Von Böhlen, *Das Alte Indien*, quoted, 110 (footnote 2).

Vyāsa, Brāhman sage, the legendary compiler of the four Vedas (3101 B.C.), and of the epic of the Mahābhārata, 118.

W

Wandewash, Battle of, and defeat of the French under Dally (1761), 379, 380.

War, Art of, in Vedic and Sanskrit times, 110.

Wargaum, Convention of (1779), 391.

Watera coal-field in the Central Provinces, 620.

Warren Hastings. — See HASTINGS, WARREN.

Water-mills in the Himālayas, 9.

Watson, Admiral, bombardment and capture of Chandarnagar, 382.

Weber, Professor, *History of Indian Literature*, quoted, 94 (footnote); 102 (footnote 1); 105 (footnote); 110 (footnote 1); 127 (footnote 3); 154 (footnote); 168 (footnote 2); 172 (footnotes 2 and 3); 175 (footnote 1); 176 (footnote 3); *Indische Studien*, quoted, 161 (footnote 1).

Wellington, General (afterwards Duke of Wellington)—the victories of Assaye and Argaum, 323; 398.

Wellesley, Marquis of, Governor-General of India (1798-1803), 394-397; French influence in India, 394, 395; Lord Wellesley's scheme, 395, 396; treaty with the Nizām, 396; third Mysore war and storming of Seringapatam, 396, 397; second Marāthā war (1802-04) and annexations to British territory, 398; British successes and disasters, 398.

Western Ghāts, mountain range along the western coast of India, 36; 39; its passes, 36, 37; rivers, 37; rainfall, 38; forests, 39.

Western Jumna Canal, 29; 532.

Wheat, Statistics of cultivation and output of, 486-488; export of, 573.

Whitney, Professor, *Sanskrit Grammar*, quoted, 334 (footnote 1).

Widows, Position of, in ancient India, 78.

Williams, Professor Monier, 114; 129 (footnote 1).

Willoughby, Sir John's attempt to force an eastern passage along the north of Europe and Asia, 363.

Wilson, Dr. H. H., *Works of*, quoted, 110 (footnote 1); 127 (footnote 2); 154 (footnote 1); *Ariana Antiqua*, 175 (footnote 1); *Vishnu Purāna*, 180 (footnote 4); 216, 217 (footnotes); *Essays*, 191 (footnote 2); *Religion of the Hindus*, 201 (footnote 2); 205 (footnote 1); 206 (footnote 2); 210 (footnote 2); 221 (footnote 2); 223 (footnotes 3 and 4).

Wilson, Dr. J., *Indian Caste*, quoted, 194 (footnote 1); 195 (footnote 2); 110 (footnote 1).

Wilson, Mr. James, his financial reforms after the Mutiny, 424.

Wise, Dr. T. A., *Review of the History of Medicine among the Asiatics*, quoted, 110 (footnote 1).

Wolf, The Indian, 654.

Women, Position of, in ancient India, and in Vishnu-worship, 78; 221.

Wood-carving, 112; 609.

X

Xavier, St. Francis, his work in India, 244, 245.

Y

Yājñavalkya's Code of Hindu Law, 114, 115.

Yajur-Veda, The, 88.

Yak cow, The, a remarkably sure-footed beast of burden in the Himālayas, 9, 10.

Yama, the Hindu god of death, Vedic legend of, 85.

Yandabu, Treaty of (1826), 403, 404.

Yavanas, the name applied to Greeks and Scythians by the Brāhmins, 93; 172, 173.

Yoga, one of the six *darsanas* or Brāhmanical systems of philosophy, 99.

Yogis, a sect of Sivaite devotees, 214.

Yoma mountain range in Burma, 6.

Yule, Colonel Henry, *Marco Polo*, quoted, 151 (footnote 5); 152 (footnote 1); 231 (footnote 1); 233 (footnotes 1 and 2); 237 (footnote 4); 238 (footnotes); 239 (footnote 3); 356 (footnote); *Cathay and the Way Thither*, 233 (footnote 2); 283 (footnote 5).

INDEX.

Z

Zamindari grant of the Twenty four
Parganas, 383
Zamindars or revenue land collectors
under the Mughals, converted into a
proprietary body by the Permanent
Settlement of Bengal, 439, 442
Zoology and Botany of India, chap
xxiv pp 652 664. The Gujarat or

maneless lion, 652, tiger, 652, leopard,
cheetah, 653, 654, wolf, fox, jackal,
dog, 654; bear, 655, elephant and
elephant-catching, 655, 656, rhinoceros,
656, wild boar and hog, 656, 657,
sheep and goats, 657, antelope and
deer, 657, 658, bison and buffalo,
658; birds of prey and game birds,
659; reptiles, 660, 661, insects, 662,
Indian flora, 662 664

END OF VOLUME VI.